TITLE 13. CALIFORNIA AIR RESOURCES BOARD

NOTICE OF PUBLIC HEARING TO CONSIDER THE "LEV III" AMENDMENTS TO THE CALIFORNIA GREENHOUSE GAS AND CRITERIA POLLUTANT EXHAUST AND EVAPORATIVE EMISSION STANDARDS AND TEST PROCEDURES AND TO THE ON-BOARD DIAGNOSTIC SYSTEM REQUIREMENTS FOR PASSENGER CARS, LIGHT-DUTY TRUCKS, AND MEDIUM-DUTY VEHICLES, AND TO THE EVAPORATIVE EMISSION REQUIREMENTS FOR HEAVY-DUTY VEHICLES

The Air Resources Board (ARB or Board) will conduct a public hearing at the time and place noted below to consider adoption of a comprehensive set of "LEV III" amendments to the California Low-Emission Vehicle (LEV) regulations. These amendments reduce emissions of criteria pollutants from new light- and medium-duty vehicles by: reducing fleet average emissions from new passenger cars, light-duty trucks, and medium-duty passenger vehicles to super ultra-low-emission vehicle levels by 2025; replacing separate non-methane organic gas (NMOG) and oxides of nitrogen standards (NOx) with combined NMOG plus NOx standards; increasing full useful life durability requirements from 120,000 miles to 150,000 miles, which guarantees vehicles operate longer at these proposed extremely low emission particulate levels; creating a backstop to assure continued production of super-ultra-low-emission vehicles after partial zero-emission vehicles as a category are moved from the Zero-Emission Vehicle program to the LEV III program in 2018; establishing more stringent particulate matter standards for light- and medium-duty vehicles; establishing zero fuel evaporative emission standards for passenger cars and light-duty trucks, and more stringent evaporative standards for medium-duty vehicles; establishing more stringent supplemental federal test procedure (SFTP) standards for passenger cars and light-duty trucks; and, for the first time, requiring medium-duty vehicles to meet SFTP standards. Other minor amendments (e.g., in-use verification testing requirements, reporting requirements, etc.) are proposed to align existing related procedures with the principal amendments. These amendments also establish more stringent greenhouse gas regulations that: are comprised of three emission standards; a CO_2 standard, a CH_4 standard and a N_2O standard; use a footprint-based approach to reduce emissions from new light-duty vehicles and medium-duty passenger vehicles; provide credits for improvements to the vehicle air conditioning system (either from the use of a refrigerant with a low Global Warming Potential or by incorporating improvements to the efficiency of the system); provide credits for technologies that reduce CO_2 emissions but are not measured on the applicable test cycles ; and provide credits for technology innovations on the largest of pickup trucks. This comprehensive set of amendments, part of the Advanced Clean Cars regulatory proposals to be heard as a package on the same day, address multiple pollutant types in the context of California's passenger motor vehicle program as a whole.

DATE: January 26, 2012

TIME: 9:00 a.m.

PLACE: Metropolitan Water District of Southern California
700 N. Alameda Street
Los Angeles, CA 90012-2944

This item will be considered at a two-day meeting of the Board, which will commence at 9:00 a.m., January 26, 2012, and may continue at 8:30 a.m., on January 27, 2012. This item may not be considered until January 27, 2012. Please consult the agenda for the hearing, which will be available at least 10 days before January 26, 2012, to determine the day on which this item will be considered.

INFORMATIVE DIGEST OF PROPOSED ACTION AND POLICY STATEMENT OVERVIEW

Sections Affected: Proposed amendments to California Code of Regulations, title 13, sections 1900, 1956.8, 1960.1, 1961, 1961.1, 1965, 1968.2, 1968.5, 1976, 1978, 2037, 2038, 2062, 2112, 2139, 2140, 2145, 2147, 2235, and 2317; and to the following documents incorporated by reference therein: "California Exhaust Emission Standards and Test Procedures for 2001 and Subsequent Model Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," as last amended September 27, 2010; "California Evaporative Emission Standards and Test Procedures for 2001 and Subsequent Model Motor Vehicles," as last amended September 27, 2010; "California Refueling Emission Standards and Test Procedures for 2001 and Subsequent Model Motor Vehicles," as last amended September 27, 2010 ; "Specifications for Fill Pipes and Openings of Motor Vehicle Fuel Tanks," as last amended January 22, 1990; "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Otto-Cycle Engines," as last amended September 27, 2010; "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Diesel Engines and Vehicles," as last amended October 12, 2011; "California Environmental Performance Label Specifications for 2009 and Subsequent Model Year Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles, " as adopted May 2, 2008; "California Test Procedure for Evaluating Substitute Fuels and New Clean Fuels, " as adopted November 2, 1993; and proposed new "Specifications for Fill Pipes and Openings of 2015 and Subsequent Motor Vehicle Fuel Tanks;" and proposed new "California Test Procedure for Evaluating Substitute Fuels and New Clean Fuels in 2015 and Subsequent Years."

Proposed adoption in California Code of Regulations, title 13, of new sections 1961.2 and 1961.3 and new "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles" incorporated by reference therein,

DATE: January 26, 2012

TIME: 9:00 a.m.

PLACE: Metropolitan Water District of Southern California
700 N. Alameda Street
Los Angeles, CA 90012-2944

This item will be considered at a two-day meeting of the Board, which will commence at 9:00 a.m., January 26, 2012, and may continue at 8:30 a.m., on January 27, 2012. This item may not be considered until January 27, 2012. Please consult the agenda for the hearing, which will be available at least 10 days before January 26, 2012, to determine the day on which this item will be considered.

INFORMATIVE DIGEST OF PROPOSED ACTION AND POLICY STATEMENT OVERVIEW

Sections Affected: Proposed amendments to California Code of Regulations, title 13, sections 1900, 1956.8, 1960.1, 1961, 1961.1, 1965, 1968.2, 1968.5, 1976, 1978, 2037, 2038, 2062, 2112, 2139, 2140, 2145, 2147, 2235, and 2317; and to the following documents incorporated by reference therein: "California Exhaust Emission Standards and Test Procedures for 2001 and Subsequent Model Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," as last amended September 27, 2010; "California Evaporative Emission Standards and Test Procedures for 2001 and Subsequent Model Motor Vehicles," as last amended September 27, 2010; "California Refueling Emission Standards and Test Procedures for 2001 and Subsequent Model Motor Vehicles," as last amended September 27, 2010 ; "Specifications for Fill Pipes and Openings of Motor Vehicle Fuel Tanks," as last amended January 22, 1990; "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Otto-Cycle Engines," as last amended September 27, 2010; "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Diesel Engines and Vehicles," as last amended October 12, 2011; "California Environmental Performance Label Specifications for 2009 and Subsequent Model Year Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles, " as adopted May 2, 2008; "California Test Procedure for Evaluating Substitute Fuels and New Clean Fuels, " as adopted November 2, 1993; and proposed new "Specifications for Fill Pipes and Openings of 2015 and Subsequent Motor Vehicle Fuel Tanks;" and proposed new "California Test Procedure for Evaluating Substitute Fuels and New Clean Fuels in 2015 and Subsequent Years."

Proposed adoption in California Code of Regulations, title 13, of new sections 1961.2 and 1961.3 and new "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles" incorporated by reference therein,

and amendment of the following document incorporated by reference therein: "California Non-Methane Organic Gas Test Procedures," as last amended July 30, 2002.

Background

California's Current Criteria Pollutant Emission Standards

The LEV II Program

In 1999, California adopted the second phase of the Low-Emission Vehicle Program (LEV). These amendments, known as LEV II, set more stringent fleet average non-methane organic gas (NMOG) requirements for model years 2004-2010 for passenger cars and light-duty trucks, established additional emission categories to provide compliance flexibility with the revised fleet average requirements, and established a new emissions category, partial zero-emission vehicle (PZEV) that could be used toward meeting the zero-emission vehicle requirement. The amendments also expanded the heavier light-duty truck (LDT2) category to include trucks and sport utility vehicles up to 8,500 lbs. gross vehicle weight rating (GVWR) and required these vehicles to meet the same emission standards as passenger cars, and extended full useful life from 100,000 miles to 120,000 miles. The LEV II amendments also established more stringent emission standards for medium-duty vehicles (MDVs) between 8,501-14,000 lbs. GVW. The following table lists the vehicle classes affected by the current LEV program.

Vehicle Class	Weight Range[1]
Passenger cars	All weights
Light-duty truck 1	0-3750 lbs. LVW
Light-duty truck 2	3751 lbs. LVW – 8,500 lbs. GVWR
Medium-duty vehicle	8,501-10,000 lbs. GVWR
	10,001-14,000 lbs GVWR

Other principal features of the current LEV program follow.

[1] There are several classifications for vehicles based on weight. Curb weight is defined as the actual weight of the vehicle. Loaded vehicle weight (LVW) is defined as the curb weight plus 300 pounds. Gross vehicle weight rating (GVWR) is the maximum designed loaded weight of the vehicle; this means curb weight of the vehicle plus full payload.

Supplemental FTP Emission Regulations

Emissions from aggressive driving and from air conditioner use are not accounted for during typical emission testing for criteria pollutants, using the Federal Test Procedures (FTP). Instead, these "off-cycle" emissions are subject to the California Supplemental Federal Test Procedures (SFTP).

Evaporative Emission Regulations

Compliance with the current evaporative emission regulations, adopted as part of the LEV II Program, is based on meeting three separate certification "whole vehicle" emission standards. Specifically, these include the running loss emission standard, the three-day diurnal plus high-temperature hot soak (three-day) emission standard, and the two-day diurnal plus moderate-temperature hot soak (two-day) emission standard.[2] The running loss emission standard ensures evaporative emission control during vehicle driving. The three-day emission standard ensures that the evaporative system can control evaporative emissions for three consecutive hot summer days. The two-day emission standard ensures an effective strategy to purge the vehicle carbon canister.

As an option, a manufacturer may certify its passenger cars and light-duty trucks to more stringent requirements by complying with zero-evaporative emission standards. Specifically, these requirements consist of more stringent three-day and two-day whole vehicle emission standards, as well as a "zero" fuel evaporative emission standard. Over the two-day and three-day test procedures, passenger cars must meet a 0.35 grams per test hydrocarbon emission standard (higher levels are allowed for larger vehicles), which includes fuel and non-fuel hydrocarbon emissions. They must also meet the zero-evaporative emission standards, which require a vehicle to emit no more than 0.054 grams per test of fuel-only evaporative emissions. Currently, manufacturers certify to zero-evaporative emission standards in order to qualify for Partial Zero-Emission Vehicle (PZEV) credits under the ZEV regulatory mandate. This PZEV certification and crediting applies only if the vehicle's exhaust emissions are also certified to SULEV exhaust standards with a 150,000-mile useful life and a 150,000 mile emission warranty.

Environmental Performance Label

Currently, all new vehicles sold in California must include a California Environmental Performance Label, which provides consumers with a user-friendly scoring system for comparing the relative smog emissions (Smog Score) and global warming emissions (Global Warming Score) from comparable vehicles. Both scores are based on a scale of 1 -10, with 10 being the cleanest and 5 representing an average new car.

---

[2] Compliance with the running loss and three-day emission standards is demonstrated over a three-day diurnal test procedure. Compliance with the two-day emission standard is demonstrated over a two-day diurnal test procedure.

Since the spring of 2010, ARB staff has advised the U.S. Environmental Protection Agency (USEPA) and the National Highway Traffic Safety Administration (NHTSA) on its proposal to revise the federal Fuel Economy Label, so that as revised it could serve as an alternative to the California Environmental Performance Label.

Important California requirements addressed by the final, adopted federal label included:

- Adding the following statement to the label: "Vehicle emissions are a significant cause of climate change and smog"
- Having a clear statement about upstream emissions and having a clear place to find this information on a regional basis.
- Including all cars in a single rating system rather than segregating by size or class.
- Including both a Greenhouse Gas and Fuel Economy Rating[3] and a Smog Rating from 1 to 10 with 10 being best.

In June 2011, USEPA and NHTSA published 40 CFR Parts 85, 86, and 600 providing requirements for the new Fuel Economy and Environment Label. This new Federal Label is required on all new cars starting with Model Year 2013 and can be affixed earlier on a voluntary basis.

On-Board Diagnostic Systems

Second generation on-board diagnostics (OBD II) systems are comprised mainly of software designed into the vehicle's on-board computer to detect emission control system malfunctions as they occur by monitoring virtually every component and system that can cause an increase in emissions. When an emission-related malfunction is detected, the OBD II system alerts the vehicle owner by illuminating the malfunction indicator light (MIL) on the instrument panel. By alerting the owner of malfunctions as they occur, repairs can be sought promptly, which results in fewer emissions from the vehicle. Additionally, the OBD II system stores important information including identification of the faulty component or system and the nature of the fault, which typically allow for quick diagnosis and proper repair of the problem by technicians. This helps owners achieve less expensive repairs and promotes repairs done correctly the first time.

Manufacturers recently approached ARB staff and requested regulation changes that they indicated were needed immediately in order to ensure compliance when they certify their 2013 model year vehicles. Manufacturers and ARB staff held discussions with interested manufacturers, including a face-to-face meeting on July 27, 2011, to discuss their proposal.

In response to the manufacturers' requests, staff agreed to minor changes to the OBD II regulation, which would have negligible emission impact.

[3] The federal value is tied only to tailpipe GHGs and excludes other vehicular GHGs (e.g. air conditioning refrigerant).

E10 Certification Fuel

The California certification fuel used for testing exhaust and evaporative emissions on passenger cars, light-duty trucks, medium-duty vehicles, and heavy-duty gasoline engines and vehicles currently contains the oxygenate methyl tertiary butyl ether (MTBE) in the quantity of 10.8 to 11.2 volume percent (equivalent to 2.0 percent oxygen by weight). MTBE was banned for use in California gasoline starting December 31, 2003. As a result of the ban of MTBE, ethanol became the prevalent oxygenate used in California gasoline. After the ban, refiners began adding approximately 5.7 volume percent ethanol to gasoline, which is equivalent to 2.0 percent oxygen by weight. California gasoline contained 5.7 percent ethanol until the end of 2009. In 2010, California refiners transitioned to producing gasoline containing 10 percent by volume ethanol (E10). Currently, all gasoline in California contains 10 percent ethanol and will continue to contain 10 percent ethanol for the foreseeable future. While the oxygenate and oxygenate amount have changed in in-use California gasoline, the certification fuel on which emission testing is being done has not.

California's Current (Pavley) Greenhouse Gas Emission Standards

Citing compelling and extraordinary air quality and other impacts California faces from global warming, in 2002 the Legislature passed and the Governor signed Assembly Bill (AB) 1493 (Pavley). This bill requires ARB to develop and adopt regulations to achieve the maximum feasible and cost-effective reduction of heat-trapping greenhouse gas emissions from passenger motor vehicles, beginning with the 2009 model year. The Board approved regulations at its September 2004 hearing, and they were adopted in their final form in August 2005.

Subsequent to that hearing, automakers, California, and the federal government committed to a series of actions to resolve ongoing disputes over the California standards through model year 2016. The result of this agreement was the development of a national greenhouse gas program for passenger vehicles that achieves equivalent or better emission reductions as the California program, additional compliance flexibilities provided in the California program, and agreement by California to accept manufacturers' demonstrated compliance with U.S. EPA-adopted greenhouse gas standards as compliance with California's standards for the 2012 through 2016 model years.

Development of California's Proposed Greenhouse Gas Emission Standards

In May of 2010, USEPA and NHTSA issued a Notice of Intent to develop greenhouse gas emission standards for passenger vehicles for the 2017 through 2025 model years. The Notice requested that USEPA and NHTSA work closely with ARB on a 2010 technical assessment that would evaluate technologies and costs to achieve varying levels of GHG emission reductions through model year 2025. The result was a September 2010 *Interim Technical Assessment Report*, jointly authored by USEPA, NHTSA, and ARB. Subsequent to that collaborative technical work, ARB staff has closely monitored the work of USEPA and NHTSA, and the agencies' staffs continued to jointly meet with various stakeholders (e.g., individual automakers, automotive suppliers, environmentalists, labor unions), examine updated technical materials, and develop consistent technology assumptions.

Current Proposal

Criteria Pollutant Emission Standards

In order to achieve further criteria emission reductions from the passenger vehicle fleet, staff is proposing several amendments representing a significant strengthening of the current LEV program. The major elements of the proposed LEV III program are:

- A reduction of fleet average emissions of new passenger cars (PCs), light-duty trucks (LDTs) and medium-duty passenger vehicles (MDPVs) to super ultra-low-emission vehicle (SULEV) levels by 2025;
- The replacement of separate NMOG and oxides of nitrogen (NOx) standards with combined NMOG plus NOx standards, providing automobile manufacturers with more flexibility in meeting these stringent standards;
- Increasing full useful life durability requirements from 120,000 miles to 150,000 miles, which guarantees vehicles operate longer at these extremely low emission levels;
- A backstop to assure continued production of super-ultra-low-emission vehicles after PZEVs as a category are moved from the Zero-Emission Vehicle program to the LEV III program in 2018;
- More stringent particulate standards for light- and medium-duty vehicles, which will reduce health effects including premature deaths associated with these emissions;
- Zero fuel evaporative emission standards for PCs and LDTs, and more stringent evaporative standards for medium-duty vehicles (MDVs);
- More stringent supplemental federal test procedure (SFTP) standards for PC and LDTs, including particulate matter (PM) emission standards, which reflect more aggressive real world driving and, for the first time, require MDVs to meet SFTP standards;

- Minor changes to the OBD II regulation, California Code of Regulations (Cal. Code Regs.), title 13, section 1968.2, and its associated enforcement regulation, section 1968.5, which provide slight additional lead time to meet a new monitoring requirement or minimal adjustment of a monitoring threshold for detecting an emission issue; and
- Certification fuel that contains 10 percent ethanol and is representative of current in-use fuel.

Greenhouse Gas Emission Standards

Based on the *Interim Technical Assessment Report*, ARB developed its second generation greenhouse gas regulations that will apply for the 2017 and subsequent model years. These regulations incorporate many of the elements of the proposed national rule, including separate emission standards for carbon dioxide (CO_2), methane (CH_4), and nitrous oxide (N_2O), providing credits toward the CO_2 standard if a manufacturer reduces refrigerant emissions from the vehicle's air conditioning system, and using a footprint-based approach for reducing emissions. Under this footprint-based approach, target CO_2 values are assigned for different vehicles based on the model type and the footprint (i.e. the area described by wheelbase times the average track width of the vehicle) of the vehicle. The overall emission reductions required of each manufacturer would be unique to that manufacturer based on the mix of vehicles it sells. The proposed California regulations also provide credits for using verifiable GHG emission-reduction technologies that are not fully accounted for with the established regulatory test cycle procedures. And the proposed regulations would allow manufacturers to demonstrate compliance with California's proposed standards by demonstrating to ARB National Program compliance.

While ARB has worked closely to coordinate development of the California and national greenhouse programs, there are a number of provisions that are unique to California. First, California's proposed regulations would continue to require that the CO_2-equivalent emissions from electric vehicles, off-vehicle charge capable hybrid electric vehicles (also known as "plug-in" hybrid electric vehicles), fuel cell vehicles, and ethanol vehicles be calculated by taking into account the upstream emissions from these vehicles. Also, the California proposal maintains the current option for a manufacturer to "pool" its sales of vehicles to California, the District of Columbia, and those states that have adopted California's motor vehicle regulations pursuant to section 177 of the Clean Air Act. However, a manufacturer that elects to demonstrate compliance with California's proposed regulations by pooling its sales must continue to maintain and report separate sales and emissions values for each pooled entity.

COMPARABLE FEDERAL REGULATIONS

Criteria Pollutant Emission Standards

There are currently no comparable federal criteria pollutant emission standards for 2015 and subsequent model passenger vehicles as stringent as this proposed California rule.

However, USEPA has indicated that it expects to issue a Notice of Proposed Rulemaking (NPRM) for their "Tier 3" next generation of criteria pollutant emission standards in January 2012, which will apply to 2017 and subsequent model year vehicles. Staff expects the Tier 3 program to be comparable to the California proposed rule in the applicable timeframe. This national rule is expected to be finalized in late-2012.

Greenhouse Gas Emission Standards

There are currently no comparable federal greenhouse gas emission standards that are as stringent as the proposed standards for 2017 and subsequent model passenger vehicles. (The current federal greenhouse gas emission standards for the 2016 and subsequent model years are comparable to those applicable in California in the 2016 model year). However, on November 16, 2011, an NPRM was issued by USEPA and NHTSA for a joint rulemaking that proposes a coordinated federal greenhouse gas emission reduction and fuel economy program for light-duty vehicles, beginning in the 2017 model year. This national rule is expected to be finalized by the end of July 2012. There are no significant differences between the proposed California greenhouse gas regulations and those presented in the NPRM. Furthermore, staff does not expect there to be any significant differences between the proposed California greenhouse gas regulations and those in USEPA's Final Rule.

AVAILABILITY OF DOCUMENTS AND AGENCY CONTACT PERSONS

ARB staff has prepared a Staff Report: Initial Statement of Reasons (ISOR) for the proposed regulatory action, which includes a summary of the economic and environmental impacts of the proposal. The report is entitled: "Staff Report: Initial Statement of Reasons for Proposed Rulemaking, Public Hearing to Consider the "LEV III" Amendments to the California Greenhouse Gas and Criteria Pollutant Exhaust and Evaporative Emission Standards and Test Procedures and to the On-Board Diagnostic System Requirements for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles, and to the Evaporative Emission Requirements for Heavy-Duty Vehicles.

Copies of the ISOR and the full text of the proposed regulatory language, in underline and strikeout format to allow for comparison with the existing regulations, may be accessed on ARB's website listed below, or may be obtained from the Public Information Office, Air Resources Board, 1001 I Street, Visitors and Environmental Services Center, First Floor, Sacramento, California, 95814, (916) 322-2990, on December 7, 2011.

Upon its completion, the Final Statement of Reasons (FSOR) will be available and copies may be requested from the agency contact persons in this notice, or may be accessed on ARB's website listed below.

Inquiries concerning the substance of the proposed regulation may be directed to the designated agency contact persons, Mr. Paul Hughes, Manager, Low-Emission Vehicle

Implementation Section, at (626) 575-6977, or Ms. Sarah Carter, Staff Air Pollution Specialist, at (626) 575-6845.

Further, the agency representative and designated back-up contact persons, to whom non substantive inquiries concerning the proposed administrative action may be directed are Ms. Lori Andreoni, Manager, Board Administration and Regulatory Coordination Unit, (916) 322-4011, or Ms. Trini Balcazar, Regulations Coordinator, (916) 445-9564. The Board staff has compiled a record for this rulemaking action, which includes all the information upon which the proposal is based. This material is available for inspection upon request to the contact persons.

This notice, the ISOR and all subsequent regulatory documents, including the FSOR, when completed, are available on ARB's website for this rulemaking at http://www.arb.ca.gov/regact/2012/leviiighg2012/leviiighg2012.htm

COSTS TO PUBLIC AGENCIES AND TO BUSINESSES AND PERSONS AFFECTED

The determinations of the Board's Executive Officer concerning the costs or savings necessarily incurred by public agencies and private persons and businesses in reasonable compliance with the proposed regulations are presented below.

Pursuant to Government Code sections 11346.5(a)(5) and 11346.5(a)(6), the Executive Officer has determined that the proposed regulatory action would not create costs or savings to any State agency or in federal funding to the State, costs or mandate to any local agency or school district, whether or not reimbursable by the State pursuant to Government Code, title 2, division 4, part 7 (commencing with section 17500), or other nondiscretionary cost or savings to State or local agencies, except that there is expected to be an unquantifiable reduction in future gasoline tax revenue due to this proposal.

In developing this regulatory proposal, ARB staff evaluated the potential economic impacts on representative private persons or businesses. The proposal is expected to increase the annual cost of compliance for vehicle manufacturers that are subject to the requirements of California's Low-Emission Vehicle regulations by approximately $40 million per manufacturer, which is assumed to be passed on in full to consumers. The proposal is therefore expected to result in a $1900 average increase in the purchase price of a new passenger vehicle when the standards include the cost associated with the ZEV program are fully phased in; however, purchasers of these new vehicles are expected to realize an average net savings of $4,000 per vehicle due to decreased operating costs.

The Executive Officer has made an initial determination that the proposed regulatory action would not have a significant statewide adverse economic impact directly affecting businesses, including the ability of California businesses to compete with businesses in other states, or on representative private persons.

In accordance with Government Code section 11346.3, the Executive Officer has determined that the proposed regulatory action would create approximately 67,000 new

jobs and eliminate approximately 30,000 current jobs within the State of California. The proposed regulatory action would not affect the creation or elimination of directly affected businesses within the State of California. However, both directly affected businesses along with businesses in other sectors within the State of California could expand or contract as a result of the proposed regulations. A detailed assessment of the economic impacts of the proposed regulatory action can be found in the ISOR.

The Executive Officer has also determined, pursuant to California Code of Regulations, title 1, section 4, that the proposed regulatory action would not directly affect small businesses, because the proposed LEV III regulations do not apply to small businesses.

In accordance with Government Code sections 11346.3(c) and 11346.5(a)(11), the Executive Officer has found that the reporting requirements of the regulation which apply to businesses are necessary for the health, safety, and welfare of the people of the State of California.
Before taking final action on the proposed regulatory action, the Board must determine that no reasonable alternative considered by the Board, or that has otherwise been identified and brought to the attention of the Board, would be more effective in carrying out the purpose for which the action is proposed, or would be as effective and less burdensome to affected private persons than the proposed action.

ENVIRONMENTAL ANALYSIS

In accordance with ARB's certified regulatory program, California Code of Regulations, title 17, sections 60006 through 60007, and the California Environmental Quality Act, Public Resources Code section 21080.5, ARB has conducted an analysis of the potential for significant adverse and beneficial environmental impacts associated with the proposed regulatory action. The environmental analysis of the proposed regulatory action can be found in Appendix B of the ISOR.

SUBMITTAL OF COMMENTS

Interested members of the public may present comments orally or in writing at the meeting, and comments may be submitted by postal mail or by electronic submittal before the meeting. The public comment period for this regulatory action will begin on December 12, 2011. To be considered by the Board, written comments, not physically submitted at the meeting, must be submitted on or after December 12, 2011 and received no later than 12:00 noon on January 25, 2012, and must be addressed to the following:

Postal mail: Clerk of the Board, Air Resources Board
1001 I Street, Sacramento, California 95814

Electronic submittal: http://www.arb.ca.gov/lispub/comm/bclist.php

You can sign up online in advance to speak at the Board meeting when you submit an electronic board item comment. For more information go to: http://www.arb.ca.gov/board/online-signup.htm.

Please note that under the California Public Records Act (Gov. Code, § 6250 et seq.), your written and oral comments, attachments, and associated contact information (e.g., your address, phone, email, etc.) become part of the public record and can be released to the public upon request.

ARB requests that written and email statements on this item be filed at least 10 days prior to the hearing so that ARB staff and Board members have additional time to consider each comment. The Board encourages members of the public to bring to the attention of staff in advance of the hearing any suggestions for modification of the proposed regulatory action.

Additionally, the Board requests but does not require that persons who submit written comments to the Board reference the title of the proposal in their comments to facilitate review.

STATUTORY AUTHORITY AND REFERENCES

This regulatory action is proposed under the authority granted in Health and Safety Code, sections 38510, 38560, 38562, 39500, 39515, 39600, 39601, 39667, 43006, 43013, 43018, 43018.5, 43101, 43104, 43105, 43200, 43210, 43210.5, and 44036.2, and Vehicle Code section 27156. This action is proposed to implement, interpret, and make specific sections 38501, 38510, 38560, 39002, 39003, 39667, 40000, 43000, 43004, 43006, 43008.6, 43009.5, 43100, 43101, 43101.5, 43102, 43104, 43106, 43205, 43205.5, 43210, 43211, 43212, and 43213, Health and Safety Code.

HEARING PROCEDURES

The public hearing will be conducted in accordance with the California Administrative Procedure Act, Government Code, title 2, division 3, part 1, chapter 3.5 (commencing with section 11340).

Following the public hearing, the Board may adopt the regulatory language as originally proposed, or with non-substantial or grammatical modifications. The Board may also adopt the proposed regulatory language with other modifications if the text as modified is sufficiently related to the originally proposed text that the public was adequately placed on notice that the regulatory language as modified could result from the proposed regulatory action; in such event, the full regulatory text, with the modifications clearly indicated, will be made available to the public, for written comment, at least 15-days before it is adopted.

The public may request a copy of the modified regulatory text from ARB's Public Information Office, Air Resources Board, 1001 I Street, Visitors and Environmental Services Center, First Floor, Sacramento, California, 95814, (916) 322-2990.

SPECIAL ACCOMMODATION REQUEST

Special accommodation or language needs can be provided for any of the following:

- An interpreter to be available at the hearing;
- Documents made available in an alternate format or another language; or
- A disability-related reasonable accommodation.

To request these special accommodations or language needs, please contact the Clerk of the Board at (916) 322-5594 or by facsimile at (916) 322-3928 as soon as possible, but no later than 10 business days before the scheduled Board hearing. TTY/TDD/Speech to Speech users may dial 711 for the California Relay Service.

Comodidad especial o necesidad de otro idioma puede ser proveído para alguna de las siguientes:

- Un intérprete que esté disponible en la audiencia.
- Documentos disponibles en un formato alterno u otro idioma.
- Una acomodación razonable relacionados con una incapacidad.

Para solicitar estas comodidades especiales o necesidades de otro idioma, por favor llame a la oficina del Consejo al (916) 322-5594 o envíe un fax a (916) 322-3928 lo más pronto posible, pero no menos de 10 días de trabajo antes del día programado para la audiencia del Consejo. TTY/TDD/Personas que necesiten este servicio pueden marcar el 711 para el Servicio de Retransmisión de Mensajes de California.

CALIFORNIA AIR RESOURCES BOARD

James N. Goldstene
Executive Officer

Date: November 29, 2011

The energy challenge facing California is real. Every Californian needs to take immediate action to reduce energy consumption. For a list of simple ways you can reduce demand and cut your energy costs, see our website at www.arb.ca.gov

CALIFORNIA ENVIRONMENTAL PROTECTION AGENCY
AIR RESOURCES BOARD

STAFF REPORT:
INITIAL STATEMENT OF REASONS FOR PROPOSED RULEMAKING, PUBLIC HEARING TO CONSIDER THE "LEV III" AMENDMENTS TO THE CALIFORNIA GREENHOUSE GAS AND CRITERIA POLLUTANT EXHAUST AND EVAPORATIVE EMISSION STANDARDS AND TEST PROCEDURES AND TO THE ON-BOARD DIAGNOSTIC SYSTEM REQUIREMENTS FOR PASSENGER CARS, LIGHT-DUTY TRUCKS, AND MEDIUM-DUTY VEHICLES, AND TO THE EVAPORATIVE EMISSION REQUIREMENTS FOR HEAVY-DUTY VEHICLES

This report has been reviewed by the staff of the California Air Resources Board and approved for publication. Approval does not signify that the contents necessarily reflect the views and policies of the Air Resources Board, nor does the mention of trade names or commercial products constitute endorsement or recommendation for use.

Date of Release: December 7, 2011
Scheduled for Consideration: January 26, 2012

EXECUTIVE SUMMARY

Background

Despite significant progress in reducing smog-forming and particulate matter criteria emissions from the passenger vehicle fleet, California needs further reductions in order to meet State and federal ambient air quality standards. In addition, climate change continues to pose a serious threat to the economic well-being, public health, natural resources, and environment of California. To address the challenge presented by climate change, vehicle greenhouse gas (GHG) emissions must be drastically reduced to meet our goal of an 80% reduction from 1990 levels by 2050.

California's Light-Duty Vehicle Program

Criteria Emissions

In 1990, the Air Resources Board (ARB or Board) established the Low Emission Vehicle (LEV) program that contained the most stringent exhaust emission regulations ever for light-duty passenger cars and trucks. The regulations included three primary elements: (1) tiers of increasingly stringent exhaust emission standards, (2) a fleet-average emission requirement for 1994-2003 that required manufacturers to phase-in a progressively cleaner mix of vehicles from year to year, and (3) a requirement that a specified percentage of passenger cars and lighter light-duty trucks be zero emission vehicles (ZEVs), vehicles with zero emissions of any pollutants.

In 1999, ARB adopted the second phase of the LEV program. These amendments, known as LEV II, set more stringent fleet average non-methane organic gas (NMOG) requirements for model years 2004-2010 for passenger cars and light-duty trucks and established a new more stringent super ultra-low emission vehicle (SULEV) standard. In addition, a partial zero-emission vehicle (PZEV) category was established for vehicles meeting the SULEV emission standard that also included extended 150,000-mile durability, zero fuel evaporative emissions, and extended emission warranty requirements. PZEVs could be used to meet a portion of the zero-emission vehicle requirement. The amendments also expanded the light-duty truck category to include trucks and SUVs up to 8,500 lbs. gross vehicle weight rating (GVWR) and required these vehicles to meet the same emission standards as passenger cars, and extended full useful life from 100,000 miles to 120,000 miles. The LEV II amendments also established more stringent emission standards for medium-duty vehicles (MDVs) between 8,501-14,000 lbs. GVW.

Greenhouse Gas Emissions

Recognizing the increasing threat of climate change to the well-being of California's citizens and the environment, in 2002 the legislature adopted and the Governor signed AB 1493 (Chapter 200, Statutes 2002, Pavley). AB 1493 directed ARB to adopt the maximum feasible and cost-effective reductions in GHG emissions from light-duty vehicles. Vehicle GHG emissions included carbon dioxide (CO_2), methane (CH_4), and nitrous oxide (N_2O) that are emitted from the tailpipe, as well as emissions of HFC134a,

the refrigerant currently used in most vehicle air conditioning systems. Table ES-1 below lists the global warming potential of these GHGs.

Table ES-1. Numerical Estimates Of Global Warming Potentials Compared With CO_2 (Kilograms Of Gas Per Kilogram Of CO_2 -- Adapted From IPCC 2007c[1])

Climate Pollutants	Lifetime (years)	Global Warming Potential		
		20 years	100 years	500 years
CO_2	~150	1	1	1
CH_4	12	72	25	7.6
N_2O	114	289	298	153
HFC134a	14	3830	1300	435

As directed by AB 1493, ARB adopted what is commonly referred to as the Pavley regulations, the first in the nation to require significant reductions of GHGs from motor vehicles. These regulations, covering the 2009-2016 and later model years, call for a 17% overall reduction in climate change emissions from the light-duty fleet by 2020 and a 25% overall reduction by 2030. They also formed the foundation for the federal GHG program for light-duty vehicles for 2012-2016 model years.

After the Board adopted the Pavley regulations, the legislature adopted and the Governor signed AB 32, the California Global Warming Solutions Act (Chapter 488, Statutes 2006, Nuñez/Pavley). AB 32 charges ARB with the responsibility of monitoring and regulating GHG emissions in the State. AB 32 also directed ARB to prepare a Scoping Plan outlining the State's strategy to achieve the maximum feasible and cost-effective reductions in furtherance of reducing GHG emissions to 1990 levels by 2020. Measure T1 of the Scoping Plan anticipates an additional 3.8 million metric tons carbon dioxide equivalent ($MMTCO_2e$) reduction by 2020 beyond the reductions from the 2009-2016 AB 1493 standards.

In addition, in 2005, in order to mitigate the long-term impacts of climate change, the Governor issued Executive Order S-3-05. Among other actions, the Executive Order called for reducing GHG emissions to 80 percent below 1990 levels by 2050. This ambitious yet achievable reduction path and goal are considered necessary to stabilize the long-term climate.

ZEV Program

Although originally part of the LEV program, in 1999, in recognition of the increasing maturity of zero emission technologies and the critical role they can play in achieving California's air quality goals, ARB established the ZEV program as a stand-alone one. Since then, the program has been modified several times to address the pace of development of zero emission technologies.

[1] IPCC 2007c: Working Group I: The Physical Science Basis, Chapter 2: Changes in Atmospheric Constituents and in Radiative Forcing, available at http://www.ipcc.ch/pdf/assessment-report/ar4/wg1/ar4-wg1-chapter2.pdf

At its March 2008 hearing, the Board directed staff to redesign the 2015 and later model year ZEV program by strengthening the requirement and focusing primarily on zero emission technologies – battery electric vehicles, hydrogen fuel cell vehicles, and plug-in hybrid electric vehicles – in order to ensure that these low GHG technology vehicles transition from the demonstration phase to full commercialization in a reasonable timeframe. The resulting proposed amendments to the ZEV program are presented in a separate staff report, also part of this comprehensive vehicle rulemaking package, the Advanced Clean Cars program.

Advanced Clean Cars Program

Continuing its leadership role in the development of innovative and ground breaking emission control programs and to achieve California's goals of meeting ambient air quality standards and reducing climate changing GHG emissions, ARB staff has developed the Advanced Clean Cars (ACC) program. The Advanced Clean Cars program combines the control of smog-causing pollutants and greenhouse gas emissions into a single coordinated package of requirements for model years 2015 through 2025 and assures the development of environmentally superior cars that will continue to deliver the performance, utility, and safety vehicle owners have come to expect. The ZEV program will act as the focused technology-forcing piece of the Advanced Clean Cars program by requiring manufacturers to produce increasing numbers of pure ZEVs and plug-in hybrid electric vehicles in the 2018-2025 model years. In addition, the Advanced Clean Cars program includes amendments to the Clean Fuels Outlet regulation that will assure ultra-clean fuels such as hydrogen are available to meet vehicle demands brought on by these amendments to the ZEV program.

Beyond 2025, the dominant force for lowering emissions from vehicles in California will be climate change. In order to meet our 2050 GHG goal, the new vehicle feet will need to be primarily composed of advanced technology vehicles such as electric and fuel cell vehicles by 2035 in order to have nearly an entire new and used advanced technology fleet by 2050. Accordingly, the Advanced Clean Cars program coordinates the goals of the LEV, ZEV, and Clean Fuels Outlet programs in order to lay the foundation for the commercialization and support of these ultra-clean vehicles.

Figure ES-1 shows the cumulative on-road passenger vehicle fleet mix for one scenario developed by staff that achieves California's 2050 GHG emission reduction goal. Importantly, ZEV sales must constitute nearly 100% of new vehicles in 2040 for ZEVs to constitute approximately 87% of the on-road fleet by 2050.

Figure ES-1. On Road Light-Duty Vehicle Scenario to Reach 2050 Goal



Criteria Emission Standards and New Certification Fuel Requirements

In order to achieve further criteria emission reductions from the passenger vehicle fleet, staff is proposing several amendments representing a significant strengthening of the LEV program. The major elements of the proposed LEV III program are:

- A reduction of fleet average emissions of new passenger cars (PCs), light-duty trucks (LDTs) and medium-duty passenger vehicles (MDPVs) to super ultra-low-emission vehicle (SULEV) levels by 2025;
- Replacement of separate NMOG and oxides of nitrogen (NOx) standards with combined NMOG plus NOx standards, which provides automobile manufacturers with additional flexibility in meeting the new stringent standards;
- An increase of full useful life durability requirements from 120,000 miles to 150,000 miles, which guarantees vehicles operate longer at these extremely low emission levels;
- A backstop to assure continued production of super-ultra-low-emission vehicles after PZEVs as a category are moved from the Zero-Emission Vehicle program to the LEV program in 2018;
- More stringent particulate matter (PM) standards for light- and medium-duty vehicles, which will reduce the health effects and premature deaths associated with these emissions;

- Zero fuel evaporative emission standards for PCs and LDTs, and more stringent evaporative standards for medium- and heavy-duty vehicles (MDVs);
- More stringent supplemental federal test procedure (SFTP) standards for PC and LDTs, which reflect more aggressive real world driving and, for the first time, require MDVs to meet SFTP standards.

Table ES-2 below lists the proposed fleet average NMOG plus NOx requirements for PCs, LDTs, and MDPVs for model years 2015-2025.

Table ES-2. Fleet Average NMOG Plus NOx Exhaust Emission Requirements for Light-Duty Vehicles (150,000 mile Durability Basis)

Model Year	Fleet Average NMOG plus NOx (grams per mile)	
	All PCs; LDT1s	LDT2s; MDPV
2015	0.100	0.119
2016	0.093	0.110
2017	0.086	0.101
2018	0.079	0.092
2019	0.072	0.083
2020	0.065	0.074
2021	0.058	0.065
2022	0.051	0.056
2023	0.044	0.047
2024	0.037	0.038
2025	0.030	0.030

Staff is also proposing three additional light-duty vehicle emission standards (ULEV70, ULEV50, and SULEV20) to which manufacturers may certify their vehicles when meeting the fleet average emission requirement. The numerical part of the standard category, such as 20 in SULEV20, refers to the emission standard, in thousandths of a gram per mile. Combined with an extended fleet average emission requirement phase-in period, providing these additional emission standards will allow manufacturers to phase-in additional emission componentry across their fleet in a cost-effective manner.

Current California certification gasoline contains methyl tertiary butyl ether (MTBE) as an oxygenate, reflecting commercial gasoline sold prior to 2003 and as such does not represent gasoline currently sold in California, which does not contain MTBE. The current maximum ethanol content allowed in commercial gasoline is 10 percent by volume and is expected to remain at 10 percent for the foreseeable future. Accordingly, staff is proposing to change the certification fuel specifications to be more representative of current in-use fuel. Staff is also proposing that vehicles certify on a fuel that reflects the octane requirement that they are operated on in-use. Therefore, for vehicles that consumers must operate on premium fuel to maintain warranty coverage,

manufacturers may certify on premium grade fuel, while all others must certify on regular grade fuel.

Greenhouse Gas Emission Standards

The proposed GHG emission standards would reduce new passenger vehicle carbon dioxide (CO_2) emissions from their model year 2016 levels by approximately 34% by model year 2025, from about 251 to about 166 gCO_2/mile, based on the projected mix of vehicles sold in California. The basic structure of the standards includes two categories – passenger cars and light-duty trucks – that are consistent with federal categories for light-duty vehicles. The standard targets would reduce car CO_2 emissions by about 36% and truck CO_2 emissions by about 32% from model year 2016 through 2025. Figure ES-2 illustrates the basic target emission trends that are projected from the car and truck standards.

For the 2017-2025 model year standards, ARB proposes to use the United States Environmental Protection Agency (USEPA) approach and adopt separate standards for CO_2, CH_4, and N_2O.

Figure ES-2. Target Emission Reductions from GHG Standards



Table ES-3 shows the year-by-year new vehicle CO_2 reductions that are projected as a result of the standards from cars, light-duty trucks, and combined light-duty vehicles. The projected result overall from 2016-2025 from these standards is to reduce car CO_2 emissions by approximately 4.9%/year, reduce truck CO_2 emissions by approximately 4.1%/year, and reduce combined light-duty CO_2 emissions by approximately 4.5%/year from 2016 through 2025. These CO_2 emission reduction estimations are approximate because the required emission level to achieve compliance with the standards for each vehicle manufacturer depends on their ultimate sales mix of vehicles.

Table ES-3. Projected Targets for Light-Duty Vehicle gCO_2/mile Emission Rates

	Model year	Car		Truck		Combined light-duty	
		gCO_2/mi	Annual change	gCO_2/mi	Annual change	gCO_2/mi	Annual change
Baseline	2008	291		396		336	
Previous Rule Targets	2013	256	2.8%	330	2.8%	283	2.6%
	2014	248	3.3%	321	2.8%	275	2.8%
	2015	236	4.5%	306	4.5%	263	4.3%
	2016	226	4.5%	292	4.5%	251	4.4%
Proposed Rulemaking Targets	2017	213	5.5%	290	0.7%	243	3.2%
	2018	203	4.9%	280	3.5%	233	4.2%
	2019	192	5.2%	273	2.8%	224	4.0%
	2020	183	4.9%	264	3.0%	215	3.9%
	2021	173	5.5%	245	7.5%	201	6.3%
	2022	165	4.4%	233	4.9%	192	4.6%
	2023	158	4.5%	221	4.9%	183	4.8%
	2024	151	4.5%	210	5.0%	174	4.8%
	2025	144	4.6%	200	4.9%	166	4.8%
Average change, (2016-2025)			4.9%		4.1%		4.5%
Change, 2008-2016		-23%		-26%		-25%	
Change, 2016-2025		-36%		-32%		-34%	
Change, 2008-2025		-51%		-50%		-51%	

Notes: Car, truck, overall targets shown are based on projected sales of vehicles by footprint, category (ultimate gCO_2/mile levels are determined by end-of-year sales); the original California GHG standards for model years 2009-2011 are based on a different two-category system (PC/LDT1 and LDT2) than the car and truck system of the 2012-2016 federal standards and proposed 2017-2025 standards; Difference of individual columns may not match due to rounding.

The already low CH_4 and N_2O standards will reflect the same stringency as the prior GHG standards. The net result is that, like the current 2009-2016 California GHG standards, the proposed 2017-2025 standards account for all major sources of vehicle GHG emissions, including upstream emissions associated with vehicle fuels. In addition, California is proposing to align its vehicle air conditioning system requirements with federal requirements.

Maximum Feasible and Cost-Effective Technologies

Vehicle manufacturers need sufficient lead-time to implement new technologies across their vehicle lines both from a feasibility and cost-effectiveness standpoint. Manufacturers will be resource challenged over the next 15 years as they strive to develop and implement technologies ranging from advanced gasoline and diesel engines to electric and fuel cell vehicles, while at the same time lowering criteria emissions of their combustion engines. The phase-in of the Advanced Clean Cars program requirements recognizes this by providing manufacturers with significant lead-time and considerable compliance flexibility.

Criteria Emissions

The technology for controlling vehicle emissions is well understood and manufacturers have a wide range of emission control technologies available to achieve SULEV emissions. Many of these technologies are already being used today on vehicles

meeting LEV II requirements and staff anticipates that with ongoing improvements to the effectiveness of these technologies, particularly catalyst technology, manufacturers will be able to meet the proposed LEV III requirements. For some vehicles, specifically the heavier vehicles with larger displacement engines, additional emission control componentry such as secondary air and hydrocarbon adsorbers may be required to achieve the proposed emission levels.

Greenhouse Gas Emissions

The proposed GHG standards are also predicated on many existing and emerging technologies that increase engine and transmission efficiency, reduce vehicle energy loads, improve auxiliary and accessory efficiency, and that recognize increasingly electrified vehicle subsystems with hybrid and electric drivetrains. The previous rulemakings (i.e., California's 2009-2016 and federal 2012-2016 standards) established an original technical basis for the proposed GHG standards. This rulemaking builds on this existing technical foundation with new technical data and understanding of evolving state-of-the-art engine, transmission, hybrid, and electric-drive technologies. As part of this effort, and without conceding any of California's separate authority, staff has been working with the USEPA and the National Highway Transportation Safety Administration (NHTSA) since early last year to develop a unified national GHG program for motor vehicles beyond 2016 that will also meet California's GHG goals.

Environmental Impacts

Criteria Emissions

Table ES-4, Table ES-5, and Table ES-6 provide the emission benefits for calendar years 2023, 2025, and 2035 for reactive organic gas (ROG), oxides of nitrogen (NOx), and particulate matter (PM2.5) respectively. Emission benefits are nearly fully realized in the 2035-2040 timeframe when most vehicles operating in the fleet are expected to be compliant with the proposed Advanced Clean Car standards. By 2035 ROG statewide emissions would be reduced by an additional 34 percent, NOx emissions by an additional 37 percent, and PM2.5 emissions by 10 percent.

Table ES-4. Statewide and Regional Emission Benefits of the Advanced Clean Car Program: Reactive Organic Gas (ROG)

Statewide ROG (tons/day)				
Calendar Year	Adjusted Baseline with Rebound	Proposed Regulation with Rebound	Benefits	Percent Reduction
2023	189.6	182.9	6.6	3%
2025	175.5	164.4	11.1	6%
2035	141.1	93.6	47.4	34%

Table ES-5. Statewide Emission Benefits of the Advanced Clean Car Program: Oxides of Nitrogen (NOx)

Statewide NOx (tons/day)				
Calendar Year	Adjusted Baseline with Rebound	Proposed Regulation with Rebound	Benefits	Percent Reduction
2023	201.3	185.6	15.7	8%
2025	183.6	161.2	22.4	12%
2035	136.8	86.4	50.4	37%

Table ES-6. Statewide and Regional Emission Benefits of the Advanced Clean Car Program: Particulate Matter (PM2.5)

Statewide PM2.5 (tons/day)				
Calendar Year	Adjusted Baseline with Rebound	Proposed Regulation with Rebound	Benefits	Percent Reduction
2023	26.7	26.0	0.6	2%
2025	27.2	26.3	0.9	3%
2035	29.7	26.8	2.9	10%

Staff used EMFAC 2011 to estimate the environmental benefits of the Advanced Clean Cars program. Staff's analysis concluded that because the operating costs of vehicles meeting the GHG standards will decrease, vehicle use may increase. This effect is known as the rebound effect. When rebound rates were included in the inventory, there were negligibly (approximately one percent) fewer emission reductions compared to the substantial overall emission reductions expected from the Advanced Clean Car regulations package.

Greenhouse Gas Emissions

The Advanced Clean Cars program would provide major reductions in greenhouse gas emissions. Table ES-7 shows the greenhouse gas emission benefits in 2020, 2025, 2035, and 2050. By 2025, CO_2 equivalent emissions would be reduced by almost 14 Million Metric Tons (MMT) per year, which is 12 percent from baseline levels. The reduction increases in 2035 to 32 MMT/Year, a 27 percent reduction from baseline levels. By 2050, the proposed regulation will reduce emissions by more than 42 MMT/Year, a reduction of 33 percent from baseline levels. Viewed cumulatively from 2017 through 2050, the proposed Advanced Clean Cars regulation would reduce emissions by more than 870 MMT CO_2 Equivalent.

Table ES-7. CO_2-Equivalent (CO_2e) Emission Benefits from Advanced Clean Car Regulations

Statewide CO_2e Emissions (Million Metric Tons / Year)				
Calendar Year	Adjusted Baseline with Rebound	Proposed Regulation with Rebound	Benefits	Percent Reduction
2020	111.2	108.1	3.1	3%
2025	109.9	96.3	13.7	12%
2035	114.8	83.2	31.5	27%
2050	131.0	88.3	42.7	33%

Cost Effectiveness

Criteria Emissions

Staff based its cost-effectiveness analysis on the projected increase in vehicle price assuming all new vehicles meet the SULEV emission standard in 2025. Based on the 2008 fleet, staff determined that the average incremental retail costs for light-duty LEV III vehicles in 2025 are as shown in Table ES-8.

Table ES-8. Incremental vehicle price increase for 2025 criteria pollutant standard compliance

Vehicle Category	Initial baseline certification level	Engine size			Average incremental price ($/vehicle)	Average incremental price ($/vehicle)
		4-cyl	6-cyl	8-cyl		
PC/LDT1	LEV	$87	$142	$248	$130	$55
	ULEV	$50	$83	$161	$68	
	SULEV	$0	$0	$0	$0	
LDT2	LEV	$87	$142	$248	$159	$117
	ULEV	$50	$83	$161	$111	
	SULEV	$0	$0	$0	$0	

The analysis concluded that the average cost-effectiveness of light-duty vehicles meeting the LEV III program exhaust requirements relative to the 2008 fleet is approximately $4.00 per pound of NMOG + NOx reduced. Staff also concluded that, since the proposed PM standards would be met by engine modifications during the normal course of engine development, no incremental increase in vehicle price would occur as a result. This cost estimate is likely conservative because the 2008 fleet average emission requirement is less stringent than the 2010 fleet average emission requirement when LEV II is fully phased-in. In addition, the 2025 fleet is projected to include a greater portion of downsized four and six cylinder engines that incur the lower costs to meet SULEV emissions. Stationary source controls can range up to $10 per pound of emissions reduced.

Greenhouse Gas Emissions

Many of the technologies that reduce climate change emissions will also reduce the operating costs of light-duty vehicles. Estimates of the average reduction in operating cost of the new vehicles range from about 4 percent for MY2017 vehicles to over 25 percent for MY2025 vehicles. Based on these expected operating cost reductions and projected gasoline prices, estimates of annual operating cost savings from 2015 through 2030 are provided in Table ES-9. As shown, for every dollar spent, the regulation could save consumers about $3, for a cost-effectiveness in 2025 of $290 in savings per ton of CO_2e reduction. These savings include the expenditures on electricity and hydrogen associated with operating the greater volume of ZEVs being proposed; in the absence of the proposed ZEV requirements, the savings and cost effectiveness would be greater. Overall, purchasers of new vehicles in 2017 and beyond would experience a significant reduction in their operating cost as a result of the proposed regulation.

Table ES-9. Estimates of Total Annual Value of New Vehicle Operating Cost Savings for Advanced Clean Cars (millions of 2009 Dollars)

Year	Cumulative Annualized Incremental Cost	Operating Cost Savings	Saving to Cost Ratio
2015	$1	$0	0.0
2016	$4	$0	0.0
2017	$33	$228	7.0
2018	$100	$487	4.9
2019	$225	$915	4.1
2020	$392	$1,438	3.7
2021	$609	$2,092	3.4
2022	$868	$2,918	3.4
2023	$1,163	$3,751	3.2
2024	$1,495	$4,671	3.1
2025	$1,827	$5,755	3.1
2026	$2,153	$6,846	3.2
2027	$2,475	$7,843	3.2
2028	$2,796	$8,803	3.1
2029	$3,114	$9,709	3.1
2030	$3,430	$10,630	3.1

Note: Operating cost savings are weighted to include costs for electricity and hydrogen for fueling zero-emission vehicles.

Economic Impacts

The greenhouse gas element of the Advanced Clean Cars program may impact several sectors of the economy. The steps that manufacturers will need to take to comply with the Advanced Clean Cars program are expected to result in price increases for new vehicles, while also leading to reduced operating costs, resulting in both positive and

negative impacts on California businesses and consumers. Any vehicle price increase will be borne by purchasers and may negatively affect businesses. However, the operating cost savings from the use of more efficient vehicles will positively impact consumers and most businesses. Based on staff's analysis, the net effect of the program on the economy is expected to be small but positive. Tables ES-10, ES-11, and ES-12 below show that overall, the benefits to California's economy increase over time as cleaner, more efficient vehicles transition into the vehicle fleet.

Table ES-10. Economic Impacts of the Proposed Advanced Clean Cars (ACC) Regulations on the California Economy in Fiscal Year 2020 (2009 dollars)

California Economy	Without ACC Regulations	With ACC Regulations	Difference	% of Total
Output (billions)	$3,600	$3,602	$2	0.1
Personal Income (billions)	$2,171	$2,172	$1	0.0
Employment (thousands)	17,913	17,919	6	0.0

Note: Difference of individual columns may not match due to rounding.

Table ES-11. Economic Impacts of the Proposed Advanced Clean Cars Regulations on the California Economy in Fiscal Year 2025 (2009 dollars)

California Economy	Without ACC Regulations	With ACC Regulations	Difference	% of Total
Output (billion)	$4,170	$4,178	$8	0.2
Personal Income (billion)	$2,525	$2,528	$3	0.1
Employment (thousands)	18,966	18,987	21	0.1

Note: Difference of individual columns may not match due to rounding.

Table ES-12. Economic Impacts of the Proposed Advanced Clean Cars Regulations on the California Economy in Fiscal Year 2030 (2009 dollars)

California Economy	Without ACC Regulations	With ACC Regulations	Difference	% of Total
Output (billions)	$4,881	$4,895	$14	0.3
Personal Income (billions)	$2,962	$2,968	$6	0.2
Employment (thousands)	20,179	20,216	37	0.2

Note: Difference of individual columns may not match due to rounding.

Impacts on Low Income and Minority Communities

ARB has made the consideration of environmental justice an integral part of its activities. Accordingly, staff evaluated the economic effects of the Advanced Clean Cars program on low-income households. For those households who purchase new vehicles, the economic effects of the regulations would be no different than on any other consumer. However, because residents in low-income communities tend to purchase used vehicles at a higher rate than residents in middle and high income communities,

staff evaluated the effects of the program on the used vehicle market and, more specifically, on low-income households that purchase used vehicles.

Staff concluded that, while the Advanced Clean Cars program will cause vehicle prices to increase, like other consumers, low-income consumers will see a significant reduction in vehicle operating costs. The fuel savings from more efficient used vehicles far outweigh the annualized cost of purchasing the vehicle (price increase spread over the years of ownership). Therefore, while purchase prices for used cars will increase by a small percentage of income, any increase in price will be more than offset by the operating cost savings. Tables ES-13 and ES-14 below show that whether purchasing new or 10-year-old used model year 2025 vehicles, the consumer will experience a net monthly savings from the program.

Table ES-13. Potential Impact on Monthly Loan Payment and Operating Cost Savings for New 2025 MY Vehicles (2009 dollars)

Description	Advanced Clean cars Program
Average Increase in New Vehicle Price	$1,900
Increase in Monthly Loan Payment	$35
Net Lifetime Savings	$4,000
Monthly Operating Cost Savings	$48
Net Monthly Savings	$12
Payback Period (Years)	2.9

Note: Difference of individual columns may not match due to rounding.

Table ES-14. Potential Impact on Monthly Loan Payment and Operating Cost Savings for Used 2025 Vehicles (2009 dollars)

Description	Advanced Clean Cars Program
Increase in Used 2025 MY Vehicle Price in 2035	$440
Increase in Monthly Loan Payment	$14
Net Lifetime Savings	$2,000
Monthly Operating Cost Savings	$36
Net Monthly Savings	$22
Payback Period (Years)	0.9

Public Process for LEV III Criteria and Greenhouse Gas Regulation Development

To support development of the Advanced Clean Cars program, beginning in March 2010, ARB staff held five public workshops to engage stakeholders and obtain input on the proposed regulations. These stakeholders primarily included representatives from Original Equipment Manufacturers (OEMs) and vehicle component suppliers.

These workshops were held at ARB offices in El Monte. The announcements and materials for these workshops were posted on ARB's website and distributed through a list serve that included over 1,500 recipients. Each workshop attracted just over 50 attendees in person. Almost all of the meetings were either telecast, webcast or available by teleconference. The dates and materials presented at the workshops are available on ARB's LEV III website at http://www.arb.ca.gov/msprog/levprog/leviii/leviii.htm.

ARB staff has also participated in dozens of individual meetings with vehicle manufacturers and vehicle component suppliers to discuss the fiscal and technical challenges presented by the proposed Advanced Clean Cars program. For the majority of the meetings concerning GHG technologies staff participated jointly with USEPA and NHTSA.

Vehicle Labeling Requirements

Starting in the Spring of 2010, ARB staff began working with USEPA and NHTSA on a new national Fuel Economy Label. Such a label could be used in lieu of the California Environmental Performance label that California has required for over a decade. As a result, important California requirements are now addressed by the federal label. These included:

- Adding the following statement to the label: "Vehicle emissions are a significant cause of climate change and smog"
- Having a clear statement about upstream emissions and having a clear place to find this information on a regional basis.
- Including all cars in the rating system rather than segregating by size or class.

Because of this successful collaboration California is able to harmonize with the federal labeling requirements.

On-Board Diagnostics Amendments

Staff is also proposing changes to the On-Board Diagnostics II (OBD II) regulations. Staff was not scheduled to go to the Board this year to update the OBD II regulation; however, manufacturers recently approached ARB staff and requested regulation changes that they indicated were needed immediately in order to ensure compliance when they certify their 2013 model year vehicles. The proposed amendments to the OBD II regulation would include relaxation of a few requirements (e.g., delays to the required start dates) in recognition of delays in technology development. Additionally, manufacturers have requested that ARB staff propose clarifications to a few requirements in the current OBD II regulations, including those that address hybrid vehicles. ARB staff has already discussed the proposed amendments with hybrid manufacturers and have come to an agreement regarding these changes, which would consist of only minor software changes.

Other Considerations

Vehicle manufacturers have urged ARB to harmonize the requirements of LEV III with the federal Tier 3 program currently under development, which is expected to be finalized in mid-2012. While staff has worked with USEPA in an effort to align many of the requirements of the two programs, some elements of the proposed LEV III program are expected to remain more stringent than the federal program in order to address California's unique air pollution problems. Nonetheless, staff believes that manufacturers will be able to certify their vehicles to both California and federal requirements when both programs are in effect.

Similarly, in response to an invitation by President Obama, ARB worked closely with USEPA and NHTSA on the development of national GHG and fuel economy requirements for 2017-2025. The footprint-indexed CO_2 standard target lines for 2017-2025 were examined jointly by the three agencies in order to address the agencies' regulatory requirements regarding technical feasibility and cost-effectiveness. While the proposed CO_2e standards for 2017-2025 reflect the same level of technical stringency for conventional vehicles staff anticipates will be adopted by USEPA in their final rulemaking, the GHG element of California's Advanced Clean Cars program remains distinctive from the federal program because of its focus on California's long-term GHG goals. By including specific ZEV requirements, the Advanced Clean Cars program lays the foundation to transform California's light-duty fleet by ensuring that ultra clean vehicles meeting consumer expectations will be commercially available in the timeframe needed to achieve critical GHG reductions by 2050.

Staff Recommendation

ARB staff recommends that the Board adopt the LEV III regulation as proposed in this Initial Statement of Reasons. The proposed regulation is intended to achieve the maximum feasible and cost effective reduction of criteria and GHG emissions from new motor vehicles.

Table of Contents

I. INTRODUCTION 1

A. OVERVIEW OF THE REGULATION 1

B. ORGANIZATION OF THE REPORT 2

II. CALIFORNIA'S LOW-EMISSION VEHICLE CRITERIA POLLUTANT EMISSION REGULATIONS 3

A. PROPOSED AMENDMENTS TO CALIFORNIA'S LOW-EMISSION VEHICLE EXHAUST EMISSION STANDARDS (LEV III) 3

1. BACKGROUND 3

2. SUMMARY OF PROPOSED AMENDMENTS 4

3. TECHNOLOGICAL FEASIBILITY OF PROPOSED STANDARDS 29

4. COST ANALYSIS 37

5. OUTSTANDING ISSUES 42

6. REGULATORY ALTERNATIVES TO EXHAUST CRITERIA POLLUTANT EMISSION PROPOSAL 42

B. CALIFORNIA'S EVAPORATIVE EMISSION REGULATIONS 43

1. BACKGROUND 43

2. SUMMARY OF PROPOSED AMENDMENTS 46

3. TECHNOLOGICAL FEASIBILITY OF PROPOSED STANDARDS 52

4. COST ANALYSIS 55

5. OUTSTANDING ISSUES 56

6. REGULATORY ALTERNATIVES TO EVAPORATIVE EMISSION PROPOSAL 58

C. VEHICLE LABELING REQUIREMENTS 59

1. BACKGROUND 59

2. SUMMARY OF PROPOSED REGULATION 61

3. COST ANALYSIS 61

D. MINOR AMENDMENTS TO THE ON-BOARD DIAGNOSTICS REGULATIONS 61

1. BACKGROUND 61

2. SUMMARY OF PROPOSED AMENDMENTS 62

3. COST ANALYSIS 72

III. CALIFORNIA'S LIGHT-DUTY GREENHOUSE GAS REGULATIONS 73

A. PROPOSED AMENDMENTS TO CALIFORNIA'S LIGHT-DUTY GREENHOUSE GAS EMISSION STANDARDS 73

1. CLIMATE CHANGE OVERVIEW 73
2. NATIONAL GREENHOUSE GAS PROGRAM DEVELOPMENT 97
3. SUMMARY OF PROPOSED REGULATION 97
4. TECHNOLOGICAL FEASIBILITY OF PROPOSED STANDARDS 101
5. CLIMATE CHANGE EMISSION STANDARDS 126
IV. CERTIFICATION GASOLINE SPECIFICATIONS 164
A. PROPOSED AMENDMENTS TO THE SPECIFICATIONS FOR CALIFORNIA CERTIFICATION GASOLINE 164
1. BACKGROUND 164
2. SUMMARY OF PROPOSED REGULATION 166
3. ALTERNATIVES TO THE PROPOSED E10 CERTIFICATION FUEL 171
V. EMISSIONS IMPACTS 171
A. OVERVIEW OF EMISSIONS INVENTORY METHODS 171
B. ASSESSING BENEFITS OF THE PROPOSED REGULATIONS 173
C. ASSESSING THE IMPACT OF THE REBOUND EFFECT 173
D. EMISSION BENEFITS OF THE PROPOSED ADVANCED CLEAN CARS PROGRAM 174
E. FUEL CYCLE EMISSIONS 178
F. HEALTH BENEFITS ASSOCIATED WITH REDUCTIONS IN PM AND NOx EMISSIONS FROM PASSENGER VEHICLES RESULTING FROM IMPLEMENTATION OF THE LEV III AND ZEV PROGRAMS 185
1. OVERVIEW 185
2. PREMATURE DEATH ESTIMATION METHODOLOGY 186
VI. ENVIRONMENTAL IMPACTS ANALYSIS 190
VII. ECONOMIC IMPACTS 191
A. LEGAL REQUIREMENTS 191
B. SUMMARY OF COMPLIANCE COST ESTIMATES 192
C. POTENTIAL IMPACTS ON BUSINESS CREATION, ELIMINATION, OR EXPANSION 197
1. ENVIRONMENTAL-DYNAMIC REVENUE ANALYSIS MODEL (E-DRAM) 198
2. AFFILIATED BUSINESSES 201
3. ECONOMIC IMPACTS OUTSIDE OF CALIFORNIA 202
D. POTENTIAL IMPACT ON CALIFORNIA BUSINESS COMPETITIVENESS 203
E. ANCILLARY BENEFITS 203

1. SOCIAL COST OF CARBON 203
2. ADDITIONAL ANCILLIARY BENEFITS 207
F. POTENTIAL COSTS TO LOCAL AND STATE AGENCIES 208
G. POTENTIAL IMPACT ON MONTHLY LOAN PAYMENT AND OPERATING SAVINGS FOR NEW VEHICLES 209
H. JUSTIFICATION FOR ADOPTING REGULATIONS DIFFERENT FROM FEDERAL REGULATIONS 210
I. CONCLUSION 210
VIII. IMPACTS ON MINORITY AND LOW-INCOME COMMUNITIES 211
A. ARB ENVIRONMENTAL JUSTICE POLICY 211
1. AB 1493 REQUIREMENTS 211
2. AB 32 REQUIREMENTS 212
3. OUTREACH TO MINORITY AND LOW-INCOME COMMUNITIES 212
B. POTENTIAL ENVIRONMENTAL IMPACTS 213
C. POTENTIAL ECONOMIC IMPACTS 213
1. POTENTIAL IMPACT ON A TYPICAL LOW-INCOME HOUSEHOLD 213
2. APPROACH 214
3. ASSUMPTIONS 214
4. RESULTS 215
5. ECONOMIC IMPACT ASSESSMENT ON AFFILIATED BUSINESSES IN LOW-INCOME CITIES OF CALIFORNIA 218
IX. OTHER CONSIDERATIONS 220
A. CONSUMER RESPONSE EFFECTS ON EMISSIONS AND STATE ECONOMY 220
1. BACKGROUND 220
2. IMPACTS ON VEHICLE PRICES AND OPERATING COSTS 221
3. IMPACTS ON VEHICLE SALES, FLEET SIZE, AND AVERAGE AGE 224
4. IMPACTS ON CRITERIA EMISSIONS 227
B. ALTERNATIVE APPROACH TO ASSESSING CONSUMER RESPONSE 229
C. ENERGY COST AND DEMAND FOR NEW VEHICLES 231
D. MANUFACTURER RESPONSE TO INCREASED VEHICLE PRICES 234
E. EFFECT OF INCREASED FUEL PRICE 235
F. SUMMARY AND CONCLUSIONS 236
X. SUMMARY AND STAFF RECOMMENDATION 236
A. SUMMARY OF STAFF PROPOSAL 236

B. STAFF RECOMMENDATION....237
LIST OF ACRONYMS AND ABBREVIATIONS....238
REFERENCES....242
APPENDICES....252

I. INTRODUCTION

Vehicle manufacturers have made remarkable progress in the last two decades in achieving increasingly stringent emission requirements. Conventional vehicles meeting ARB's most stringent emission standards have achieved emission levels that seemed impossible when the Low-Emission Vehicle (LEV) program was adopted in 1990. However, despite significant progress in reducing criteria emissions from the vehicle fleet, health-based State and federal ambient air quality standards continue to be exceeded in regions throughout California.

To achieve the 1997 ozone standard by the attainment date in 2023, NOx emissions in the greater Los Angeles region must be reduced by two thirds, even after considering all of the control measures in place today. In the San Joaquin Valley, the 2007 State Implementation Plan identified the need to reduce oxides of nitrogen emissions by 80 tons per day in 2023 through the use of long-term and advanced technology strategies. To put this in context, this is equivalent to eliminating the NOx emissions from all on-road vehicles operating in these regions. Furthermore, California's growing population and increasing use of motor vehicles will continue to exert upward pressure on statewide emissions.

In addition, climate change continues to pose a serious threat to California. Global warming is projected to have detrimental effects on some of California's largest industries (including agriculture and tourism), increase the strain on electricity supplies, and contribute to unhealthy air. [2,3,4] While significant reductions of vehicle greenhouse gas (GHG) emissions will be achieved by existing requirements of the LEV program, due to increasing vehicle population and vehicle miles traveled, continuing upward pressure beyond 2016 exists for GHG emissions. Furthermore, if we are to address the challenge presented by climate change, vehicle GHG emissions must be drastically reduced beyond current requirements to reach our goal of an 80% reduction from 1990 levels by 2050.

A. OVERVIEW OF THE REGULATION

As the first in the nation to recognize the contribution of motor vehicles to environmental pollution, California has traditionally been a leader in the development of pioneering vehicle emission control programs. Continuing this tradition, and recognizing interrelated technologies reducing both criteria and GHG pollutants, the proposed LEV III regulations build upon the existing LEV program and address both criteria and GHG emissions as part of a whole program. The criteria element of LEV III calls for further reductions in vehicle emissions by requiring the average emissions of new vehicles to be equivalent to super-ultra-low emission (SULEV) levels by 2025. To place that in context, SULEV emission levels represent a reduction from uncontrolled vehicle

[2] CRNA, 2009. California Natural Resources Agency. 2009. "*2009 California Climate Adaptation Strategy*"
[3] UC Berkeley, 2008. University of California, Berkeley. November 2008. "*California Climate Risk and Response*"
[4] ARB 2009a. California Air Resources Board. May 11, 2009 Update. "Climate Change Scoping Plan" http://www.arb.ca.gov/cc/scopingplan/document/scopingplandocument.htm

emissions of greater than 99 percent. Phased-in from 2015-2025, the proposed criteria pollutant emission program provides significant flexibility to manufacturers by providing: 1) an extended phase-in period for manufacturers to incorporate improved emission control systems across their vehicle lines: 2) an array of emission standards to which manufacturers may certify their vehicles, as long as their fleet average emissions meet the declining fleet average requirement: and 3) combined non-methane organic gas (NMOG) plus oxides of nitrogen (NOx) standards, which will enable manufacturers to more cost-effectively tailor their emission control systems.

The GHG element of LEV III essentially continues the LEV II "Pavley" standards ARB developed in 2003-2004 in response to AB 1493, and requires further reductions in vehicle GHG emissions beyond 2016. Phased in from 2017-2025, LEV III differs from the fleet average GHG requirement of the Pavley standards in that it establishes a set of footprint curves for each model year that sets target GHG emissions for each vehicle model depending on its footprint (the area described by wheelbase times the average track width of the vehicle). Similar to the criteria element of LEV III, manufacturers may produce models that emit above the footprint curve as long as their emissions are offset by models that emit below the footprint curve. In essence, the GHG requirements for LEV III are based on the sales weighted fleet average footprint of a manufacturer's model lines and will vary between manufacturers depending on their vehicle model mix. Therefore, the GHG element of LEV III will mirror the structure of planned federal GHG requirements for motor vehicles.

B. ORGANIZATION OF THE REPORT

The report begins with a description of exhaust criteria emission requirements, including the supplemental federal test procedure (SFTP), of the proposed LEV III program (section II.A.). This section also includes a discussion of the technical feasibility of the proposed standards and staff's analysis of the compliance costs for manufacturers. Section II.B continues with a discussion of the proposed evaporative emission requirements and the technical feasibility and costs to achieve the requirements. Section II.C discusses changes to California's Environmental Performance labeling requirements. Specifically discussed in this section is how staff worked with USEPA and NHTSA to ensure that the new federal Fuel Economy and Environmental Label meets California's vehicle labeling requirements. California could thereby move to one national vehicle labeling program to avoid confusion among consumers trying to compare the environmental impacts of vehicles they are considering. Section III addresses the proposed greenhouse gas element of LEV III, starting with a discussion on climate change and its impact on California's economic well-being, public health, natural resources, and environment. The section then describes the proposed GHG requirements for light-duty vehicles and the technology and costs to comply. Section IV discusses changes being proposed to the specifications for California certification fuel that are designed to reflect the composition of current and future in-use gasoline. Section V includes discussion of the emission benefits of the criteria and GHG elements of LEV III, as well as discussions on fuel cycle emissions, health effects, and energy cost and demand. Section VI summarizes the environmental analysis performed in

response to requirements of the California Environmental Quality Act. Section VII describes the economic impacts of the proposed regulations on California businesses, State and local agencies, and individual consumers, while section VIII focuses on the economic impact on minority and low-income communities. Section IX covers other considerations such as the effect of consumer response on emissions and the state economy, alternative approaches to assessing consumer response, effects on vehicle miles traveled, manufacturer response to increases in vehicle prices, and the effect of increased fuel prices.

II. CALIFORNIA'S LOW-EMISSION VEHICLE CRITERIA POLLUTANT EMISSION REGULATIONS

A. PROPOSED AMENDMENTS TO CALIFORNIA'S LOW-EMISSION VEHICLE EXHAUST EMISSION STANDARDS (LEV III)

1. BACKGROUND

In 1999, California adopted the second phase of the Low-Emission Vehicle Program (LEV). These amendments, known as LEV II, set more stringent fleet average non-methane organic gas (NMOG) requirements for model years 2004-2010 for passenger cars and light-duty trucks and established a new more stringent super ultra-low emission vehicle (SULEV) standard. In addition, a partial zero-emission vehicle (PZEV) category was established for vehicles meeting the SULEV emission standard that also included extended 150,000-mile durability, zero fuel evaporative emissions, and extended emission warranty requirements. PZEVs could be used to meet a portion of the zero-emission vehicle requirement. The amendments also expanded the light-duty truck category to include trucks and SUVs up to 8,500 lbs. gross vehicle weight rating (GVWR) and required these vehicles to meet the same emission standards as passenger cars, and extended full useful life from 100,000 miles to 120,000 miles. The LEV II amendments also established more stringent emission standards for medium-duty vehicles (MDVs) between 8,501-14,000 lbs. GVW. Table II-A-1-1 below lists the vehicle classes affected by the LEV program.

Table II-A-1-1. LEV Vehicle Classes

Vehicle Class	Weight Range[5]
Passenger cars	All weights
Light-duty truck 1 (LDT1)	0-3750 lbs. LVW
Light-duty truck 2 (LDT2)	3751 lbs. LVW – 8,500 lbs GVWR
Medium-duty vehicle	8,501-10,000 lbs GVWR
	10,001-14,000 lbs GVWR

[5] There are several classifications for vehicles based on weight. Curb weight is defined as the actual weight of the vehicle. Loaded vehicle weight (LVW) is defined as the curb weight plus 300 pounds. Gross vehicle weight rating (GVWR) is the maximum designed loaded weight of the vehicle; this means curb weight of the vehicle plus full payload.

2. SUMMARY OF PROPOSED AMENDMENTS

In order to achieve further emission reductions from the light- and medium-duty fleet, staff is proposing several amendments together that represent a significant strengthening of the LEV program. The proposed amendments would:

- Reduce fleet average emissions of new light-duty vehicles to super-ultra-low-emission vehicle (SULEV) levels by 2025, an approximate 75 percent reduction;
- Replace separate NMOG and oxides of nitrogen (NOx) standards with combined NMOG plus NOx standards;
- Establish additional emission standard categories to provide additional options for compliance;
- Eliminate intermediate useful life (50,000 miles) standards;
- Increase full useful life durability requirements from 120,000 miles to 150,000 miles;
- Provide a backstop to help ensure continued production of super-ultra-low-emission vehicles after PZEVs migrate from the Zero-Emission Vehicle (ZEV) program to the LEV program in 2018. Without a backstop, beginning in 2018, manufacturers would not need to produce SULEVs until 2023 in order to meet the fleet average requirement;
- Establish more stringent emission requirements for medium-duty vehicles (MDV);
- Require all MDVs between 8,501-10,000 lbs, GVWR to certify on a chassis dynamometer, which would greatly enhance the ability to perform in-use compliance evaluation of these vehicles;
- Establish more stringent particulate matter (PM) standards for light- and medium-duty vehicles;
- Establish more stringent evaporative emission standards for light-, medium-, and heavy-duty vehicles;
- Establish more stringent supplemental federal test procedure (SFTP, reflecting more aggressive driving) standards for light-duty vehicles and, for the first time, require medium-duty vehicles to meet SFTP standards;
- Allow pooled fleet average NMOG plus NOx emissions from California and the federal Clean Air Act Section 177 States that adopt the LEV III program; and
- Revise the Non-Methane Organic Gas Test Procedures.

2.1. Proposed Federal Test Procedure Exhaust Emission Requirements

A complete description of the regulatory amendments is contained in the appendices; a brief summary of each proposed amendment follows here.

2.1.1. Proposed NMOG Plus NOx SULEV Fleet Average Emission Requirement

As mentioned above, staff is proposing that the NMOG fleet average requirement be replaced by a NMOG plus NOx fleet average requirement and be tightened down to SULEV emission levels by 2025. This represents a reduction from the current fleet average NMOG plus NOx emission requirement of approximately 75 percent. Table II-A-2-1 below lists the proposed fleet average requirement for passenger cars, light-duty trucks and medium-duty passenger vehicles (MDPV) for model years 2015-2025.

Table II-A-2-1. Fleet Average NMOG Plus NOx Exhaust Emission Requirements for Light-Duty Vehicles (150,000 mile Durability Basis)

Model Year	Fleet Average NMOG plus NOx (grams per mile)	
	All PCs; LDT1s	LDT2s; MDPV
2015	0.100	0.119
2016	0.093	0.110
2017	0.086	0.101
2018	0.079	0.092
2019	0.072	0.083
2020	0.065	0.074
2021	0.058	0.065
2022	0.051	0.056
2023	0.044	0.047
2024	0.037	0.038
2025	0.030	0.030

Staff based the proposed SULEV level fleet average emission requirement in part on current certification data for vehicles meeting the PZEV emission standard. Vehicles meeting this emission standard represent a significant portion of the new light-duty vehicle fleet currently marketed in California, and certification in the passenger car (PC), light-duty truck 1 (LDT1), and light-duty truck 2 (LDT2) categories confirms feasibility. In addition, manufacturers have indicated that with the application of improved emission control systems they will be able to achieve this emission level across their light-duty fleet. To provide sufficient development time for manufacturers to incorporate improved emission control systems across their fleet, staff is proposing an extended eleven year phase-in from 2015-2025 to meet the SULEV fleet average requirement. This phase-in is also consistent with a similar phase-in of greenhouse gas requirements (2017-2025), also part of this rulemaking, and recognizes that the resources needed to simultaneously comply with multiple requirements are not unlimited.

2.1.2. Combined NMOG Plus NOx Emission Standards

Second, staff is proposing to combine the separate NMOG and NOx emission standards into a single NMOG plus NOx standard. Table II-A-2-2 below includes the proposed LEV III NMOG plus NOx emission standard categories for PCs and LDTs.

Table II-A-2-2. Exhaust Federal Test Procedure Emission Standards for New 2015 and Subsequent Model Year LEV III Passenger Cars and Light-Duty Trucks

LEV III Exhaust Mass Emission Standards for New 2015 and Subsequent Model Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles						
Vehicle Type	**Durability Vehicle Basis (mi)**	**Vehicle Emission Category**	**NMOG + Oxides of Nitrogen (g/ml)**	**Carbon Monoxide (g/mi)**	**Formaldehyde (mg/mi)**	**Particulates (g/mi)**
All PCs; LDTs 8500 lbs. GVWR or less; and MDPVs Vehicles in this category are tested at their loaded vehicle weight	150,000	LEV160	0.160	3.4	4	0.003
		ULEV125	0.125	1.7	4	0.003
		ULEV70	0.070	1.7	4	0.003
		ULEV50	0.050	1.7	4	0.003
		SULEV30	0.030	1.0	4	0.003
		SULEV20	0.020	1.0	4	0.003

Staff recognizes that achieving SULEV emission levels across the light-duty fleet presents a significant challenge to vehicle manufacturers and is therefore proposing several modifications designed to provide significant compliance flexibility without compromising needed emission reductions. First, as noted above, staff is proposing to replace separate NMOG and NOx emission standards with a combined NMOG plus NOx standard. These standards were combined in part because of the challenges achieving SULEV emission levels for larger vehicles. Specifically, achieving the 10 mg/mi SULEV NMOG standard is more problematic for vehicles equipped with larger displacement engines than achieving the 20 mg/mi SULEV NOx standard. So, by providing an opportunity to slightly exceed the existing 10 mg/mi NMOG standard, a combined NMOG plus NOx standard would enable manufacturers to more cost-effectively tailor their emission control systems while still achieving extremely low emission levels across their light-duty fleet. In contrast, though, smaller engines tend to be easier to control for NMOG emissions, but with more stringent GHG standards, these smaller engines will be under higher average loads, making NOx emission reductions comparatively more challenging. From an environmental perspective, staff continues to seek all technically feasible reductions of both NMOG and NOx, and the combined standard approach assures this is accomplished across all models and engine displacements very effectively.

Staff is also proposing three additional light-duty vehicle emission standards (ULEV70, ULEV50, and SULEV20) to which manufacturers may certify their vehicles when meeting the fleet average emission requirement (as with LEV II, compliance is determined by averaging the discrete emission standard achieved for each model sold by the manufacturer, rather than the measured emissions from that model). Combined with an extended fleet average emission requirement phase-in period, providing these additional emission standards will allow manufacturers to phase-in additional emission componentry across their fleet in a more cost-effective manner.

Table II-A-2-3 below presents the phase-in requirements for passenger cars, light-duty trucks, and medium-duty passenger vehicles certifying to the LEV III FTP and SFTP standards.

Table II-A-2-3. LEV III Phase-in Requirements for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles

LEV III FTP and SFTP Phase-In					
Year	**2015**	**2016**	**2017**	**2018**	**2019**
PC/LDT1	10%	20%	40%	70%	100%
LDT2/MDPV	10%	20%	40%	70%	100%

2.1.3. Proposed Interim In-Use Emission Standards for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles

Staff is proposing that during the phase-in period manufacturers would be subject to less stringent in-use compliance standards (for the purpose of determining if a test group is in non-compliance and a possible recall is warranted) for the first two years after a test group is subject to a new, more stringent emission standard. These interim in-use standards would apply only to vehicles certifying to ULEV70 and more stringent emission standards. This provision reduces a manufacturer's risk of recall should emissions in-use turn out to be somewhat higher for a new technology than suggested by development and pre-sale certification testing. Vehicles certifying to PZEV requirements, including vehicles meeting the PZEV backstop provision (see section II.A.2.1.7 below), would not qualify for such interim in-use standards. Accordingly, the proposed interim standards will be applicable to those vehicles certifying to LEV III requirements prior to model year 2019. Table II-A-2-4 below lists the proposed intermediate in-use standards.

Table II-A-2-4. Passenger Car, Light-Duty Truck, and Medium-Duty Passenger Vehicle Interim Federal Test Procedure In-Use Emission Standards

Emission Standard	Interim FTP In-Use Emission Standards NMOG+NOx (g/mi)
ULEV70	0.098
ULEV50	0.070
SULEV30	0.042
SULEV20	0.028

2.1.4. Proposed Elimination of Intermediate Useful Life Standards and Extension of Full Useful Life Standards to 150,000 Miles

Currently, with the exception of the SULEV emission standard, manufacturers are required to demonstrate compliance with an intermediate useful life standard at 50,000 miles and a full useful life standard at 120,000 miles. Staff is proposing to eliminate the intermediate useful life emission standard for all emission standards and retain only the full useful life emission standard. Eliminating the intermediate useful life standards will align compliance requirements with the current SULEV requirement and federal Tier 2 requirements for emission standards for Bin 5 and below for light-duty vehicles. This provision is being implemented in conjunction with a requirement extending full useful life standards from 120,000 miles to 150,000 miles. Extending full useful life durability from 120,000 miles to 150,000 miles would ensure more robust performance of emission control systems and, consequently, lower in-use emissions as vehicles age. Elimination of the intermediate useful life provision is not expected to impact vehicle in-use emission performance.

2.1.5. Proposed NMOG Plus NOx Highway Emission Standards

In order to control NOx emissions at speeds encountered on the highway test cycle, LEV II vehicles must certify to a highway NOx standard equal to 1.33 times the FTP NOx standard. Staff is proposing to carry over this requirement into LEV III. However, because the proposed LEV III emission standards are combined NMOG plus NOx standards, staff is proposing that NMOG plus NOx emissions on the highway emission test cycle not exceed the applicable NMOG plus NOx FTP emission standard. While no increase from FTP emissions is allowed under this approach, the combined NMOG plus NOx highway requirement provides manufacturers with considerable compliance flexibility in meeting this requirement, since current highway NMOG plus NOx emission certification values indicate significant compliance headroom exists for a combined highway emission standard.

2.1.6. Non-Methane Hydrocarbon/Non-Methane Organic Gas Factor

In the current LEV II program, manufacturers are provided the option to apply a factor to their non-methane hydrocarbon (NMHC) emissions when reporting NMOG emissions to demonstrate compliance with the standards. The factor is based on current certification fuel and accounts for the oxygenated hydrocarbon components of the exhaust that are not measured by hydrocarbon instrumentation typically used in vehicle emission test cells. As described in section IV below, current California certification gasoline contains methyl tertiary butyl ether (MTBE) as an oxygenate, reflecting commercial gasoline sold prior to 2003 and as such does not represent gasoline currently sold in California. Therefore, staff is proposing to change gasoline certification fuel specifications to be more representative of current in-use commercial fuel that contains 10 percent ethanol as an oxygenate. Accordingly, staff is proposing a new factor for fuel containing 10 percent ethanol that was derived from emission test results from vehicles operating on E10 from a test program contracted by the federal Department of Energy[6] to support the federal waiver for E15. Based on the data from this study for E10 fuel specifically, a NMHC/NMOG factor of 1.11 was derived for emissions generated by a fuel with 10 percent ethanol as an oxygenate.

2.1.7. Proposed Passenger Car, Light-Duty Truck, and Medium-Duty Passenger Vehicle Particulate Matter Emission Standards

The LEV II standard for particulate matter (PM) for light-duty vehicles is 0.010 grams per mile. This standard was adopted primarily to provide an upper limit on PM emissions from light-duty vehicles since test data from typical gasoline vehicles at that time showed PM emission levels on the order of 0.001 to 0.002 grams per mile. Diesel vehicles meeting this standard were expected to employ particulate filters. This action also aligned California's PM requirements with the federal Tier 2 program.

Since then, California and federal emission requirements to reduce greenhouse gas emissions have fostered development of advanced internal combustion technology such as gasoline direct injection engines (GDI). Unlike conventional internal combustion engines using port fuel injection (PFI) where fuel is injected and mixed with air in the intake manifold prior to entering the combustion chamber, as the name implies, GDI engines inject fuel directly into the combustion chamber. Among other advantages, this provides a cooling effect on the air/fuel mixture, allowing for higher compression ratios and, therefore, improved engine efficiency and lower CO_2 emissions.

While test data from early versions of GDI engines have demonstrated compliance with the current 0.010 grams per mile PM emission standard, some vehicles have tested at measured PM emission levels of up to 0.008 grams per mile, significantly higher than comparable vehicles with PFI engines that typically test at PM levels at 0.001 gram per mile PM. However, later versions of GDI engines have tested at PM levels approaching

[6] EPA Docket EPA-HQ-OAR-2009-0211

0.001 grams per mile, indicating that significant improvements in PM emissions from GDI engines are achievable.

First generation GDI engines, called wall-guided GDI, used side mounted fuel injectors where the fuel spray pattern is formed by the piston crown and directed towards a center-mounted spark plug. In these systems, some fuel may impinge on the cylinder walls, valves, or other components, resulting in incomplete combustion and increased PM formation. In later generation wall-guided GDI systems, fuel impingement is minimized through use of higher pressure solenoid-controlled injectors that achieve a more finely atomized fuel charge, careful changes in combustion chamber geometry, piston shape, valve placement or other means. Perhaps even more effective, by again using center-mounted higher pressure solenoid-controlled fuel injectors, very low levels of PM emissions can be achieved more efficiently since the fuel charge would more easily avoid impinging on intake and exhaust valves or other combustion chamber components. This latter system is known as a spray-guided GDI system. Appendix P provides a more detailed discussion of GDI technology and its impact on PM emissions.

Accordingly, to encourage the continued development of GDI engines that emit PM at the same low levels as PFI engines, as listed in Table II.A.2.1.2 above, staff is proposing to reduce the PM standard from 0.010 grams per mile to 0.003 grams per mile for PCs and LDTs. Table II-A-2-5 below presents the phase-in requirements for this proposed 0.003 g/mi PM standard. The phase-in requirement represents the minimum percent of a manufacturer's vehicle sales in each model year that must comply with the proposed 0.003 g/mi PM standard (whereas the remainder of the sales must comply with the 0.010 g/mi PM standard).

Table II-A-2-5. Particulate Matter Emission Standard Phase-In Requirements

Year	2017	2018	2019	2020	2021
PC/LDT1	10%	20%	40%	70%	100%
LDT2/MDPV	10%	20%	40%	70%	100%

Staff is also proposing an interim in-use compliance standard of 0.006 grams per mile during the phase-in period. Accordingly, vehicles certifying to the 0.003 gram per mile PM standard during model years 2017-2021, would be held to a 0.006 grams per mile PM standard for in-use compliance testing. Manufacturers would be required to emission test two test groups per year to demonstrate compliance with the proposed PM standards. These test groups would be selected by ARB during the model year pre-certification process. Manufacturers would also be required to perform PM emission testing on one high-mileage in-use vehicle per test group.

To order to further reduce the health impacts of PM, staff is proposing to reduce the PM standard to 0.001 grams per mile. This will ensure the continued development of low PM GDI engine technology and associated PM measurement procedures. The proposed phase-in for this standard is 25% in 2025, 50% in 2026, 75% in 2027, and 100% in 2028 for both PC/LDT1 and LDT2. The phase-in requirement represents the

minimum percent of a manufacturer's vehicle sales in each model year that must comply with the proposed 0.001 g/mi PM standard (whereas the remainder of the sales must comply with the 0.003 g/mi PM standard).

2.1.7.1. Reasoning for Removal of Earlier Staff Recommendation for New Particle Number and Black Carbon Standards for the LEV III PM Proposal

The downward trend in new vehicle tailpipe emissions presents additional challenges to the accurate and repeatable measurement of PM using the traditional gravimetric approach. Consequently, these emerging challenges are promoting interest in alternative measurement methods. At the November 2010 LEV III workshop, ARB sought comment on a proposal that would allow manufacturers to certify for compliance with the new proposed PM mass limits applicable to light- and medium-duty vehicles by using an optional and equivalent certification approach based on a new Solid Particle Number (SPN) standard. The proposed alternative would have required the measurement of SPN emissions using the instrumentation, protocols, and test procedures promulgated by the Particulate Measurement Programme (PMP). PMP recommendations for particle mass and number measurements were adopted into the Euro 5 and subsequent standards for cars. The PNP program is discussed in this staff's report (Appendix P: Technical Support Document – Development of PM standards).

Originally, ARB staff established, in a discussion paper published in May 2010, that the intent of allowing for certification to an optional SPN standard was three-fold. First, the particle number limit proposal was a means to provide some compliance flexibility to vehicle manufacturers subject to LEV III who are also subject to the Euro standards. Broadly, flexibility was based on allowing for the use of a common set of test data for certification in Europe and California. Second, a SPN limit was seen as formal recognition of the emerging importance of ultrafine particle number emissions and as an update of the science underpinning California's policies for clean cars. Finally, the proposed SPN limit allowed for a more practical, sensitive, and lower cost certification test procedure that would demonstrate good PM control. Recognition of the importance of the nexus between air and climate pollution also led to a preliminary recommendation for a new black carbon (BC) emission standard for future cars.

New information and input provided to ARB staff suggests that there are still some important knowledge gaps in critical areas. Subsequent analysis and consideration of that information resulted in recognition that the proposal for SPN and BC standards was premature. Thus, at this point, staff is not proposing new SPN or BC limits. Additional discussion of knowledge gaps is provided below. However, staff is proposing more stringent PM mass limits and is recognizing the need for continuing PM method research and development efforts to help address the remaining data needs.

The federal government is expected to make improvements to the gravimetric measurement for PM mass encompassed in 40 Code of Federal Regulations (CFR) Part 1065 for applicability to LDV emissions. The changes will improve the sensitivity, repeatability, and reproducibility of the technique and, hence, result in an accurate measurement of PM mass at the 0.003 g/mi level of emissions. ARB anticipates that the measurement of PM emissions at the 0.001 g/mi level will likely require further improvements. For this reason, the new limits are proposed to be phased in over many years in order to allow for, among other things, additional test method research and development.

Alternative approaches to PM mass measurement will also be areas for additional testing and research. Today, there is evidence of a statistical correlation between PM mass, SPN, and BC. However, this evidence is very limited and not as definitive as the clear connection between higher temperatures and increased smog. At this time, ARB lacks data on the correlation of mass, number, and BC for various LDV technology types (i.e., PFI, GDI, GPF-equipped LDVs, etc.), for low and high mileage vehicles, or for vehicles with normal and abnormal oil consumption. This information is crucial before a conclusive link between PM mass, SPN, and BC can be established. However, the primary concern voiced by stakeholders with the proposed SPN measurement under PMP is its exclusion of particles in the sub-23 nm size range. Particles in this size range are known to be organic in nature and, hence, they are of high interest from a health protection perspective. In addition, ARB research suggests that exclusion of these particles does not appear to be necessary based on currently available instruments and laboratory practices. Additional research is underway in this area. Conversely, advantages to the alternative metrics for SPN and BC have also been observed. The measurement of BC appears to be an order of magnitude more sensitive than the measurement of PM mass. And the measurement of SPN appears to be an order of magnitude more sensitive than the measurement of BC. This implies that measurement of either SPN or BC could demonstrate PM mass control and that either method may be more than adequate for measuring the ultra-low PM emission levels expected from future vehicles.

Black carbon emission reductions have great promise as part of climate change mitigation efforts. Since Black Carbon is a potent short-lived warming agent with emissions that can be considerably reduced using currently available technology, emission reductions can provide rapid short-term reductions in radiative forcing and hence slow global warming significantly in the short-term. Light-duty vehicles are currently a minor source of BC emissions compared to heavy-duty diesel engines. CARB anticipates that the stringency of the proposed amendments to the existing PM mass standard will result in reduced BC emissions that can yield significant local and regional climate and health benefit.

ARB will continue work on PM mass measurement methods and also on alternative approaches to the conventional mass-based measurement, with a focus on the 1 mg/mile standard for model year 2025. As discussed in Appendix P of this staff report, the most promising alternatives today include the consideration of potential

improvements to the European PMP approach so that it includes sub-23 nm particles as well as other emerging approaches based on the integration of the particle size distribution of the PM emissions or on the chemical reconstruction of PM mass profile. As we embark in these and other important undertakings that will set the stage for the future of laboratory measurements and vehicle emissions, ARB staff is committed to continue to share findings and hopes to receive cooperation and participation from all interested expert stakeholder groups.

2.1.8. Proposed Backstop for Partial Zero-Emission Vehicle Production

Beginning in 2018, the Zero-Emission Vehicle (ZEV) program, also a part of the Advanced Clean Car rulemaking package, will undergo a major restructuring designed to focus on developing a commercial market for advanced electric drive vehicles such as battery electric, fuel cell and plug-in hybrid electric vehicles. Concurrently, partial zero-emission vehicles (PZEVs) and advanced technology partial zero-emission vehicles (AT-PZEVs) such as conventional hybrid electric vehicles (HEVs) and natural gas vehicles (NGVs), which are required to demonstrate emission durability for 150,000 miles for SULEV and zero-fuel evaporative emissions, will transition from the ZEV program to the LEV program in 2018. In order to preserve the continued production of these very clean vehicles that a manufacturer would not need to produce in order to meet the proposed NMOG plus NOx fleet average requirement until it falls below ULEV50 levels in 2023, staff is proposing to require manufacturers to continue their production after they phase-out of the ZEV program. Therefore, staff is proposing that beginning in 2018, manufacturers be required to continue to certify a percentage of their new vehicle fleet meeting SULEV exhaust emissions and zero evaporative emissions for 150,000 miles equal to the average percentage of the sum of PZEVs and AT-PZEVs produced in model years 2012-2014. While these vehicles would continue to be required to meet SULEV exhaust and zero-fuel evaporative requirements, in 2018 and subsequent model years their movement from the ZEV to LEV program will mean manufacturers will no longer be required to offer an extended full life emission warranty. This reduction in warranty coverage is a result of a restriction in current California statute that limits the warranty period to 7 years or 70,000 miles, whichever occurs first.

2.1.9. Proposed Medium-Duty Vehicle Emission Standards

Medium-duty vehicles (MDVs) are defined as those with a gross vehicle weight rating (GVWR) between 8,501-14,000 lbs. Vehicles included in this category include the heavier pickup trucks such as the Ford F250 and F350, larger vans designed for carrying cargo such as the Ford Econoline 250 and 350, as well as delivery trucks with purpose built containers. Since these vehicles are typically used for work purposes and are subject to a more rigorous duty cycle, they are subject to less stringent emissions standards than trucks and minivans in the LDT2 category. While taking into account the more rigorous duty cycle, staff is proposing that overall emissions meet an equivalent MDV SULEV emission level for ninety percent of these vehicles. In 2022, 10 percent of MDVs may meet a less stringent ULEV standard in order to provide compliance margin for promising unanticipated greenhouse gas technologies. Table II-A-2-6 lists the

emission standards for MDVs. The MDV emission standards are to be phased-in from 2016-2022. Tables II-A-2-7 and II-A-2-8 list the minimum sales-weighted phase-in requirements for the FTP and SFTP standards, the extended durability requirement, and the use of E10 certification fuel. Staff is also proposing to sunset, in model year 2022, the least stringent LEV395 and LEV340 standards for MDVs between 8,501-10,000 lbs. GVWR and the LEV630 and LEV570 standards for MDVs between 10,001-14,000 lbs. GVWR.

Table II-A-2-6. Proposed FTP Exhaust Emission Standards for New 2016 and Subsequent Model Year LEV III Medium-Duty Vehicles

Proposed LEV III Exhaust Mass Emission Standards for New 2016 and Subsequent Model Medium-Duty Trucks						
Vehicle Type	**Durability Vehicle Basis (mi)**	**Vehicle Emission Category**	**NMOG + Oxides of Nitrogen (g/mi)**	**Carbon Monoxide (g/mi**	**Formaldehyde (mg/mi)**	**Particulates (g/mi)**
MDVs 8500 - 10,000 lbs. GVWR, excluding MDPVs Vehicles in this category are tested at their adjusted loaded vehicle weight	150,000	LEV395[1]	0.395	6.4	6	0.008
		ULEV340[1]	0.340	6.4	6	0.008
		ULEV250	0.250	6.4	6	0.008
		ULEV200	0.200	4.2	6	0.008
		SULEV170	0.170	4.2	6	0.008
		SULEV150	0.150	3.2	6	0.008
MDVs 10,001-14,000 lbs. GVWR Vehicles in this category are tested at their adjusted loaded vehicle weight	150,000	LEV630[1]	0.630	7.3	6	0.010
		ULEV570[1]	0.570	7.3	6	0.010
		ULEV400	0.400	7.3	6	0.010
		ULEV270	0.270	4.2	6	0.010
		SULEV230	0.230	4.2	6	0.010
		SULEV200	0.200	3.7	6	0.010

[1] These certification levels would no longer be available from 2022 on

Table II-A-2-7. Medium-Duty Vehicles 8,500-10,000 lbs. GVWR Federal Test Procedure Exhaust Emission Standards (Proposed)

Medium-Duty Vehicles 8,500-10,000 GVW (g/mi NMOG+NOx)							
Year	LEV	ULEV340	ULEV250	ULEV200	SULEV170	SULEV150	Phase-in
	0.395	0.340	0.250	0.200	0.170	0.150	150K, E10, SFTP
2016	20%	60%	20%				20%
2017	10%	50%	40%				40%
2018		40%	50%		10%		60%
2019		30%	40%		30%		70%
2020		20%	30%		50%		80%
2021		10%	20%		70%		90%
2022			10%		90%		100%

Table II-A-2-8. Medium-Duty Vehicle 10,001-14,000 lbs. GVWR Federal Test Procedure Exhaust Emission Standards (Proposed)

Medium-Duty Vehicles 10,001-14,000 GVW (g/mi NMOG+NOx)							
Year	LEV	ULEV570	ULEV400	ULEV270	SULEV230	SULEV200	Phase-in
	0.630	0.570	0.400	0.270	0.230	0.200	150K, E10, SFTP
2016	20%	60%	20%				20%
2017	10%	50%	40%				40%
2018		40%	50%		10%		60%
2019		30%	40%		30%		70%
2020		20%	30%		50%		80%
2021		10%	20%		70%		90%
2022			10%		90%		100%

2.1.10. Chassis-Certification of Medium-Duty Vehicles Between 8,500 - 10,000 lbs. GVW

Staff is also proposing that all MDVs in the 8,501-10,000 lbs. GVWR category be certified to chassis dynamometer-based emission standards. Currently, manufacturers may choose to certify incomplete gasoline and all diesel powered MDVs in this weight class to engine dynamometer emission standards. Staff is proposing to eliminate this option for several reasons. First, manufacturers are increasingly choosing to chassis certify their complete diesel MDVs in this category and have indicated that they will be expanding the number of chassis-certified vehicles in this weight class. Second, some manufacturers are already chassis certifying some of their incomplete MDVs. More importantly, requiring these vehicles to be certified to chassis dynamometer emission standards would facilitate in-use verification of their emissions by avoiding the need to remove the engine for in-use emission testing of vehicles certified to engine dynamometer emission standards. For these chassis-certified vehicles, manufacturers will need to include in the certification application the maximum recommended GVWR, curb weight, equivalent test weight, frontal area and applicable chassis dynamometer

settings.

2.1.11. Pooling Fleet Average NMOG plus NOx Emissions from California and Section 177 States

Beginning in 2015, staff is proposing to provide an option to allow compliance with the fleet average NMOG plus NOx requirement be demonstrated using the pooled fleet average NMOG plus NOX emissions of new vehicles produced and delivered for sale in California and all states, including the District of Columbia if applicable, that adopt California's emission requirements for light- and medium-duty vehicles. Manufacturers that choose this option would be required to report the number of vehicles produced and delivered for sale and the emission standards to which they are certified for each state, and the District of Columbia if applicable, that adopts California emission requirements. Including this provision provides additional compliance flexibility to vehicle manufacturers, particularly with respect to meeting a separate fleet average requirement in those states with limited new vehicle sales. While this represents a departure from past practice, staff believes that the emission impact of this provision within California and states that adopt California requirements will be minor due to the very low level of fleet emissions required by this program. Assigning credits and debits under this fleet emission-averaging scheme is discussed in the following section on credits and debits.

2.1.12. Credits and Debits

In the LEV II program, manufacturers may earn NMOG credits if they over-comply with the fleet average NMOG requirements and debits if they do not achieve it. Credits may be banked for future use to offset any NMOG debits or traded with other manufacturers. Under the current provisions, credits may be carried forward for three years, but are discounted beyond the first year and sunset in the fourth year. Debits must be offset the following model year. Staff is proposing to change the credit provisions to allow credits to be carried forward five years and carried back three years. This change will provide harmonization of LEV III emission credit provisions with federal emission credit provisions and provide an increased level of flexibility to manufacturers in meeting LEV III requirements. Staff does not anticipate an emission impact from this change due to very low fleet emission levels of the LEV III program.

Most manufacturers are expected to have NMOG credits banked when LEV III starts in 2015. Credits earned prior to 2015 would be discounted under the LEV II protocol and expire four years after they were accrued. In order to convert any LEV II NMOG credits carried forward to 2015 to NMOG plus NOx credits, staff is proposing a conversion factor of 3.0. This factor is derived by dividing the projected California fleet average for NMOG plus NOx for model year 2014 based on new vehicle sales of PC, LDT1, and LDT2 from EMFAC 2011 for 2014 by the NMOG fleet average requirement for 2014. A conversion factor of 3.0 is derived because the projected NMOG plus NOx fleet average in 2014 is approximately three times the NMOG fleet average. Similarly, any NMOG debits carried over to 2015 would be converted to NMOG plus NOx debits by multiplying

them by a factor of 3.0 and must be offset by any NMOG plus NOx credits earned in model years 2015 through 2018.

As noted above, LEV III provides manufacturers with an option to pool their criteria emissions in California and the 177 states when determining compliance with program fleet average requirements. This means that a manufacturer may be over compliant in some states and under compliant in others but its compliance status is determined by the pooled emissions of vehicles produced and delivered for sale in California and the 177 states. Note that manufacturers choosing this pooling option must still report their model year criteria emissions in each state. In addition, as noted above, the credit provisions are being changed to allow credits to be carried forward five years and carried back three years. In this case, a manufacturer would be non-compliant with the fleet average requirement when, it has no credits (either to carry forward or carry back or that can be purchased from other manufacturers) to offset any outstanding debits.

Staff is proposing that when a manufacturer is deemed non-compliant with the pooled fleet average requirement, each state in which the manufacturer is determined to be non-compliant may take enforcement action based on the debits outstanding in that state. This is similar to the approach that California (and Section 177 States) took in allowing compliance with federal GHG standards in 2012-2016 to serve as compliance in California.

Staff is also proposing a 0.005 NMOG plus NOx gram per mile credit for vehicles that the manufacturer provides a 15 year/150,000 mile emission warranty. This credit would be applied to the emission values of the applicable test group when a manufacturer calculates its NMOG plus NOx fleet average value.

2.1.13. Proposed FTP Phase-In Requirements to 150,000 Mile Full Useful life Emission Standards and E10 Certification Fuel

As discussed in section IV, staff is proposing to require emission certification on two new California certification fuels. These fuels would have an ethanol content of 10 percent and two octane ratings, 87 and 91 AKI, or "antiknock index." AKI is defined as the average of ASTM research octane number (RON) and motor octane number (MON). Vehicles for which the manufacturer *requires* consumer operation on premium fuel to maintain warranty coverage may certify using California 91 AKI certification fuel. All other vehicles, including vehicles that the manufacturer *suggests* or *recommends* operation on premium fuel, must certify using California 87 AKI fuel. The ethanol content and octane values of the new certification fuels are designed to assure that the fuel vehicles are certified on more accurately reflects the fuel they are operated on. Staff also proposes to retain the option to certify on federal Tier 3 certification fuel, which staff understands will be based on E15.

Accordingly, staff is proposing that manufacturers phase-in compliance to LEV III 150,000 mile durability requirements, from 2015 through 2019, using the new California E10 certification fuels. To align with federal Tier 3 phase-in requirements, staff is

proposing that beginning in 2015 all vehicles certifying to emission standards below ULEV125 meet LEV III requirements to 150,000-mile durability using E10 certification fuel. Manufacturers would be required to certify all of their vehicles to 150,000-mile durability and E10 certification fuel in 2020. Because the declining fleet average requirement will require manufacturers to certify an increasing percentage of their vehicles to lower emission standards, staff believes this will assure an ordered progression of LEV III vehicles into the fleet, while providing flexibility to manufacturers in meeting LEV III requirements

2.1.14. Early Phase-in Provision

In order to encourage an earlier-than-required introduction of cleaner, more durable vehicles and to provide additional flexibility to manufacturers, staff is proposing an early phase-in option for vehicles certifying to ULEV70 and more stringent emissions standards. Because PZEVs already are required to achieve 150,000-mile durability per the ZEV program, PZEVs would not be eligible for early phase-in credits. Under this option, the percentage of vehicles certifying in 2014 to LEV III NMOG plus NOx 150,000-mile standards and SFTP requirements (certification using the new E10 certification fuels would not be required) would be counted towards a manufacturer's LEV III phase-in requirements.

2.1.15. Small Volume Manufacturer Requirements

Independent vehicle manufacturers with a California three-year sales volume average of 4,500 units per year or less of new PCs, LDTs, MDVs and heavy-duty vehicles and engines are currently defined as Small Volume Manufacturers. The manufacturers meeting this sales volume criterion (approximately a half dozen) were primarily those with very low volume sales (less than a thousand units per year) of high performance vehicles. In LEV II, compliance with the fleet average NMOG requirement for small volume manufacturers was deferred until 2007, the end of the phase-in period, Beginning in 2007, they were required to meet a fleet average requirement approximately 53% less stringent than the fleet average requirement for larger manufacturers. The less stringent requirement for these manufacturers was adopted in recognition of their limited model lines with which to comply with fleet average requirements and limited investment and engineering resources to meet more stringent emission standards.

For LEV III, ARB is proposing to provide a similar relaxation in requirements to a subset of the Small Volume Manufacturers category that has a three-year average sales volume of less than 5,000 vehicles and engines nationwide. Staff estimates that a limited number of manufacturers (i.e., Lotus, McLaren, and Aston Martin) with limited vehicle model lines would meet the nationwide sales of 5,000 vehicles or less per year criterion. Staff believes that manufacturers that previously qualified for relaxed standards under the Small Volume Manufacturers category will continue to qualify for relaxed standards under this proposal.

Less stringent requirements for these very low volume manufacturers are justified for several reasons. First, these manufacturers are on the leading edge in developing vehicles using advanced vehicle design and lightweight materials. Their vehicles demonstrate in very real terms, the potential for innovative approaches to vehicle design and material use to achieve vehicle lightweighting without compromising safety (especially important for achieving very low GHG emissions). Second, as mentioned previously, they are at a competitive disadvantage (in terms of both investment and engineering resources) in that they must compete with full line manufacturers who are able to offset the emissions of their low volume high performance vehicles with higher volume, lower emission vehicles. Lastly, staff believes that periodic reviews of these manufacturers' emission capability assures that they will continue to improve the emissions of their vehicles.

Accordingly, for qualifying vehicle manufacturers, staff is proposing that compliance with the LEV III requirements be deferred until the 2022 model year. Prior to 2022, small volume manufacturers with nationwide sales of 5,000 vehicles or less per year may petition ARB for relaxed emission standards. Consideration of relaxed standards would be based on a review of the manufacturers' engineering and economic resources, criteria emissions of comparable vehicles certified by large volume manufacturers with a similar horsepower to weight ratios, documentation of good faith efforts to purchase credits from other manufacturers, and other relevant data. If determined appropriate, alternative emission standards would be granted for a period of up to 5 years and reconsidered at future 5-year intervals.

2.2. Proposed SFTP Exhaust Emission Standards

The California Supplemental Federal Test Procedure (SFTP) was developed to quantify and control motor vehicle emissions not accounted for by the Federal Test Procedure (FTP). Specifically, the SFTP captures so-called "off-cycle" emissions resulting from aggressive driving and air conditioner use. Off-cycle operating modes represent a significant portion of real-world driving and could result in significant emissions if vehicles are not properly calibrated. While the SFTP program is not intended to drive the installation of emission-control hardware, staff believes the emission standards are necessary to ensure that vehicular emissions are controlled through all modes of operation.

In this rulemaking, staff is proposing to amend the SFTP program primarily in the following ways: 1) increase durability requirements; 2) expand applicability to medium-duty vehicles; 3) develop more stringent emission standards; and 4) add PM emission standards. These new proposed requirements would be implemented beginning with the 2015 model year and be phased in through the 2025 model year.

This section presents an overview of staff's specific proposal. Further detail is available in Appendix O, while the proposed test procedure text is included in Appendix C.

2.2.1. Increasing Durability Requirements to Full Useful Life

Staff is proposing a 150,000-mile durability requirement for SFTP emission standards to replace the 4,000-mile durability requirement currently in effect. The proposed durability requirement would be phased-in in accordance with the 150,000-mile durability phase-in proposed for the FTP.[7] This proposed change would align the SFTP's durability basis with that of the FTP and would ensure that control of off-cycle emissions is extended throughout the full useful life of on-road motor vehicles.

When staff developed the existing 4,000-mile SFTP emission standards, it was unclear how aging of emission-control hardware would impact emissions over the SFTP driving cycles. However, data available today indicate that as vehicles age, increases in SFTP emissions are generally equivalent to increases in FTP emissions. Staff developed the 150,000-mile SFTP emission standards based on such findings and believes it is appropriate to align the SFTP durability basis with that of the FTP.

2.2.2. Applicability of SFTP Requirements

The proposed SFTP requirements would apply to 2015 and subsequent model year PCs, LDTs, and MDPVs, and 2016 and subsequent model year MDVs through 14,000 pounds GVWR, including gasoline, diesel, alternative-fueled, and hybrid electric vehicles. MDVs and alternative-fueled vehicles were not previously subject to SFTP requirements because test data were not available to show they could comply with the emission standards and/or because manufacturers contended that such vehicles do not operate in the manner captured by the SFTP. Current driving patterns and emissions data, as presented in Appendix O, make it clear that it is appropriate to subject these vehicles to the proposed SFTP requirements.

2.2.3. SFTP Passenger Car, Light-Duty Truck, and Medium-Duty Passenger Vehicle NMOG+NOx and Carbon Monoxide (CO) Emission Standards and Phase-In

For PCs, LDTs, and MDPVs, staff is proposing two pathways to comply with the SFTP NMOG+NOx and CO emission standards. Option 1 would use stand-alone emission standards while Option 2 would use a composite emission standard approach with a fleet-averaging provision for NMOG+NOx. A fleet must commit to the option selected for the entire phase-in period. Under either approach, when a test group[8] certifies to the 150,000-mile durability requirements for LEV III FTP, it would be required to certify to 150,000-mile SFTP emission standards as well. Capping CO emission standards would also apply for both Options 1 and 2 with the goal of preventing backsliding from current SFTP CO emission control levels. Staff believes that these options would provide planning flexibility without compromising the required emission reductions.

---

[7] See section II.A.2.1.12 for further information.
[8] See 40 CFR §86.1827-01 for the test group determination procedure.

2.2.3.1. Stand-Alone Option (Option 1)

Table II-A-2-10 shows staff's proposed Option 1 NMOG+NOx and CO exhaust emission standards for PCs, LDTs, and MDPVs. The phase-in of these emission standards would be tied directly to LEV III FTP certifications beginning with the 2015 model year. Specifically, a test group certifying to a particular LEV III FTP emission category would also be required to comply with the corresponding SFTP emission category (e.g., test groups certifying to LEV III FTP ULEV125, ULEV70, or ULEV50 would be required to meet the SFTP ULEV emission standards shown in Table II-A-2-10 below).

Table II-A-2-10. SFTP NMOG+NOx and CO Exhaust Emission Standards for New 2015 and Subsequent Model Year LEVs, ULEVs, and SULEVs in the Passenger Car, Light-Duty Truck, and Medium-Duty Passenger Vehicle Classes, Option 1[1,2]

			US06 Test (g/mi)		SC03 Test[3] (g/mi)	
Vehicle Type	Mileage for Compliance	Vehicle Emission Category[4]	NMOG + NOx	Carbon Monoxide	NMOG + NOx	Carbon Monoxide
All PCs, LDTs 0-8,500 lbs GVWR, and MDPVs Vehicles in this category are tested at their loaded vehicle weight (curb weight plus 300 pounds).	150,000	LEV	0.140	9.6	0.100	3.2
		ULEV	0.120	9.6	0.070	3.2
		SULEV Option A[5]	0.060	9.6	0.020	3.2
		SULEV	0.050	9.6	0.020	3.2

[1] *Air to Fuel Ratio Requirement.* See footnote 1, Table 2, Appendix O.
[2] *"Lean-On-Cruise" Calibration Strategies.* See footnote 2, Table 2, Appendix O.
[3] *A/C-on Specific Calibrations.* See footnote 4, Table 2, Appendix O.
[4] *Vehicle Emission Categories.* Manufacturers must certify all vehicles, which are certifying to a LEV III FTP emission category on a 150,000-mile durability basis, to the emission standards of the equivalent, or a more stringent, SFTP emission category set forth in this table. All LEV III FTP LEVs certified to 150,000-mile durability shall comply with the 150,000-mile SFTP LEV standard, all LEV III FTP ULEVs certified to 150,000-mile durability shall comply with the 150,000-mile SFTP ULEV standard, and all LEV III FTP SULEVs certified to 150,000-mile durability shall comply with the 150,000-mile SFTP SULEV standard.
[5] *Optional SFTP SULEV Standard.* MDPVs and LDTs 6,001-8,500 lbs. GVWR that are equipped with a particulate filter could certify to a higher NMOG+NOx emission standard for model years 2015 through 2020 in exchange for an extended 200,000-mile particulate filter emission warranty. See footnote 6, Table O-2, Appendix O.

2.2.3.2. Composite Emission Standards with NMOG+NOx Fleet Averaging Option (Option 2)

The goal of the SFTP program is to ensure that software calibrations are optimized so that vehicles continue to effectively control exhaust emissions during off-cycle operations. It is not meant to be a driver of new hardware installation. Although staff had proposed Option 1 as the sole compliance option in their initial concept, after

additional analysis and discussions with stakeholders, staff determined that the Option 1 emission standards would likely require diesel-fueled vehicles (which manufacturers have indicated they plan to produce to meet California and federal greenhouse gas and fuel efficiency mandates) to have additional costly emission-control hardware installed. Consequently, ARB staff is proposing a second option that would accommodate diesel-fueled vehicles through less stringent emission standards and a fleet averaging provision. Staff expects that if a manufacturer has higher SFTP emissions from a diesel vehicle, it could make cleaner gasoline-fueled vehicles to partially offset the higher diesel emissions. Staff estimates that today's fleet emits 7.5 tons per day (TPD) of NMOG+NOx during off-cycle driving conditions. This number would be reduced to approximately 2.9 TPD if all manufacturers certified to SFTP using Option 1 and 3.8 TPD if all manufacturers certified using Option 2. Although Option 2 would not achieve the same level of NMOG+NOx emission reductions as Option 1, it is being proposed to be consistent with ARB's original goal of developing an SFTP program that does not drive the installation of new emission-control hardware. While most OEMs have indicated to staff that they plan to choose Option 2 for SFTP compliance, ARB staff is still proposing Option 1 for OEMs that may not want to utilize fleet averaging, as well as for SVMs. SVMs would have a delayed phase-in into LEV III and thus would not have to certify to the more stringent SULEV emission category in Option 1 until after the last year of the phase-in, at which point they could simply elect to transition into Option 2.

Under Option 2, for each test group, manufacturers would calculate composite emission values by weighting emission test results from the FTP, US06, and SC03 tests in g/mi, as shown by the following equation:

SFTP Composite Emission Value = 0.28 x US06 + 0.37 x SC03 + 0.35 x FTP [Eq. 1]

This is the same equation currently being used to determine compliance with federal SFTP emission standards.

For CO, every test group certifying to SFTP would be required to meet the CO composite emission standard of 4.2 g/mi. However, for NMOG+NOx, manufacturers would use a sales-weighted fleet average to determine compliance. Specifically, manufacturers would certify test groups to "bins", each with a bin-specific emission limit analogous to a family emission limit, or FEL. Manufacturers would then weight each bin based on sales volume to calculate their fleet-average emission value, as shown by the following equation:

$$\frac{\sum_{i=1}^{n}[(\text{number of vehicles in the test group})_i \times (\text{Composite Value of Bin})_i]}{\sum_{i=1}^{n}(\text{number of vehicles in the test group})_i} \quad \text{[Eq. 2]}$$

where "n" = a manufacturer's total number of certification bins in the PC, LDT 0-8,500 pounds GVWR, and MDPV categories for a given model year;

"number of vehicles in the test group" = the number of vehicles produced and delivered for sale in California in the certification test group;

"Composite Emission Value of Bin" = the numerical value selected by the manufacturer for the bin that serves as the emission standard for the vehicles in the test group with respect to all testing, instead of the emission standard specified. Vehicles would certify to bins in increments of 0.010 g/mi. Beginning with the 2018 model year, vehicles would not be able to certify to bin values above a maximum of 0.180 g/mi.

During the phase-in (shown in Table II-A-2-11 below), the fleet average would be calculated using a combination of carryover 4,000-mile SFTP composite emission values (adjusted to 120,000-miles and converted to NMOG+NOx) and new-certification 150,000-mile SFTP composite emission values.

As presented in Table II-A-2-11, the composite emission standards would become more stringent each model year until the 2025 model year. Although this option would not be directly linked to FTP certification of LEV III vehicles, it would achieve fleet-wide SULEV level emission performance by the 2025 model year.

Table II-A-2-11. SFTP NMOG+NOx and CO Composite Exhaust Emission Standards for New 2015 and Subsequent Model Year Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles (Option 2)[1,2,3,4]

Model Year	**2015**	**2016**	**2017**	**2018**	**2019**	**2020**	**2021**	**2022**	**2023**	**2024**	**2025**
All PCs; LDTs 0-8,500 lbs GVWR; and MDPVs 8,501-10,000 lbs GVWR Vehicles in this category are tested at their loaded vehicle weight (curb weight plus 300 pounds).	SFTP NMOG+NOx Sales-Weighted Fleet-Average Composite Exhaust Emission Standards (g/mi)[5,6]										
	0.140	0.110	0.103	0.097	0.090	0.083	0.077	0.070	0.063	0.057	0.050
	SFTP CO Composite Exhaust Emission Standard (g/mi)[7]										
	4.2										

[1] *Air to Fuel Ratio Requirement.* See footnote 1, Table 2, Appendix O.

[2] *"Lean-On-Cruise" Calibration Strategies.* See footnote 2, Table 2, Appendix O.

[3] *A/C-on Specific Calibrations.* See footnote 4, Table 2, Appendix O.

[4] MDPV test groups would neither be subject to these emission standards nor be included in the NMOG+NOx fleet average until they certify to FTP emission standards at 150,000-mile durability.

[5] For carry-over test groups not certified to LEV III FTP emission standards on a 150,000-mile durability basis, SFTP emission values shall be projected out to a 120,000-mile durability basis. Carry-over test groups may use the applicable deterioration factor from the FTP test. For test groups certified to a 150,000-mile durability basis on the FTP, the SFTP emission values shall be projected out to 150,000-miles for purposes of meeting the composite emission standards in this table.

[6] Test groups would certify to bins in increments of 0.010 g/mi. Beginning with the 2018 model year, vehicles would not be able to certify to bin values above a maximum of 0.180 g/mi.

[7] *CO requirement.* Unlike the NMOG+NOx composite emission standards, manufacturers would not be able to meet the proposed CO composite emission standard through fleet averaging. Each individual test group would be required to comply with the standard. Compliance would be determined using a composite emission value of the FTP, US06, and SC03 test results, as calculated using Equation 1. This CO emission standard would only apply to test groups certified to LEV III FTP emission standards at 150,000-mile durability. Test groups not subject to this CO emission standard would be required to meet the 4,000-mile CO emission standards of the existing SFTP program. The CO composite emission standard in this table does not apply to MDPVs until such vehicles are certified to LEV III FTP 150,000-mile durability requirements.

2.2.3.2.1. Calculation of Fleet Average Total NMOG+NOx Credits or Debits

Option 2 would also allow manufacturers to generate credits or debits for each model year. A sales-weighted emission value lower than the composite emission standard would generate credits while a sales-weighted emission value greater than the composite emission standard would generate debits. For each model year, manufacturers would calculate their NMOG+NOx emission balance, as follows:

> [(NMOG+NOx Composite Emission Standard) – (Manufacturer's Sales-Weighted Fleet-Average Emission Value)] x (Total Number of Vehicles Produced and Delivered for Sale in California in the PC, LDT 0-8,500 pounds GVWR, and MDPV categories) [Eq. 3]

Total credits earned in a given model year would retain full value through the fifth model year after they are earned. At the beginning of the sixth model year, the total credits would have no value. Manufacturers would be required to offset all debits incurred in a specific model year within three model years, using available credits that either they have generated or have obtained via trading with other companies. Manufacturers would be allowed to trade credits with other manufacturers at any time.

2.2.4. Proposed SFTP NMOG+NOx and CO Emission Standards for Medium-Duty Vehicles

Staff is proposing to extend SFTP applicability to MDVs starting with the 2016 model year. For NMOG+NOx and CO, MDVs certifying to SFTP standards would be required to comply with the applicable composite emission standards shown in Table II-A-2-12. To demonstrate compliance, manufacturers would calculate composite emission values for each test group by weighting emission test results from the FTP, US06 (or US06 Bag 2 or UC, as appropriate), and SC03 tests using Equation 1, above.

Table II-A-2-12. SFTP NMOG+NOx and CO Composite Exhaust Emission Standards for New 2016 and Subsequent Model Year ULEVs and SULEVs in the Medium-Duty Vehicle Class[1,2,3]

					SFTP Composite Standard[4] (g/mi)	
Vehicle Type[5]	**Mileage for Compliance**	**Hp/GVWR[6]**	**Test Cycle**	**Vehicle Emission Category**	**NMOG + NOx**	**Carbon Monoxide**
MDV 8,501-10,000 lbs GVWR	150,000	≤ 0.024	US06 Bag 2, SC03, FTP	ULEV	0.550	22.0
				SULEV	0.350	12.0
		> 0.024	Full US06, SC03, FTP	ULEV	0.800	22.0
				SULEV	0.450	12.0
MDV 10,001-14,000 lbs GVWR	150,000	n/a	UC (LA92),	ULEV	0.550	6.0
			SC03, FTP	SULEV	0.350	4.0

[1] *Air to Fuel Ratio Requirement.* See footnote 1, Table 2, Appendix O.
[2] *"Lean-On-Cruise" Calibration Strategies.* See footnote 2, Table 2, Appendix O.
[3] *A/C-on Specific Calibrations.* See footnote 4, Table 2, Appendix O.
[4] SFTP Composite Emission Value for MDVs 8,501-10,000 pounds GVWR = 0.28 x US06 (or US06 Bag 2, as appropriate) + 0.37 x SC03 + 0.35 x FTP, in g/mi.
SFTP Composite Value for MDVs 10,001-14,000 pounds GVWR = 0.28 x UC + 0.37 x SC03 + 0.35 x FTP, in g/mi.
[5] Vehicles in this category would be tested at their adjusted loaded vehicle weight (average of curb weight and GVWR)
[6] If all vehicles in a test group have a power to weight ratio at or below a threshold of 0.024 would have the option to run the US06 Bag 2 in lieu of the full US06 cycle. The cutoff would be determined by using a ratio of the engine's horsepower to the vehicle's GVWR in pounds and would not include any horsepower contributed by electric motors in the case of hybrid electric or plug-in hybrid electric vehicles. Manufacturers would have the option to test to the full cycle regardless of the calculated ratio. In that case, manufacturers would be required to meet the requirements under the >0.024 provision.

As can be seen in Table II-A-2-12, the different types of MDVs have different test cycles. This is necessary due to difficulties some of these heavier vehicles may have in following the accelerations present in the full US06 cycle. In general, MDVs in the 8,501 through 10,000 pounds GVWR category would be subject to the US06 and SC03 test procedures. However, some lower-powered MDVs in this category may have difficulties following the entire US06 trace. Specifically, the frequent and aggressive speed fluctuations of the US06 could cause overheating problems and be particularly troublesome for lower-powered MDVs. Therefore, staff is proposing to allow manufacturers of these vehicles to comply only with Bag 2 of the US06 cycle if the ratio of the engine's horsepower to the vehicle's GVWR in pounds is 0.024 or less. While the US06 Bag 2 cycle includes operation at the same maximum speed (80.3 mph) as the full US06 cycle, it does not include the frequent accelerations and decelerations found at the beginning and end of the full cycle. The proposed US06 Bag 2 emission standards have been adjusted to account for the change in testing cycle, but they are equivalent in stringency to the full US06 emission standards. The US06 Bag 2 test cycle is presented in Appendix O.

Similarly, MDVs greater than 10,000 pounds GVWR may also have difficulty following the rapid accelerations contained in the US06 driving trace. Therefore, staff is proposing to have these vehicles use the California Unified Cycle (UC) instead. The UC is similar to the US06 test cycle, but with less aggressive speeds and acceleration. The proposed standards have been adjusted to reflect the different emission results that would be obtained under the UC as opposed to the US06 test cycle. The UC test cycle is presented in Appendix O.

Manufacturers expressed some concern about costs associated with the SC03 test for MDVs. Because MDVs have significantly larger displacement engines and more power and torque than LDVs, the effect of using the air conditioner on emissions for this class is relatively modest. In addition, because manufacturers have noted that significant upgrades would be required for their environmental test cells to handle MDVs, staff proposes to allow an engineering evaluation in lieu of testing when certifying these vehicles to the proposed SC03 emission standards. Manufacturers electing to submit an engineering evaluation would use their FTP result instead of the SC03 result in Equation 1 when calculating compliance with the composite standard.

The proposed SFTP requirements for MDVs would be phased in beginning with the 2016 model year. The phase-in would be based on the percentages of ULEVs and SULEVs certified on the FTP. Specifically, the percentage of MDVs required to certify to the SFTP SULEV emission standards would have to be equal to or greater than the percentage certified as a LEV III SULEV on the FTP. The same phase-in requirement would apply to ULEVs with the exception that instead of meeting or exceeding the LEV III FTP-certified ULEV percentage with SFTP ULEVs, a manufacturer could also certify additional SFTP SULEVs to meet or exceed this percentage.

2.2.5. SFTP PM Emission Standards for PCs, LDTs, MDPVs, and Other MDVs

Staff is also proposing new SFTP PM Exhaust Emission Standards. Current GDI engines typically have higher PM emissions than port fuel injection engines. Because of this, PM exhaust levels, especially from gasoline-powered vehicles, have become a growing concern as the industry shifts from PFI engines towards GDI engines. All vehicles counted towards the 150,000-mile FTP PM emission standards phase-in in Table II-A-2-5 would comply with the SFTP PM Exhaust Emission Standards shown in Table II-A-2-13. The emission standards are primarily intended to prevent excessive oil consumption and fuel enrichment during aggressive driving and should not force installation of additional emission control technology. The PM emission standards are based on limited test data and will be reexamined as additional data become available. Because the data are limited, the proposed PM standards are not as stringent as the test data might suggest as feasible. This extra margin should ease manufacturer concerns about the relatively small test samples. The test data are presented and discussed in Appendix O.

Table II-A-2-13. SFTP PM Exhaust Emission Standards for New 2017 and Subsequent Model Year Passenger Cars, Light-Duty Trucks, Medium-Duty Passenger Vehicles, and Other Medium-Duty Vehicles

Vehicle Type	Test Weight	Mileage for Compliance	Hp/GVWR[1]	Test Cycle[2]	PM mg/mi
PCs 0-8,500 lbs GVWR; LDTs 0-6,000 lbs GVWR	Loaded vehicle weight	150,000	n/a	US06	10.0
LDTs 6,001-8,500 lbs GVWR; MDPVs	Loaded vehicle weight	150,000[2]	n/a	US06	20.0
MDVs 8,501-10,000 lbs GVWR	Adjusted loaded vehicle weight	150,000	≤ 0.024	Composite US06 Bag 2	7.0
			> 0.024	Composite US06	10.0
MDVs 10,001-14,000 lbs GVWR	Adjusted loaded vehicle weight	150,000	n/a	Composite UC (LA92)	7.0

[1] See Table II-A-2-3, footnote 5.
[2] See Table II-A-2-3, footnote 4.

2.2.6. Other Proposed SFTP Amendments

As part of the Advanced Clean Cars Program, staff is proposing to amend the certification gasoline specifications, as discussed in section IV, by removing MTBE as an obsolete specification, and requiring 10 percent ethanol by volume instead. This proposed modification would better align the specifications of certification test fuel with the properties of in-use fuel. For each test group, SFTP emission testing must be completed using the same fuel that is used to certify to FTP emission standards, as discussed in section II.A.2.1.12.

Staff is also proposing to regulate ozone precursors on the basis of NMOG+NOx instead of NMHC+NOx to harmonize with the FTP and federal requirements. The new NMOG+NOx emission standard basis better characterizes ozone formation potential because NMOG includes some ozone precursors that are not captured by the NMHC definition. Staff is proposing to use a factor of 1.03 to convert NMHC values to NMOG as discussed in Appendix O.

Staff recently discovered that some manufacturers have been misinterpreting the test weight requirements of the existing SFTP program. Specifically, some manufacturers have been certifying LDTs[9] 6,001-8,500 lbs. GVWR to the SFTP emission standards at "loaded vehicle weight," which is defined as curb weight plus 300 lbs. However, only PCs and LDTs 0-6,000 lbs. GVWR are supposed to be tested at loaded vehicle weight.

[9] These vehicles are designated as MDVs 6,001-8,500 lbs. GVWR under the current SFTP program for MY2014 and prior vehicles.

LDTs 6,001-8,500 lbs. GVWR are required to be tested at "average loaded vehicle weight," which is defined as the curb weight plus half of its payload capacity. The average loaded vehicle weight is generally greater than the loaded vehicle weight, and reflects the greater payload capacity of these larger LDTs. Staff is proposing to amend the existing SFTP program in order to clarify its test weight requirements.

2.2.7. US06 and SC03 Emission Benefits/Cost Assessment

Compliance with the proposed SFTP regulation is expected to require better calibration and software upgrades. Staff does not believe any additional emission control hardware will be necessary to meet the proposed SFTP emission standards. Based on staff's analyses, SFTP is expected to reduce NMOG+NOx emissions by 0.2 tons per day in 2025. These expected reductions would be driven entirely by US06 requirements and primarily from MDV requirements. Although staff is not attributing any NMOG+NOx emission reductions to the proposed SC03 emission standards, staff believes they are still necessary to ensure proper calibration of vehicular air conditioning systems. Additionally, the CO emission standards for both US06 and SC03 are being proposed to prevent backsliding from current emission levels, and the SFTP PM emission standards are being proposed to prevent excessive oil consumption and fuel enrichment during aggressive driving. For more details regarding the emission reduction analysis, see Appendix O.

Most of the vehicle design and associated costs are covered in the LEV II and proposed LEV III FTP regulations. However, for MDVs and MDPVs, staff projects an additional testing cost of $10,000 per test group during the first year of SFTP phase-in due to the additional testing required and testing facility upgrades that could be needed to certify these vehicles to the proposed SFTP requirements. Based on certification data from previous model years, there would be approximately 30 test groups in the affected weight categories, thus yielding a $300,000 fleet-wide cost for SFTP. Based on the emission benefits noted above, the estimated cost-effectiveness of these regulations is approximately $0.20 per pound of NMOG+NOx reduced.

2.3. Proposed Modifications to the Non-Methane Organic Gas Test Procedures

Staff is proposing several modifications to the "California Non-Methane Organic Gas Test Procedures," as last amended July 30, 2002. This document describes the test methods and calculations that are to be used to determine vehicle NMOG mass emissions. Since the document was last amended, NMOG test methods used by ARB to determine NMOG mass emissions have changed. In addition, the calculations to determine NMOG emissions from vehicles operating on alternative fuels were based on M85 (fuel containing 85 percent methanol and 15 percent gasoline). This fuel is no longer available and has been replaced in the commercial fuel market by E85 (fuel containing 85 percent ethanol and 15 percent gasoline). Accordingly, the proposed modifications include updating the test methods and revising the calculation methodology to accommodate E85. Some modifications to align the mass emission

calculation with similar modifications USEPA has indicated that they will make are included.

2.4. Proposed Modifications to the "California Test Procedures for Evaluating Substitute Fuels and New Clean Fuels"

In order to facilitate the marketing of substitute and new clean fuels, in 1993, ARB developed a test procedure[10] designed to assure that any proposed substitute or new clean fuel would not increase emissions from new and used vehicles. This test procedure required a specific mix of model year vehicles and the emission standards to which they were to be certified to be included in the demonstration test fleet. Since that time, vehicle technology and the emission standards to which they certify have changed significantly. As a result, the test fleet required in this test procedure is no longer representative of vehicles operating on the road today. Accordingly, staff is proposing a new test procedure that specifies a test fleet more representative of current new and used vehicles.

3. TECHNOLOGICAL FEASIBILITY OF PROPOSED STANDARDS

Emission control technology has under gone dramatic improvement over the last decade and is well understood by the industry. This section provides a brief discussion of the technology and recent advancements that have been made by both vehicle manufacturers and emission control component suppliers.

3.1. Emission Control Technology

Close-Coupled and Underfloor Catalysts: Catalysts used on today's vehicles typically use a combination of the precious metals rhodium, platinum and/or palladium as the catalytic material to control emissions of three major pollutant categories (hydrocarbons (HC), CO, and NOx). While significant advancements have been made in improving the performance of three-way catalytic converters, further improvements in catalyst design and materials are on-going. One example of this is the development of a "zoned" catalyst where precious metal distribution is optimized for maximum conversion efficiency. This same study demonstrated that optimizing the distribution and composition of the oxygen storage materials in the catalyst and improving the precious metal support structure resulted in a reduction of rhodium sintering, thereby allowing for "thrifting", or reducing, the amount of rhodium used (SAE 2011-01-0296). Other ongoing refinements to catalyst technology such as higher cell density, thin wall substrates and improved catalyst washcoats to enhance oxidation and reduction reactions have further improved catalyst performance.

Because of the continued improvement in the performance of three-way catalysts, most light-duty vehicles are expected to continue using this technology without the need for other aftertreatment devices such as hydrocarbon adsorbers.

[10] "California Test Procedure for Evaluating Substitute Fuels and New Clean Fuels," adopted November 2, 1993.

Improved Catalyst Washcoat and Cell Density: Multi-layer washcoat technologies allow optimization of the amount of the precious metal used in the catalyst by reducing undesired metal-metal and/or metal-base oxide interactions while allowing desirable interactions. Studies have shown that catalyst durability and conversion efficiencies are enhanced with improved washcoats (SAE 2009-01-1070, SAE 2008-01-0812, SAE 2011-01-0301). This improvement in catalyst materials is one of the most significant developments that have enabled manufacturers to meet the SULEV standard at a relatively low cost.

Cell densities for catalysts vary, depending on catalyst location. Typical cell densities for close coupled catalysts used on vehicles meeting SULEV emissions levels are on the order of 600 to 900 cells per square inch (cpsi), with some applications utilizing cell densities as high as 1200 cpsi. These high cell density catalysts with thin wall substrates help reduce catalyst light-off time that is critical for reducing cold-start emissions by decreasing the thermal mass of the catalyst. Furthermore, by maintaining catalyst volume at the same level, using a higher cell density catalyst increases the amount of surface area available for promoting oxidation and reduction reactions.

Increased Catalyst Volume: The ratio of catalyst volume to engine displacement determines the space velocity of the catalyst, which in turn determines the residence time of the exhaust gases in the catalyst. Catalytic converters are sized to provide the optimum space velocity needed to meet the emission standard such that the exhaust gas residence time in the catalyst is sufficient to allow the necessary oxidation and reduction reactions to occur. As a general rule, the larger the displacement of the engine, the larger the volume of the catalyst system that is needed.

Secondary Air: While most vehicles operate lean of stoichiometric or near stoichiometric after a cold-start to reduce engine out emissions, for some vehicle applications this will not be desirable because of driveability concerns. For these vehicles, a brief period of cold operation with a rich A/F mixture may be used to provide more stable combustion and better driveability. However, operating rich at start-up when the engine is cold increases emissions of unburned HC and CO. Therefore, to control these emissions, vehicles that incorporate a rich cold-start fueling strategy are expected to include an electric air injection system, also called secondary air, to inject air upstream of the three-way catalyst so that a stoichiometric A/F ratio at the catalyst can be achieved for optimum emission performance. To further enhance quick catalyst light-off, ignition retard in conjunction with supplemental air may also be utilized to provide additional heat to the catalyst.

Hydrocarbon Adsorber Systems: For some vehicles, particularly those with larger displacement engines, the limiting factor for achieving SULEV emission levels may be controlling HCs at start-up. One possible solution could be the use of a HC adsorber system. Two types of HC adsorber systems for use in motor vehicles have been developed. These systems all operate on the same principle, trapping HC emissions while the catalyst is cold and unable to convert HCs by utilizing an adsorbing material that holds onto the hydrocarbons until the catalyst warms up. One type, commonly

known as an active adsorber system, incorporates valves and channels to bypass the primary catalyst on start-up. With this type of adsorber or HC trap, exhaust is channeled to the adsorber and trapped during cold start before the catalyst has reached light-off. After catalyst light-off, the HC is released and directed to the catalyst for treatment. Another adsorber system, known as a passive adsorber, is much simpler in design (but is less effective) and does not utilize any valves or other moving parts. In this system, HC adsorption material is included in the washcoat of the catalyst. Once the catalyst is warmed up, the heat generated by the catalyst releases the trapped HCs from the absorption material and are then oxidized by the now fully active catalyst. While the principle is simple, the technical solution is not uncomplicated, because adsorption and desorption of the HC must be timed correctly to prevent premature release of unburned HCs (i.e., the HC must be released only after the catalyst has warmed-up).

Optimized Thermal Management: Reducing the time to catalyst light-off is critical to reducing cold-start emissions. One effective approach to reducing catalyst light-off time is to conserve exhaust heat generated by the engine through the use of optimized thermal mass manifolds and insulated exhaust systems. Through the use of laminated air-gap exhaust manifolds and thin double-wall exhaust pipes (i.e., manifolds and exhaust pipes with metal inner and outer walls and an insulating layer of air sandwiched between them), more heat is retained in the exhaust system, enabling quicker catalyst light-off. As an added benefit, the use of insulated exhaust pipes also reduces exhaust noise.

Low Thermal Mass Turbocharger: Since turbochargers are located upstream of the catalyst they absorb some of the exhaust heat before it reaches the catalyst. Consequently, they present a challenge to achieving quick thermal light-off of the catalytic converter in order to reduce cold-start emissions. Reducing the size and weight of the turbocharger would reduce its thermal mass, enabling more of the exhaust heat to reach the catalyst. Lighter, smaller turbochargers would also improve the response time of the turbocharger thereby reducing turbocharger lag (the time the turbocharger takes to respond to a power demand by the driver). These lighter, smaller turbochargers are currently under development.

Reduced Crevice Volumes: Emission performance is also being improved by reducing crevice volumes in the combustion chamber. Unburned fuel can be trapped momentarily in crevice volumes before being subsequently released. Since trapped and re-released fuel can increase engine-out emissions, elimination of crevice volumes is beneficial to emission performance. To reduce crevice volumes, vehicle manufacturers are designing engines to include pistons with reduced top "land heights (the distance between the top of the piston and the first ring). Although reducing the top land height could reduce the durability of the piston, improved design and materials allow moving the ring higher on the piston.

Reduced Oil Consumption: Lubrication oil leaking into the combustion chamber can lead to increased emissions, including emissions of particulate matter, because the

heavier HCs in oil are not easily oxidized and some components in the oil can poison the catalyst, reducing its effectiveness. In addition, oil in the combustion chamber may trap HCs and later release them unburned. This can be particularly problematic for high mileage vehicles as engine wear occurs. To minimize oil consumption, vehicle manufacturers are improving the tolerances and surface finish on cylinders and pistons, improving piston ring design and materials, and improving exhaust valve stem seals to prevent leakage of lubricating oil into the combustion chamber. Virtually all low-emission vehicles with newly redesigned engines incorporate features to reduce oil consumption.

Electronic Exhaust Gas Recirculation (EGR): One of the most effective emission controls for reducing NOx emissions is exhaust gas recirculation. By recirculating spent exhaust gases into the intake manifold to reenter the engine, peak combustion temperatures are lowered, reducing NOx emissions. In the past, EGR systems utilized an electronic EGR valve actuator in order to provide the precisely-controlled EGR rates needed to achieve low NOx levels. Manufacturers are now incorporating variable valve control for improved efficiency and lower engine out emissions that provides an internal EGR function in their engines. This represents another approach for achieving desired EGR rates that may be used solely or in conjunction with electronic EGR valve actuators and cooled exhaust gas.

Air Fuel Ratio Sensor (AFS): Vehicles that employ lean at start A/F control strategies (i.e., use less fuel than required to achieve a stoichiometric ratio) are utilizing AFSs (also called a universal exhaust gas oxygen sensor) for fuel control in lieu of conventional oxygen sensors. This is because conventional oxygen sensors are "limit" switches in that they can only determine that the engine's A/F ratio is higher or lower than stoichiometric; they do not have the capability of recognizing specific A/F ratios. In contrast, AFSs are capable of recognizing a wide-range of A/F ratios since the voltage output of the AFS is "linear" (i.e., each voltage value corresponds to a certain A/F ratio). Therefore, maintaining a lean A/F is attainable with the use of AFS sensors. Since operating lean of stoichiometric during cold-start situations can assist heating of the catalyst, some low-emission vehicles incorporate these sensors. In addition to their capability of maintaining a tight lean A/F, some manufacturers claim AFSs allow the fuel control system to maintain a tighter band around stoichiometric, thereby increasing the efficiency of the catalytic converter. In this way, AFSs assist vehicles in achieving very precise control of the A/F ratio.

Central Mounted Fuel Injector (Solenoid): Manufacturers are expected to incorporate gasoline direct injection (GDI) engines across their vehicle fleets in the future to meet existing and proposed GHG requirements. Gasoline direct injection engines offer significant GHG benefits due to their inherent efficiency advantage over conventional gasoline engines using port fuel injection (PFI). As the nomenclature implies, unlike PFI engines that mix the air and fuel in the intake manifold, GDI engines inject fuel directly into the combustion chamber that enables higher compression ratios and, therefore, improved engine efficiency. However, testing of first generation versions of this technology has demonstrated increased levels of particulate matter (PM) emissions compared to PM emissions of PFI engines. Testing of later versions of GDI engines that use center mounted spray guided fuel injectors has demonstrated the potential for these engines to achieve PM emission levels comparable to PFI engines. Nonetheless, some manufacturers have stated that they believe they can achieve GDI PM emissions levels comparable to that of PFI engines by improving their current side mounted fuel injector systems by using higher pressure injectors and minimizing fuel impingement on valves, cylinder walls, or other combustion chamber surfaces.

Individual Cylinder Air/Fuel (A/F) Control: In order to further improve fuel control, some vehicles utilize software algorithms to achieve individual cylinder fuel control. While dual oxygen sensor systems are capable of maintaining A/F ratios within a narrow range, some vehicle manufacturers believe that even more precise control is needed to achieve low emissions and have developed individual cylinder control systems. On most current vehicles, fuel control is modified whenever the oxygen sensor determines that the combined A/F of all cylinders in the engine or engine bank is too far from stoichiometric. The needed fuel modifications (i.e., inject more or less fuel) are then applied to all cylinders simultaneously. Although this fuel control method will maintain the bulk of A/F for the entire engine or engine bank around stoichiometric, it would not be capable of correcting for individual cylinder A/F deviations that can result from differences in manufacturing tolerances, fuel injector wear, or other factors. With individual cylinder fuel control, A/F variation among cylinders will be diminished, thereby further improving the effectiveness of the emission control system. By modeling the behavior of the exhaust gases in the exhaust manifold and using software algorithms to predict individual cylinder A/F, a feedback fuel control system for individual cylinders can be developed. Except for the replacement of the conventional front oxygen sensor with an AFS sensor and a more powerful engine control computer, no additional hardware is needed in order to achieve individual cylinder fuel control. Software changes and the use of mathematical models of exhaust gas mixing behavior are required to perform this operation. Individual cylinder A/F control also provides an opportunity to reduce precious metal content of the catalyst. Control algorithms for individual A/F cylinder control have been developed using either conventional switching oxygen sensors or wide range air fuel sensors (SAE 2011-01-0710).

Retarded Spark Timing at Start Up: Besides the hardware modifications described above, low-emission vehicles also utilize engine calibration changes such as a brief period of substantial ignition retard, increased cold idling speed, and leaner air-fuel mixtures to quickly provide heat to catalysts after cold-starts. Since only software

modifications are required, engine calibration modifications provide manufacturers with an inexpensive method to quickly achieve light-off of catalytic converters. When combined with close-coupled catalysts and other heat conservation techniques described above, engine calibration techniques can be quite effective at providing the required heat to the catalyst for achieving SULEV emission levels. Heat producing engine calibrations such as described above are already in production and are widely used on low-emission vehicles.

Diesel Vehicles: In response to existing and proposed GHG and fuel economy requirements, some manufacturers are planning to increase the percentage of diesel vehicles in their new vehicle fleet. Due to increased levels of engine out NOx from diesel engines, this can present a challenge to achieving SULEV emissions for them. Significant work is underway by these manufacturers to improve the emission performance of diesel vehicles and at least one diesel emission control system with the potential to achieve SULEV emissions has been described in the technical literature (SAE 2008-01-0449). This system incorporates a hydrocarbon trap and diesel oxidation catalyst upstream of a lean NOx trap (LNT) and a catalyzed soot filter. The SULEV system was based on a Tier 2 Bin 5 system for a 2.8 liter diesel engine and demonstrated the potential to meet SULEV emissions at 120,000 miles without increasing catalyst volume and precious metal loading. Staff anticipates that future diesel vehicles will use a selective catalyst reduction (SCR) system rather than a LNT in order to meet US06 emission requirements. In a SCR system, a reduction agent such as urea is injected into the SCR system to promote the reduction of NOx, instead of trapping and then reducing NOx using a LNT. Staff expects that similar improvements to enable SCR systems to achieve SULEV emissions will be developed.

Direct Ozone Reduction Technologies (DOR): DOR devices involve special coatings on radiators or other surfaces in such a way that the amount of ozone in the ambient air, which crosses through or across such surfaces, is reduced. The Air Resources Board considers these devices to be emission control devices since the NMOG credit accrued by such devices is used to offset the exhaust or evaporative emissions of motor vehicles. Therefore, the manufacturer must demonstrate the performance and durability of such devices for the full useful life of the vehicle, provide an onboard diagnostic system to, at minimum, monitor the presence of the device, and provide the appropriate emission control warranty.

3.2. Projected Emission Control Technology Application Rates (Passenger Cars and Trucks Less Than 8,501 lbs. GVWR)

From the foregoing list of technologies, it is clear that manufacturers have a wide range of options available to achieve SULEV emissions and that many of these technologies are already being used today on vehicles meeting the SULEV standard. Table II-A-3-1 below lists the additional emission control technology application rates that staff determined may be needed to meet LEV III requirements, over and above those currently used on low-emission vehicles. A discussion of the associated costs to meet LEV III requirements can be found in section II.A.4.

Table II-A-3-1. Additional Emission Control Technology (Passenger Cars and Trucks Less Than 8,501 lbs. GVWR)

Additional Emission Control Technology Requirements												
Technology component	From ULEV125 to SULEV						From LEV160 to SULEV					
	PC/LDT1 (No of cylinders)			LDT2 (No of cylinders)			PC/LDT1 (No of cylinders)			LDT2 (No of cylinders)		
	4	6	8	4	6	8	4	6	8	4	6	8
Greater catalyst loading	100%	100%	100%	100%	100%	100%	100%	100%	100%	100%	100%	100%
Optimized close-coupled catalyst(s)	0%	0%	0%	0%	0%	0%	50%	60%	75%	50%	60%	75%
Secondary air	0%	25%	75%	0%	25%	75%	0%	25%	75%	0%	25%	75%
HC adsorber (active)	0%	0%	0%	0%	0%	15%	0%	0%	0%	0%	0%	15%
Optimized thermal mass manifold	25%	25%	25%	25%	25%	25%	25%	25%	25%	25%	25%	25%
Low thermal mass turbocharger	0%	0%	0%	0%	0%	15%	0%	0%	0%	0%	0%	15%
Evap equip	100%	100%	100%	100%	100%	100%	100%	100%	100%	100%	100%	100%

Table II-A-3-2 below lists emission control technologies that generally are already used on current low-emission vehicles, or will likely be incorporated on future vehicles to meet other requirements such as greenhouse gas emission (GHG) requirements. For example the use of centrally mounted fuel injection in GDI engines can provide stratified air/fuel mixtures in lean-burn engines that combust more completely to reduce NMOG and PM emissions while also reducing CO_2 emissions. Similarly, digital valve control in conjunction with turbocharging and downsized engines can provide lower NOx emissions via multiple valve events in each engine cycle while reducing CO_2 emissions.

Table II-A-3-2. Low-Emission Vehicle Additional Emission Control Technology

Systems that May Used to Some Extent												
Technology Component	From ULEV125 to SULEV						From LEV160 to SULEV					
	PC/LDT1 (No of cylinders)			LDT2 (No of cylinders)			PC/LDT1 (No of cylinders)			LDT2 (No of cylinders)		
	4	6	8	4	6	8	4	6	8	4	6	8
Double layer washcoat & cell density	X	X	X	X	X	X	X	X	X	X	X	X
Engine modifications	X	X	X	X	X	X	X	X	X	X	X	X
Central mounted fuel injector (solenoid)	X	X	X	X	X	X	X	X	X	X	X	X
Air Fuel Sensor	X	X	X	X	X	X	X	X	X	X	X	X
Air-assisted fuel injection	X	X	X	X	X	X	X	X	X	X	X	X
Individual cylinder fuel control	X	X	X	X	X	X	X	X	X	X	X	X
Retarded spark timing at start-up	X	X	X	X	X	X	X	X	X	X	X	X
Direct ozone reduction (e.g., Premair)	X	X	X	X	X	X	X	X	X	X	X	X
Digital valve control	X	X	X	X	X	X	X	X	X	X	X	X

3.3. Projected Emission Control Technologies (Medium-Duty Vehicles (8,501 - 14,000 lbs. GVW)

Staff performed a similar evaluation of the additional hardware needed for medium-duty vehicles. Staff determined that all gasoline medium-duty vehicles would require additional catalyst loading and 25 percent would need thermally optimized manifolds. Similarly, 25 percent of diesel fueled vehicles would require thermally optimized manifolds and 100 percent would need improved selective catalyst reduction (SCR) systems. Table II-A-3-3 below lists the additional hardware for gasoline medium-duty vehicles that may be needed to meet LEV III requirements.

Table II-A-3-3. Additional Emission Control Components (Gasoline Medium-Duty Vehicles)

	Technology Component	Percent of Technology Needed	
		8,501-10,000 lbs GVWR	10,001-14,000 lbs GVWR
		8-cylinder	
Systems with additional technology costs	Greater catalyst loading	100%	100%
	Optimized close-coupled catalyst(s)	0%	0%
	Secondary air	0%	0%
	HC adsorber (active)	0%	0%
	Optimized thermal management	25%	25%
	Low thermal mass turbocharger	0%	0%
	Evaporative equipment	100%	100%

Table II-A-3-4 below lists the additional emission control technologies staff determined would be required for diesel fueled medium-duty vehicles to meet the proposed emission standards.

Table II-A-3-4. Additional Emission Control Components (Diesel Medium-Duty Vehicles)

	Technology Component	Percent of Technology Needed	
		8,501-10,000 lbs GVWR	10,001-14,000 lbs GVWR
		8-cylinder	
Systems with additional technology costs	Greater catalyst loading	0%	0%
	Optimized close-coupled catalyst(s)	0%	0%
	Secondary air	0%	0%
	HC adsorber (active)	0%	0%
	Optimized thermal management	25%	25%
	Low thermal mass turbocharger	0%	0%
	SCR optimization	100%	100%

4. COST ANALYSIS

4.1. Cost methodology

Costs affecting vehicle price are generally assigned to direct costs (cost of hardware to the manufacturer) and indirect costs (research and development, warranty, corporate salaries, pensions, health care, transportation, dealer support and marketing). In past rulemakings, staff developed retail price equivalent factors (RPE) that assumed incremental increases in direct costs resulted in a constant percentage increase to all indirect costs. In general, RPE can be expressed by:

$$RPE = (\text{direct costs} + \text{indirect costs} + \text{profit})/(\text{direct manufacturing costs})$$

In this cost analysis, staff relied on recent work by the USEPA that developed a modified multiplier, referred to as an indirect cost multiplier (ICM), by evaluating the components of indirect costs that are most likely to be affected by regulation-induced vehicle modifications. For example, while an improved catalyst may contain greater precious metal loading and therefore higher direct cost to the manufacturer, there is no reason to expect that this would result in increased labor costs or other indirect costs such as pension and health costs to install the catalyst in a vehicle. The ICMs developed by this work also included a more refined approach to determine indirect costs by taking into consideration the complexity of the technology employed (see Rogozhin et al 2009, 2010). The ICMs have been further refined in the latest technical analysis by USEPA (see USEPA and NHTSA, 2011c). Based on the latest USEPA development of the ICM factors, Table II-A-4-1 below lists the ICMs that are applied in this incremental cost analysis.

Table II-A-4-1. Indirect Costs Multipliers

Complexity	Indirect Cost Multiplier
	Long-Term
Low	1.19
Medium	1.29

As a first step, staff performed a comprehensive cost analysis of direct costs for the proposed LEV III exhaust emission requirements applicable to passenger car, light-duty trucks and medium-duty vehicles. Specifically, staff estimated the incremental direct component costs of a SULEV30 vehicle compared to a LEV160 vehicle and a ULEV125 vehicle for passenger cars and light-trucks less than 8500 lbs. GVWR for four-, six-, and eight-cylinder applications. These comparisons were chosen because their costs represent the highest costs manufacturers would incur in achieving SULEV emission levels across their fleet. Model year 2008 California new vehicle fleet, the latest year complete fleet data were available, was used to determine the fleet mix of vehicles using four-, six-, and eight-cylinder engines in each of the vehicle categories of PC/LDT1 and LDT2. Table II-A-4-2 below shows a breakdown of the new vehicle fleet mix for the 2008 model year. Staff notes that this cost assessment is inherently conservative for several reasons. The projected technology requirements for model year 2025 represent component costs for all vehicles to meet the most stringent requirements of LEV III (whereas some models will utilize less stringent certification levels, e.g., ULEV50). In addition, based on manufacturers' plans, it appears likely that by 2025 a greater portion of the fleet will consist of vehicles using downsized engines that have the lower compliance costs.

Table II-A-4-2. 2008 California Fleet Emission Certification Level Mix

Category	Certification Level	4-cyl	6-cyl	8-cyl
PC/LDT1	LEV	44%	45%	12%
	ULEV	64%	29%	8%
	SULEV	79%	20%	0%
LDT2	LEV	8%	71%	20%
	ULEV	3%	59%	38%
	SULEV	53%	47%	0%
PC/LDT1	overall	66%	28%	6%
LDT2	overall	7%	61%	32%

In assessing the incremental costs, staff first defined the additional systems and technologies that would be used by manufacturers to meet the proposed emission levels. Staff relied on confidential information provided by vehicle manufacturers, emission control component suppliers, the technical literature and staff's engineering evaluation of the likely need for additional emission control hardware. In addition, staff worked closely with the USEPA in developing these costs, since the goals of LEV III

and the federal Tier 3 program currently under development are very similar (fleet SULEV emissions levels in 2025).

After considerable discussion, a consensus was reached on the most likely configurations of emission control systems needed to meet LEV III program requirements. Tables II-A-3-1 above list staff's evaluation of the additional emission control components needed to meet SULEV30 emission levels.

4.2. Cost Analysis

4.2.1. Passenger cars and Light-Duty Trucks

Once the most likely additional emission hardware likely to be used to meet SULEV emissions had been determined, staff then assigned costs for each component. Costs for these components were derived from vehicle manufacturers, emission control component suppliers and staff assessment of existing data. Tables II-4-1 and Table II-4-2 in list the manufacturers' direct costs for additional emission control components and the resulting incremental increase in vehicle price in 2025 in 2009 dollars. Annual cost reductions of 3% per year for 2015-2020 and 2% per year for 2021-2025 were applied to the direct costs to reflect reductions in manufacturing costs due to learning and continual technical improvements in emission control technology. A Low complexity long-term ICM of 1.19 was applied to all components, with the exception of the HC adsorber where a Medium long-term ICM of 1.29 was used to reflect the increased complexity of incorporating this component into the vehicle emission control system. Staff assigned no additional costs for compliance with the proposed PM standards for two reasons. First, staff concluded that, since the proposed PM standards would be met by engine modifications during the normal course of engine development, no incremental increase in vehicle price would occur as a result. In addition, staff is optimistic that real-time measurement procedures would be developed in the requisite timeframe such that costs for any additional PM testing facilities would be negligible on a per-vehicle basis.

Table II-4-1 Cost of Additional Emission Control Components (LEV160 to SULEV30)

	Technology Component	From LEV to SULEV					
		PC/LDT1			LDT2		
		4-cyl	6-cyl	8-cyl	4-cyl	6-cyl	8-cyl
Systems with additional technology costs	Greater catalyst loading	$47	$62	$78	$47	$62	$78
	Optimized close-coupled catalyst(s)	$8	$19	$35	$8	$19	$35
	Secondary air	$0	$19	$58	$0	$19	$58
	HC adsorber (active)	$0	$0	$17	$0	$0	$17
	Optimized thermal management	$6	$6	$6	$6	$6	$6
	Low thermal mass turbocharger	$0	$0	$0	$0	$0	$0
	Evap equip	$13	$13	$13	$13	$13	$13
Total incremental cost		$73	$119	$207	$73	$119	$207
Total incremental price		$87	$142	$248	$87	$142	$248

Table II-4-2 Cost of Additional Emission Control Components (ULEV125 to SULEV30)

	Technology Component	From ULEV to SULEV					
		PC/LDT1			LDT2		
		4-cyl	6-cyl	8-cyl	4-cyl	6-cyl	8-cyl
Systems with additional technology costs	Greater catalyst loading	$23	$31	$39	$23	$31	$39
	Optimized close-coupled catalyst(s)	$0	$0	$0	$0	$0	$0
	Secondary air	$0	$19	$58	$0	$19	$58
	HC adsorber (active)	$0	$0	$17	$0	$0	$17
	Optimized thermal management	$6	$6	$6	$6	$6	$6
	Low thermal mass turbocharger	$0	$0	$0	$0	$0	$0
	Evap equip	$13	$13	$13	$13	$13	$13
Total incremental cost		$42	$69	$134	$42	$69	$134
Total incremental price		$50	$83	$161	$50	$83	$161

4.2.2. Medium-Duty Vehicles

Staff performed a similar cost analysis of the additional hardware needed for medium-duty vehicles. Again, costs for these components were derived from vehicle manufacturers, emission control component suppliers and staff judgment. Table II-A-4-3 below lists the incremental hardware for gasoline medium-duty vehicles that may be needed to meet LEV III requirements.

Table II-A-4-3. Additional Emission Control Components (Gasoline Medium-Duty Vehicles)

	Technology Component	Cost of Technology Needed	
		8,501-10,000 lbs GVWR	10,001-14,000 lbs GVWR
		8-cylinder	
Systems with additional technology costs	Greater catalyst loading	$40	$40
	Optimized close-coupled catalyst(s)	$0	$0
	Secondary air	$0	$0
	HC adsorber (active)	$0	$0
	Optimized thermal management	$6	$6
	Low thermal mass turbocharger	$0	$0
	Evaporative equipment	$17	$17
Total incremental direct cost		$62	$62
Total incremental vehicle price		$75	$75

Table II-A-4-4 lists the additional hardware that may be needed for diesel medium-duty vehicles.

Table II-A-4-4. Additional Emission Control Components (Diesel Medium-Duty Vehicles)

	Technology Component	Cost of Technology Needed	
		8,501-10,000 lbs GVWR	10,001-14,000 lbs GVWR
		8-cylinder	
Systems with additional technology costs	Greater catalyst loading	$0	$0
	Optimized close-coupled catalyst(s)	$0	$0
	Secondary air	$0	$0
	HC adsorber (active)	$0	$0
	Optimized thermal management	$6	$6
	Low thermal mass turbocharger	$0	$0
	Evaporative equipment	$0	$0
	SCR optimization	$40	$40
Total incremental direct cost		$45	$45
Total incremental vehicle price		$54	$54

4.3. Incremental Cost of the Standards

From the cost analysis described above, the following conclusions are drawn.

- Based on the 2008 fleet breakdown by engine size and initial certification level, the projected average incremental retail prices for light-duty LEV III vehicles in 2025 are shown in Table II-A-4-5.

Table II-A-4-5. Incremental vehicle price increase for 2025 criteria pollutant compliance

Vehicle Category	Initial baseline certification level	Engine size			Average incremental price[a] ($/vehicle)	Average incremental price[b] ($/vehicle)
		4-cyl	6-cyl	8-cyl		
PC/LDT1	LEV	$87	$142	$248	$130	$55
	ULEV	$50	$83	$161	$68	
	SULEV	$0	$0	$0	$0	
LDT2	LEV	$87	$142	$248	$159	$117
	ULEV	$50	$83	$161	$111	
	SULEV	$0	$0	$0	$0	

[a] *Sales-weighted average for each initial certification level*
[b] *Sales-weighted average for vehicle category*

- The average cost-effectiveness of light-duty vehicles meeting the LEV III program exhaust requirements relative to the 2008 fleet is approximately $4.00 per pound of NMOG + NOx reduced. Motor vehicle control measures typically range up to $5 per pound of emissions while stationary source controls range up to $10 per pound of emissions reduced.

- The projected average incremental price increase in 2025 for medium-duty

vehicles is $75 for gasoline fueled vehicles and $54 for diesel fueled vehicles.

5. OUTSTANDING ISSUES

While developing this proposal, staff worked with the USEPA in an effort to provide as much consistency as possible between LEV III requirements and the federal Tier 3 program currently under development, while still meeting California criteria emission reduction needs. In addition, California test procedures contain extensive references to sections of the federal Code of Federal Regulations (CFR) pertaining to test procedures and protocols for demonstration of compliance to the emission standards. Since the Tier 3 program is not expected to be finalized and incorporated into the CFR until sometime in 2012 after the scheduled Board hearing for LEV III, staff will need to update the test procedure references subsequent to the Board's consideration of the LEV III regulations. If Tier 3 is finalized and the CFR updated with sufficient time remaining before the LEV III regulatory package is due to the Office of Administrative Law, staff plans to issue a 15-day notice on the revisions to the test procedure references. Otherwise, staff will return to the Board after these amendments are adopted in final form, to present updated test procedures for the Board's consideration.

6. REGULATORY ALTERNATIVES TO EXHAUST CRITERIA POLLUTANT EMISSION PROPOSAL

As noted in the introduction to section II, significant reductions of criteria emissions are needed if California is to achieve federal and state health based air quality standards. Staff has presented a LEV III proposal above that it believes achieves the maximum cost-effective and feasible reductions for the timeframe considered. The proposed LEV III program will result in significant emission reductions from the light-duty fleet by 2025 and beyond. Nonetheless, staff considered three alternatives to the proposed LEV III program in an effort to determine whether other approaches could achieve equivalent or greater emission reductions.

6.1. Do Not Amend Current California LEV Program

Many areas of California are still designated as non-attainment for federal and State ambient air quality standards. Light- and medium-duty vehicles are a major contributor to the emission inventory and with increasing vehicle population and vehicle miles traveled, their contribution to the emission inventory will also increase. In order to achieve healthful air quality and make further progress towards meeting federal and State ambient air quality standards, further reductions in mobile source emissions are needed. In addition, California's LEV program for criteria pollutants would likely differ from, and be less stringent than, comparable federal standards, presenting a potential issue for EPA's consideration of California's request for a waiver pursuant to Clean Air Act Section 209(b). As a result, staff believes that not amending the LEV III criteria pollutant standards is not a reasonable alternative.

6.2. Adopt Less Stringent Standards

Staff believes that consideration of less stringent standards would put the State at risk of not achieving the emission reduction goals of the SIP. Given the large amount of emission reductions that are still needed to achieve federal and State ambient air quality standards, staff believes that any relaxation of the LEV III proposal would seriously impact California's ability to achieve its air quality goals.

6.3. Adopt More Stringent Standards

The proposed LEV III program requires new light-duty fleet emissions to be reduced to SULEV NMOG and NOx emission levels by 2025. This represents an emission level that approaches the very low power plant emissions associated with the recharging of battery electric vehicles. In developing the LEV III proposal, staff held numerous meetings with vehicle manufacturers and emission component suppliers in order to determine the most cost-effective approach to achieving these low levels given manufacturers' resource constraints of lead-time and costs to incorporate advanced emission control technology across their vehicle lines. Staff determined that requiring a more aggressive reduction in fleet emissions would result in substantial vehicle cost increases to the consumer and place a significant compliance burden on the manufacturers without a commensurate reduction in emissions.

B. CALIFORNIA'S EVAPORATIVE EMISSION REGULATIONS

1. BACKGROUND

1.1. Evaporative Emissions

Evaporative emissions consist of fuel hydrocarbon vapors from a motor vehicle, which are released into the atmosphere. Evaporative emissions are classified into three types: running loss, hot soak, and diurnal. Running loss emissions occur during vehicle operation, originating from various sources within the fuel system and from fuel vapor overflow of the on-board carbon canister. Hot soak emissions occur immediately after the termination of engine operation, when latent engine heat vaporizes residual fuel in the engine system. Diurnal emissions are caused by daily cycling of ambient temperatures when a vehicle is parked, where ambient temperature increases result in fuel tank vapor generation. Another type of emissions, refueling emissions, occurs during refueling of the vehicle when the entering liquid fuel volumetrically displaces the fuel vapors in the fuel tank.

One main source of vehicular evaporative emissions is the carbon canister, where excess vapors in the fuel tank are routed for storage instead of being released into the atmosphere. In many evaporative emission systems, the canister also captures fuel tank vapor emissions during refueling as part of onboard refueling vapor recovery (ORVR.) The carbon canister is regenerated during vehicle operation when the fuel vapors stored in the canister are purged into the engine's intake system and subsequently burned in the combustion process. Substantial evaporative emission

losses from the canister occur when the generated fuel tank vapors routed to the canister are greater than its storage capacity, and thus, hydrocarbon escape from the canister into the atmosphere. In addition, small evaporative losses from the canister, called bleed emissions, result when hydrocarbon emissions escape the canister due to diffusion of adsorbed hydrocarbons as the vehicle rests over a period of time. Another main source of evaporative emissions is through permeation of fuel through elastomeric hoses, joints, and valves, as well as through plastic fuel tanks.

1.2. Current Evaporative Standards and Test Procedures

Compliance with the current evaporative emission regulations, adopted as part of the LEV II Program, is based on meeting three separate certification "whole vehicle" emission standards. Specifically, these include the running loss emission standard, the three-day diurnal plus high-temperature hot soak (three-day) emission standard, and the two-day diurnal plus moderate-temperature hot soak (two-day) emission standard.[11] The running loss emission standard ensures evaporative emission control during vehicle driving. The three-day emission standard ensures that the evaporative system can control evaporative emissions for three consecutive hot summer days. The two-day emission standard ensures an effective purging strategy of the vehicle carbon canister. These standards are shown in Table II-B-1-1.

As an option, a manufacturer may certify its passenger cars and light-duty trucks to more stringent requirements by complying with zero-evaporative emission standards. Specifically, these requirements consist of more stringent three-day and two-day whole vehicle emission standards, as well as a "zero" fuel evaporative emission standard. Over the two-day and three-day test procedures, passenger cars must meet a 0.35 grams per test hydrocarbon emission standard (higher levels are allowed for larger vehicles as shown in Table II-B-1-1), which includes fuel and non-fuel hydrocarbon emissions. They must also meet the zero-evaporative emission standards, which require a vehicle to emit no more than 0.054 grams per test of fuel-only evaporative emissions. Currently, manufacturers certify to zero-evaporative emission standards in order to qualify for PZEV credits under the ZEV regulatory mandate. This can occur only if the vehicle's exhaust emissions are also certified to SULEV exhaust standards with a 150,000-mile useful life and a 150,000 mile warranty.

[11] Compliance with the running loss and three-day emission standards is demonstrated over a three-day diurnal test procedure. Compliance with the two-day emission standard is demonstrated over a two-day diurnal test procedure.

Table II-B-1-1. Current LEV II evaporative emission standards

Vehicle type	Hydrocarbon standards		
	Running loss (grams per test)	Three-day diurnal plus hot soak (grams per test)	Two-day diurnal plus hot soak (grams per test)
Passenger cars	0.05	0.50	0.65
Light-duty trucks 6,000 lbs. GVWR and under	0.05	0.65	0.85
Light-duty trucks from 6,001-8,500 lbs. GVWR	0.05	0.90	1.15
Medium-duty vehicles (8,501-14,000 lbs. GVWR)	0.05	1.00	1.25
Heavy-duty vehicles (over 14,000 lbs. GVWR)	0.05	1.00	1.25

1.3. Rulemaking Considerations

In the 2010 model year, 28 percent of passenger cars and light-duty trucks were certified (as PZEVs) to the zero-evaporative emission standards. As part of the proposed Advanced Clean Cars Program, the proposed changes to the ZEV program[12] would disallow conventional gasoline vehicles to accrue PZEV credits beyond the 2018 model year. Thereafter, no incentive exists to certify a vehicle to meet the zero-evaporative emission standards, and thus, mandatory regulatory requirements are needed to continue and increase zero-evaporative certified vehicles. The proposed LEV III evaporative emission standards would not only continue the zero-evaporative requirements beyond 2018 for PZEVs but also extend them to the remaining vehicles in the passenger car and light-duty truck vehicle categories as well as to the heavier vehicle categories.

Another major consideration that surfaced during the rulemaking process was the requirement to demonstrate compliance with the fuel-only emission standard. This demonstration currently requires the construction of an apparatus, or "rig", composed of fuel and evaporative system components (e.g., the fuel tank, fuel hoses, carbon canister, etc.) for each zero-evaporative emission family. The rig is used to demonstrate compliance with the 0.0 grams per test emission standard over the two-day and three-day test procedures. Under the current regulations, this demonstration does not impose a significant burden on manufacturers because the number of vehicles certifying to the zero-evaporative emission standard is relatively low. However, manufacturers contend that the proposed regulations (i.e., requiring all vehicles to comply with the zero-evaporative emission standard) would result in a significantly increased testing burden. Thus manufacturers have requested that the rig test requirement be eliminated. Manufacturers have argued that the rig test is unnecessary because the whole vehicle evaporative emission standards are low enough to ensure sufficient control of fuel evaporative emissions. Staff disagrees. Current certification

[12] Proposed revisions to ARB's ZEV Program are a separate but concurrent rulemaking as part of the Advanced Clean Cars package of regulatory measures.

data on zero-evaporative emission families show that 8 percent of families are certified to whole-vehicle diurnal plus hot soak emission levels less than 0.150 grams per test compared to a 0.35 grams per test emission standard. If the rig test is eliminated, the opportunity would exist for a manufacturer to increase fuel emissions on these low-certifying zero-evaporative vehicles but still comply with the whole-vehicle emission standards. To resolve this issue, staff's proposal includes a compliance option (Option 2) that addresses both staff's and manufacturers' concerns.

2. SUMMARY OF PROPOSED AMENDMENTS

2.1. Proposed Evaporative Emission Standards

To maintain continuity of vehicles certified to the zero-evaporative emission standards and to expand the use of existing zero-evaporative technology to the remaining vehicle classes, staff proposes to require all passenger cars, light-duty trucks, medium-duty vehicles, and heavy-duty vehicles that are gasoline-fueled, liquefied petroleum gas-fueled, and alcohol-fueled, to comply with the zero-evaporative emission standards. This would require amending section 1976, title 13, California Code of Regulations (CCR) (Appendix A) and the incorporated "California Evaporative Emission Standards and Test Procedures for 2001 and Subsequent Model Motor Vehicles" (Appendix F). The proposed lower evaporative emission standards are equivalent in stringency to the optional LEV II zero-evaporative emission standards.

2.1.1. Compliance Options

Two options for complying with the zero-evaporative emission standards are proposed. Note that the current running loss emission standards and the vehicle evaporative durability requirement (also known as "useful life") of 15 years or 150,000 miles, whichever first occurs, would remain unchanged from LEV II levels.

a. Option 1 – Whole-vehicle plus fuel-only evaporative emission standards

In this option, the proposed evaporative emission standards for passenger cars and light-duty trucks are identical to the current optional zero-evaporative emission standards which are currently used by manufacturers to earn PZEV credits, as shown in Table II-B-2-1. However, the proposed Option 1 whole-vehicle emission standards are 35 to 46 percent lower than the current non-zero-evaporative LEV II two-day emission standard and 17 to 30 percent lower than the current non-zero-evaporative LEV II three-day emission standard, depending on the vehicle type.

Table II-B-2-1. Proposed option 1 evaporative emission standards

Vehicle type	Hydrocarbon emission standards		
	Running loss (grams per miles)	Three-day diurnal + hot soak, and two-day diurnal + hot soak	
		Whole vehicle (grams per test)	Fuel only (grams per test)
Passenger car	0.05	0.350	0.0
Light-duty truck 6,000 lbs. GVWR and under	0.05	0.500	0.0
Light-duty truck from 6,001-8,500 lbs. GVWR	0.05	0.750	0.0
Medium-duty passenger vehicle	0.05	0.750	0.0
Medium-duty vehicle (8,501-14,000 lbs. GVWR)	0.05	0.750	0.0
Heavy-duty vehicle (over 14,000 lbs. GVWR)	0.05	0.750	0.0

b. Option 2 – Whole-vehicle evaporative emission standards with a fleet average option and a canister bleed test requirement

Option 2 would provide manufacturers another compliance path while maintaining the same stringency level as Option 1. To address manufacturers' concern of an overly burdensome rig test, Option 2 would eliminate this requirement. But to maintain and ensure adequate fuel evaporative control, two other major revisions, compared to Option 1, are proposed. Specifically, for Option 2, staff proposes to increase the stringency of the whole-vehicle emission standards and require manufacturers to demonstrate compliance with a new "canister bleed test, which verifies the vehicle's ability to prevent hydrocarbon diffusion from the canister into the atmosphere."[13] The proposed Option 2 emission standards are shown in Table II-B-2-2. The canister bleed test would ensure that the vehicle's carbon canister is optimally designed using the best control technology and that adequate canister purge occurs during vehicle operation. Based on staff's discussions with emission control industry experts, canister bleed emission values from current zero-evaporative systems are below the level of detection and therefore meet the proposed emission standards, with the exception of a few hybrid vehicles. As described in the subsequent technology section, staff believes additional technologies may be needed in some cases to enable hybrid systems to meet the proposed standard. Staff is confident that the combination of the lower whole-vehicle standard and the canister bleed test would be equally effective in ensuring equivalent emission control as compared to the current zero-evaporative emission standards.

Option 2 would also allow manufacturers to demonstrate compliance with the proposed diurnal plus hot soak emission standard through fleet averaging. For example, if a manufacturer's evaporative fleet average certification emission level for a particular

[13] The canister bleed test, significantly less costly and burdensome compared to the rig test, is described in further detail in section II.B.2.1.4, "Test Procedure Modifications."

emission standard category equals, or is less than, the applicable emission standard, the manufacturer would be in compliance for that given emission standard category. However, if the manufacturer's fleet average level for an emission standard category exceeds the applicable emission standard, the manufacturer would incur evaporative emission debits and be required to offset these debits within three model years with emission credits earned in previous or subsequent model years. If the debits are not offset after the three model year period, the manufacturer may be subject to civil penalties. Under this proposed fleet averaging provision, evaporative emission credits could be used for the five model years following the model year in which they are earned to offset any evaporative emission debits in the same emission standard category. Furthermore, the manufacturer may also use the emission credits from the passenger car and smallest light-duty truck emission standard category to offset debits from other emission standard categories at the end of the debit offset period.

Under Option 2, compliance determination using the three-day and two-day test results would differ from the methodology used in the existing regulations. The current methodology uses the three-day and two-day test results and compares them individually with their respective emission standards for each test. However, under the proposed Option 2, the higher emission result between the two tests would be used to determine compliance with the emission standard.

Table II-B-2-2. Proposed option 2 evaporative emission standards

Vehicle type	Hydrocarbon emission standards		
	Running loss (grams per test)	Highest diurnal plus hot soak (grams per test)	Canister bleed (grams per test)
Passenger car; and Light-duty truck 6,000 lbs. GVWR and under, and 0 – 3,750 lbs. LVW	0.05	0.300	0.020
Light-duty truck 6,000 lbs. GVWR and under, and 3,751 – 5,750 lbs. LVW	0.05	0.400	0.020
Light-duty truck 6,001 - 8,500 lbs. GVWR; and Medium-duty passenger vehicle	0.05	0.500	0.020
Medium-duty vehicles (8,501 – 14,000 lbs. GVWR); and Heavy-duty vehicle (over 14,000 lbs. GVWR)	0.05	0.600	0.030

2.1.2. Proposed Implementation Schedule

The proposed implementation of the LEV III evaporative emission standards would begin in the 2015 model year and be phased in through the 2022 model year, as shown in Table II-B-2-3. In the 2015 through 2017 model years, the proposed minimum percent requirement would be the average percentage of vehicles generating PZEV credits in a manufacturer's vehicle fleet for the previous three model years, i.e., 2012, 2013, and 2014. The proposed 2015 through 2017 model year requirement would ensure that a manufacturer maintains at least the same percentages of zero-evaporative vehicles as previous model years. The proposed phase-in of the LEV III evaporative standards would increase to 60 percent in the 2018 model year, to 80 percent in the 2020 model year, and to full implementation in the 2022 and later model years.

An alternate phase-in schedule to comply with the phase-in requirements is also proposed, which would provide added flexibility to manufacturers. The alternate phase-in schedule would allow manufacturers to select phase-in percentages that are different than those indicated in Table II-B-2-3 so long as it is shown that an equivalent weighted compliance volume of phased-in vehicles would be achieved by 2022. This alternative phase-in schedule could only be applied to the 2018 through 2022 model years.

Table II-B-2-3. Proposed evaporative standard implementation schedule

Model year	Minimum percentage of vehicle fleet
2015 to 2017	Average of previous 3 model year PZEVs
2018 to 2019	60
2020 to 2021	80
2022 and subsequent	100

2.1.3. E10 Certification Fuel Phase-In Schedule

As part of the Advanced Clean Cars Program, staff is proposing to amend certification test fuel specifications by eliminating required testing with MTBE laden fuel, and requiring 10 percent ethanol by volume instead, as discussed in section IV. This proposed modification would better align the specifications of certification test fuel with the properties of in-use fuel. It is proposed that all vehicles certifying to the LEV III evaporative emission standards would be certified using the proposed test fuel with 10 percent volume ethanol, and that by the 2020 model year all evaporative emission certifications would be certified using the proposed test fuel with 10 percent volume ethanol.

2.1.4. Test Procedure Modifications

As briefly mentioned earlier, a canister bleed test would be required when certifying under Option 2. This proposed test procedure involves component testing of the vehicle's carbon canister while connected to the vehicle's fuel tank, and generally

mimics the two-day test procedure. In this procedure, the canister would be stabilized to a 4,000-mile test condition and preconditioned through loading and purging. The canister would then be connected to the fuel tank vent port, and both the canister system and the fuel tank placed in a testing enclosure where the ambient temperature is cycled between 65°F and 105°F, for a period of two 24-hour cycles. To determine compliance with the proposed canister bleed test, the amount of hydrocarbons emitted over each 24-hour period would have to be equal to or less than the proposed emission standard. The proposed canister bleed test requires substantially less time and is less labor-intensive than the rig test manufacturers currently perform for the zero-evaporative emission standards, although the canister bleed test is not as comprehensive as the rig test, which tests every evaporative emission control and fuel system component. However, staff believes the proposed canister bleed test and standards coupled with the proposed Option 2 lower whole vehicle standards would be equally effective in ensuring equivalent emission control as the current zero-evaporative emission standards.

2.1.5. Pooling Evaporative Emissions from California and Section 177 States

Beginning in 2015, staff is proposing to provide an option to allow compliance with the fleet average Highest Diurnal plus Hot Soak requirement, set forth in section II.B.2.1.1.b., be demonstrated using the pooled fleet average of the Highest Diurnal plus Hot Soak emission values of new vehicles produced and delivered for sale in California and all states, including the District of Columbia if applicable, that adopt California's evaporative emission requirements for light-, medium-, and heavy-duty vehicles. Staff is also proposing to allow pooling to comply with the phase-in requirements discussed in section II.B.2.1.2. Manufacturers that choose this option would be required to report the number of vehicles produced and delivered for sale and the emission standards, and family emission limits, if applicable, to which they are certified for each state, and the District of Columbia if applicable, that adopts California emission requirements. Including this provision provides additional compliance flexibility to vehicle manufacturers, particularly with respect to meeting a separate fleet average requirement in those states with limited new vehicle sales. While this represents a departure from past practice, staff believes that the emission impact of this provision within California and states that adopt California requirements will be minor due to the very low level of fleet emissions required by this program.

2.2. Proposed Onboard Refueling Vapor Recovery (ORVR) Amendments

The ORVR regulations were previously updated in 2009 for changes related to plug-in hybrid vehicles. The changes proposed in LEV III are to bring the applicability of ORVR standards into alignment with the current federal regulations and expected Tier 3 amendments to 40 CFR §86-1811-04(e)(3). California's current ORVR standards (13 CCR §1978) only apply to vehicles up to 8,500 pounds GVWR. The proposed change would increase the applicability of the ORVR requirements to complete vehicles up through 14,000 pounds GVWR inclusive. The proposed regulatory language for section 1978, title 13, CCR is provided in Appendix A. The "California Refueling Emission

Standards and Test Procedures for 2001 and Subsequent Model Motor Vehicles" is incorporated by reference into section 1978, title 13, CCR and proposed revisions to the incorporated test procedures are provided in Appendix G.

Under the current federal ORVR regulations, complete vehicles up through 10,000 pounds GVWR are required to meet the ORVR standards. However, OEMs have indicated that complete vehicles up through 14,000 pounds GVWR contain ORVR equipment in an effort to minimize evaporative system variants among the MDV class. Thus, to come into alignment with current practice and prevent future backsliding, staff is proposing that, beginning with model year 2015, complete vehicles up through 14,000 pounds GVWR comply with the ORVR standards. The proposed LEV III standards are unchanged from the LEV II standards of 0.20 grams hydrocarbons per gallon of fuel dispensed for gasoline-fueled, diesel-fueled, and hybrid electric vehicles (hydrocarbons mean organic material hydrocarbon equivalent for alcohol-fueled vehicles), and 0.15 grams hydrocarbons per gallon of fuel dispensed for liquefied petroleum gas-fueled vehicles.

In addition to increasing the GVWR applicability, staff is proposing an option to allow OEMs to use California certification fuel (gasoline with 10 percent ethanol) during the certification testing in lieu of federal certification fuel, with the provision that California test temperatures are also used (Appendix G). This change is being proposed to allow streamlining between the ORVR and evaporative emission testing when California certification fuel is used for evaporative emission testing. The proposed increase in the refueling temperature from 67°F ± 1.5°F to 79°F ± 1.5°F if California certification fuel is used would ensure comparability with the federal test procedures and test fuels, which have a higher vapor pressure but lower test fuel temperature. The vehicle soak temperature would remain unchanged in order to ensure equivalent stringency regardless of the certification fuel used.

The proposed changes to the ORVR regulations and test procedures are not expected to result in any emission reduction or OEM cost due to current federal requirements for vehicles 8,501 through 10,000 pounds GVWR, OEM practice for vehicles 10,000 through 14,000 pounds GVWR, and use of on-site vapor recovery at refueling stations located in ozone non-attainment areas. Thus, these proposed changes serve to harmonize California and federal regulatory requirements and ensure the best available refueling vapor recovery systems on all complete vehicles equal to or less than 14,000 pounds GVWR.

2.3. Proposed Amendments to the Specifications for Fill Pipes and Openings of Motor Vehicle Fuel Tanks

The specifications for fill pipes and openings of motor vehicle fuel tanks (13 CCR §2235) were last amended in 1990 and were based upon Society of Automotive Engineers (SAE) specifications that have since been withdrawn and superseded by the International Organization for Standardization (ISO) standard, "Road vehicles – Filler pipes and openings of motor vehicle fuel tanks – Vapour recovery system" (ISO 13331-

1995(E)). This ISO standard is based upon the original SAE standards, but addresses several errors and clarifies aspects of the design criteria.

In order to bring the "Specifications for Fill Pipes and Openings of Motor Vehicle Fuel Tanks" up to date with the most current industry standards, staff is proposing to revise the current specifications so that they would be applicable only through model year 2014 (Appendix H). Beginning with model year 2015, the specifications based on the SAE standards ("Specifications for Fill Pipes and Openings of 1977 through 2014 Model Motor Vehicle Fuel Tanks") would be sunsetted and replaced by new specifications that incorporate the ISO standards by reference ("Specifications for Fill Pipes and Openings of 2015 and Subsequent Model Motor Vehicle Fuel Tanks"). The proposed specification language for 2015 and subsequent model year vehicles is available in Appendix I. Because the fill pipe specifications in the ISO-13331-1995 standard are substantially similar to and primarily clarifications of the SAE specifications referenced in the 1990 revision of 13 CCR Section §2235, no OEM changes for compliance are anticipated. All test procedures would continue to be required and would be unchanged from the 1990 amendments.

3. TECHNOLOGICAL FEASIBILITY OF PROPOSED STANDARDS

3.1. Current Evaporative Emission Technology

Today's most advanced evaporative emission control technologies are in vehicles meeting the optional zero-evaporative emission standards. The current state-of-the-art in evaporative technology is described in the ensuing paragraphs. Evaporative emission control technology can basically be grouped into three categories: carbon canister system, fuel storage / delivery system, and air intake system.

3.1.1. Carbon Canister System

A carbon canister system is employed to adsorb hydrocarbon vapors generated in the fuel tank during a refueling event, during vehicle operation, and while the vehicle is parked. These vapors are adsorbed by activated carbon granules contained in the canister. Canister system emissions generally fall into two categories: breakthrough and bleed. In a typical evaporative test sequence, breakthrough is the point when 2.0 grams of hydrocarbon has been emitted from the canister. The canister system emissions that occur before the onset of breakthrough are bleed emissions. Target canister system emission levels for zero-evaporative vehicles are in the 0.003-0.010 gram/test range. These bleed emissions occurring at this level are not due to lack of adsorptive capacity in the canister, but are due to diffusion (i.e., transfer of adsorbed fuel molecules through the canister to the port which is open to the atmosphere) (Williams et al. 2001).

The majority of zero-evaporative vehicles incorporate a hydrocarbon scrubber in order to achieve very low level bleed emissions. Most often, the scrubber is an auxiliary activated carbon honeycomb attached to the canister's atmosphere port. Simulated real

time two-day diurnal testing, at 150 bed volumes of purge, yielded emissions of 0.196 grams with a standard canister, which were reduced to 0.015 grams with the addition of a hydrocarbon scrubber (Williams et al. 2001).

3.1.2. Fuel Storage and Delivery System

Fuel permeation through the fuel tank, fuel lines, and vapor lines, combined with leakage from the associated connections for these components, contribute to evaporative emissions. In the fuel systems of current zero-evaporative vehicles, both system configuration and materials selection are optimized to achieve minimal evaporative emissions.

A system that has a minimal number of connections and components exposed to the atmosphere will have fewer opportunities for leakage. One current design practice involves integrating components such as venting valves, the fuel filter, and the fuel pump inside the fuel tank. Some fuel tanks use a common entry port for these internal components. For sealing off exposed components and critical joints, such as the fuel tank inlet, some designs include an external barrier film application.

Hydrocarbon permeation is reduced in current fuel system designs by minimizing the permeable materials' fuel exposure area and incorporating low/no permeation materials. Steel and plastic are used for the rigid components of the fuel system. Gasoline and alcohol do not permeate steel, while with plastic, permeation does occur, but this is drastically reduced by adding barrier layer(s) composed of low permeation materials. Rigid component barrier layer materials such as ethylene vinyl alcohol (EVOH) and fluoropolymers have shown good performance in limiting permeation with ethanol-containing fuels (Nulman et al. 2001). For seal, gasket, and hose applications, fluoroelastomers have been shown to limit permeation from ethanol containing fuels while retaining the mechanical properties required for a robust seal (Thomas et al. 2009).

Staff expects that the proposed test fuel containing 10 percent ethanol would result in a small increase in evaporative emissions during certification testing in comparison to certification tests conducted using the current MTBE-based fuel with no ethanol. The expected increase in certification emissions would be due to increased permeation, which can increase fuel system hydrocarbon emissions by as much as 0.028 grams on a zero-evaporative passenger car (Haskew et al. 2006). However, most vehicles currently contain low-permeation materials because manufacturers must design for the commercial fuel in California, which contains up to 10 percent ethanol. Therefore, staff does not expect manufacturers to make significant changes to the fuel system to accommodate the proposed test fuel, nor does staff expect any impact on fleet evaporative emissions due to the change.

3.1.3. Air Intake System Evaporative Controls

The vehicle's air intake system (AIS) is another channel from which evaporative emissions can escape. These emissions result when fuel injector leakage, vapors from uncombusted fuel in the intake manifold, and crankcase blow-by gases escape out of the vehicle's AIS. AIS emissions occur when the engine is turned off and the engine compartment is exposed to residual engine heat in addition to heat from diurnal temperature variations. The majority of current zero-evaporative vehicles are equipped with some form of AIS emission control element. Non-zero-evaporative vehicles are typically certified without an AIS element.

An AIS control element is typically placed in either the vehicle's airbox or in the air tube between the throttle body and the airbox. The AIS element adsorbs hydrocarbon vapors that pass by or through it by the means of an activated carbon or synthetic Zeolite material. Similar to the carbon canister's functionality, when the engine is operated, the hydrocarbons adsorbed on the AIS element are drawn into the engine for combustion. These devices are designed to be permanently installed and maintain their function for the vehicle's full useful life.

3.2. Potential Technologies for Compliance with Proposed Standards

Staff expects that the fuel system and evaporative control technology package required for a vehicle to meet the proposed standards would be equivalent to what is in today's zero-evaporative vehicle. However, hybrid vehicles could require some additional technology to meet the proposed bleed emission test standard, because they have less available purge to regenerate the carbon canister. Since the internal combustion engine in a hybrid may be turned off for long periods during vehicle operation, there are fewer opportunities to purge the canister. Purge volume is normally expressed in terms of canister bed volumes displaced during the two-day test procedure. Currently, a non-hybrid zero-evaporative vehicle yields 150-250 bed volumes while, in contrast, a hybrid with an integrated evaporative system produces 70-100 bed volumes. A trend of decreasing available purge is expected for future hybrid vehicles, due to increased time in engine-off mode.

A partially pressurized fuel tank is expected to be one of the most feasible technologies to compensate for hybrid vehicles' lower available purge. Since the fuel tank would be sealed up to a particular threshold pressure, this technology would facilitate reduced canister loading. Heated purge may be another option for addressing low-purge by increasing the efficiency of a given purge volume.

4. COST ANALYSIS

4.1. Cost methodology

Staff has estimated the cost to auto manufacturers to implement the proposed changes to the evaporative emission program. Cost information was obtained by consulting with fuel system suppliers, vehicle manufacturers, and USEPA. A typical vehicle meeting the current LEV II evaporative standards was used as the baseline for determining incremental costs.

4.2. Cost Analysis

Table II-B-4-1 shows an estimate of the added cost per vehicle for various parts of the fuel and evaporative control system to meet the proposed standards. The majority of the costs are expected to be due to the expansion of existing zero-evaporative technology. Some manufacturers have already integrated zero-evaporative components to a large extent on the rest of their fleet, which should reduce their compliance costs. The cost values noted below have been weighted based upon the fact that it takes a combination of the modifications listed below, not necessarily all of them, to achieve a zero-evaporative system. Four dollars of indirect costs were added to account for overhead as well as fixed (one time) costs that would be incurred in a small proportion of cases requiring a new component design for an in-house manufactured part, such as a fuel tank. Staff does not expect there to be a substantial difference in incremental cost among the various vehicle weight categories. The heavier vehicles would require more materials, but this should balance out cost-wise since the additional space allows for a more simple design and layout of fuel system components.

Table II-B-4-1. Evaporative Technologies' Incremental cost

Component	Changes	Added cost per vehicle
Fuel tank	Minimize ports (locate vents and valves inside tank, entry through a common port), low permeation material, vapor block valve for hybrids	$2.90
Canister	Addition of hydrocarbon scrubber	$10.00
AIS System	Addition of control element	$2.00
Fuel lines and system connections	Fewer components, low permeation material	$2.10
Total direct manufacturing costs		$17
Total + $4.00 indirect costs		$21

5. OUTSTANDING ISSUES

During the development of the evaporative emission proposal, staff deliberated with affected vehicle manufacturers on various issues related to the rulemaking. In addition, staff held several rulemaking workshops for the general public to solicit feedback on the proposal. Although most of the rulemaking issues have been resolved, there is one remaining issue that is still under consideration. This issue pertains to vehicle evaporative emissions as measured in the field. A recent USEPA test program showed that for many vehicles, in-use evaporative emissions are much higher than those observed during certification, indicating the need to strengthen current certification and in-use compliance programs. Although test data on current zero-evaporative emission vehicles (i.e., PZEVs) are limited, it is expected that the materials and connections used to meet the proposed LEV III evaporative emission requirements will reduce emissions over the lifetime of the vehicle, in part by reducing in-use deterioration. Current on-board diagnostic (OBD) systems also monitor for evaporative system leaks, although not all leaks may be detected and the onus is on the vehicle owner to have the leak repaired. Thus, if even a small percentage of vehicles develop leaks in-use, significant gains from LEV III could be lost. As such, ARB staff is working with EPA to develop a leak emission standard and test procedure. A requirement that vehicles be subject to a "leak test" requirement both at certification and in-use could be incorporated into LEV III when the currently proposed rule is finalized or, more likely, through a separate rulemaking in the future. Because fuel system leaks develop as vehicles age and new systems are unlikely to fail the leak test as proposed, it is anticipated that manufacturers would be given the option to provide an attestation of compliance at certification, with compliance testing conducted primarily during the in-use verification program.

Although ARB, USEPA, and industry are still working on the details of the leak test, a general outline of the procedure is provided in Figure II-B-5-1. The leak test would utilize a test apparatus that would attach to the vehicle fuel system, either through a dedicated test port or through a fuel system opening such as the filler pipe. The fuel system would then be sealed and slightly pressurized (less than 0.5 pounds per square inch) with an inert gas. The test apparatus would be calibrated such that at a given temperature and system pressure, the flow of gas through the apparatus corresponds to the leak size. For example, a larger leak in the fuel system would be correlated with a higher flow rate through the apparatus due to the need for more inert gas to maintain a given pressure as gas is lost through the leak(s). It is expected that the certification and in-use standards for maximum permissible orifice size will be set between 0.01 and 0.02 inches. Staff anticipates that manufacturers would be able to conduct this test either in sequence with the current 2-day or 3-day diurnal test procedure or as a stand-alone test procedure utilizing the same preconditioning procedures as the diurnal tests. This requirement would complement the OBD evaporative system leak monitoring requirement, not replace it.

Figure II-B-5-1. Flow chart depicting the outlined procedure for the proposed leak test.



While detailed regulatory text for the leak test requirement is not currently proposed as part of the LEV III evaporative emissions program, staff proposes that the LEV III/GHG regulatory proposal, as part of the Advanced Clean Cars rulemaking package, be finalized with the final federal leak test and standard as described, provided it is substantially similar to that depicted in Figure II-B-5-1. ARB staff anticipates that USEPA will incorporate the leak test and associated standards when the Tier 3 rulemaking is finalized in 2012, at which time ARB staff will evaluate whether this test requirement should be included into LEV III for certification and in-use verification

purposes. Assuming staff determines that the leak test and standard are appropriate for inclusion into LEV III, the finalized federal regulatory language, as modified by California, would be subject to additional public comment – ideally occurring before ARB has finalized the current rule – in order to promote harmonization within the national program.

6. REGULATORY ALTERNATIVES TO EVAPORATIVE EMISSION PROPOSAL

As part of the regulatory development process, the following alternatives to this proposal were considered.

6.1. Do Not Amend the Evaporative Emission Standards

To continue to reduce smog-forming VOC emissions, staff believes it is necessary to increase the stringency of the current evaporative standards. Based on staff's analyses, the proposed regulation is feasible and cost-effective since for the most part, it would require only expansion of existing zero-evaporative technology.

6.2. Adopt More Stringent Evaporative Emission Standards

6.2.1. Zero-fuel test requirement

Extending the zero fuel, or rig test, to the entire fleet was seen as a way to reduce evaporative emissions. However, manufacturers contend that this test is excessively burdensome due to the complexity and cost of setting up fuel system rigs, and the new test facilities that would be required. Option 2, with the lower whole vehicle standard and the canister bleed test, has been proposed to give manufacturers an alternative to the rig test. Staff considers Option 2 to provide equivalent emission control as compared to the higher whole vehicle standard and rig test which make up the current zero-evaporative requirement. This rig test will be an option for manufacturers, as it is contained in the proposed Option 1.

6.2.2. Lower whole vehicle emission standard

Staff believes that the fuel systems on vehicles certified to the zero-evaporative emission standard represent the best of currently available evaporative control technology. A large proportion of the evaporative emissions on zero-evaporative certified vehicles come from non-fuel sources. Although there are current zero-evaporative vehicles with two-day and three-day diurnal plus hot soak certification levels below 0.150 grams, these vehicles have very low background (non-fuel) emissions, which staff believes would be very difficult to achieve on an average fleet-wide basis. Based upon a review of average zero-evaporative vehicle certification values, staff believes that the proposed emission standards are appropriate to expand the use of zero-evaporative technology to the rest of the fleet, and that a lower whole vehicle emission standard would not allow sufficient margin for non-fuel evaporative emissions.

C. VEHICLE LABELING REQUIREMENTS

1. BACKGROUND

Since 1995, California's Smog Index Label helped consumers assess the relative smog emissions from new cars. In 2005 Assembly Bill 1229 was signed into law (Nation, Chap. 75, Stats. 2005, codified at Health and Safety Code §43200.1). These amendments to California's vehicle labeling regulations created a more user-friendly scoring system for determining the Smog Score and added a Global Warming Score. Both scores are based on a scale of 1 -10 with 10 being the cleanest and 5 representing an average new car.

The California Environmental Performance Label (Figure II-D-1-1) is required on all new vehicles sold in California that were manufactured after January 1, 2009.

Figure II-D-1-1. California Environmental Performance Label



Per the Energy Independence and Security Act of 2007, the United States Department of Transportation, United States Department of Energy and USEPA were directed to revise the Federal Fuel Economy Label to reflect an automobile's fuel economy and greenhouse gas and other emissions over the useful life of the automobile. It also required the revised label to include a rating system that would make it easy for consumers to compare the fuel economy and greenhouse gas and other emissions at the point of purchase.

Starting in the Spring of 2010, ARB staff began working with USEPA and NHTSA on revisions to the Fuel Economy Label. The goal of working with USEPA and NHTSA was to provide input on the information needed on the Federal label to allow California to use this Label in lieu of the California Environmental Performance label.

Important California requirements addressed by the federal label included:

- Adding the following statement to the label: "Vehicle emissions are a significant cause of climate change and smog"
- Having a clear statement about upstream emissions and having a clear place to find this information on a regional basis.
- Including all cars in the rating system rather than segregating by size or class.

Because of this successful collaboration California is able to harmonize with the federal labeling requirements.

In June 2011, USEPA and NHTSA published 40 CFR Parts 85, 86, and 600 providing requirements for the new Fuel Economy and Environment Label meeting these requirements. This new Federal Label (Figure II-D-1-2) is required on all new cars starting with Model Year 2013 and can be affixed earlier on a voluntary basis. The new Federal Fuel Economy and Environment Label is a redesign that now includes a Greenhouse Gas and Fuel Economy Rating from 1 to 10 with 10 being best and a Smog Rating, also from 1 to 10 with 10 being cleanest. The content and graphical design are sufficiently similar to and were inspired by the Global Warming and Smog Scores on California's Environmental Performance Label.

Figure II-D-1-2. Federal Fuel Economy and Environment Label, June 6, 2011

2. SUMMARY OF PROPOSED REGULATION

Staff is proposing to add language to the "California Smog Index Label Specifications for 2009 and Subsequent Model Year Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles," incorporated by reference at Title 13, California Code of Regulations, Section 1965), that would deem manufacturer compliance with the Federal Fuel Economy and Environment Label published in 40 CFR Parts 85, 86, and 600 as promulgated on July 6, 2011 as compliant with the California Environmental Performance Label requirements. Providing consumers with only one label that includes substantial environmental information meeting California's statutory requirements will avoid confusion as well as information overload.

Staff is also proposing to add clarifying language about Neighborhood Electric Vehicles (NEVs). NEVs are not permitted to affix the Federal Fuel Economy and Environment Label because only those vehicles that qualify for Corporate Average Fuel Economy (CAFE) credits are permitted to have these labels. Since NEVs cannot receive these credits, they cannot affix this label. Therefore, for consistency, staff proposes to no longer require the Environmental Performance Label on these types of vehicles.

3. COST ANALYSIS

By allowing OEMs to use the new Federal Fuel Economy and Environment to meet the California's vehicle labeling requirements, OEMs will save money by not having to also print and affix the California Environmental Performance Label.

According to the May 4, 2007 Initial Statement of Reasons for the Environmental Performance Label, the initial annualized cost for compliance for the industry as a whole with these requirements was estimated to be $3,500 and the annual ongoing cost for a typical manufacturer was estimated to be $4,667, making an OEM's total annual cost for printing the California Environmental Performance Label and affixing it to all of their cars to be $8,167. Although the initial annualized costs will not change, the ongoing annual cost will go to zero.

D. MINOR AMENDMENTS TO THE ON-BOARD DIAGNOSTICS REGULATIONS

1. BACKGROUND

Second generation on-board diagnostics (OBD II) systems are comprised mainly of software designed into the vehicle's on-board computer to detect emission control system malfunctions as they occur by monitoring virtually every component and system that can cause an increase in emissions. When an emission-related malfunction is detected, the OBD II system alerts the vehicle owner by illuminating the malfunction indicator light (MIL) on the instrument panel. By alerting the owner of malfunctions as they occur, repairs can be sought promptly, which results in fewer emissions from the vehicle. Additionally, the OBD II system stores important information including identification of the faulty component or system and the nature of the fault, which would

allow for quick diagnosis and proper repair of the problem by technicians. This helps owners achieve less expensive repairs and promotes repairs done correctly the first time.

With OBD II systems having been required on all 1996 and newer vehicles produced for sale in California and most vehicles sold nationwide, more than 110 million vehicles are currently equipped with them. Input from manufacturers, service technicians, inspection and maintenance (I/M) programs, and in-use evaluation programs indicate that OBD II systems are very effective in finding emission problems and facilitating repairs. Accordingly, US EPA issued a final rule indicating its confidence in the performance of OBD II systems by requiring states with I/M programs to perform OBD II checks for these newer cars and allowing them to be used in lieu of current tailpipe tests. The California I/M program (Smog Check) has adopted these provisions.

The California Air Resources Board (ARB) originally adopted the light- and medium-duty vehicle OBD II regulation in 1989 for the 1994 and newer model years. As directed by the Board, the regulation has been reviewed and updated at regular updates since then, with the last major update to the regulation occurring in 2006 as well as updates to the medium-duty diesel requirements occurring in 2009. Staff was not scheduled to go to the Board this year to update the OBD II regulation; however, manufacturers recently approached ARB staff and requested regulation changes that they indicated were needed immediately in order to ensure compliance when they certify their 2013 model year vehicles. Manufacturers and ARB staff held discussions with interested manufacturers, including a face-to-face meeting on July 27, 2011, to discuss their proposal.

In response to the manufacturers' requests, staff is proposing changes to the OBD II regulation, California Code of Regulations (Cal. Code Regs.), title 13, section 1968.2, and its associated enforcement regulation, section 1968.5.

2. SUMMARY OF PROPOSED AMENDMENTS

Section 1968.2(c): Definitions

The OBD II regulation currently defines "calculated load value" for diesels as "determined by the ratio of current output torque to maximum output torque at current engine speed as defined by suspect parameter number (SPN) 92 of SAE J1939." Manufacturers have indicated that the definition in Society of Automotive Engineers (SAE) J1939 only applies to heavy-duty diesel engines, so they need a comparable definition that would apply to light- duty and medium-duty diesel vehicles. Thus, ARB staff is proposing to modify the language to allow manufacturers to use the definition of "calculated load value" that was recently amended in SAE J1979 for diesel vehicles.

The OBD II regulation currently allows manufacturers to erase a confirmed fault code if the identified malfunction has not been again detected in at least 40 engine warm-up cycles and the MIL is presently not illuminated for that malfunction. The regulation

currently defines "warm-up cycle" as "sufficient vehicle operation such that the coolant temperature has risen by at least 40 degrees Fahrenheit from engine starting and reaches a minimum temperature of at least 160 degrees Fahrenheit (140 degrees Fahrenheit for applications with diesel engines)." Manufacturers have expressed concern that certain vehicles such as hybrid vehicles or vehicles with highly efficient engines may not be able to meet these temperature criteria under normal driving and ambient conditions. Thus, manufacturers have requested language that allows manufacturers to use an alternate minimum temperature criterion. Staff understands that some allowances should be made for such vehicles that are unable to warm-up the engine coolant temperature to the defined temperatures even if it has been sufficiently driven. Thus, staff is proposing to allow manufacturers the option to define a "warm-up cycle" as a driving cycle in which the criteria to erase a permanent fault code for continuous monitors are met (sections 1968.2(d)(2.5.2)(B)(iii)a., b. and c.). This would ensure that the vehicle has been operated for a sufficient period of time to reasonably detect a recurrence of the malfunction but does not delay erasure of confirmed fault codes.

Staff is proposing changes to the permanent fault code erasure requirements and the in-use monitor performance requirements that would apply to hybrid vehicles, details of which are described below. Given the context of the proposed changes, new definitions would be needed to complement the proposed requirements. Thus, staff is also proposing four new definitions for "hybrid vehicle," "plug-in hybrid electric vehicle," "fueled engine operation," and "propulsion system active" to supplement the proposed changes. More details about the proposed definitions can be found below.

Section 1968.2(d)(2.5): Erasing a Permanent Fault Code

The OBD II regulation requires the OBD II system to store a "permanent" fault code for an emission-related fault in non-volatile memory that can only be erased if the monitor responsible for setting that fault code has run and passed enough times to confirm that the fault is no longer present. Currently, the regulatory language (section 1968.2(d)(2.5.1)) states that the permanent fault code can be erased "only if the OBD II system itself determines that the malfunction that caused the permanent fault code to be stored is no longer present and is not commanding the MIL on, pursuant to the requirements of section (d)(2.3) (which for purposes of this section shall apply to all monitors)." Manufacturers have expressed confusion about the exact timing of erasing the permanent fault code. Thus, staff is proposing to clarify the requirement by adding language indicating that erasure of the permanent fault code shall occur in conjunction with extinguishing the MIL or no later than the start of the first driving cycle that begins with the MIL commanded off.

Additionally, staff is proposing changes to address issues concerning permanent fault code erasure on hybrid vehicles for monitors that are designed to run continuously, including monitors that must wait until similar conditions are satisfied (e.g., gasoline misfire and fuel system monitors). Currently, the regulation requires that the permanent fault code for these monitors be erased only after the vehicle has been operated such

that, among other conditions, criteria similar to those for a general denominator (section 1968.2(d)(4.3.2)(B)) have been satisfied on a single driving cycle (with the exception that the general denominator conditions require ambient temperature above 20 degrees Fahrenheit or below 8000 feet in elevation). This ensures that the vehicle has been operated for a sufficient period of time to reasonably detect a recurrence of the malfunction but does not unnecessarily delay erasure of the permanent fault code. Among these conditions is the criterion that the "cumulative time since engine start" be greater than or equal to 600 seconds. Manufacturers have indicated that changes are needed to account for the fact that hybrid vehicles, especially plug-in hybrids, may encounter a significant number of driving cycles where the engine starts very late (if at all) in a typical drive cycle and the cumulative amount of engine runtime is limited. Thus, for hybrid vehicles, staff is proposing to clarify that manufacturers should use 600 cumulative seconds of "propulsion system active" time in lieu of the 600 cumulative seconds after engine start, with "propulsion system active" defined as when the vehicle is operated, regardless of whether it is powered by the battery or the engine or both. Staff believes this new definition would ensure equivalent vehicle operation time between conventional vehicles and hybrid vehicles. Further, the new language is consistent with how manufacturers have been implementing such counters to date on hybrid vehicles but the clarifications will provide more guidance especially to those that have not yet certified hybrid vehicles.

Sections 1968.2(d)(3.2), (d)(4.3.2), and (d)(5.5) and Section 1968.5: In-Use Monitor Performance Specifications

The OBD II regulation requires manufacturers to track monitor performance by counting the number of monitoring events and the number of driving events. The number of monitoring events is defined as the numerator and the number of driving events is defined as the denominator. The ratio of these two numbers is referred to as the monitoring frequency and provides an indication of how often the monitor is operating relative to vehicle operation. The regulation also requires all vehicles to keep track of a "general denominator", which is a measure of how often the vehicle is operated. The regulation requires manufacturer to increment this denominator only if certain criteria are satisfied on a single driving cycle. This method allows very short trips or trips during extreme conditions such as very cold temperatures or very high altitude to be filtered out and excluded from the count. This is appropriate because these are also conditions where most OBD II monitors are neither expected nor required to operate.

The regulation currently requires all vehicles to increment the general denominator if, among other conditions, the "cumulative time since engine start" is greater than or equal to 600 seconds. For the same reasons noted above, hybrid vehicles, especially plug-in hybrids, need an alternate definition to recognize trips where the engine does not start or starts much later in the trip. Manufacturers are concerned that with the current regulatory language, the general denominator will increment more often than it should compared to how often the monitors will have had a chance to run in-use (i.e., how long the engine will actually be turned on) and are concerned that the resulting ratios will not be able to meet the minimum required ratios. They further argued that this may force

them to increase engine operation just to run the monitors to meet the required ratios, which would reduce vehicle efficiency and basically reduce the advantages of the plug-in capability. Staff agrees that some changes are needed to account for these issues. Thus, similar to the changes proposed above for the permanent fault code erasure protocol, for hybrid vehicles, staff is proposing to clarify that manufacturers must use 600 cumulative seconds of "propulsion system active" time in lieu of the 600 cumulative seconds after engine start when incrementing the general denominator. Additionally, staff is also proposing to require 10 seconds of "fueled engine operation" to be met in order to increment the general denominator to discern between trips with and without engine operation. This condition would ensure that only trips where the engine has at least turned on once during the driving cycle are counted when looking at how often engine-related emission control component monitors are running. These proposed changes would apply to 2014 and subsequent model year hybrid vehicles.

Additionally, manufacturers indicated changes are needed to the denominator incrementing criteria for evaporative system monitors. Unlike tailpipe emissions where the engine has to operate in order for emissions to occur, evaporative emissions such as gasoline vapor escaping from the gasoline tank to the atmosphere can occur from a vehicle while it is parked or being operated off of battery power. Accordingly, the evaporative system monitors need to work, regardless of how often the engine is actually started or used on the vehicle. The regulation currently requires the evaporative system monitor denominator to be incremented only on trips that meet a 'cold start' definition (i.e., if the engine coolant temperature (ECT) and the ambient temperature are considered cold and the ECT at engine start is less than or equal to 12 degrees Fahrenheit higher than ambient temperature at start). The criteria were set to ensure that the vehicle has had a long enough soak period such that the evaporative system (fuel tank, canister, etc.) will have cooled down and stabilized by the beginning of the driving cycle and it would be technically feasible to run a robust evaporative system monitor.

While this current 'cold start' definition works adequately for conventional vehicles and traditional hybrids, manufacturers have argued that plug-in hybrid electric vehicles will have some driving cycles that are all-electric and that the definition does not address such conditions. Specifically, the existing definition could result in multiple increments of the evaporative system monitor denominator after short all-electric drive trips even though the evaporative system is no longer at a stabilized condition because ECT will still be within the cold start-defined window relative to ambient temperature. Staff agrees that changes are needed to avoid these issues and is proposing alternative criteria for plug-in electric hybrid vehicles that would better ensure a long soak period similar to that on conventional vehicles and traditional hybrids. Specifically, for 2015 and subsequent model year plug-in hybrid electric vehicles, staff is proposing that the denominator be incremented when the soak period immediately preceding the driving cycle is greater than or equal to 6 hours in lieu of requiring the ECT at engine start to be less than or equal to 12 degrees Fahrenheit higher than ambient temperature at start. For example, a conventional car would first look at ECT and ambient temperature at engine start, make sure they agree with each other to confirm it is a cold start of the

vehicle, make sure ambient temperature is within acceptable ranges, and then look for the drive cycle to meet the rest of the criteria to count as an evaporative system denominator trip. Plug-in hybrids, however, would instead first look at the amount of time the vehicle has been off/not operated when the vehicle is first started, make sure that it has been at least 6 hours since the previous vehicle trip to confirm it is a cold start of the vehicle, and then make sure the ambient temperature is within range and that the drive cycle meets the rest of the criteria to count as an evaporative system denominator trip. For additional flexibility to manufacturers, plug-in hybrid electric vehicles built prior to the 2015 model year would have the option of using these new criteria or the existing criteria to increment the evaporative system monitor denominator.

Manufacturers have also argued that a smaller minimum required ratio is needed to account for the limited engine operation time for plug-in hybrid vehicles and to allow them to maximize electric operation/minimize CO_2 emissions. While staff believes some relief is needed with respect to the ratio, staff believes a smaller ratio is only needed for the interim years considering the proposed revisions to the denominator criteria above would already provide substantial relief in meeting the in-use performance ratio requirements relative to conventional vehicles. Thus, staff is proposing that for monitors of components or systems that require engine operation on plug-in hybrid electric vehicles, manufacturers would be required to meet a minimum ratio of 0.100 in lieu of the current higher ratios (e.g., 0.336 for most monitors) through the 2016 model year. This would allow manufacturers to run monitors less frequently on plug-in hybrids and still be considered compliant. Starting with the 2017 model year, the interim relief would end and these monitors would be required to meet the higher minimum ratios currently required in the regulation. However, staff will also plan to revisit this requirement once plug-in hybrid electric vehicles are in-use and data are available to better strike a balance between monitoring frequency (to detect emission faults in a timely manner) and reduced engine operation (and the resultant CO_2 emissions). Staff is also accordingly proposing changes in the OBD II enforcement regulation (Cal. Code Regs., title 13 section 1968.5) to account for the newly proposed ratio when determining OBD II non-compliances for plug-in hybrid electric vehicles.

Lastly, staff is proposing changes to the ignition cycle counter requirements for hybrid vehicles and plug-in hybrid electric vehicles. Currently, manufacturers are required to track and report an ignition cycle counter, which is required to be incremented every time the vehicle is started (i.e., "engine start" is met). This is basically a counter of the number of driving cycles experienced by the vehicle. First, staff is proposing to modify the incrementing criteria for hybrid vehicles – specifically, staff is proposing to clarify that manufacturers increment the ignition cycle counter when the "propulsion system active" definition is met (e.g., each time the vehicle is operated, without respect to whether the engine is started or used). This is consistent with how hybrid manufacturers have been tracking this counter to date. Second, staff is proposing that 2014 and subsequent model year plug-in hybrid electric vehicles track and report an additional, separate ignition cycle counter that would be incremented when the "fueled engine operation" definition has been met (e.g., each time the vehicle is operated and the engine is started at least once). These data would provide valuable information

about how often all-electric driving cycles occur in-use for plug-in hybrid electric vehicles, which would help staff determine if further changes are needed to the in-use monitor performance requirements, including the required minimum acceptable in-use performance ratios, for these vehicles.

Staff is also proposing changes to the denominator incrementing criteria for particulate matter (PM) sensor and PM sensor heater monitors. These proposed changes are discussed in more detail below in the *"Diesel PM Filter Monitoring"* section.

Section 1968.2(e)(3.3): Gasoline Misfire Monitoring

The OBD II regulation currently requires manufacturers to continuously monitor for misfire faults from no later than the end of the second crankshaft revolution after engine start. The language, however, does not specifically address engines that employ engine shutoff strategies (e.g., hybrid vehicles that shut off the engine at idle) and can restart the engine multiple times within the same driving cycle. Additionally, the term "engine start" is currently being used in the OBD II regulation for many requirements with the intent that "engine start" signifies the start of vehicle operation, which may or may not involve the engine actually being started in a hybrid vehicle. Since more time is needed to determine appropriate industry-wide conditions to require misfire monitoring after the engine is first started and subsequently restarted, staff is, in the meantime proposing to require manufacturers to propose their own conditions for ARB approval. As with other similar items in the regulation, the criteria that ARB will use to approve such requests are identified in the regulation and, in this specific case, are primarily based on the equivalence of the manufacturer-proposed conditions compared to the current requirements to enable as soon as technically possible, which is typically within two crankshaft revolutions of engine starting.

Section 1968.2(f)(1.2.3)(B): Diesel Non-Methane Hydrocarbon (NMHC) Converting Catalyst Monitoring

The OBD II regulation requires manufacturers to monitor the NMHC catalyst for its NMHC conversion capability and for its ability to perform other emission-related functions. One such function is the ability of the catalyst to generate a desired feedgas (e.g., nitrogen dioxide (NO_2)) to promote better performance in a downstream aftertreatment component (e.g., for higher NOx conversion efficiency in a selective catalytic reduction (SCR) system). Currently, the regulation requires 2010 and subsequent model year light-duty vehicles and 2013 and subsequent model year medium-duty vehicles to meet this requirement. Manufacturers have asked ARB to delay the start date to meet this requirement in part because their original plans to comply were based on using monitors for the NMHC conversion efficiency of the NMHC catalyst and/or NOx conversion efficiency of the SCR system and such approaches were not uniformly successful. This resulted in manufacturers having to investigate alternative monitoring strategies and consequently indicating they need more time to verify these strategies. While staff believes it is feasible to develop a monitor to meet this requirement, staff acknowledges that more time is needed to develop a robust

monitor to meet this requirement. Thus, staff is proposing to delay monitoring of proper feedgas generation until the 2015 model year for light-duty and medium-duty vehicles. Considering this proposed delay is for a secondary function of the NMHC catalyst, staff determined this delay would not result in any lost emission benefits.

Sections 1968.2(d)(4.3.2), (f)(9.2.4), (f)(17.1), and (k): Diesel PM Filter Monitoring

The OBD II regulation currently requires the OBD II system to identify malfunctions of the PM filter when the filtering capability degrades to a level such that tailpipe emissions exceed a specific threshold. For 2013 and subsequent model year light-duty vehicles, the threshold is 1.75 times the applicable standards, and for 2013 and subsequent model year medium-duty vehicles, the PM threshold is 0.03 g/bhp-hr (approximately 3 times the applicable standards). Manufacturers have expressed concern that the thresholds are too stringent and not technically feasible for the 2013 model year time frame, contending that the current status of technology (e.g., the usage of differential pressure sensors) cannot support such thresholds.

In order to achieve the thresholds, manufacturers believe PM sensors are necessary, and while PM sensor suppliers have been rapidly developing and refining their products, only some of the vehicle and engine manufacturers are able to introduce such sensors on their 2013 model year products. In some cases, the manufacturers have indicated that the sensor suppliers have selected only certain manufacturers to work with on a limited introduction to continue to test out the sensor before wide-scale implementation, while others have indicated that they have run into issues that need to be resolved by both them and the supplier before the sensors are production ready. Thus, manufacturers have asked ARB to delay the start date of the 2013 thresholds of 1.75 times the standards to a later model year.

ARB staff agrees that PM sensors do not appear to be available to meet wide-scale demand in 2013 and understands that relief is needed based on discussions with manufacturers about their progress in meeting the monitoring requirements. However, staff believes more discussions are needed to determine when the appropriate start date should be. In the meantime, staff is proposing to allow light-duty and medium-duty diesel manufacturers that do not successfully introduce a PM sensor in the 2013 model year to extend the deficiency allowance for the PM filter performance monitor so that all 2013 model year products can be certified (albeit with a deficiency). Concurrently, staff is proposing necessary associated changes to extend the allowance to exclude detection of specific failure modes for PM filter monitoring (section (f)(17.1)) through the 2013 model year. This allowance recognizes one of the issues that monitoring techniques that do not use a PM sensor may have with respect to detecting failures such as a partially melted and partially cracked substrate that theoretically have offsetting impacts on the detectable parameter (e.g., differential pressure across the filter). Considering the delay is only one additional year, staff determined this delay would not result in any lost emission benefits.

Additionally, staff is proposing amendments that would apply to those manufacturers that do implement PM sensors on their 2013 and/or 2014 model year vehicles. The OBD II requirements are often technology forcing and PM filter monitoring is definitely one such requirement. Many believe that PM sensors will be the only viable way to meet the final monitoring thresholds and staff wants to continue to encourage those manufacturers that aggressively push forward to implement such technologies. Considering these sensors are new technology that haven't been used in the field, some of the manufacturers that are still on track to implement such technology for the 2013 and/or 2014 model year expressed concern about meeting the regulation should something not work out as well as expected with the sensor. Specifically, manufacturers are worried about the PM filter monitor that the sensor is intended to be used for as well as monitoring of the sensor itself. Thus, manufacturers have indicated that they may not incorporate PM sensors if changes weren't made to the regulation that would reduce the risks should something fall short, especially given the costs of being one of the first to incorporate such sensors. Accordingly, staff is proposing additional changes that would apply only to those that do implement a PM sensor in the 2013 and/or 2014 model year to help achieve a balance that continues to encourage early implementation by removing some of the risk to manufacturers should something fall short of the current requirements. Specifically, for the 2013 and 2014 model years, staff is proposing to allow these light-duty and medium-duty diesel manufacturers to certify their vehicles with "free" deficiencies (i.e., deficiencies that would not be subject to fines) for the PM filter performance monitor and PM sensor and sensor heater monitors. Further, staff is also proposing amendments to the in-use monitor performance requirements for PM sensor and PM sensor heater monitors. The OBD II regulation currently requires the PM sensor monitoring capability monitor (section 1968.2(f)(5.2.2)(D)) and the PM sensor heater monitor (section 1968.2(f)(5.2.4)(A)) to use the general denominator as the monitor denominators. PM sensors, like PM filters, may be regenerated infrequently in-use, which may make frequent monitoring difficult. Manufacturers are concerned that using the general denominator may result in the denominator incrementing more often than is appropriate for the sensor technology and how it is used. Thus, staff is proposing to allow manufacturers to propose alternate criteria (for ARB review and approval) to increment the denominator for PM sensor monitoring capability monitors. For PM sensor heater monitors, staff is proposing to require manufacturers to increment the denominator when, in addition to the general denominator criteria, the heater has been commanded to function on two or more occasions for greater than two seconds or for a cumulative time greater than or equal to ten seconds.

The OBD II regulation also requires manufacturers to monitor the NMHC conversion capability of catalyzed PM filters. Currently, the regulation requires 2010 and subsequent model year light-duty vehicles and 2013 and subsequent model year medium-duty vehicles to meet this requirement. Similar to the discussion above regarding monitoring a secondary function of NMHC converting catalysts (e.g., their ability to generate a proper feedgas for SCR catalysts), the catalyzed coating of a PM filter has secondary functions that have an emission impact. These functions can include promotion of passive regeneration at lower exhaust temperatures, conversion of

HC and carbon monoxide created during an active regeneration, and generation of NO_2 feedgas for downstream SCR systems. Manufacturers, however, have argued that many of these functions are just side effects that directionally help, but are not necessary to comply with the emission standards. They further indicated that there are currently no suitable robust monitoring strategies available to discern the proper operation of these secondary functions. Thus, manufacturers have asked ARB to delay the start date to meet this requirement.

As discussed in the 2009 HD OBD and OBD II Staff Report, ARB staff believes that such secondary functions are not trivial and warrant monitoring to ensure overall effectiveness of the emission control system. Staff proposed several possibilities for monitoring strategies in the last Staff Report and manufacturers have not investigated all of the possibilities for monitoring at this point. The success of the monitoring approaches may still be highly dependent on the actual catalyst configuration, significance of the catalyst loading on the PM filter, and regeneration strategy (especially reliance on high levels of passive regeneration) and thus require manufacturers to take OBD monitoring capability into consideration when designing and implementing the aftertreatment system and control strategy. However, recognizing that the OBD engineers have often been left out of the design process due to the rapid deployment of new technologies and increasingly stringent standards, staff is proposing to delay the monitoring requirements of the catalyst function of catalyzed PM filters until the 2015 model year for light-duty and medium-duty vehicles to give manufacturers more time to refine their systems, optimize regeneration strategies, and better investigate the impacts of the catalyzed PM filter. Given the minimal delay, the smaller impact of these secondary functions of the emission controls, and the continued presence of other monitors of these emission controls (albeit it not for these specific functions), staff determined this delay would not result in any lost emission benefits.

Section 1968.2(f)(15.2.2)(F): Fuel Control System Component Monitoring

The OBD II regulation currently requires manufacturers to monitor fuel control system components (e.g., injectors, fuel pumps) that have tolerance compensation features implemented in hardware or software during production or repair procedures on 2013 and subsequent model year diesel vehicles. Examples of these include individually coded injector-to-injector tolerances and fuel pumps that use in-line resistors to correct differences in fuel pump volume output. Monitoring of the components would ensure that misassembled systems, erroneous programming, or incomplete repair procedures that result in incorrect adjustment being applied (and consequently, increases in emission levels) will be detected. Manufacturers, however, have questioned the need to monitor this feature and have expressed concern about meeting this requirement in the 2013 timeframe. Manufacturers have indicated they have been working hard on improvements to their fuel system adaptive strategies to fully compensate or learn out any errors that may occur due to mismatches in the injector and the programmed tolerance/adjustment. This would allow manufacturers to avoid adding new hardware, such as a communication chip in the injector that would automatically communicate its characteristics to the engine computer, and avoid other alternatives such as tighter

tolerances on the injectors to meet this requirement. However, most are not currently able to fully achieve this. In some cases, the improved strategies can learn out most, but not all, of the error; in other cases, the learning can take a substantially long time. Staff believes that more lead time is necessary for manufacturers to fully refine their strategies. Thus, staff is proposing to delay the monitoring requirement of this feature until the 2015 model year for light-duty and medium-duty diesel vehicles. Given the minimal delay and that manufacturers will continue to improve and implement the strategies even during the delay years, staff determined this delay would not result in any lost emission benefits.

Section 1968.2(g)(1): Reference Documents

Staff is proposing amendments that would incorporate another reference SAE document. As is common practice with technical standards, industry periodically updates the standards to add specification or clarity. The current OBD II regulation incorporates the May 2007 version of SAE J1979 "E/E Diagnostic Test Modes". The proposal would update the regulation to incorporate a newly published sub-document of SAE J1979, the October 2011 version of SAE J1979-DA "Digital Annex of E/E Diagnostic Test Modes"[14]. This document contains some clarifications and modifications to the standardized data that must be reported by OBD II systems and is needed to properly implement some of the proposed changes on 2013 and subsequent model year vehicles.

Section 1968.2(g)(4.2): Data Stream

An important aspect of OBD II is the ability of technicians to access critical information from the on-board computer in order to diagnose and repair emission-related malfunctions. ARB believes there are certain emission critical components and systems for which electronic information access through the data link connection would provide invaluable assistance in properly repairing vehicles. The availability of real-time information would also greatly assist technicians in responding to driveability complaints because the vehicle could be operated under the problem conditions and the technician would be able to know how various sensors and systems were acting at that time. Fuel use complaints, loss of performance complaints, intermittent problems, and others could also be potentially addressed.

The OBD II regulation currently defines a number of data parameters that manufacturers are required to report to generic scan tools, including some parameters (mostly diesel-related) that must be reported starting in the 2013 model year. While in virtually every case, staff worked with SAE to ensure that the applicable SAE standards are updated well before they become required, in this particular instance, one parameter went through recent revisions as the manufacturers got further clarification

[14] For organizational purposes, the SAE J1979 document that previously contained both the text descriptions of how to implement standardized data and tables of the actual standardized data has been split into two subparts. The second of those, called the Digital Annex, has what was previously contained in the tables and is what is being updated and incorporated by reference here.

on how the parameter would be used. Specifically, for the data stream parameter "type of fuel currently being used", which is currently required on all 2013 and subsequent model year vehicles, the staff is proposing to delay the requirement until the 2015 model year to allow manufacturers time to implement the latest revisions of the format for this parameter and address interpretations by some manufacturers that this parameter was only required on flex fuel vehicles.

Additionally, the current regulation mistakenly lists "PM sensor output" as being required starting in both the 2010 model year and the 2013 model year. Therefore, staff is proposing to delete the reference to "PM sensor output" under the 2013 and subsequent model year language (section 1968.2(g)(4.2.6)(B)).

3. COST ANALYSIS

Most of the proposed amendments would either relax or clarify the current requirements in the OBD II regulation. Thus, the technological feasibility of the proposed amendments has already been determined and discussed above and in the staff reports for the previous OBD II rulemakings. A few other proposed changes that would be considered new requirements would consist of only minor software changes and are both being requested by industry and consistent with how industry has been implementing or planning for implementation.

Considering most of the proposed amendments are intended to either relax or clarify the current requirements, the proposed amendments are also not expected to add any additional cost to manufacturers. For proposed changes that would be considered new requirements, these changes would consist of only software changes, and staff is proposing enough lead time for manufacturers to meet these requirements. Further, specific to the proposed new requirement changes, the existing requirements cannot be implemented without software changes for plug-in hybrids, so manufacturers are not incurring any extra cost to make that change consistent with the proposed requirements. Thus, the costs associated with these changes are considered negligible. Accordingly, the proposed amendments are not expected to alter the previously calculated emissions benefits or cost effectiveness values.

III. CALIFORNIA'S LIGHT-DUTY GREENHOUSE GAS REGULATIONS

Section III reports on the ARB staff assessment of climate change science and the proposed regulations for reducing climate change-related impacts from light-duty vehicles. The section is organized as follows. Section A.1 presents an overview of the climate change science that has provided the basis for a broad suite of policies in California to mitigate the risks of anthropogenic climate change via the reduction of greenhouse gas (GHG) emissions from major sources in the State. The following sections describe the logic, technical basis, and regulatory details for the proposed GHG standards for light duty vehicles. Section A.2 provides some context for the proposed standards with respect to the federal standards; section A.3 summarizes the proposed regulations; section A.4 provides the technical feasibility basis for reducing light-duty vehicle GHG emissions; and section A.5 describes the proposed GHG standards.

A. PROPOSED AMENDMENTS TO CALIFORNIA'S LIGHT-DUTY GREENHOUSE GAS EMISSION STANDARDS

1. CLIMATE CHANGE OVERVIEW

The Earth's climate has always changed; the paleo-record of the last million years shows large changes with the growth and retreat of the great ice sheets over the continents. Nevertheless, over the past century the northern hemisphere has warmed at a rate faster than at any other time over the last millennium, and that change is because human activities are altering the chemical composition of the atmosphere through the buildup of GHGs, primarily CO_2, CH_4, N_2O, and HFCs. These gases play a role in the "greenhouse effect", a natural phenomenon that helps regulate the temperature of the Earth. Human activities, primarily the burning of fossil fuels and clearing of forests, have greatly intensified the natural greenhouse effect, causing global warming. Emissions of GHGs due to human activities have increased globally since pre-industrial times, with an increase of 70 percent between 1970 and 2004[15].

Though CO_2 is the single most important anthropogenic GHG, non-CO_2 anthropogenic GHGs, such as CH_4, N_2O, and HFCs, play a significant role in the Earth's energy balance. Hence, control of non-CO_2 GHGs is a critical component of climate change mitigation efforts, and particularly in the near term these reductions can complement early efforts to control CO_2. Climate change can also be affected by the increase of ozone levels in the troposphere. Ozone is produced by photochemical reactions. Its precursor components are primarily the result of fossil fuel combustion. Unlike many of the other GHGs, ozone is a short-lived gas that is found in regionally varying concentrations. Nevertheless, it is a strong GHG and its global mean concentration has increased by about 35% since the pre-industrial times, with some regions experiencing larger and some with smaller increases.

---

[15] IPCC. (2007a). *Climate Change 2007: Synthesis Report. Contribution of Working Groups I, II and III to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change.* Cambridge University Press. http://www.ipcc.ch/pdf/assessment-report/ar4/syr/ar4_syr.pdf .

The large interest in airborne particles and their radiative impact is derived in part from the Intergovernmental Panel on Climate Change (IPCC)'s assertion that human-caused climate change has resulted primarily from changes in the amounts of GHGs in the atmosphere, but also from changes in small particles. Major components of fine particles such as sulfate, nitrate, organic carbon, dust, and sea salts have reflective properties that scatter radiation (negative radiative forcing or cooling impact). Of the 20+ models used in the IPCC 4th assessment report, most included sulfate direct radiative forcing, but only a fraction considered other aerosol types. The primary purpose was to establish whether the pattern of warming was altered by including aerosol-induced cooling in regions of high emissions. Carbonaceous particles (those that contain organic and black carbon) are particularly important because of their abundance in the atmosphere, and the characteristics of the carbon vary significantly depending on their origin. In recent years there has been increased attention in the particle research community about the potential of black carbon (BC) to cause global warming. The ability of BC to absorb light energy and its role in key atmospheric processes link it to a range of climate impacts, including increased temperatures, accelerated ice and snow melt, and disruptions to precipitation patterns.

The heat-trapping property of GHGs is undisputed. Although there is uncertainty about exactly how and when the earth's climate will respond to increasing concentrations of GHGs, combining observations with climate models indicates that detectable changes are under way. These observed changes go beyond a global mean rise in temperature, including also changes in regional temperature extremes, precipitation, and sea level, all of which could have significant adverse effects on water resources, ecological systems, and human health and the economy.

Global warming is already impacting the Western U.S., particularly California in more severe ways than the rest of the country. The 2010 Climate Action Team (CAT) report[16] concluded that climate change will affect virtually every sector of the state's economy and most of our ecosystems. Significant impacts will likely occur even under moderate scenarios of increasing global GHG emissions and associated climate change. Compared to the rest of the country, California is particularly vulnerable to significant resource and economic impacts from at least three effects of climate change. First, as sea level rise and coastal erosion and flooding increase, California (with its long coastline) will experience loss of, and damage to, coastal property, infrastructure, recreational beaches, wildlife habitat, and coastal water supplies. Second, California relies on its snowpack for water supply and storage, and this resource is predicted to decrease substantially this century. Third, California's urban, suburban, and rural areas are highly impacted by wildfires in ways most of the country simply does not face, and climate change will increase the incidence and severity of wildfires and resulting air quality and economic impacts. In addition, California is a major contributor to the

[16] Climate Action Team (CAT 2010) Report to the Governor and Legislature; available at http://www.energy.ca.gov/2010publications/CAT-1000-2010-004/CAT-1000-2010-004.PDF

nation's food supply; increasing droughts and higher temperatures put this production at risk.

After considering both observed and projected future effects of climate change (including key uncertainties, and the full range of risks and impacts to public health and welfare occurring within the State), the evidence points to the conclusion that climate change is already occurring at levels that harm our health and welfare, and that the effects will only worsen over time in the absence of regulatory action. California's transportation sector is the single largest contributor of GHGs in the State, producing close to 40% of all such emissions. On State highways in the coming decades, vehicle miles traveled are expected to continue to outstrip population growth under "business as usual" scenarios. Longer commute distances also have contributed to increases in vehicle miles traveled, while congestion has continued to increase; both factors contribute to GHG emissions. These trends indicate that if action is not taken that achieves significant long-term emission reductions, climate change will continue and its effects will worsen.

This chapter first presents the causes and projections for climate change (Section III.A.1.1). The chapter then discusses climate change pollutants (Section III.A.1.2), definition of global warming potentials used in the proposed regulation (Section III.A.1.3), indicators of climate change in California (Section III.A.1.4), and potential impacts of climate change on California (Section III.A.1.5). The chapter concludes with a brief discussion of abrupt climate change (Section III.A.1.6).

1.1. Climate Change Causes and Projections

Climate change is a shift in the "average weather" that a given region experiences. This is measured by changes in the features that we associate with weather, such as temperature, wind patterns, precipitation, and storms. Global climate change means change in the climate of the Earth as a whole. Global climate change can occur naturally; an ice age (due to variations in the Earth's orbit and inclination toward the sun that cause cyclical variations in solar energy received by the Earth) is an example of naturally occurring climate change. The Earth's natural climate has always been, and still is, constantly changing. The climate change we are seeing today, however, differs from previous climate change in both its rate and its magnitude.

The temperature on Earth is regulated by a system commonly known as the "greenhouse effect". Naturally occurring GHGs, primarily water vapor, CO_2, CH_4, and N_2O, absorb heat radiated from the Earth's surface. As the atmosphere warms, it in turn radiates heat back to the surface, to create what is commonly called the "greenhouse effect". The Earth's surface temperature would be about 34°C (61°F) colder than it is now if it were not for the natural heat trapping effect of GHGs. Water vapor is the most abundant and important of these naturally occurring GHGs. In addition to its direct effect as a GHG, clouds formed from atmospheric water vapor also affect the heat balance of the Earth by reflecting sunlight (a cooling effect), and trapping infrared radiation (a heating effect). Human activities add and subtract water vapor to and from

the atmosphere; however, these amounts are insignificant compared to the water moved by natural processes.

Fluctuations in levels of natural GHGs have been measured over the past 650,000 years. However, there are several reasons for attributing the rise in GHGs over the past 250 years to human activity rather than to naturally occurring climatic changes. The IPCC 4th assessment report (2007b)[17] confirms that over the past 8,000 years, prior to industrialization in 1750 , CO_2 concentration in the atmosphere increased by a mere 20 parts per million (ppm). The concentration of atmospheric CO_2 in 1750 was 280 ppm, and increased to 379 ppm in 2005. That is an enormous increase of 100 ppm in 250 years. For comparison, at the end of the most recent ice age there was approximately an 80 ppm rise in CO_2 concentration. This rise took over 5,000 years. Higher values than what we see today have only occurred many millions of years ago.

Human activities are exerting a major and growing influence on some of the key factors that govern climate by changing the composition of the atmosphere and by modifying the land surface. The human impact on these factors is clear. This increase has resulted from the burning of coal, oil, and natural gas, and the destruction of forests around the world to provide space for agriculture and other human activities. Rising concentrations of CO_2 and other GHGs are intensifying the Earth's natural greenhouse effect.

In its most recent assessment on climate change, the IPCC provided an estimate of global GHG emissions and projections of surface temperatures from 2000 to 2100 under six likely scenarios. Each scenario reflects a particular path for human society to grow. The main hypotheses concerning demography, agricultural practices, technology spreading, etc. are turned - through simple models - into projections about energy consumption, food production, and the corresponding GHG emissions. The IPCC report[18] projects an increase of global GHG emissions by 25% to 90% (CO_2e) between 2000 and 2030 (see Figure III-A-1-1 below taken from IPCC 2007 synthesis report), with fossil fuels maintaining their dominant position in the global energy mix to 2030 and beyond. Including uncertainties in future GHG concentrations and climate modeling, the IPCC anticipates a warming of 1.1 C to 6.4 C (2.0°F to 11.5°F) by the end of the 21st century.

[17] IPCC. (2007b). Technical Summary: *Climate Change 2007: The Physical Science Basis, Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change.* Cambridge University Press. https://www.ipcc-wg1.unibe.ch/publications/wg1-ar4/ar4-wg1-ts.pdf

[18] IPCC (2000), Special Report on Emissions Scenarios (SRES), available at http://www.ipcc.ch/pdf/special-reports/spm/sres-en.pdf

Figure III-A-1-1. Global GHG emission and temperature projections under different GHG emissions scenarios (taken from IPCC 2007c [19])



All emissions scenarios result in an increase in the atmospheric concentration of CO_2. For the six illustrative scenarios, the projected concentrations of CO_2 in the year 2100 range from 560 to 970 ppm, compared to about 280 ppm in the pre-industrial era and about 388 ppm in the year 2010. Every scenario imagines a world in which no explicit action is taken to combat GHG emissions. In the lowest-emission scenario, B1, it is assumed that technical and societal developments lead to a reduction in the use of fossil fuels. In this case, CO_2 levels are expected to continue rising, but to stabilize at a level that is roughly twice the pre-industrial level. Most analysts suggest that a doubling of GHG concentrations from pre-industrial levels will increase global temperatures about 3°C from pre-industrial levels, although many studies suggest the climate could be even more sensitive to a doubling of CO_2 concentrations.

Substantial scientific evidence indicates that an increase in the global average temperature of 2°C above pre-industrial levels (about 1.1°C above present levels) poses severe risks to natural systems and human health and well-being. Stabilizing the CO_2 concentrations at or below 450 ppm offers a 50% chance of keeping the global average temperature from rising more than 2°C, or 3.6°F, above pre-industrial levels. The same level is believed to result in a 33% chance of temperatures rising more than 3°C. Therefore, a 450 ppm CO_2 stabilization target generally represents the upper limit for the concentration of heat-trapping emissions in global policies that seek to avoid catastrophic climate change. Recent empirical evidence indicates climate change is taking place considerably faster than scientists had expected only a decade ago. Furthermore, paleoclimatic research indicates that earlier climate change episodes also took place rapidly. If rapid change is occurring, a considerably lower policy target than 450 ppm is justified. The goal of 350 ppm atmospheric CO_2 is supported by the most up-to-date science.

[19] IPCC (2007c), Synthesis report; available at http://www.ipcc.ch/pdf/assessment-report/ar4/syr/ar4_syr_spm.pdf).

The concentration of GHGs in the atmosphere is determined by the difference between the rate of emissions and the rate of uptake by the world's ecosystems and oceans. Since the rate of CO_2 emissions currently exceeds the rate of uptake, halting emissions is not enough to stop the build-up of atmospheric CO_2. Temperatures will continue to rise long after emissions are reduced and GHG concentrations are stabilized. Hence, reducing GHG concentrations in the atmosphere to the lowest feasible level is critical to limiting warming to no more than 2°C. There is considerable uncertainty as to whether we will reach the 2°C target given the lack of prompt and meaningful global action.

Executive Order S-3-05 established GHG targets for the State such as: returning to year 2000 emission levels by 2010; 1990 levels by 2020; and 80 percent below 1990 levels by 2050. If the industrialized world were to follow California's lead, it would increase the likelihood that California and the world would be on track to avoid the more severe climate change impacts. This estimate of the impact of an 80 percent reduction by the industrialized world has on global emissions depends crucially on the growth rate and energy strategies of the developing world.

In the Kyoto Protocol a number of industrialized countries (the "Annex I Parties") made commitments to limit or reduce GHG emissions by 2012. The current internationally-agreed mitigation targets apply only to industrialized countries and do not extend beyond 2012. Successfully limiting emissions in order to stabilize atmospheric GHG concentrations at acceptable levels will require the participation of all major emitting countries. The "most challenging" mitigation case would stabilize atmospheric concentrations of CO_2 at 450 ppm. This is significant because avoiding substantial temperature change by mid-century is a starting point for achieving more aggressive long-term targets. The 450 ppm target would make it possible to limit long-term global mean temperature increases and to avoid some of the most severe risks of climate change.

The climate system is highly dynamic: External "forcings" such as anthropogenic GHG emissions, "reflective" aerosol particles from volcanoes and fossil fuel combustion, and solar radiation alter the amount of radiation in the Earth's atmosphere. "Feedbacks" (such as cloud or ice-albedo feedbacks) amplify or dampen the effect of forcings. While all climate models project that significant warming will result of rising GHG concentrations, the amount of warming that will result from anthropogenic GHG emissions will depend on the intensity of and interactions between these forcings and feedbacks. The consequences of the warming will depend on the degree and speed of temperature rise, and the internal dynamics of the climate system—the atmosphere, oceans, land, ice sheets, and biosphere—and whether or not any non-linear climate thresholds are reached that result in catastrophic damages (IPCC 2007, Synthesis Report).

1.2. Climate Change Pollutants

Naturally occurring GHGs include water vapor, carbon dioxide, methane, nitrous oxide, and ozone (O_3). Several classes of halogenated substances that contain fluorine,

chlorine, or bromine are also GHGs, but they are, for the most part, solely a product of industrial activities. Chlorofluorocarbons (CFCs) and hydrochlorofluorocarbons (HCFCs) are halocarbons that contain chlorine, while halocarbons that contain bromine are referred to as bromofluorocarbons (i.e., halons).

Because CFCs, HCFCs, and halons are substances which deplete stratospheric ozone, they are regulated by the Montreal Protocol on Substances that Deplete the Ozone Layer. The United Nations Framework Convention on Climate Change (UNFCCC) defers to this earlier international treaty; consequently these gases are not included in national GHG inventories. However, large quantities of CFCs, halons, and other ozone depleting substances (ODS) produced prior to phase-out deadlines under the Montreal Protocol remain legally in use or storage in older equipment, building and appliance insulation, and other "banks." ODSs not only contribute to the depletion of the stratospheric ozone layer, but they are also potent GHGs with global warming potentials up to thousands of times higher than CO_2. Without intervention, most of the banks are expected to be emitted by 2020 as a result of regular equipment and appliance turnover. The window for addressing emissions from banks is relatively narrow with every year lost translating into millions of tons of CO_2e emitted.

The Parties to the Montreal Protocol are preparing to take another important step towards better ozone layer protection and climate change mitigation to promote the destruction of ODS banks. These proposals seek to recover and destroy ODSs before they are emitted from existing stockpiles and from discarded products and equipment, and before they harm the ozone layer and climate system. To reduce statewide GHG emissions to 1990 levels by 2020, CARB is also considering policies to reduce emissions of high global warming potential gases—including ODS as well as ODS substitutes.

Other fluorine-containing gases—hydrofluorocarbons (HFCs), perfluorocarbons (PFCs), and sulfur hexafluoride (SF_6)—do not deplete stratospheric ozone but are potent GHGs. These latter substances are addressed by the UNFCCC and accounted for in State and national GHG inventories. GHG concentrations in the atmosphere are a function of both the emissions of the GHGs and the effective lifetime of these gases. Because it takes one to two years to mix the emissions of a species throughout the troposphere, gases that are chemically stable and persist in the atmosphere over time scales of decades to centuries or longer are referred to in the IPCC as "long-lived" or "well-mixed" gases.

Each gas has a characteristic lifetime that is a function of the total atmospheric burden and the removal mechanism (i.e., sinks) for that gas. Each GHG has different interactions of each gas with the various available sinks, which include chemical reaction with the hydroxyl (OH) free radical or other highly reactive species, photolysis by sunlight, dissolution into the oceans, reactions on the surface, biological processes, or other mechanisms. According to the IPCC (2007), the lifetime of the HFCs of industrial importance range from 1.4 to 270 years, the lifetime of N_2O is 114 years, the lifetime of CH_4 is 12 years, and the lifetime of the PFCs and SF_6 range from 1,000 to 50,000 years. Carbon dioxide has a very different life cycle compared to the other

GHGs, which have well-defined lifetimes. Instead, unlike the other gases, CO_2 is not destroyed by chemical, photolytic, or other reaction mechanisms, but rather the carbon uptake in CO_2 cycles between different reservoirs in the atmosphere, ocean, land vegetation, soils, and sediments.

Historic data show that current atmospheric concentrations of the two most important directly emitted, long-lived GHGs (CO_2 and CH_4) are well above the natural range of atmospheric concentrations compared to at least the last 650,000 years. Atmospheric GHG concentrations have been increasing because anthropogenic emissions have been outpacing the rate at which GHGs are removed from the atmosphere by natural processes over timescales of decades to centuries.

The California GHG inventory compiles statewide anthropogenic GHG emissions and sinks. It includes estimates for CO_2, CH_4, N_2O, SF_6, nitrogen trifluoride (NF_3), HFCs, and PFCs. The current inventory covers years 2000 to 2008 (available at http://www.arb.ca.gov/cc/inventory/data/data.htm). Individual climate change pollutants are briefly discussed in the following sections.

Carbon Dioxide (CO_2): California's total CO_2 emissions from fossil fuel combustion in 2008 were 485 million metric tons of CO_2 equivalent ($MMTCO_2e$), and represent about 89% of California's total GHG emissions. Annual statewide emission inventories provide the basis for establishing historical emission trends. There are many factors affecting GHG emissions and year to year changes, including the state of the economy, changes in demography, improved efficiency, and changes in environmental conditions such as drought. In 2008, California observed a small decrease in statewide GHG emissions, driven by a noticeable drop in on-road transportation emissions. 2008 also reflects the beginning of the economic recession and fuel price spikes.

Despite lower overall GHG emissions in 2008, transportation remained the largest source with 36% of California's gross inventory. On-road emissions (from passenger vehicles and heavy-duty trucks) constitute 93% of the transportation sector total. On-road emissions grew to a maximum of 171 $MMTCO_2e$ in 2005, plateaued until 2007, and decreased in 2008 to 163 million. The amount of gasoline and diesel fuel consumed by on-road vehicles followed a similar trend. As the economy recovers, GHG emissions are likely to rise again without other mitigating actions.

Figure III-A-1-2. California's 2008 GHG emissions by Sector



Source: http://www.arb.ca.gov/cc/inventory/data/graph/graph.htm

Methane (CH_4): Methane accounted for approximately 5% (29 $MMTCO_2e$) of gross 2008 GHG emissions in California. Methane is produced during anaerobic decomposition of organic matter in biological systems. Decomposition occurring in landfills accounts for the majority of anthropogenic CH_4 emissions in California and in the United States as a whole. Agricultural processes such as enteric fermentation, manure management, and rice cultivation are also significant sources of CH_4 in California. Methane emission levels from a source can vary significantly from one region to another, depending on many factors such as climate, industrial and agricultural production characteristics, energy types and usage, and waste management practices. Results of a study[20] indicate that current inventory of CH_4 emissions from the Central Valley are underestimated; suggesting that actual CH_4 emissions could be about 20-60% higher than California-specific inventory estimates.

Nitrous Oxide (N_2O): Another gas that contributes to global warming is N_2O. Agricultural soil management activities and mobile source fuel combustion compose the major sources of these emissions. N_2O emissions comprised around 3% (14 MMT CO_2e) of California's overall GHG emissions in 2008. Nitrous oxide emission levels from a source can also vary significantly from one region to another, depending on many factors such as industrial and agricultural production characteristics, combustion technologies, waste management practices, and climate. For example, utilization of synthetic nitrogen fertilizers in crop production typically results in more N_2O emissions from agricultural soils than that occurring from less intensive, low-tillage techniques. Also, the presence or absence of control devices on combustion sources, such as

[20] Zhao, C., A. E. Andrews, L. Bianco, J. Eluszkiewicz, A. Hirsch, C. MacDonald, T. Nehrkorn, and M. L. Fischer (2009), Atmospheric inverse estimates of methane emissions from Central California, J. Geophys. Res., 114, D16302, doi:10.1029/2008JD011671.

catalytic converters on automobiles, can have a significant effect on the level of N_2O emissions from these types of sources. The IPCC provides default emission factors. Using the IPCC default values as opposed to conducting monitoring programs could introduce a large degree of uncertainty. Hence; it seems the current estimates of N_2O emissions may be underestimated.

In addition to CO_2 emissions, light-duty vehicle GHG emissions also include CH_4 and N_2O. Although emissions of these compounds are generally orders of magnitude lower than emissions of CO_2, the global warming potential of both CH_4 and N_2O is greater than that of CO_2. As a result, it is important to consider these emissions in determining the overall GHG impact potential of light-duty vehicles. It is important to recognize, however, that current vehicles produce and emit substantially less CH_4 and N_2O than their older counterparts and it is almost certain that future vehicles will exhibit even lower emission rates. Existing standards for non-methane organic compounds and NO_X result in reduced CH_4 and N_2O emissions through the design and implementation of advanced combustion and catalyst technologies.

Hydrofluorocarbons (HFCs), Perfluorocarbons (PFCs), and Sulfur Hexafluoride (SF_6): HFCs, PFCs and SF_6 accounted for another 3% of 2008 GHG emissions in California. HFCs are primarily used as substitutes for ozone-depleting substances regulated under the Montreal Protocol. PFCs and SF_6 are generally emitted from various industrial processes including aluminum smelting, semiconductor manufacturing, electric power transmission and distribution, and magnesium casting.

For vehicular HFC emissions (particularly HFC-134a), four emission sources, all related to air conditioning, should be considered: emissions leaking from the hoses, seals, and system components of vehicle air conditioning system, and emissions that are released when the air conditioning system is opened for servicing. HFC emissions can also occur when the vehicle is scrapped at the end of its useful life or due to sudden releases (e.g., traffic accident refrigerant releases). HFC-134a, commercially known as R-134a, is presently the vehicle refrigerant of choice among vehicle manufacturers.

Water Vapor (H_2O): It should be noted that there's an important difference between water vapor and other GHGs. Human activities do not seem to be appreciably changing the atmospheric concentration of water vapor in any direct way on the global average. Nor does water vapor accumulate in the atmosphere over the multi-year periods that other GHGs do. Natural processes (e.g., rain) remove water vapor when it reaches certain limits. Water stays in the atmosphere for a few days, while other GHGs linger for decades or centuries. The overall impact of water vapor with respect to global climate change is not well understood as it can lead to both warming (absorption of long-wave radiation from Earth) and cooling (cloud formation/reflection of solar radiation).

Other Radiatively Important Species: There are also several gases that do not have a direct global warming effect but indirectly affect terrestrial and/or solar radiation absorption by influencing the formation or destruction of GHGs, including tropospheric

and stratospheric ozone. These gases include carbon monoxide (CO), oxides of nitrogen (NO_X), and non-CH_4 volatile organic compounds (NMVOCs). The sequence of reactions that removes CO, NO_X, and NMVOCs from the atmosphere, however, tends to promote the formation of tropospheric ozone (a potent GHG). The reactions that produce ozone or alter the losses of CH_4 are strongly affected by the relative concentrations of various pollutants, the ambient temperature, and local weather conditions. At present, there is large scientific uncertainty in estimating their radiative forcing effects. The above listed compounds, regulated in the USEPA and California pursuant to the Clean Air Act, are often referred to as "criteria pollutants". The criteria pollutants are reactive compounds, and they tend to remain in the atmosphere for a much shorter time than most other GHGs.

Aerosols, which are extremely small particles or liquid droplets, such as those produced by sulfur dioxide (SO_2) or black carbon (BC) emissions, can also affect the absorptive characteristics of the atmosphere. Four of the more important aerosols are sulfates, nitrates, organic carbon, and BC. While some aerosols are directly emitted, others are formed through secondary reactions (for example, sulfates and nitrates can be formed by oxidation of SO_2 and NO_X respectively), and their properties can change as they mix and react in the atmosphere. Aerosols affect radiative forcing in both direct and indirect ways: directly by scattering and absorbing solar and thermal infrared radiation; and indirectly by altering the cloud properties and atmospheric heating rates that in turn modify the formation, precipitation efficiency, and radiative properties of clouds. The effect of aerosols on regional and global climate is complex: in general, sulfate aerosols enhance the reflection of sunlight and cool the Earth, while black carbon aerosols enhance the absorption of sunlight and warm the Earth. Appendix U provides a more detailed discussion of climate change impacts of black carbon particles.

Black carbon is the light-absorbing carbonaceous fraction of particulate matter (PM) that results from incomplete combustion of fossil fuels and biomass. In recent years, there has been increased attention in the particle research community to the potential of BC to cause global warming. The ability of BC to absorb light energy and its role in key atmospheric processes link it to a range of climate impacts, including increased temperatures, accelerated ice and snow melt, and disruptions to precipitation patterns. It has been proposed that light absorbing particles in the atmosphere act as a greenhouse pollutant whose net forcing is warming only second to CO_2. Ramanathan and Carmichael[21] estimate a BC forcing of 0.9 W/m^2 or more than half of the 1.6 W/m^2 attributed to CO_2. This estimate of the forcing due to BC is larger than most prior estimates including those of the IPCC 4th assessment report.

The relatively short atmospheric residence time (only a few weeks) of BC makes reductions in BC emissions a potential near-term opportunity to postpone the effects of rising GHG levels on the global climate. Unlike the benefits associated with reductions in GHG emissions which take decades to be fully realized, reductions in BC emissions yield immediate improvements. However, a number of issues that may impede policy

[21] Ramanathan, V. and Carmichael, G. (2008) Global and regional climate changes due to black carbon. Nature Geoscience 156, 221-227.

action include the fact that BC emissions are not covered in the Kyoto Protocol and the co-emission of BC with cooling pollutants, namely organic carbon, complicates accounting and development of effective interventions. Additional remaining uncertainties in BC climate effects (due to its ability to affect clouds) and the lack of an internationally agreed-upon global warming potential or other metric for BC are current obstacles towards a uniform policy framework and are likely to be research questions that should be addressed.

California's unique emissions and fuel standards for cars, trucks, buses, motorcycles, and other motor vehicles have dramatically reduced criteria pollutant emissions, as have controls on non-automotive pollution sources that are administered by the State's 35 local air pollution control districts. California has achieved these improvements despite the State's substantial growth in population, vehicle use, and business activities.

1.3. Global Warming Potentials

Radiative forcing is often defined as a net imbalance in energy flux in the atmosphere, and is expressed in watts per square meter (W/m^2), (i.e., heat per area of the Earth's surface). Radiative forcing of the surface-troposphere system, resulting, for example, from a change in GHG concentrations, is the change in the balance between radiation coming into the atmosphere and radiation going out. A positive radiative forcing tends, on average, to warm the surface of the Earth, and negative forcing tends, on average, to cool the surface. The impact of a GHG emission upon the atmosphere is related not only to radiative properties of the gas and its initial abundance, but also to the length of time the GHG remains in the atmosphere. Radiative properties control the absorption of radiation per kilogram of gas present at any instant, but the lifetime of the gas controls how long an emitted kilogram remains in the atmosphere and hence its cumulative impact on the atmosphere's thermal budget. The climate system responds to changes in the thermal budget on time-scales ranging from the order of months to millennia depending upon processes within the atmosphere, ocean, and biosphere.

Gases in the atmosphere can contribute to the greenhouse effect both directly and indirectly. Direct effects occur when the gas itself is a GHG. Indirect radiative forcing occurs when chemical transformations of the original gas produce other GHGs, when a gas influences the atmospheric lifetimes of other gases, and/or when a gas affects atmospheric processes that alter the radiative balance of the Earth (e.g., cloud formation). The concept of a Global Warming Potential (GWP) has been developed in parallel to the concept of ozone depletion potential developed under the Montreal Protocol to compare the ability of each GHG to trap heat in the atmosphere relative to another gas. CO_2, the primary anthropogenic GHG, has been chosen as the reference gas.

GWP is defined as the ratio of the time-integrated radiative forcing from the release of 1 kilogram of a trace substance relative to that of 1 kg of CO_2 (IPCC 2007). While any length of integration can be selected, the 100-year GWPs are recommended by the IPCC and are employed by ARB for policy-making and reporting purposes.

GWP values allow a comparison of the impacts of emission changes (reductions or increases) of different gases. In addition to communicating GHG emissions in units of mass, we have also chosen to use GWPs to reflect their inventories in CO_2 equivalent terms because it effectively places all of the GHGs on the same comparative scale. It should be noted that when the lifetime of the species in question differs substantially from the response time of CO_2 (nominally about 150 years), then the GWP becomes very sensitive to the choice of time horizon. The GWP concept is only relevant for compounds that have sufficiently long lifetimes to become globally well-mixed. Therefore, short-lived gases and aerosols with varying atmospheric distributions and lifetimes pose a problem in the simple GWP framework.

Table III-A-1-1 lists GWPs for CO_2, CH_4, N_2O, HFCs, PFCs, and SF_6 for the 20-, 100-, and 500-year time horizons. Assembly Bill 1493 calls for reductions in GHGs, which are defined in the bill as CO_2, CH_4, N_2O, HFCs, PFCs, and SF_6. The first four of these identified GHGs are clearly associated with motor vehicle use in California. PFCs and SF_6 are not known to be associated with motor vehicle emissions in California and therefore are not addressed further in the staff report. Table III-A-1-1 includes all six climate change pollutants including CO_2, CH_4, and N_2O, hydrofluorocarbons (HFCs), perfluorocarbons (PFCs), and sulfur hexafluoride (SF6) that are proposed/listed in AB32.

As mentioned earlier, in addition to the six GHGs identified above, there are a number of man-made pollutants, emitted primarily as byproducts of combustion (both of fossil fuels and of biomass), that affect the climate. Several of these substances have both warming and cooling effects, with considerable uncertainty as to the net effect. Those generally believed to result in net warming include CO, NMVOC, and the fraction of particulate matter (PM) substantially consisting of BC. The 2007 IPCC states that in addition to the gases targeted in the Kyoto Protocol, the contribution of tropospheric O_3 to the greenhouse effect is also important. The report further states that in order to curb global warming it is necessary to reduce the emissions of both GHGs and other gases that influence the concentration of GHGs. Air pollutants such as NO_X, CO, and NMVOC generate O_3 and impact tropospheric OH radicals, which in turn alters CH_4 levels. Hence, they are called indirect GHGs. This interrelationship of direct and indirect GHGs is one reason it is important to simultaneously control smog-forming and particulate matter pollutants, as well as the "traditional" six GHGs such as CO2, sometimes with the same technologies (e.g. advanced hybrid technology and zero-emission vehicles).

Table III-A-1-1. Numerical Estimates of Global Warming Potentials Compared With CO_2 (Kilograms Of Gas Per Kilogram Of CO_2 -- Adapted From IPCC 2007d[22])

Climate Pollutants	Lifetime (years)	Global Warming Potential		
		20 years	100 years	500 years
CO_2	~150	1	1	1
CH_4	12	72	25	7.6
N_2O	114	289	298	153
HFCs (depending on type of HFC)	2-270	437-12,000	124-14,800	38-12,200
PFCs (depending on type of PFC)	740-50,000	5,210-13,200	7,390-17,700	11,200-21,200
SF_6	3,200	16,300	22,800	32,600

All of these substances have significantly greater uncertainty associated with quantifying their impacts on climate than the six pollutants identified in the Kyoto Protocol. This is partly due to the fact that their impacts occur by influencing the concentrations of direct GHGs through a series of complex chemical reactions, and their high chemical activity and large variation in source strengths lead to temporal and spatial variations. Therefore, these other agents typically have not been directly included in climate-related emission reduction efforts due to scientific uncertainty regarding the magnitude or direction of their climate change effect and difficulty in quantifying their impact in terms of "CO_2 equivalent", which is the standard metric of global warming potential.

In summary, multi-component abatement strategies to limit human-induced climate change need a framework and numerical values for the trade-off between emissions of different GHGs. Alternative metrics to compare emissions of GHGs can result in very different priorities for abatement of different gases in mitigation strategies. The GWP with a 100 year time horizon is the most widely accepted metric for comparing GHGs. Although shortcomings have been identified, no other metric has gained comparable status to GWPs. Both at the national and international levels, the GWP remains an appropriate metric for comparing the potential climate impact of the emissions of different forcing agents.

1.4. Indicators of Climate Forcing and Climate Change in California

Over the last several decades, evidence of human influences on climate change has become increasingly clear and compelling. There is indisputable evidence that human activities are adding to the concentrations of greenhouse gases that are already naturally present in the atmosphere. These heat-trapping gases are now at record-high

[22] IPCC (2007d), Working Group I: The Physical Science Basis, Chapter 2: Changes in Atmospheric Constituents and in Radiative Forcing, available at http://www.ipcc.ch/pdf/assessment-report/ar4/wg1/ar4-wg1-chapter2.pdf

levels in the atmosphere compared with the recent and distant past. Warming of the climate system is well documented, evident from increases in global average air and ocean temperatures, widespread melting of snow and ice, and rising global average sea level. Most of the observed increase in global average temperatures since the mid-20th century is very likely due to the observed increase in anthropogenic GHG concentrations (IPCC 2007a).

Indicators of climate forcing and actual climate change can be used to illustrate trends, measure the suitability of particular actions in certain areas, measure progress made in meeting climate change policy targets, identify requirements for adaptation and mitigation measures, and encourage public awareness of the climate change impacts. Hence, collecting and interpreting environmental indicators has played a critical role in our increased understanding of climate change and its causes. An indicator represents the state of certain environmental conditions over a given area and a specified period of time. Examples of climate change indicators include temperature, precipitation, sea level, and GHG concentrations in the atmosphere.

Trends in GHG emissions are useful in these areas. Atmospheric CO_2 and other GHG concentrations are a key indicator for international negotiations on emission reduction. Climate and atmospheric variables such as temperature change and trends in precipitation are also important. In general, indicators to describe the impact of climate change on human health are still limited due to lack of data. Climate change can exacerbate heat waves resulting in higher rates of morbidity and mortality. Furthermore, higher temperatures could lead to an increase of water and food related diseases. Scientists, analysts, decision-makers, and others use environmental indicators, including those related to climate, to help track trends over time in the state of the environment, key factors that influence the environment, and effects on ecosystems and society.

California began one of the earliest efforts to track and reduce greenhouse gas emissions and to support research to better understand climate change and its impacts. Palpable signs or "indicators" of climate change in California can be found in this wealth of scientific research and environmental monitoring. These indicators help tell the story of how California's climate is changing and how these changes are influencing many of our natural systems. Several potential climate change indicators have been suggested, including anthropogenic GHG emissions, air temperature, annual Sierra Nevada snow melt runoff, and sea level rise in California (EPIC, 2009)[23]. Changes occurring in California are largely consistent with those occurring globally. In summary, the indicators of climate change in the 2009 EPIC report show the following:

- Emissions of GHGs have increased since 1990, with CO_2 from the combustion of fossil fuels for transportation accounting for the largest proportion of emissions. The contribution of GHG from the combustion of different fuels varies by fuel

[23] Office of Environmental Health Hazard Assessment. Environmental Protection Indicators for California (EPIC), 2009. Available at: http://oehha.ca.gov/multimedia/epic/pdf/ClimateChangeIndicatorsApril2009.pdf).

type. Nonrenewable fossil fuels are used more than any other fuel type in California and emissions from the combustion of gasoline and natural gas have increased the most between 1990 and 2004.

- Atmospheric concentrations of CO_2 have been increasing in coastal areas of the state, consistent with global trends. Measurements at La Jolla, as well as shorter term measurements at Trinidad Head and Point Arena, are consistent with global trends, as represented by the measurements at Mauna Loa, Hawaii.

- Temperature data have been collected at many weather stations in the State for almost a century. The air temperature indicator can be used to track trends in statewide surface air temperatures and regional variations, allowing for a comparison of temperature changes in California with those occurring globally. Air temperatures have increased over the past century, with nighttime minimum temperatures showing a greater rate of increase than daytime maximum temperatures. The 11 climate regions within the State are showing the same warming trends over the last century. The entire State has been warming in both minimum and mean temperatures, at approximately 2°F per century. There are modest differences around the State in the rate of daytime warming. Counties with populations over 1 million are warmer than those with populations under 100,000. Conversely, counties with less than 100,000 people had the lowest average rate of temperature increase. The rate of temperature increase -- 0.7°F (0.5°C) per century -- from the rural group agrees with a global estimated mean surface temperature increase of 0.5 to 1.0°F (0.3 to 0.6°C) since the 19th century.

- Summertime temperature extremes, especially at night, have been decreasing over the past half century. Likewise, winter chill hours, a factor critical for fruit trees to produce flowers and fruit, have been decreasing in the fruit growing valleys of California over the same time period.

- Precipitation in the form of rain and snow is a major component of the biological and economic lifeblood of California. The historical likelihood of wet and dry episodes of various durations must be factored into planning for management of water resources (municipal and industrial water supplies, agriculture, hydropower, recreation, fish habitat, and others) and in planning for both floods and droughts. Over the entire 112-year period of record, the linear trend of annual precipitation is an increase of about 17 percent per century. Of note are the large year-to-year variations in precipitation, particularly since the 1930s, and long episodes of consecutive dry or wet years at many times during the observational record.

- The warming of global climate could increase evaporation rates, thereby potentially increasing precipitation and storms in the State. Snowmelt and runoff volume data can be used as a climate change indicator to document changes in runoff patterns. For example, the percentage of annual runoff fraction during the spring snowmelt period of the Sacramento River has decreased by 10 percent

since 1906. Less spring runoff can reduce the amount of potential summer water available for the State's water needs and hydroelectric power production. These specific regional changes are related, at least in part, to the climate change associated with the observed global mean warming. In California, large accumulations of snow occur in the Sierra Nevada and southern Cascade Mountains from October to March. Each winter, at the high elevations, snow accumulates into a deep pack, preserving much of California's water supply in cold storage. If the winter temperatures are warm, more of the precipitation falls as rain instead of snow, and water directly flows from watersheds before the spring snowmelt. Thus, there is less buildup of snow pack; as a result, the volume of water from the spring runoff is diminished. Less spring runoff can reduce the amount of potential summer water available for the state's water needs and hydroelectric power production. Lower runoff volumes can also impact recreation opportunities, and impair cold water habitat for salmonid fishes.

- Snow-water contents have trended towards less water stored in snow-packs in the Northern Sierra Nevada, and towards more water stored in snow-packs in the Southern Sierra Nevada during the past several decades. During spring, snow-water contents have declined by about 15 percent in the northern Sierra Nevada since 1950, while increasing by about 15 percent in the southern Sierra Nevada. Together, the decreases in the north and increases in the south have combined to yield little or no net change in the statewide snow-water content averages.

- Glaciers are important indicators of climate change. Over the 20th century, with few exceptions, alpine glaciers have been receding throughout the world in response to a warming climate. The surface area of seven Sierra Nevada glaciers has decreased over the past century. In 2004, the area of these seven glaciers ranged from 22 to 69 percent of their 1900 area.

- Sea level rise provides a physical measure of possible oceanic response to climate change. Increasing global mean temperatures will result in the rise in mean sea level. Warming of the ocean water will cause a greater volume of sea water because of thermal expansion. This contributes the largest share of sea level rise, followed by melting of mountain glaciers and ice caps.

- Along California's coast, sea level already has risen by three to nine inches over the last century (three inches at Los Angeles, eight inches at San Francisco, and an estimated nine inches at La Jolla near San Diego), and it is likely to rise by another 7 to about 30 inches by 2100. Differences in sea level rise along the coast can occur because of local geological forces, such as land subsidence and plate tectonic activity. Global warming studies predict that global sea level will rise at an accelerated rate, much beyond that seen in prehistoric natural cycles of warming and cooling evidenced by geologic data.

- The scientific evidence suggests that terrestrial, marine and freshwater biological systems are also being strongly influenced by recent warming. From 1983 to

2004, tree mortality resulting from stress and biotic causes (as opposed to mechanical causes) in temperate old-growth forests of the Sierra Nevada has increased at the average rate of 3 percent per year. The increase in mortality rate coincides with a temperature-driven increase in estimated climatic water deficit, a measure of drought.

- Large-wildfire (fire event ≥400 hectares) activity in western U.S. forests increased suddenly and markedly in the mid-1980s. From 1987 to 2003, wildfire frequency was nearly four times the average number, and the total area burned was more than six times the level seen between 1970 and 1986. Inter-annual variability in wildfire frequency is strongly associated with regional spring and summer temperature. Also, when comparing 1970-1986 with 1987-2003, the length of the yearly wildfire season (March through August) extended by 78 days, a 64 percent increase, and the duration of individual fires increased from one week to about five weeks.

- The lower edge of the conifer-dominated forests in the Sierra Nevada has been retreating upslope over the past 60 years. The spring and fall arrivals of some migratory birds are changing. Small mammals in Yosemite National Park are found today at different elevational ranges compared to earlier in the century. Butterflies in the Central Valley have been arriving earlier in the spring over the past four decades.

The climate change indicators described above represent key properties of the climate system that are considered sensitive to climate change. Many additional potential indicators remain to be explored. For example, climate change may influence the frequency of extreme weather events, ecosystem structures and processes, and species distribution and survival. It may affect forestry, energy and other industries, insurance and other financial services, and human settlements. In addition, the impacts can vary from one region, ecosystem, species, industry, or community to the next. Research into the regional impacts of climate change is ongoing, and the potential climate change indicators will be updated and expanded as new information becomes available.

1.5. Potential Impacts on California

Climate is a central factor in Californian life. It is at least partially responsible for the State's rapid population growth in the past 50 years, and largely responsible for the success of industries such as agriculture and tourism. The potential effects of climate change on California have been widely discussed from a variety of perspectives. The signs of a global warming trend continue to become more evident and much of the scientific debate is now focused on expected rates at which future changes will occur.

Climate change poses serious risks to California's natural resources. California-specific impacts are expected to include changes in temperature, precipitation patterns, and water availability, as well as rising sea levels and altered coastal conditions. These

physical changes will have economic repercussions across the California economy, including in agriculture, forestry, energy production and consumption, air quality, coastal infrastructure, and public health.

California has a long history of studying the potential impacts of climate change on the State's natural resources and economy. In 2005, Executive Order S-3-05 established GHG targets for the State such as: returning to year 2000 emission levels by 2010; 1990 levels by 2020; and 80 percent below 1990 levels by 2050. The Executive Order also requires biennial reports on progress toward meeting those targets and updates on the impacts of global warming on California. The Climate Action Team produced its first Assessment Report in March 2006. The second assessments report (CAT 2010) provides the most comprehensive review and analysis of climate change modeling for California to date. This study is also the first state-level evaluation of both the physical and economic consequences from potential future climate change.

Through its reliance on peer-reviewed scientific studies, the 2010 CAT report provides strong evidence of the benefits of putting California and the world on the path to a low carbon future. The climate change scenarios describe changes in temperature, changes in precipitation patterns and water availability, and rising sea levels and altered coastal conditions. Each of these basic climatological changes in turn drives changes in natural and human systems that have the potential to alter the future of the State. Specific research highlights include:

Agriculture: The diversity and size of California's agricultural sector creates unique opportunities and challenges in its responses to climate change. Global warming is likely to change precipitation, temperature averages, maximums and minimums, pest and weed ranges, the length of the growing season, and other factors. These will all affect crop productivity. Lee et al.[24] looked at productivity changes from 1950–2099 for seven annual field crops: alfalfa (hay), cotton, maize, winter wheat, tomatoes, rice, and sunflower. Compared to 2000, in 2050 cotton, maize, sunflower, and wheat yields decrease from 3 percent to 8 percent, while rice and tomato yields were essentially the same. Alfalfa yields increased, but the results were not consistent across counties. However, by the end of the century, yields of all crops except alfalfa decreased, and the differences between high- and low-GHG emissions scenarios were pronounced. The results suggest that climate change will decrease annual crop yields in the long-term, particularly for cotton, unless future climate change is minimized and/or adaptation of management practices and improved cultivars becomes widespread.

Extreme events may be among the greatest challenges, as they can lead to large losses. Since 1980, nighttime temperature has increased about three times as much as daytime temperature, and in some areas there has been a reduction in yield for wheat, maize, and barley. If the climate shifts toward a severe drought, not only will more irrigation be needed, but also the snow pack at higher elevations will be lacking. This

[24] Lee, J., S. De Gryze, J. Six. (2009). Effect of Climate Change on Field Crop Production in the Central Valley of California. California Energy Commission. CEC-500-2009-041-F. http://www.energy.ca.gov/2009publications/CEC-500-2009-041/CEC-500-2009-041-F.PDF

can be disastrous for producers that grow fruit trees and vines that will require years to reestablish production. By the end of the century modeling predicts that yields of almost all high value crops studied will decrease.

Forestry: California timber production has been declining over the past few decades due to several factors, including moderate warming, increased wildfires, land use change and growing emphasis on recreation. Climate change has the potential to further affect the extent of forests, the amount of timber production in the State and the value of timber on the market. The long-term increase in fire occurrence associated with GHG emissions is substantial, as well as an increased estimated burned area in California. Westerling et al.[25] constructed a statistical model of wildfire as a function of climate and land surface characteristics in California. Model results suggest increases in wildfire, although the range of outcomes is large and expands with time. The long-term increase in fire occurrence associated with the higher GHG emissions pathway is substantial, with increases statewide ranging from 58 percent to 128 percent by 2085. Likewise, estimated burned area increased 57 percent to 169 percent.

Water Resources: The Sierra Nevada snowpack is California's main water reservoir, and higher temperatures equate to more rain and less snow. The high elevation snowpack serves as a natural reservoir that stores fresh water during the wet, cold season and releases it gradually during the dry, warm season. About 60% of the water supply for Southern California comes from melting Sierra Nevada snowpack. The State may be facing a future with as much as 70 to 90% reduction in the Sierra Nevada snow pack. Snowmelt also affects hydropower generation in California (Vicuña et al.[26]). The impact of global warming on the Sierra Nevada snowpack has become one of the leading topics in the regional climate change studies for the California region. Hadley et al.[27] examined the concentration of BC aerosols in snow in California and the potential of these aerosols to reduce albedo and increase melt. This study provides one of the first direct measurements for the efficient removal of black carbon from the atmosphere by snow and its subsequent deposition to the snow packs of California. The data reveal that BC concentrations in the Sierra Nevada snowpack are sufficient to perturb both snow melt and surface temperatures.

California's water delivery and usage is delicately balanced. Any major changes in rainfall, snowpack, and timing would have serious ramifications. For instance, climate change would result in the need for more irrigation coming from a less reliable water supply. The reliability of the State Water Project and federal Central Valley Project water supply systems are expected to be reduced, so without changes in operating

---

[25] Westerling, A.L., B. P. Bryant, H.K. Preisler, H G. Hidalgo, and T. Das. 2009. Climate Change, Growth, and California Wildfire. California Energy Commission. CEC-500- 2009-046-F. http://www.energy.ca.gov/2009publications/CEC-500-2009-046/CEC-500-2009-046-F.PDF

[26] Vicuna, S., R. Leonardson, M. Hanemann, L. Dale, and J. Dracup. 2008. "Climate change impact on high elevation hydropower generation in California's Sierra Nevada: A case study in the upper American River." *Climatic Change* **87**:S123–S137.

[27] Hadley, O. L., Corrigan, C. E., Kirchstetter, T. W., Cliff, S. S., and Ramanathan, V. (2010). Measured black carbon deposition on the Sierra Nevada snow pack and implication for snow pack retreat, Atmos. Chem. Phys., 10, 7505-7513, doi:10.5194/acp-10-7505.

rules, gains in efficiency, and expanded infrastructure, the statewide water supply systems could be severely affected.

Coastal Areas: Sea level rise is one of the most obvious and severe impacts of a warming world, leading to displacement of human populations and severe economic impacts. As global warming continues, California's coastal regions will be increasingly threatened by more intense storms and warmer water temperatures. Many of the areas indicated as vulnerable to sea water inundation are presently behind levees and would be inundated if those levees breached or were overtopped. Other areas with critical infrastructure, such as the San Francisco and Oakland airports, would need levee protection.

Energy: Anticipated climate change will affect residential electricity demand patterns for California's households. On average, statewide electricity demand in the residential sector may increase by about 7% in the next few decades solely due to increases in mean temperature and frequency of extreme heat events from climate change. These changes represent substantial impacts to California's residents and an added stress to the electricity generating sector. California's water and hydropower energy resources are also vulnerable to climate change. Changes in precipitation amount or pattern will have a direct impact on hydropower generation. If snowpack decreases, hydropower generation during these months would be reduced.

Air Quality: Californians experience – on a cumulative basis – the worst air quality in the nation. Ozone and particulate matter are the pollutants of greatest concern, and climate change could slow progress toward attainment of health-based air quality standards and increase pollution control costs by increasing the potential for high ozone and high particulate days. Reductions needed to counter man-made and natural biogenic emissions will be particularly important during strengthened temperature inversion events and summertime stagnation episodes. By 2050, the effects of climate change may partially or completely offset the benefits of emission control programs on ambient levels of ozone. This offsetting of air quality improvements by climate change-induced temperature and emission changes has been termed the "climate penalty."

Public Health: Climate change has the potential to significantly impact the health of Californians. Climate change may alter the frequency, timing, intensity, and duration of extreme weather events (meteorological events that have a significant impact on local communities). Injury and death are the direct health impacts most often associated with natural disasters. Research suggests that the most serious health effects will not be primarily related to changes in average climate, but rather to increased frequency of extreme conditions, principally more frequent, longer, and more intense heat waves. Studies of heat waves in urban areas have shown an association between increases in mortality and increases in heat, measured by maximum or minimum temperature, heat index (a measure of temperature and humidity), or air-mass conditions. Heat wave conditions are also associated with weather patterns conducive to increased air pollution formation (such as tropospheric ozone) and wildfire outbreaks, both of which pose risks to public health. In addition, climate change has the potential to influence

asthma symptoms, the incidence of infectious disease, and the potential to affect humans indirectly through impacts on food and water supplies and quality.

Ecological Impact: Climate change could have an impact on many of California's species and ecosystems. Several studies have shown that the relatively minor changes in climate in the 20th century are already having noticeable ecological impacts. Climate change is affecting U.S. biodiversity and ecosystems, and it is very likely that climate change will increase in importance as a driver for changes in biodiversity over the next several decades. Persistent changes in tree mortality rates can alter forest structure, composition, and ecosystem services such as carbon sequestration.

Economic Impacts: By putting a dollar value on the physical impacts of climate change, the 2009 CAT report examines in economic terms the cost associated with climate change if no corrective actions are taken. These assessments are in the early stages of development and are expected to evolve as improved data and methods are developed. This current assessment demonstrates that climate change poses significant financial risks for California, indicating that the value of reducing global emissions is substantial. The potential economic losses highlight the need for effective adaptation policies as part of the State's response to climate change.

- Climate change could result in an overall decline in the value of harvested timber, with decreases between 4.9% and 8.5% in the State.

- Net economic loss for the water delivery system due to climate change is predicted to be between $140 and $400 million annually by the end of the century.

- The costs of replacing property at risk of coastal flooding or protecting vulnerable areas are estimated to be at least $100 billion and $14 billion, respectively.

- Total incremental annual electricity expenditures in the residential sector, due solely to climate change, range from $3.5 to $15 billion. Hydropower generation in California comes from units associated with relatively large reservoirs (low-elevation units) and units in high-elevations. Total annual generation is a strong function of the amount of precipitation falling in California. For high-elevation hydropower units, up to 20% decreases in annual electricity generation would translate to an annual loss of about $1 billion.

- Economic impacts assessments on the environment under different climate scenarios are still in its infancy. For example, projected economic effects due to changes in above-ground carbon stock vary greatly, depending on many factors such as temperature increases, forest fires, development, and a future carbon price.

In summary, abundant evidence now shows that climate change is not just a future problem, but is already observable now, with measurable impacts for the state's

citizens, natural resources, and economic sectors. The emerging projections of climate change impacts offer several sobering conclusions. In areas such as sea level rise and carbon emissions, recent scientific progress suggests that impacts are likely to be more severe than previously anticipated. Moreover, climate change impacts will not occur in isolation from other global environmental and societal changes, but will compound underlying environmental and economic stresses that are already occurring in California from development and urbanization. In addition, impacts that may occur in distant places can impact California through physical transport, such as air pollution from Asia, or via societal and economic interactions.

California's position as a national leader of state-sponsored climate change research provides us a unique perspective on how to best prepare for the effects of climate change. Future considerations should recognize that current emissions have committed the State to some amount of ongoing and irreversible climate change. The consequences of taking no action on adaptation and mitigation would be costly for California and the world.

1.6. Abrupt Climate Change

When most people think about climate change, they imagine gradual increases in temperature and only marginal changes in other climatic conditions, continuing indefinitely or even leveling off at some time in the future. It is assumed that human societies can adapt to gradual climate change. However, recent climate change research has uncovered a disturbing feature of the Earth's climate system: it is capable of sudden, violent shifts. This is a critically important realization. Climate change will not necessarily be gradual, as assumed in most climate change projections, but may instead involve relatively sudden jumps between very different states. A mounting body of evidence suggests that continued GHG emissions may push the oceans past a critical threshold and into a drastically different future.

Change in any measure of climate or its variability can be abrupt, including a change in the intensity, duration, or frequency of extreme events. For example, single floods, hurricanes, or volcanic eruptions are important for humans and ecosystems, but their effects generally would not be considered abrupt climate changes. A rapid, persistent change in the number or strength of floods or hurricanes might, however, be an abrupt climate change. Societies have faced both gradual and abrupt climate changes for millennia and have learned to adapt through various mechanisms, such as developing irrigation for crops, and migrating away from inhospitable regions. Nevertheless, because climate change will likely continue in the coming decades, denying the likelihood or downplaying the relevance of past abrupt events could be costly.

Evidence from the geologic past suggests that very abrupt climatic and environmental changes can happen, and that these abrupt changes are more likely the more a system is pushed out of its dynamic equilibrium. This is currently occurring with the climate as a result of anthropogenic forcing and there is considerable concern in the scientific community that abrupt changes—imaginable, but not predictable at present—may occur

again. Thus, in addition to the gradual (albeit accelerated) climate changes projected by current climate models, Californians need to be aware of the possibility of much more sudden climate shifts. These shifts have a scientifically well-founded place among the possible futures facing the State and should be among the possibilities accommodated in planning and adaptation measures. The social and economic costs of such abrupt changes have not been assessed but may be beyond the capacity of many communities to absorb without major suffering[28].

1.7. Summary

Climate change is a long-term shift in the climate of a specific location, region or planet. The shift is measured by changes in features associated with average weather, such as temperature, wind patterns, and precipitation. Available scientific evidence strongly supports the conclusion that most of the increased average global temperatures since the mid-20th century is very likely due to human-induced increases in GHG concentration. The burning of fossil fuels emits GHGs into the atmosphere, while deforestation and land-use changes remove trees and other kinds of vegetation that store ("sequester") carbon dioxide.

Global warming is no longer a matter of the future or of places far away. Rather, climate change is already evident in California, and it is happening now. Climate change is a critical issue facing California's citizens, ecosystems, and economic vitality. Sea levels have risen by as much as seven inches along the California coast over the last century, increasing erosion and pressure on the State's infrastructure, water supplies, and natural resources. California is the only state that relies to such a great degree on water supply and storage in our snowpack. The State has also seen increased average temperatures, more extreme hot days, fewer cold nights, a lengthening of the growing season, shifts in the water cycle with less winter precipitation falling as snow, and both snowmelt and rainwater running off sooner in the year. These climate driven changes affect resources critical to the health and prosperity of California. For example, forest and wild-land fires are becoming more frequent and intense due to dry seasons that start earlier and end later. Agriculture is especially vulnerable to altered temperature and rainfall patterns, and new pest problems. Economic evaluations of potential impacts due to climate change show that climate change could impose substantial costs to Californians on the order of tens of billions of dollars per year.

The emerging projections of climate change impacts offer several sobering conclusions. In areas such as sea-level rise and carbon emissions, recent scientific progress suggests that impacts are likely to be more severe than previously anticipated. The preceding section has focused on the ways in which changes in climate are projected to affect the environment and society though the 21st century. However, what will actually occur depends greatly on efforts to reduce emissions and to minimize future negative impacts. In short, human decisions are key to determining the true severity of future

[28] The future is now: An update on climate change science impacts and response options for California (2008). Publication # CEC-500-2008-071.
http://www.energy.ca.gov/2008publications/CEC-500-2008-071/CEC-500-2008-071.PDF

impacts. California has already demonstrated the enormous potential for positive change. Mitigation of emissions to slow down climate change and efforts in adaptation to deal with the impacts of change will help minimize the harmful impacts of climate change and provide valuable co-benefits.

2. NATIONAL GREENHOUSE GAS PROGRAM DEVELOPMENT

In May of 2010, USEPA finalized its GHG emission standards for light-duty vehicles for model year 2012-2016 vehicles. This national program will implement footprint-indexed standards for all cars and light trucks sold in the U.S., with a projected fleet average model year 2016 requirement of 250 grams of carbon dioxide emissions per mile.[29] The 2016 federal endpoint is nearly identical to the precedential California 2009-2016 standards and extends California's promotion of lower GHG technologies (e.g., for engines, transmission, and air-conditioning technologies) nationwide to achieve a similar 2016 new vehicle fleet outcome. This initial national GHG program was developed by USEPA, in coordination with NHTSA, which administers Corporate Average Fuel Economy (CAFE) Standards. The national 2012-2016 program was the subject of commitment letters from the State of California and major automakers. As a result, ARB modified its regulations to explicitly accept federal compliance with the USEPA standards as sufficient to demonstrate compliance with California's standards for the 2012-2016 model years.

Also in May of 2010, a Presidential Memorandum directed USEPA and NHTSA to work jointly to develop continuing GHG standards for model years 2017-2025 (USEPA and NHTSA, 2011a). The Memorandum requested that USEPA and NHTSA work closely with ARB on a 2010 technical assessment that would assess technologies and costs to achieve varying levels for GHG emission reduction through model year 2025. The result was a September 2010 *Interim Technical Assessment Report,* jointly authored by USEPA, NHTSA, and ARB. Subsequent to that collaborative technical work, ARB staff has closely monitored the work of USEPA and NHTSA, the staffs continued to jointly hold meetings with various stakeholders (e.g., individual automakers), examine updated technical materials, and develop consistent technology assumptions. In November 2011, USEPA and NHTSA proposed 2017-2025 federal standards (USEPA and NHTSA, 2011b).

3. SUMMARY OF PROPOSED REGULATION

In this section III.3, a summary of the proposed standards and major provisions is provided. After this summary section, the technical feasibility basis for the standards is described in section III.4, while a more thorough description and assessment of compliance with the proposed standards is shown in section III.5.

3.1. Pollutants Included in the Proposed Regulation

[29] For the national GHG program page see USEPA's Office of Transportation and Air Quality, "Regulations and Standards." http://www.epa.gov/otaq/climate/regulations.htm

The proposed regulation sets emission standards for CO_2, CH_4, and N_2O, and provides credits toward the CO_2 standard if a manufacturer reduces refrigerant emissions from the vehicle's air conditioning system.

3.2. Footprint-Indexed Greenhouse Gas Emission Standards

The proposed greenhouse gas (GHG) emission standards would reduce new light-duty carbon dioxide (CO_2) emissions from their regulatory model year 2016 levels by approximately 34% by model year 2025, from about 251 to about 166 gCO_2/mile, based on the projected mix of vehicles sold in California. The basic structure of the standards includes two categories – passenger cars and light-duty trucks – that are consistent with federal categories for light-duty vehicles. The standard targets would reduce car CO_2 emissions by about 36% and truck CO_2 emissions by about 32% from model year 2016 through 2025. Figure III-A-3-1 illustrates the basic target emission trends that are projected from the car and truck standards.

Figure III-A-3-1. Target emission reductions from GHG standards



Within the two categories, the CO_2 standard targets for vehicle models sold by each automaker are indexed to the vehicles' footprint, which is calculated as each vehicle model's wheelbase times the average track width. As a result of the proposed regulatory structure, the precise CO_2 emission rates that will result from the standards in each year from 2017 through 2025 will depend on the ultimate sales-weighted mix of vehicles (i.e., according to vehicle sales in each category and the footprint of the models) sold in each year. Figure III-A-3-2 illustrates model year 2008 vehicle models, the 2016 standard targets (which overall are approximately 25% below model year 2008 vehicles), and the 2025 standard targets (which overall are about 34% below the 2016 targets). The combined result of the 2012-2016 standards and the 2017-2025 standards would reduce vehicle CO_2 emissions by approximately 51% from their 2008 levels.

Figure III-A-3-2. Illustration of 2025 car and truck standard GHG targets compared to the 2008 fleet and 2016 standard targets



Table III-A-3-3 shows the year-by-year new vehicle CO_2 reductions that are projected as a result of the standards from cars, light-duty trucks, and combined light-duty vehicles. The projected result overall from 2016-2025 from these standards is to reduce car CO_2 emissions by approximately 4.9%/year, reduce truck CO_2 emissions by approximately 4.1%/year, and reduce combined light-duty CO_2 emissions by approximately 4.5%/year from 2016 through 2025. These CO_2 emission reduction estimations are approximate because the required emission level to achieve compliance with the standards for each vehicle manufacturing company depends on their ultimate sales mix of vehicles.

Table III-A-3-3. Projected targets for light-duty vehicle gCO_2/mile emission rates

	Model year	Car		Truck		Combined light-duty	
		gCO_2/mi	Annual change	gCO_2/mi	Annual change	gCO_2/mi	Annual change
Baseline	2008	291		396		336	
Previous Rule Targets	2009-2011						
	2012	263		340		290	
	2013	256	2.8%	330	2.8%	283	2.6%
	2014	248	3.3%	321	2.8%	275	2.8%
	2015	236	4.5%	306	4.5%	263	4.3%
	2016	226	4.5%	292	4.5%	251	4.4%
Proposed Rulemaking Targets	2017	213	5.5%	290	0.7%	243	3.2%
	2018	203	4.9%	280	3.5%	233	4.2%
	2019	192	5.2%	273	2.8%	224	4.0%
	2020	183	4.9%	264	3.0%	215	3.9%
	2021	173	5.5%	245	7.5%	201	6.3%
	2022	165	4.4%	233	4.9%	192	4.6%
	2023	158	4.5%	221	4.9%	183	4.8%
	2024	151	4.5%	210	5.0%	174	4.8%
	2025	144	4.6%	200	4.9%	166	4.8%
Average change, (2016-2025)			4.9%		4.1%		4.5%
Change, 2008-2016		-23%		-26%		-25%	
Change, 2016-2025		-36%		-32%		-34%	
Change, 2008-2025		-51%		-50%		-51%	

Notes: Car, truck, overall targets shown are based on projected sales of vehicles by footprint, category (ultimate gCO_2/mile levels are determined by end-of-year sales); the original California GHG standards for model years 2009-2011 are based on a different two-category system (PC/LDT1 and LDT2) than the car and truck system of the 2012-2016 federal standards and proposed 2017-2025 standards; Difference of individual columns may not match due to rounding.

Proposed standards also apply to other greenhouse gases, in particular CH_4, and N_2O. In addition, reductions in high global warming potential refrigerant emissions (e.g., vehicle refrigerant HFC-134a) create a credit expressed in CO_2-equivalents. In the current 2009 to 2016 ARB GHG standards, CH_4 and N_2O emissions are converted to CO_2-equivalents, and included in the calculation used to determine compliance with the CO_2 standard. USEPA, in their 2012-16 standards, adopted separate standards for CH_4 and for N_2O. Both approaches account for the principal GHGs emitted by passenger motor vehicles, reflecting the purpose and intent of the respective regulatory programs to control GHG air pollutants.

For the 2017-2025 model year standards, ARB proposes to use the USEPA approach and adopt separate standards for CO_2, CH_4, and N_2O. The CH_4 and N_2O standards will reflect the same stringency as the prior, separate federal standards. This revised approach avoids having to adjust the CO_2 footprint curves to reflect the other two pollutants. Crediting for reductions in high global warming refrigerant emissions will continue similar to the current regulations, and staff intends that both ARB and USEPA regulations will use the same credit values. Additional discussion of the CH_4 and N_2O standards appears later in this report. The net result is that, like the current 2009-2016 California GHG standards, the proposed 2017-2025 standards account for all major sources of vehicle GHG emissions, including upstream GHG emissions associated with the production and transportation of various vehicle fuels. Again, the purpose and intent is to account for and seek reductions in GHG air pollutants.

3.3. Flexibilities and Alternative Compliance Mechanisms

The two primary flexibilities of the standards are to allow a fluctuation of the future new vehicle fleet's CO_2 emissions according to each company's car-truck composition and sales-weighted sales according to vehicle footprint. These primary flexibilities were deemed critical to allow the standards to accommodate a diverse fleet of vehicle types and their potential to shift according to consumer trends, fluctuating fuel prices, and other factors. Beyond these fleet-accommodating features, many of the flexibilities from the model year 2016 standards will continue. For example, regulated companies are allowed averaging, banking (5-year credit carry-forward, 3-year credit carry-back), trading between car and truck categories, and trading between companies.

In addition, a number of other crediting mechanisms are provided. Crediting for more efficient systems, lower-refrigerant leakage designs, and alternative low-global-warming potential refrigerants are provided for innovations in vehicle air conditioning systems. Off-cycle credits are permitted for verifiable GHG emission-reduction technologies that are not fully accounted for with the established regulatory test cycle procedure. Also, special crediting is provided for alternative fuel vehicles for which there are no direct tailpipe exhaust CO_2 emissions.

4. TECHNOLOGICAL FEASIBILITY OF PROPOSED STANDARDS

4.1. Background

The proposed standards continue California's original "Pavley" standards that were developed in 2003-2004 in response Assembly Bill 1493 of 2002, as well as implement AB 32. Since adoption of the original California 2009-2016 standards, California has deemed automaker compliance with the similar federal 2012-2016 GHG standards, promulgated by the U.S. Environmental Protection Agency (USEPA) in 2009, to suffice for compliance with California standards for those model years.

Since federal adoption of GHG standards in 2009, the federal government and the California Air Resources Board have been jointly engaged in extensive analysis and technical collaboration with automobile manufacturers and suppliers. The joint work between USEPA, NHTSA and ARB has ensured that the utmost technical knowledge is jointly held and deliberated among the technical staffs of the three agencies, that the agencies' develop regulations that are harmonized in terms of their stringency and basic provisions, and that the standards are consistent with the regulatory authority of all three agencies. In addition, the joint work has sought to ensure that California maintains and preserves its leading role in forcing technology to meet passenger vehicle emission reduction standards, accepting National Program compliance only if those standards achieve the type of federally unprecedented, substantial emission reductions envisioned by the President's announcement and the newly proposed standards (USEPA and NHTSA, 2011a; 2011b).

The joint agency technical efforts have involved four public technical workshops that spanned topics of efficiency, mass-reduction, and safety technology; collaborative technical contract work (e.g., with FEV, Ricardo, Lotus); hundreds of internal joint-agency meetings; and dozens of agency-automaker meetings. A major milestone in the technical work was the *Interim Technical Assessment Report* (or "TAR"), finalized by USEPA, NHTSA, and ARB in September 2010. This TAR, in turn, further encouraged greater technical collaboration between the agencies, automobile companies, automotive suppliers, and other stakeholders.

4.2. Technology Assessment

The standards are predicated on many existing and emerging technologies in vehicles that increase engine and transmission efficiency, reduce vehicle energy loads, improve auxiliary and accessory efficiency, and that could increasingly electrify vehicle subsystems with hybrid and electric drivetrains. Previous rulemakings (i.e., California's 2009-2016 and federal 2012-2016 standards) established an original technical basis for GHG standards that is bearing out in practice, as manufacturers have met their GHG requirements in California for the 2009 and 2010 model years, and appear to be well on track for 2011. This rulemaking builds on this existing technical foundation with new technical data and understanding of evolving state-of-the-art engine, transmission, hybrid, and electric-drive technologies.

Table III-A-4-1 shows an illustrative summary of technologies with high potential for CO_2 emission reduction along with their adoption within the 2008 fleet. As suggested by the summary table, there are many individual technologies available with substantial CO_2 reduction potential. The listed technologies can each have many different configurations, varying CO_2 potential, and differing applicability across different vehicle types. As shown in the table, many of the technologies have, up to now, only seen limited deployment in new vehicle models in the fleet. It must be remembered, however, that the Pavley standards are only halfway implemented, with at least four full model years remaining to increase deployment.

Table III-A-4-1. Emerging technologies' CO_2 reduction potential and current adoption

Area	Technology or mechanism for CO_2 reduction		Potential CO_2 reduction	Share, MY2008	Share, MY2010
Powertrain	Engine	Variable valve timing	2-8%	53%	86%
		Cylinder deactivation	3-6%	7%	7%
		Turbocharging	2-5%	3%	3%
		Gasoline direct injection	8-15%	2%	9%
		Compression ignition diesel	15-40%	0.1%	0.5%
		Digital valve actuation	5-10%	0%	0%
	Transmission	6+ speed	3-5%	21%	40%
		Continuously variable	6-11%	8%	10%
		Dual-clutch, automated manual	4-13%	1%	-
Vehicle	Aerodynamics		5-8%	-	-
	Tire rolling resistance		2-8%	-	-
	More efficient auxiliaries (steering, air cond., alternator)		2-10%	-	-
	Lower refrigerant emissions (low-leak, low-GWP)		2-10%	-	-
	Mass-reduction	Advanced material component	5-10%	-	-
		Integrated vehicle design	10-20%	-	-
	Hybrid systems	Stop-start mild hybrid	5-25%	<1%	<1%
		Full hybrid electric system	20-50%	2%	4%
	Electric-drive	Plug-in capable electric vehicles	30-100%	0%	0%
		Fuel cell vehicles	30-100%	0%	0%

"–" indicates technologies areas where available deployment share estimates are not available; Sources: USEPA and NHTSA, 2010; USEPA, NHTSA, CARB, 2011; NRC, 2011; Ricardo, 2011; USEPA, 2010

The above table offers an illustrative summary of the CO_2 potential – but the modeling efforts to analyze the potential of technologies required specific identification of the engineering capabilities of particular technologies for deployment on various vehicle classes. The following tables identify technologies that were investigated for their potential adoption within the 2025 timeframe of this rulemaking. The following technology description tables are separated as follows:

- Vehicle road load and accessory energy reduction (Table III-A-4-2)
- Engine efficiency technology (Table III-A-4-3)
- Transmission efficiency technology (Table III-A-4-4)
- Hybrid efficiency technology (Table III-A-4-5)
- Electric drive technology (Table III-A-4-6)
- Air conditioning system technology (Table III-A-4-7)

Vehicle road load and accessory energy reduction: There are a number of technologies that reduce the overall energy loads on the vehicle to thereby result in reductions in overall vehicle tailpipe CO_2 emissions. There are a number of auxiliary, ancillary, and parasitic energy losses within the vehicle. Some of these energy losses, for example from power steering, alternator efficiency losses, water pumps, and cooling fans, all offer potential efficiency improvements. Larger in magnitude is the potential CO_2-reduction from reducing the overall physical energy requirement to propel the vehicle forward. The ultimate energy requirement of the vehicle is the energy load required at the motive wheel to overcome aerodynamic drag, tire rolling resistance, inertial acceleration, and grade. These energy loads can be reduced with improved

aerodynamic design, tires with lower rolling resistance, and mass reduction through advanced materials and optimized vehicle design.

Table III-A-4-2. Vehicle load reduction and accessory improvements investigated for potential CO_2 reduction

Low-rolling-resistance tires (ROLL) - have characteristics that reduce frictional losses associated with the energy dissipated in the deformation of the tires under load, thereby reducing fuel use and CO2 emissions.
Low-drag brakes (LDB) - reduce the sliding friction of disc brake pads on rotors when the brakes are not engaged because the brake pads are pulled away from the rotors.
Front or secondary axle disconnect for four-wheel drive systems (SAX) - provides a torque distribution disconnect between front and rear axles when torque is not required for the non-driving axle, reducing associated parasitic energy losses.
Aerodynamic drag reduction (AERO) - This can be achieved via two approaches, either reducing the drag coefficients or reducing vehicle frontal area. To reduce drag coefficients, skirts, air dams, underbody covers, and more aerodynamic side view mirrors can be applied. In addition to the standard aerodynamic treatments, the agencies have included a second level of aerodynamic technologies which could include active grille shutters, rear visors, and larger under body panels.
Electric power steering (EPS)/ Electro-hydraulic power steering (EHPS) - is an electrically-assisted steering system that replaces a continuously operated pump of traditional hydraulic power steering, thereby reducing parasitic losses from the accessory drive.
Improved accessories (IACC) - may include high efficiency alternators, electrically driven (i.e., on-demand) water pumps and cooling fans. This excludes other electrical accessories such as electric oil pumps and electrically driven air conditioner compressors.
Mass Reduction (Mass) - This technology includes material substitution, smart design, and mass reduction compounding. The actual amount of reduction from the 2008 baseline was determined based on confidential business information from vehicle manufacturers, material suppliers, existing studies in the literature, and NHTSA/USEPA/ARB assessment of the levels of mass reduction that are both technologically feasible and can be implemented reasonably safely.

Engine efficiency technology: Often considered the most fundamental aspect of vehicle efficiency and tailpipe CO_2 emissions is the vehicle's central power source, the internal combustion engine. The engine has considerable opportunities for energy efficiency improvement by reducing engine pumping losses due to the movement of intake and exhaust gases, friction losses from moving parts, thermodynamic efficiency losses, and exhaust heat losses. Substantial improvements from low-viscosity lubrication and engine friction reduction improvements can reduce friction losses. Improved valvetrain systems that offer increased engine control with cam phasing and variable valve lift help enable independent valve timing, thermodynamic efficiency, and further engine improvements. Digital valve actuation (either electronically or electro-hydraulically actuated) offers the ability to partially or fully eliminate camshafts (and associated losses) and enable improved controls for cam phasing and lift, as well as cylinder deactivation. The use of cam phasing, turbocharging, engine downsizing, gasoline direct injection and higher compression ratios allows for reduced pumping losses and higher thermodynamic efficiency, for an expanded operating zone of low fuel consumption and low CO_2 emissions. A further advancement in downsized turbocharged direct injection engines is to introduce high amounts of recirculated exhaust gas – cooled before mixing with intake air – with further boosting to reduce pumping losses, reduce friction loss, and reduce exhaust heat loss.

Table III-A-4-3. Engine efficiency technologies investigated for potential CO_2 reduction

Low-friction lubricants (LUB) - low viscosity and advanced low friction lubricants oils are now available with improved performance and better lubrication. If manufacturers choose to make use of these lubricants, they would need to make engine changes and possibly conduct durability testing to accommodate the low-friction lubricants.
Reduction of engine friction losses (EFR) - can be achieved through low-tension piston rings, roller cam followers, improved material coatings, more optimal thermal management, piston surface treatments, and other improvements in the design of engine components and subsystems that improve engine operation.
Cylinder deactivation (DEAC) - deactivates the intake and exhaust valves and prevents fuel injection into some cylinders during light-load operation. The engine runs temporarily as though it were a smaller engine, substantially reducing pumping losses.
Variable valve timing (VVT) - alters the timing of the intake valve, exhaust valve, or both, primarily to reduce pumping losses, increase specific power, and control residual gases. Two forms: dual cam phasing (DCP) and coupled cam phasing (CCP)
Discrete variable valve lift (DVVL) - increases efficiency by optimizing air flow over a broader range of engine operation which reduces pumping losses. Accomplished by controlled switching between two or more cam profile lobe heights.
Continuous variable valve lift (CVVL) - is an electromechanical or electrohydraulic system in which valve timing is changed as lift height is controlled. This yields a wide range of performance optimization and volumetric efficiency, including enabling the engine to be valve throttled.
Digital valve actuation (dVA) – involves electromagnetic or electrohydraulic actuation of engine intake and exhaust valves, allowing for potential elimination of camshafts and associated efficiency losses. This provides greater independent control of cam phasing and lift for improved optimization of engine operation.
Stoichiometric gasoline direct-injection technology (SGDI) - injects fuel at high pressure directly into the combustion chamber to improve cooling of the air/fuel charge within the cylinder, which allows for higher compression ratios and increased thermodynamic efficiency.
Turbocharging and downsizing (TBDS) - increases the available airflow and specific power level, allowing a reduced engine size while maintaining performance. Engines of this type use gasoline direct injection (GDI) and dual cam phasing. This reduces pumping losses at lighter loads in comparison to a larger engine.
Turbocharging and downsizing with cooled exhaust-gas recirculation (EGR) - additional charge dilution reduces the incidence of knocking combustion and obviates the need for fuel enrichment at high engine power. This allows for higher boost pressure and/or compression ratio and further reduction in engine displacement and both pumping and friction losses while maintaining performance. Engines of this type use GDI and both dual cam phasing and discrete variable valve lift. The EGR systems considered in this assessment would use a dual-loop system with both high and low pressure EGR loops and dual EGR coolers. The engines would also use single-stage, variable geometry turbocharging with higher intake boost pressure available across a broader range of engine operation than conventional turbocharged SI engines.
Diesel engines - have several characteristics that give reduced CO_2 emissions and lower fuel use, including reduced pumping losses due to lack of (or greatly reduced) throttling, and a combustion cycle that operates at a higher compression ratio and with a very lean air/fuel mixture relative to an equivalent-performance gasoline engine. This technology requires additional enablers, such as a NOx adsorption catalyst system or a urea/ammonia selective catalytic reduction system for control of NOx emissions during lean (excess air) operation. For purposes of this technical assessment, due to insufficient time, we have not included advanced diesel engines in our modeling scenarios. This does not mean that the agencies do not see a role for diesels in the future fleet since we fully expect some manufacturers will rely on diesels as part of their future strategy.

Transmission efficiency technology: Transmission technologies are fundamental in efficiently transferring engine torque at variable speeds to the wheels. In terms of overall vehicle efficiency, transmission technology is also critically important in allowing the operation of the engine in its lowest fuel consumption operating points more frequently. More gears (perhaps up to 8-speeds or more), closer gear ratio spacing, and optimized controls that put and keep transmissions and engines within their optimal speeds all offer increased vehicle efficiency for lower CO_2 emissions. Dual-clutch transmissions allow essentially the same efficiency as manual transmissions by eliminating torque converter losses and allowing faster shifting between gears, including the pre-selection of gears.

Table III-A-4-4. Transmission efficiency technologies investigated for potential CO_2 reduction

Improved automatic transmission controls (IATC) - optimizes shift schedule to minimize fuel use and CO_2 emissions under wide ranging conditions, and minimizes losses associated with torque converter slip through lock-up or modulation.
Six-, seven-, eight-and nine speed automatic transmissions - the gear ratio spacing and transmission ratios are optimized to enable the engine to operate in a more efficient operating range over a broader range of vehicle operating conditions. While a six speed transmission application was most prevalent for the 2012-2016 final rule, eight speed transmissions are expected to be readily available and applied in the 2017 through 2025 timeframe.
Dual clutch or automated shift manual transmissions (DCT) - are similar to manual transmissions, but the vehicle controls shifting and launch functions. A dual-clutch automated shift manual transmission uses separate clutches for even-numbered and odd-numbered gears, so the next expected gear is pre-selected, which allows for faster and smoother shifting.
Continuously variable transmission (CVT) - commonly uses V-shaped pulleys connected by a metal belt rather than gears to provide ratios for operation. Unlike manual and automatic transmissions with fixed transmission ratios, continuously variable transmissions can provide fully variable and an infinite number of transmission ratios that enable the engine to operate in a more efficient operating range over a broader range of vehicle operating conditions.
Manual 6-speed transmission (6MAN) - offers an additional gear ratio, often with a higher overdrive gear ratio, than a 5-speed manual transmission.
High-efficiency gearbox (HEG) - improves the mechanical efficiency of transferring torque from engine to axle(s).

Hybrid efficiency technology: Hybrid technology includes the use of stop-start capability, electric machines (with motor-assist and electric generator braking capability), and increased vehicle battery electric storage capability to dramatically improve vehicle efficiency. Hybrid technologies offer the potential for far more efficient use of fuel on-board the vehicle through the elimination of engine idling, reduction of fuel consumption during deceleration, reduction of acceleration power requirement through launch assist, and the recovery of vehicle energy losses through regenerative braking during deceleration. These energy-saving mechanisms are dependent on system controls that can allow for optimal utilization of the engine and/or transmission within certain engine operating zones. A number of hybrid architectures have emerged, ranging from simpler stop-start systems with some amount of launch assist, to parallel systems with one motor-generator and one or two clutches, to power-split systems with two or more electric machines.

Table III-A-4-5. Hybrid system technologies investigated for potential CO_2 reduction

12-volt micro-hybrid (MHEV) - also known as idle-stop or start-stop and commonly implemented as a 12-volt belt-driven integrated starter-generator, is the most basic hybrid system that facilitates idle-stop capability. This system replaces a common alternator with a belt-driven high-power starter-alternator, a revised accessory drive system, and an additional battery.
Higher Voltage Stop-Start/Belt Integrated Starter Generator (BISG) - provides idle-stop capability and uses a higher voltage battery with increased energy capacity over typical automotive batteries. The higher system voltage allows the use of a smaller, more powerful electric motor for increased launch, power assist, and regenerative braking capability.
P2 Hybrid (P2HEV) - uses a transmission integrated electric motor placed between the engine and a gearbox or CVT used to decouple the motor/transmission from the engine. In addition, a P2 Hybrid would typically be equipped with a larger electric machine. Engaging the clutch allows all-electric operation and more efficient brake-energy recovery. Disengaging the clutch allows efficient coupling of the engine and electric motor and, when combined with a DCT transmission, reduces gear-train losses.
2-mode hybrid (2MHEV) - is a hybrid electric drive system that uses an adaptation of a conventional stepped-ratio automatic transmission by replacing some of the transmission clutches with two electric motors that control the ratio of engine speed to vehicle speed, while clutches allow the motors to be bypassed. This improves both the transmission torque capacity for heavy-duty applications and reduces fuel consumption and CO2 emissions at highway speeds relative to other types of hybrid electric drive systems. 2-mode hybrids have not been considered in this assessment.
Power-split hybrid (PSHEV) - a hybrid electric drive system that replaces the traditional transmission with a single planetary gearset and a motor/generator. This motor/generator uses the engine to either charge the battery or supply additional power to the drive motor. A second, more powerful motor/generator is permanently connected to the vehicle's final drive and always turns with the wheels. The planetary gear splits engine power between the first motor/generator and the drive motor to either charge the battery or supply power to the wheels. Power-split hybrids have not been considered in this assessment.

Electric drive technology: Electric-drive vehicle technologies, including plug-in hybrid electric, electric, and hydrogen fuel cell, offer the most dramatic potential for CO_2 reduction. These technologies offer the potential to fundamentally eliminate thermodynamic and other efficiency losses that are inherent to internal combustion engines. These technologies also offer the prospect of decoupling vehicles from GHG-intensive petroleum fuels – by utilizing electricity and hydrogen fuel sourced from a variety of renewable and other low-GHG primary sources.

Table III-A-4-6. Electric-drive technologies investigated for potential CO_2 reduction

Plug-in hybrid electric vehicles (PHEV) - are hybrid electric vehicles with the means to charge their battery packs from an external electric source. These vehicles have larger battery packs with more energy storage and a greater capability to be discharged than other hybrid electric vehicles. They also use a control system that allows the battery pack to be substantially depleted under electric-only or blended mechanical/electric operation and batteries that can be cycled in charge sustaining operation at a lower state of charge than is typical of other hybrid electric vehicles.
Battery Electric vehicles (BEV) - are vehicles with all-electric drive and with vehicle systems powered by energy-optimized batteries charged primarily from grid electricity. BEV's with several ranges of 75-, 100-, and 150-mile real-world range have been included.
Fuel cell electric vehicles (FCVs) - utilize a full electric drive platform but consume electricity generated by an on-board fuel cell and hydrogen fuel. Fuel cells are electro-chemical devices that directly convert reactants (hydrogen and oxygen via air) into electricity, with the potential of achieving more than twice the efficiency of conventional internal combustion engines. High-pressure gaseous hydrogen storage tanks are used by most automakers for FCVs that are currently under development. The high-pressure tanks are similar (but higher pressure) to those used for compressed gas storage in CNG vehicles worldwide.

Air conditioning system technology: Air conditioning systems have GHG emissions associated directly with their refrigerant and, indirectly, through air conditioning systems' increased use of fuel in real-world vehicle operations. Improvements in air conditioning systems are not evaluated as part of the primary city-highway test cycle procedure for measuring CO_2 emissions. With similar provisions as in the current standards, the, air-conditioning technologies in the proposed standards are to be credited according to a

design-based approach that grants credits (based on design criteria and engineering data) for given systems. Air conditioning improvements are credited in three main areas. The first involves increased efficiency air conditioning systems that reduce "indirect" real-world CO_2 emissions when the air conditioning system is engaged to cool the vehicle cabin. The second involves reduced leakage of the "direct" HFC-134a refrigerant emissions through less permeable systems. Finally, switching the refrigerant from its current HFC-134a (GWP=1430) to one with a lower global warming potential (e.g., HFO-1234yf with GWP=4 or CO_2 with GWP=1) offers potential improvements and GHG-reduction credits.

Table III-A-4-7. Air conditioning system technologies investigated for potential CO_2 reduction

Air conditioning efficiency (ACEff) – improve efficiency of air conditioning operation, for example, with externally controlled compressor, air recirculation, blower controls, electronic expansion valves, improved evaporator and condenser, oil separator. Technologies provided a system of credits as utilized in USEPA 2012-2016 rulemaking, up to approximately 5-7 gCO_2e/mile for cars and trucks.
Air conditioning low refrigerant leak (LowLeak) – reduces leakage of refrigerant HFC-134a emissions with changes, such as low-permeability hoses and low-leak seals and connectors, as measured through SAE International's J2727 standard and USEPA calculation method. Technologies provided a system of credits as utilized in USEPA 2012-2016 rulemaking, up to approximately 6-8 gCO_2e/mile for cars and trucks.
Low global warming potential refrigerant replacement (GWP) – replaces conventional refrigerant HFC-134a (GWP=1430) with lower global warming potential refrigerants such as HFO-1234yf (GWP=4), CO_2 (GWP=1), HFC-152a (GWP=124). Technologies are provided a system of credits as utilized in USEPA 2012-2016 rulemaking, up to approximately 14-17 gCO_2e/mile for cars and trucks.

Combined Benefits: The combined benefits of the various CO_2-reduction technologies must be evaluated synergistically in order to accurately account for their interactions on vehicles through various driving conditions. The past ARB staff 2009-2016 rulemaking leveraged the vehicle simulation modeling work of AVL (see NESCCAF, 2004). This regulatory development technical work utilizes the assessment of technology effectiveness from the USEPA and NHTSA 2012-2016 rulemaking and new 2010-2011 vehicle simulation work of Ricardo. The regulatory technical work incorporates the state-of-the-art Ricardo data into an updated version of the USEPA Lumped Parameter modeling tool that includes emerging technologies and better incorporates their synergies per the new Ricardo results.

The Ricardo (2011) vehicle simulation study analyzed six different light-duty vehicle classes: subcompact car (Toyota Yaris), standard car (Toyota Camry); large car (Chrysler 300); small sport utility vehicle (Saturn Vue); large multi-purpose vehicle (Dodge Grand Caravan); and large truck (Ford F150). The technologies incorporated in the Ricardo modeling include most of those listed in the above tables. ARB technical staff collaborated with USEPA and Ricardo on the project in 2009-2010 to ensure the study explored the boundaries of engine, transmission, and hybrid technologies within the 2020-2025 timeframe.

The Ricardo data makes a number of improvements over all previous vehicle simulation modeling efforts for the context of this rulemaking in terms of technical rigor, technology relevance, technology timing, and technology data quality. The rigor of the Ricardo

model is reflected by Ricardo's existing ongoing work with automotive companies to study potential efficiency and CO_2 improvement as multiple technologies are synergistically applied to vehicles. The technical underpinnings of the model are well validated, having received advanced engine maps from lab testing and proprietary work with other automotive clients. The Ricardo simulation incorporates the most relevant emerging technologies to best reflect the likely technologies (e.g., valvetrain, fuel injection, transmission) that will be applied to vehicles in the 2015-2025 timeframe, whereas previous efforts tend to focus on vehicle technologies and data that are already to some extent outdated, are not being developed by automakers, and/or are not expected to be widely deployed in the 2025 timeframe. The Ricardo work also covers a wider span of vehicle classes, technology configurations, performance characteristics, and road load factors than previous such modeling efforts.

A number of key technical innovations in the Ricardo modeling made it superior to similar previous work and the most relevant study for this proposed rulemaking. Compared to previous work, the Ricardo study has included cutting-edge engine technologies that have not otherwise been modeled comprehensively and synergistically on new vehicles. Such technologies include advanced turbocharged downsized (at 18-, 24-, and 27-bar brake mean effective pressure [BMEP]) engines with direct injection, as well as cooled exhaust gas recirculation. Other powertrain technologies that were investigated with new simulation rigor include cam-switching, digital valve actuation, dual-clutch transmissions, and stop-start technology. Beyond these advanced powertrain technologies, the new Ricardo study added technical rigor to its study of new parallel hybrid technology that involves a pre-transmission clutch (that is similar to systems being deployed by Nissan, Hyundai, and Volkswagen).

The Ricardo results involved many thousands of simulations of various technology configurations, across the vehicle classes, across vehicle cycles, including ability to scale the various road load characteristics of the vehicles. A selection of the modeling and analytical findings from the Ricardo vehicle simulation study are summarized here. The study analyzed vehicle performance characteristics in order to selectively include only technology configurations that offered constant (or improved) utility attributes (e.g., acceleration, passing, and grade performance). The Ricardo study explicitly investigated emerging technologies that have the potential for widespread application across model year 2020 models.

Ricardo advanced technology findings are compared with existing models in the standard car, multi-purpose vehicle, and large truck classes in the figures below. Figure III-A-4-1 shows the standard car Ricardo results, as compared with the modeling reference 2007 Toyota Camry. Several other existing models were added to the chart – including two more recent models (2010 Toyota Camry, 2011 Hyundai Sonata with turbocharging and direct injection) and three existing hybrids (Toyota Camry, Hyundai Sonata, Ford Fusion – to show the span of more advanced existing technology. As depicted, the advanced powertrain options (turbocharged downsizing, stoichiometric GDI, cooled EGR, DCT) and road load reduction technologies (aerodynamic, tire rolling resistance, and mass-reduction improvements) have the potential to surpass existing

hybrid technology models with lower CO_2 emissions and greater efficiency. As compared with the reference 2007 Toyota Camry, the Ricardo results suggest that advanced non-hybrid technology can achieve a 50% CO_2 reduction and hybrid technology could achieve a 60% CO_2 reduction. Staff notes that the following three figures that are based on Ricardo modeling results show the vehicle efficiency, measured as miles per gallon of gasoline consumed for comparison with values presented by Ricardo; these energy-to-CO_2 relationships do not incorporate the effects of other regulated GHG emissions (as are assessed below).

Figure III-A-4-1. Ricardo (2011) mid-size sedan results versus existing models



Note: Figure does not include non-CO_2 GHG emissions

The Ricardo results exhibited similar technology potential findings for the multi-purpose vehicle class, as shown in Figure III-A-4-2. From the reference 2007 Dodge Grand Caravan, substantial CO_2 reduction potential was found with the utilization of engine, transmission, and road load reduction technologies. For example, with the application of a state-of-the-art turbocharged downsized direct injection engine, an 8-speed dual-clutch transmission, and vehicle load reductions, CO_2 reduction of 48-51% is achieved. These non-hybrid powertrain efficiency improvements, as depicted in the figure, achieve even lower CO_2 emissions than existing hybrid models (e.g., Ford Escape and Lexus RX450h) that are currently the low-CO_2 leading technologies within the US light-duty truck fleet. With diesel technology, the Ricardo results showed a potential for a 55% CO_2 reduction from the 2007 reference. With hybridization, the Ricardo results for this multi-purpose vehicle class indicate the potential for a 59% CO_2 reduction.

Figure III-A-4-2. Ricardo (2011) small light-duty truck results versus existing models



Note: Figure does not include non-CO_2 GHG emissions

As for the above result for a standard car and multi-purpose vehicle, the Ricardo results similarly showed high potential for very low CO_2 emissions within full-size light-duty trucks. Figure III-A-4-3 shows the reference 2007 Ford F150, two leading 2011 models, and the Ricardo results for new powertrain and hybrid technology packages. From the reference 2007 Ford F150, the application of cool EGR, turbocharged, downsizing direct injection engine, an 8-speed dual-clutch transmission, and vehicle load reductions results in CO_2 reduction of 46%. The GDI technology packages surpassed even the existing low-CO_2 full-size truck (the Chevrolet Tahoe two-mode hybrid system). With diesel technology, the Ricardo results showed a potential for a 52% CO_2 reduction from the 2007 reference. With hybridization, the Ricardo results for this large truck class indicated the potential for a 55% CO_2 reduction.

Figure III-A-4-3. Ricardo (2011) full-size truck results versus existing models



Note: Figure does not include non-CO_2 GHG emissions

In order to base the technology assessment across each vehicle model across the entire new US vehicle fleet, the Ricardo results were utilized to further develop the USEPA Lumped Parameter Model in order to accurately account for the impact of each technology, independently as well as synergistically with other technologies across a greater variety of vehicle types across the entire new vehicle fleet. Table III-A-4-8 illustrates the levels of CO_2 improvement that result from a selection of various technologies. The results show the extent to which the technologies vary, in some cases, from smaller car classes to larger trucks.

Table III-A-4-8. CO_2 reduction from individual technologies from 2008 reference

Area	Technology	Small car	Mid-size car	Small light-duty truck	Large light-duty truck
Engine technologies	Engine friction reduction	3.5%	4.5%	3.4%	4.2%
	Cylinder deactivation	-	6.1%	4.7%	5.7%
	Discrete cam phasing (DCP)	4.1%	5.2%	4.1%	4.9%
	Discrete variable valve lift (DVVL)	4.1%	5.2%	4.0%	4.9%
	sGDI (18-bar, 33% downsize)	12.2%	14.2%	12.1%	13.6%
	sGDI+DCP+DVVL (18-bar, 33% TDS)	14.9%	17.5%	14.8%	16.8%
	cEGR sGDI+DCP+DVVL (27-bar, 56% TDS)	21.4%	24.3%	21.2%	23.5%
	Compression-ignition DCP diesel	19.8%	21.3%	19.1%	21.3%
Transmission technologies	Torque convertor lock-up	0.4%	0.5%	0.5%	0.5%
	Aggressive shift logic	2.0%	2.5%	1.9%	2.4%
	High efficiency gearbox	3.3%	3.9%	3.8%	4.3%
	Optimized shifting	5.2%	6.6%	5.1%	6.2%
	6-speed automatic	1.8%	2.2%	1.7%	2.1%
	8-speed automatic	6.5%	7.8%	6.8%	7.8%
	Wet dual clutch 8-speed	9.7%	11.5%	10.5%	11.9%
	Dry dual clutch 8-speed	10.3%	12.2%	11.1%	12.6%
	Continuously variable	11.0%	6.3%	6.0%	-
Vehicle load and accessory technologies	Low drag brakes	0.8%	0.8%	0.8%	0.8%
	Secondary axle disconnect	1.2%	1.4%	1.4%	1.6%
	Electric power steering	1.5%	1.3%	1.2%	0.8%
	Improved accessory efficiency	3.3%	3.0%	2.6%	3.5%
	Mass reduction (-10% curb mass)	5.1%	5.1%	5.1%	5.1%
	Mass reduction (-20% curb mass)	10.4%	10.4%	10.4%	10.4%
	Tire low rolling resistance (-10% C_rr)	1.9%	1.9%	1.9%	1.9%
	Tire low rolling resistance (-20% C_rr)	3.9%	3.9%	3.9%	3.9%
	Aerodynamics (-10% C_dA)	2.3%	2.3%	2.3%	2.3%
	Aerodynamics (-20% C_dA)	4.7%	4.7%	4.7%	4.7%
Hybrid system technologies	12V stop-start	6.1%	6.8%	5.6%	6.5%
	High-voltage belt-alternator system	7.4%	7.6%	6.8%	8.0%
	Parallel hybrid (23-40 kW)	34.3%	34.6%	32.8%	31.9%
Reference vehicle characteristics	Test weight (lb)	2625	3625	4000	6000
	Rated power (hp)	106	158	169	300
	Rated torque (ft-lb)	103	161	161	365

Notes: All potential CO2 improvements are from 2008 US baseline technology based on the combined US test procedure (55% UDDS, 45% highway); sGDI= stoichiometric gasoline direct injection; DCP=dual cam phasing; DVVL=discrete variable valve lift; TDS = turbocharged downsize; cEGR= cooled exhaust gas recirculation; DCT = dual clutch transmission

The technologies and their associated percent CO_2 improvements shown above are generally not simply additive. Generally combining any two technologies listed tends to be less than the simple sum of the two CO_2 potential values because of the ways that the two technologies can both impact the same fundamental physical energy efficiency losses through the various vehicle systems (e.g., valvetrain, fuel injection, thermodynamic engine efficiency, transmission, etc). Directly built upon the Ricardo vehicle simulation modeling results, the USEPA Lumped Parameter model incorporates technologies' system interaction effects when technologies are jointly implemented. The analysis involved from the Ricardo results to the Lumped Parameter modeling is described in detail in the federal agencies' Technical Support Document (USEPA and NHTSA, 2011c).

EPA's modeling involved the analysis of many dozens of technologies configured into technology packages across each of the different vehicle classes. The modeling resulted in varying complexity that ranged from the reference 2008 baseline technology, to many incremental engine and transmission package steps, to advanced hybrids and

electric-drive technologies. The technology package "walk-up" of technologies was separately analyzed for each of the 19 USEPA vehicle classifications that range from subcompact cars to large full-size trucks.

Figure III-A-4-4 shows a representative progression of powertrain efficiency technology for the mid-size car (USEPA's vehicle class #5). The vehicle class includes mainstream mid-size cars like the Toyota Camry, Ford Fusion, and Honda Accord and has a 3.3-liter V6 baseline engine. This is the one of 19 USEPA vehicle classes that most closely relates to the average US fleet characteristics (average gram CO_2/mile, curb weight, vehicle footprint size, etc). This vehicle class has an average 2008 CO_2 emission level of 336 gram CO_2/mile (compared to the California 2008 baseline of 336 gCO_2/mile and the US 2008 fleet's 339 gCO_2/mile). Moving down in the figure shows the incremental addition of more efficiency technology from the baseline. The first step involves a cluster of technologies that includes a 6-speed dual clutch transmission, engine friction reduction, low-drag brakes, aggressive shift logic, improved accessory efficiency, high-efficiency gearbox, 10% reduced aerodynamic drag, 10% reduced tire rolling resistance, 5% mass reduction, and an improved air conditioning system. This first step, referred to as the primary package, is included on all the gasoline efficiency technology packages that are to the right of it in the figure.

Figure III-A-4-4. Technology packages for GHG emission reduction from mid-size car (each successive package moving right includes applicable previous technologies)



Adding incrementally to the primary technology package, the CO_2 reductions are shown with the addition of increasingly advanced technology. The addition of an 8-speed dual clutch (from a 6-speed), downsized turbocharging with an 18-bar BMEP engine, lower rolling resistance tires, and lower aerodynamic drag results in a package that delivers a CO_2 emission level of 188 gCO_2e/mile that is beneath the approximate 2021 target of 201 gCO_2e/mile. Subsequent GHG reduction steps of air conditioning improvements (for maximum potential 18.8 gCO_2e/mi car credit) achieved 169 gCO_2e/mile, and the use of cooled exhaust gas recirculation or a diesel engine would bring the midsize sedan's emission level down to 156 gCO_2e/mile, which is below the 2025 overall target emission level of 166 gCO_2e/mile. Further CO_2 reductions beyond the 2025 target levels – useful both for offsetting higher GHG vehicles and for potentially more stringent standards after 2025 – include greater amounts of mass reduction, hybrid, plug-in hybrid electric, electric, and fuel cell technology. Future California GHG intensity for electricity and hydrogen are assumed for electric and fuel cell vehicles, as described in section III.A.5.3.

The full data tables with the CO_2 reduction potential from the various technology packages for each of the 19 vehicle classes are shown in Appendix Q.

4.3. Incremental Costs of Technologies

Following the technical vehicle simulation modeling efforts, extensive new technical work was conducted by the agencies to analyze the incremental costs of the CO_2-reduction technologies. This regulatory development work utilizes and builds upon the previous work from the technical analysis of the 2012-2016 USEPA and NHTSA rulemaking (USEPA and NHTSA 2009a; 2009b), the joint agency *TAR* assessment (USEPA, NHTSA, CARB, 2010), and the development toward proposed federal 2017-2025 standards (USEPA and NHTSA, 2011b; 2011c).

In past rulemaking developments, generally there has been reliance upon cost estimations from confidential business information from automakers, suppliers, and various other automotive industry estimations. As described by the National Academy of Sciences (2010), "Available cost estimates are based on a variety of sources: component cost estimates obtained from suppliers, discussions with experts at automobile manufacturers and suppliers, publicly available transaction prices, and comparisons of the prices of similar vehicles with and without a particular technology... Estimates based on the more rigorous method of teardown analysis would increase confidence in the accuracy of the costs of reducing fuel consumption." The agencies have followed this guidance and sought to support their cost estimation with best available technical cost data, including teardown analysis of the major CO_2-reduction technologies.

As part of the federal 2012-2016 rulemaking and in continuing efforts since then in the joint-agency-*TAR* work, use of the comprehensive teardown cost method has been demonstrated. In a series of studies done under contract for the USEPA, FEV Engineering, Inc. has conducted detailed and transparent analyses on the costs of

variable valve engine technologies, turbocharged downsized engines with direct injection, 6-speed transmissions, dual clutch transmissions, belt-alternator system mild hybrids, power-split and parallel hybrid (including motors, braking, air conditioning, batteries, power electronics, etc). These data from the various analyses include detailed breakdowns of all the components and materials from each of the technologies and provides strong technical data support for the technology cost estimations for this rulemaking. These FEV data (see FEV 2009, 2010, 2011) were utilized along with the agencies' direct input from suppliers and automakers to estimate the direct manufacturing cost of the applicable technologies. Through various communications with automakers, ARB staff has received strong validation of the technology cost data used in this analysis across the various powertrain technologies.

To incorporate how the regulation could have cost impacts that go beyond the increase in direct costs from the manufacture of new automotive technologies, indirect cost multipliers (ICMs) are utilized. The ICM framework was originally developed by a contractor for USEPA (Rogozhin et al, 2009; 2010) in order to delineate the relative impacts of the various indirect cost components (e.g., overhead, warranty, R&D, depreciation, corporate overhead, marketing, dealer profit). The resulting ICMs reflect changes with the introduction of new technology from the regulation in the short-term and long-term based on complexity of the technology integration on the vehicle. The framework had been further developed for the 2012-2016 rulemaking and the joint-agency *TAR,* and has been further refined for this regulatory analysis (also see USEPA and NHTSA, 2011c).

The ICMs used in this analysis are summarized in Table III-A-4-9. The ICMs are multiplied by the direct manufacturing cost to approximate the full incremental price increase from the regulation. As shown, the ICMs increase with technology complexity, but decrease when going from short- to long-term. Most incremental engine, transmission, and vehicle technologies are in the "Low" and "Medium" categories, and therefore are marked up 24-39% in the shorter term and 19-29% in the longer term. More advanced technologies (e.g., mass-reduction greater than 20%, hybrid, and electric) have larger ICM factors of 1.50 and above. This ICM framework was analytically developed based on incremental gasoline efficiency technology, and ARB staff continues to study the appropriate ICM values for advanced electric-drive vehicles to be used in the future. For example, a report by the National Research Council indicates that HEVs and plug-in hybrid electric vehicle technologies should only apply mark-up factors of 1.33 (NRC, 2011), and battery electric vehicles tend to have less integration complexity than HEVs and plug-in hybrid electric vehicles and could likewise be well below our conservatively assumptions.

Table III-A-4-9. Summary of indirect cost multipliers utilized in assessment

Complexity	Indirect cost multiplier[a]		Applicable technologies
	Short-term	Long-term	
Low	1.24	1.19	Low rolling resistance tires, variable valve timing, engine friction reduction, low-friction lubrication, downsize, 6-speed, aggressive shift logic, torque convertor lock-up, improved accessory efficiency, electronic power steering, electro-hydraulic power steering, low-drag brakes, aerodynamics (10%), mass reduction (5%, 10%)
Medium	1.39	1.29	Dual-clutch transmission (wet, dry), 8-speed transmission, continuously variable transmission, cylinder deactivation, dual cam phasing, discrete valve lift, aerodynamics (20%), 42-volt accessory, stop-start, mass-reduction (15%, 20%), turbocharged downsizing, gasoline direct injection, lean-burn gasoline, diesel (LNT, SCR), continuous cam phasing, continuous valve lift, cooled exhaust gas recirculation
High 1	1.56	1.35	Mass reduction (25%, 30%), hybrid (powersplit, parallel), plug-in hybrid (non-battery costs), electric vehicle charger, fuel cell vehicle
High 2	1.77	1.50	Plug-in hybrid battery, electric vehicle battery, electric vehicle non-battery

[a] *ICM factors shown are approximate; the factors involve two separate components (warranty and non-warranty); see USEPA and NHTSA, 2011c*

The resulting incremental price increase, including the direct manufacturing cost plus the indirect cost mark-up, for individual technologies are shown in Table III-A-4-10. As shown, many of the technology costs scale differently from the smaller vehicle car classes to the larger light-duty truck classes. Also, generally the higher cost technologies listed in the table are associated with larger potential CO_2 reductions, as illustrated in the summary table above. These summary costs for individual technologies are used in sections below, where the technologies are built up into many different packages for each of the vehicle classes.

Table III-A-4-10. Incremental vehicle price increase in year 2012 for CO_2-reduction technologies

Area	Technology	Small car	Mid-size car	Small light-duty truck	Large light-duty truck
Engine technologies	Engine friction reduction	124	182	182	240
	Cylinder deactivation	-	214	214	241
	Discrete cam phasing (DCP)	104	104	224	224
	Discrete variable valve lift (DVVL)	178	259	259	369
	sGDI (18-bar, 33% downsize)	305	305	305	459
	sGDI+DCP+DVVL (18-bar, 33% TDS)	578	578	578	974
	cEGR+sGDI+DCP+DVVL (27-bar, 56% TDS)	1445	1445	1445	2435
	Compression-ignition diesel (with aftertreatment)	3261	3994	3268	4569
Transmission technologies	Torque convertor lock-up	33	33	33	33
	Aggressive shift logic	36	36	36	36
	High efficiency gearbox	282	282	282	282
	Optimized shifting	38	38	38	38
	6-speed automatic	-11	-11	-11	-11
	8-speed automatic	77	77	77	77
	Wet dual clutch 8-speed	52	52	52	52
	Dry dual clutch 8-speed	-20	-20	-20	-20
	Continuously variable	243	284	284	-
Vehicle load and accessory technologies	Low drag brakes	73	73	73	73
	Secondary axle disconnect	0	0	0	108
	Electric power steering	121	121	121	121
	Improved accessories	158	158	158	158
	Mass reduction (-10% curb mass)	94	109	125	171
	Mass reduction (-20% curb mass)	417	482	552	756
	Tire low rolling resistance (-10% C_{rr})	7	7	7	7
	Tire low rolling resistance (-20% C_{rr})	72	72	72	72
	Aerodynamics (-10% C_dA)	54	54	54	54
	Aerodynamics (-20% C_dA)	234	234	234	234
Hybrid system technologies	12V stop-start	573	650	650	713
	High-voltage belt-alternator	2358	2497	2497	2774
	Parallel hybrid (23-40 kW electric motor size)	4408	4997	4824	5174
Reference vehicle characteristics	Test weight (lb)	2625	3625	4000	6000
	Rated power (hp)	106	158	169	300
	Rated torque (ft-lb)	103	161	161	365

Notes: All potential incremental prices are in 2009 dollars and are from 2008 US baseline technology and include indirect cost multipliers for warranty, overhead, research and development, profit, etc; prices are for year 2012, and therefore time- and volume-based learning reduced incremental prices from 2012 through 2025 are not included; sGDI= stoichiometric gasoline direct injection; DCP=dual cam phasing; DVVL=discrete variable valve lift; cEGR= cooled exhaust gas recirculation; DCT = dual clutch transmission; in ultimate technology packages, all technologies are considered along with other technologies in the table

Because some of the technologies that were considered in the rulemaking also went beyond the engine, transmission, and hybrid technologies to examine the future state of emerging electric plug-in vehicles, further data beyond that from teardown analytical work were required. To model the future costs of advanced battery packs for plug-in hybrid and full electric vehicles, battery cost estimates relied on modeling from US Department of Energy Argonne National Laboratory (Santini et al, 2010; Nelson et al, 2011). Because the emerging battery technologies have different power and energy characteristics, the agencies utilized the Argonne battery model to analyze the specific technical characteristics of the hybrid, plug-in, and electric vehicles across the various vehicle classes. The agencies applied the Argonne model estimates for battery packs with lithium manganese spinel cathodes and graphite anodes. Per peer-reviewer feedback on the ANL cost modeling and further agency consideration with feedback from industry suppliers, additional active thermal management and safety disconnect equipment were added, thereby increasing the plug-in hybrid electric vehicle and battery

electric vehicle battery pack costs from the TAR generally by roughly 40-70%. Commonly battery costs are reported as the cost per rated kilowatt-hour (kWh) of energy storage capacity. For this assessment, the battery pack direct manufacturing costs are estimated to be $200-250/kWh for battery electric vehicles, $300-400/kWh for plug-in hybrid electric vehicles and $550-700/kWh for HEVs in 2025. In addition, external residential electricity charging equipment was included in the final cost for plug-in hybrid electric vehicle and battery electric vehicle technology.

Although the available GHG credit provisions for improvements in air conditioning systems are optional, it is expected that they will be widely utilized by the automakers for compliance with the 2017-2025 standards. Table III-A-4-11 summarizes the estimations of technology costs associated with the available air conditioning system crediting mechanisms. Staff projects that the major compliance path will be to deploy air conditioning system efficiency technologies for maximum "indirect" credit, plus low-leak technology and substitution of the alternative refrigerant (i.e., HFO-1234yf) at a total marked-up price of $132 per vehicle in 2025, for an average total air conditioning credit of 21 gCO_2/mile (18.8 for cars and 24.4 for trucks). The crediting system is a flexibility mechanism, and therefore automakers could choose different approaches, perhaps using less of any of the three air conditioning crediting provisions.

Table III-A-4-11. GHG credits for air conditioning systems and incremental price

	CO_2 credit (gCO_2e/mile)			Incremental technology price ($/vehicle)	
	Car	Truck	LDV [a]	In 2016	In 2025
Air conditioning efficiency	5.0	7.2	5.9	$61	$50
Low-leak improvements	6.3	7.8	6.9	$20	$17
Alternative refrigerant	13.8	17.2	15.1	$101	$65
Projected deployment [b] (AC effic. + low-leak + alternative refrig.)	18.8	24.4	21.0		$132

[a] *Light-duty vehicle average based on projected 61% car, 39% truck mix in 2025*
[b] *Low-leak and alternative refrigerant credits are not directly additive (see Appendix R)*

Cost learning effects for all technologies are incorporated in order to consider the trajectory of costs for future years. The assessment utilizes both volume- and time-based learning effects. The volume-based learning is included only for relatively new technologies in earlier years, whereas time-based learning is generally considered at 3%/year cost reductions (newer technologies) down to 1%/year (mature technologies in the longer-term). These assumptions for learning are consistent with assumptions applied in the US EPA 2012-2016 rulemaking (US EPA and NHTSA, 2010) and the joint-agency *TAR* (USEPA, NHTSA, CARB, 2010).

The analysis on technology package CO_2 potential, technology costs, and indirect cost mark-up factors are brought together in incremental price - CO_2 data files for each of the 19 vehicle technologies. These vehicle price versus CO_2 reductions become the basis for analyzing the maximum technology capability for given levels of cost for each vehicle class, and therefore these serve as the critical inputs to analyze standard stringency

levels and potential compliance scenarios for the fleet as a whole for each of the affected automakers.

Figure III-A-4-5 shows a representative walk-up in price with incremental additions in CO_2 reduction technology for a mid-size sedan (vehicle class 5 out of 19). The data in the figure show the progression from the lowest cost technologies to more advanced technologies with higher costs. The first package of technologies includes engine friction reduction, a 6-speed dual-clutch transmission, low-drag brakes, aggressive shift logic, improved accessories, electric power steering, high-efficiency gearbox, reduced vehicle loads (10% lower aerodynamic drag, 10% lower tire rolling resistance, and 5% mass reduction). From the primary package, moving up and to the right in the figure shows the addition of 8-speed transmission, downsized turbocharged GDI engine, further load reduction, air conditioning technologies, and more advanced technologies. Note that hybrid, plug-in hybrid, electric, and fuel cell technologies have higher costs and higher potential CO_2 reduction and are not represented in the chart (although they are shown in Figure III-4-A-4-7 below).

Figure III-A-4-5. Vehicle CO_2 reduction and incremental price with additional technologies from 2008 baseline for mid-size car (Vehicle class 5 out of 19)



Figure III-A-4-6 shows the increasing price with incremental additions in CO_2 reduction technology for a large truck with a baseline 5.7-liter V8 engine with overhead valves and 4-speed transmission (vehicle class 13 out of 19). Many of the engine, transmission, and vehicle load technologies are similar to the above car. However, there are a number of differences for this truck class from the car class above. For example, the truck utilizes an 8-speed automatic instead of dual-clutch transmission, would receive greater air conditioning credit, and deploys more GHG reduction technologies before switching to a turbocharged, downsized engine. Note that hybrid technology for this package is greater than $5000 and is similarly not represented in the chart. The agencies have studied plug-in hybrid and full electric vehicle technologies for larger

body-on-frame truck classes but did not include these technologies in the final analysis for these larger trucks due to uncertainties about total cost and full utility functioning (electric drive technologies were however included in crossover truck classes). The full lists of technology packages, vehicle price, and CO_2 potential for the 19 vehicle classes are shown in Appendix Q.

Figure III-A-4-6. Vehicle CO_2 reduction and incremental price with additional technologies from 2008 baseline for full-size truck (Vehicle class 13 out of 19)



The two above technology figures for the mid-size car and a full-size truck focused on incremental engine, transmission, and vehicle technologies that are the most prominent near-term technologies for complying with 2017-2025 standards. To show a more full spread of the advanced technologies, the following Figure III-A-4-7 illustrates the technology, CO_2-reduction, and incremental price for two smaller car classes (USEPA classes 1, 2, and 4) that are more likely to see hybrid, electric, and fuel cell deployment in the 2025 timeframe. The figure shows similar incremental technologies to those above, but it also shows parallel hybrid technology at about $4,000, plug-in hybrid technology at about $9,000-$14,000, fuel cell technology at $8,000-$11,000, and full battery electric technology at about $10,000-$15,000 over the baseline 2008 vehicle. Note that, in this figure, plug-in vehicles are shown according to their projected future California electricity GHG emissions for the extent to which they are powered by grid electricity. Similarly, the fuel cell vehicles are shown according to their projected upstream GHG emission rate (e.g. including emissions from hydrogen production from natural gas and renewable sources) per existing and proposed California fuel policy, as described in greater detail below.

Figure III-A-4-7. Vehicle CO_2 reduction and incremental price with additional technologies from 2008 baseline for small to mid-size cars



The results of the joint agency assessment indicated that hybrid technology and electric-drive technologies would continue to remain at high costs for some time. ARB staff believes ultimately that these projected advanced technology costs are conservative (i.e., actual costs may be lower), as they are limited by our current understanding of a number of immature in-development technologies that are rapidly evolving compared to the incremental efficiency technologies. As one potential indicator of the inherent conservatism of these estimates, there are many hybrid and diesel vehicles in the market with incremental prices (versus their comparable conventional gasoline versions) that are considerably less than the incremental prices applied in this assessment of 2020-2025 technologies. In addition, ARB staff continues to investigate the ways in which electric vehicles could have much lower indirect cost multipliers than conventional supplier-sourced gasoline efficiency components. Conservatively, electric-vehicle components are estimated here to have indirect cost multipliers of 1.50 to 1.77, whereas the National Research Council (NRC) suggests that a more accurate indirect multiplier for such battery-heavy technologies could be more like 1.33 (NRC, 2011). Due to the relatively small current numbers of these relatively new technologies, staff believes that these conservative assumptions are justified at this time.

4.4. Lifetime Cost of Technologies to Vehicle Owner-Operator

As part of the technology cost assessment, all of the technology packages have been examined with respect to their lifetime impact on vehicle owners. Table III-A-4-12 summarizes details for 2025 incremental price, consumer lifetime savings, benefit/cost ratio, and consumer payback period for technology packages for the mid-size car with a V6 engine (USEPA class #5). This vehicle class is shown here to provide a

representative summary of vehicle class in the middle of the fleet (by footprint size, engine size, and CO_2 emissions). As shown in Table III-A-4-12, there are 12 different technology packages that result in somewhere between 30% and 52% CO_2 reduction from the 2008 baseline, that deliver consumer benefits that are least 5 times higher than the original vehicle cost, and that pay for themselves within the first two years of the consumer's purchase (i.e., payback period). To highlight an example from the table, the technology package that includes turbocharged, downsized gasoline direct injection engine, 8-speed dual-clutch transmission, and vehicle load reduction technologies (improvements of 20% aerodynamic drag, 20% low rolling resistance tires, 10% mass reduction); results in 44% lower CO_2 emissions; has an increased 2025 price to consumers of $1,431 (from 2008); returns lifetime consumer savings of $11,761; offers 8.2 times greater benefits than costs; and delivers a payback period in the first year.

Table III-A-4-12. Summary sample technology package effectiveness, price, lifetime savings, payback period for mid-size vehicle versus 2008 baseline technology

Technology package	GHG reduction from baseline	Incremental price in 2012	Incremental price in 2020	Incremental price in 2025	Lifetime consumer fuel savings	Benefit/cost	Consumer payback period (years)
Base: 3.3L 4V DOHC V6, 4sp AT	0.0%	$0	$0	$0	$0	-	0
4V DOHC V6, EFR2, LDB, ASL2, IACC, EPS, Aero1, LRRT1, HEG, 6sp DCT, 5% mass	27.3%	$782	$676	$627	$7,263	11.6	1
4V DOHC I4, EFR2, LDB, ASL2, IACC, EPS, Aero1, LRRT1, HEG, DCP, GDI, TDS18, 6sp DCT, 5% mass	37.4%	$1,365	$1,101	$1,039	$9,953	9.6	1
4V DOHC I4, EFR2, LDB, ASL2, IACC, EPS, Aero1, LRRT1, HEG, DCP, GDI, TDS18, 8sp DCT, 5% mass	39.4%	$1,519	$1,234	$1,153	$10,479	9.1	1
4V DOHC I4, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, GDI, TDS18, 8sp DCT, 5% mass	42.6%	$1,825	$1,491	$1,367	$11,341	8.3	1
4V DOHC I4, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, GDI, TDS18, 8sp DCT, 10% mass	44.2%	$1,915	$1,562	$1,431	$11,761	8.2	1
4V DOHC I4, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, GDI, TDS18, 8sp DCT, 15% mass	45.8%	$2,094	$1,717	$1,556	$12,187	7.8	1
4V DOHC I4, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, GDI, SAX, TDS18, 8sp DCT, 15% mass	46.1%	$2,202	$1,804	$1,636	$12,277	7.5	1
4V DOHC I4, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, DVVL, GDI, SAX, TDS18, 8sp DCT, 15% mass	46.6%	$2,381	$1,946	$1,767	$12,393	7.0	2
4V DOHC I4, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, GDI, TDS24, EGR, 8sp DCT, 10% mass	48.0%	$2,540	$2,140	$1,891	$12,770	6.8	2
4V DOHC I4, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, GDI, TDS24, EGR, 8sp DCT, 15% mass	49.5%	$2,719	$2,295	$2,015	$13,166	6.5	2
4V DOHC I4, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, GDI, SAX, TDS24, EGR, 8sp DCT, 15% mass	49.8%	$2,827	$2,382	$2,096	$13,250	6.3	2
4V DOHC I4, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, GDI, SS, SAX, TDS24, EGR, 8sp DCT, 15% mass	50.3%	$3,477	$2,768	$2,439	$13,383	5.5	2
4V DOHC I4, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, GDI, SS, SAX, TDS27, EGR, 8sp DCT, 15% mass	50.8%	$4,055	$3,266	$2,863	$13,510	4.7	2
4V DOHC V6, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, DVVL, GDI, ATKCS, HEV, 8sp DCT, 20% mass	59.3%	$7,519	$5,702	$5,024	$15,773	3.1	3
4V DOHC V6, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, DVVL, GDI, ATKCS, HEV, SAX, 8sp DCT, 20% mass	59.6%	$7,627	$5,790	$5,104	$15,848	3.1	3
4V DOHC I4, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, DSL-Adv, SAX, 8sp DCT, 15% mass	47.8%	$5,659	$4,573	$4,181	$12,731	3.0	3
EV75 mile, IACC2, Aero2, LRRT2, EPS, 20% mass	91.7%	$29,835	$16,554	$12,579	$19,304	1.5	7
EV100 mile, IACC2, Aero2, LRRT2, EPS, 20% mass	91.7%	$34,198	$18,903	$14,314	$19,304	1.3	9
4V DOHC V6, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, DVVL, GDI, ATKCS, REEV20, 8sp DCT, 20% mass	71.8%	$22,671	$14,433	$12,156	$17,068	1.4	8
4V DOHC V6, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, DVVL, GDI, ATKCS, REEV40, 8sp DCT, 20% mass	79.3%	$30,922	$18,714	$15,341	$17,894	1.2	11
EV150 mile, IACC2, Aero2, LRRT2, EPS, 20% mass	91.7%	$48,556	$26,545	$19,951	$19,304	1.0	16
FCV, IACC2, Aero2, LRRT2, EPS, 10% mass	78.2%	$84,885	$18,282	$14,357	$14,029	1.0	16

Notes: Assumptions for lifetime consumer savings, benefit/cost ratio, and payback period include median vehicle lifetime for cars of 14 years, 186,000 miles; fuel prices from California Energy Commission (e.g., $4.02/gallon gasoline in 2025); 5% discount rate; on-road consumer fuel consumption per mile is 25% greater than regulatory test-cycle values; air conditioning credits that would be worth about 18.8 gCO_2e/mile at about $132/vehicle are not shown; $0.15/kWh for electric vehicles; $6 per kilogram hydrogen for fuel cell vehicle; 2020 California primary energy sources are assumed for electric and fuel cell vehicles.

Although the full summary of technology packages for the 19 vehicle classes is shown in Appendix Q, an illustrative selection of CO_2-reduction packages that corresponds approximately with the proposed standard stringency levels is shown in Table III-A-4-13. The table x shows example technology packages that deliver an approximately 50% CO_2e emission reduction from a 2008 reference technology for four different vehicle classes. Technology comparisons against a projected 2016 fleet are made below when compliance scenarios are analyzed. Across the four classes the technology package that is shown is quite similar. All involve turbocharged, gasoline direct injection, 8-speed transmissions, load reduction technologies (from 10-20% reductions in mass, aerodynamics, and tire rolling resistance), improved accessory efficiency, and low-CO_2e air conditioning technologies. Each of the listed technologies achieves benefits in consumer savings that are between 4.7 and 7.4 times greater than the initial price increase for the technology, and the consumer payback period of each package is within 2 years.

Table III-A-4-13. Example of technology packages for 50% GHG-reduction for four different vehicle classes

		Small car	Mid-size car	Midsize truck	Large truck
Baseline 2008 technology	USEPA class	2	5	8	13
	Baseline engine	Base: 2.4L 4V DOHC I4	Base: 3.3L 4V DOHC V6	3.7L 2V SOHC V6	5.7L 2V OHV V8
	Test cycle CO_2 (gCO_2/mi)	238	336	390	448
	Example models	Honda Civic; Chev Malibu; Hyundai Elantra	Honda Accord; Toyota Camry; Ford Fusion	Ford Ranger; Jeep Liberty	Chev Tahoe; Chev Silverado
Example of technology for 2025	Technology package	4V DOHC I4, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, GDI, TDS18, 8sp DCT, 2% mass	4V DOHC I4, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, GDi, TDS18, 8sp DCT, 10% mass	4V DOHC I4, EFR2, LDB, ASL2, IACC2, EPS, Aero2, LRRT2, HEG, DCP, GDI, TDS24, EGR, 8sp DCT, 10% mass	4V DOHC I4, EFR2, LDB, ASL2, IACC2, EHPS, Aero2, LRRT2, HEG, DCP, GDI, SAX, TDS27, EGR, 8sp AT, 10% mass
	Test cycle CO_2 (gCO_2/mi)	139	188	217	242
	Test cycle CO_2 reduction from 2008	42%	44%	44%	46%
	Air conditioning credit (gCO_2e/mi)	18.8	18.8	24.4	24.4
	Regulatory GHG (gCO_2e/mi)	120	169	192	218
	GHG reduction after A/C credit	50%	50%	51%	51%
	Incremental price versus 2008 ($)	1,645	1,563	2,103	2,730
	Lifetime savings[b] versus 2008 ($)	7,871	11,761	15,320	18,256
	Benefit/cost [b]	4.8	7.5	7.3	6.7
	Consumer payback period (years) [b]	2	1	2	2

[a] *A 2008 technology baseline is used for vehicle simulation modeling, cost estimations; further below, in compliance assessment, future scenarios are compared against a model year 2016 baseline that is more appropriate as a "no new policy" reference that includes standards through 2016.*

[b] *Consumer impacts based on 5% discount rate, fuel prices from 2011 CEC forecast (e.g., $4.09/gallon gasoline in 2025), California median vehicle lifetime (186,000, 14 years for car; 234,000 17 years), real world on-road fuel efficiency is lower than that calculated for CAFE.*

4.5. Summary

This section III.A.4 reported on Staff's investigation into available CO_2-reduction technologies, their associated incremental prices and potential fuel savings to consumers. The findings from this assessment reveal that there are wide-ranging technology options available to automakers to reduce the CO_2 emissions of vehicles in the 2017-2025 timeframe. Many of the technologies are already well known today and are beginning to emerge within new vehicle introductions. Many of the technologies are more advanced, involving cutting edge technology innovation by automakers. Many of the technologies for CO_2 reduction will be combined in packages to deliver substantial CO_2 reduction in new vehicles that amount to between 30% and 55% from 2008 technology levels. For comparison, the 2016 standards would result in an approximate 25% CO_2 reduction from 2008 reference, so the technologies investigated would go far beyond the emission levels required for the 2016 standards. These levels of CO_2 reduction typically represent payback periods of 1-3 years for vehicle purchasers because of the emerging relatively low-cost engine, transmission, and vehicle load technologies. Hybrid technologies typically result in 50-60% CO_2 emission reduction from each vehicle class at higher costs. Plug-in electric and fuel cell technology will continue to offer the lowest CO_2 emissions of all, but typically at a greater price premium. In nearly every case of the technology packages investigated, the benefits of the new technologies offer consumer benefits that outweigh their initial technology costs, often well within the average first vehicle purchaser's ownership and several times over during the vehicle's life.

5. CLIMATE CHANGE EMISSION STANDARDS

The establishment of GHG standards from the technical work outlined above involved a collaborative process between the technical staffs of the USEPA, NHTSA, and ARB. The collaborative standard-setting process allowed the agencies to set standards that simultaneously met the agencies' respective statutory authorities and rulemaking procedures.

5.1. Determination of Maximum Feasible Emission Reduction Standard

The proposed standards involve continuing use of footprint-indexed CO_2-standards that are part of the federal 2012-2016 standards, a structure that is justified on both technical and regulatory consistency grounds. The technical basis for footprint-indexed standards is well established in the USEPA and NHTSA (2009) rulemaking (and NHTSA's previous rulemakings) for its benefits in promoting all known CO_2 reduction technologies, accommodating fluctuating consumer demands for vehicle size and classes, and protecting fleet diversity across the wide array of different products that automakers market. ARB staff finds the existing non-footprint-indexed California 2009-2016 standards are valid on account of their more certain emission reduction outcome; however, for regulatory continuity with the federal 2012-2016 standards and their above-stated benefits, it was critical that the same footprint-indexed regulatory design

be applied. Because compliance with the federal 2012-2016 standards will be deemed as sufficient for compliance with California's GHG standards for those model years and because of the federal US-California collaboration on issuing joint standards, the standard design with separate car and truck footprint-indexed standard lines was maintained.

The footprint-indexed CO_2 standard target lines for 2017-2025 were determined jointly by the three agencies in order to meet the agencies' regulatory requirements that include the agencies' criteria regarding technical feasibility and cost-effectiveness. ARB staff were guided by the overarching ARB objectives from AB 1493 (Chap. 200, Stats. 2002) remains to "develop and adopt regulations that achieve the maximum feasible and cost-effective reduction of greenhouse gas emissions" such that the standards are "Economical to an owner or operator of a vehicle, taking into account the full life-cycle costs of a vehicle." In addition, AB 32 (Chap. 488, Stats. 2006) instructs staff to adopt measures "to achieve the maximum technologically feasible and cost-effective [GHG] reductions." Among the agencies' considerations in their analyses were the technical feasibility (across the various vehicle types and sizes), statutory provisions of the agencies (e.g., different treatment by NHTSA of air conditioning credits), company competitiveness, relative cost-effectiveness across vehicle sizes and types, risks of eroded GHG program benefits from consumer trends, risks of eroded GHG program benefits from strategic vehicle reclassification by vehicle manufacturers, and the potential market shifting effects on fleet safety.

The primary technical data that was utilized in the standard-setting process was the vehicle simulation modeling of technology packages that includes many of the engine, transmission, and vehicle technologies (as discussed in the previous section) that are projected to be widely available by the 2025 timeframe. The vehicle technologies that were applied to vehicle models in the standard-setting analysis included downsized turbocharged engines, gasoline direct injection, 8-speed transmissions, vehicle load reduction (aerodynamics and low-rolling resistance tires), improved and more efficient accessories, engine friction reduction, and transmission shift optimization. The technology packages used in the analytical development of the footprint-indexed curves in the standard-setting process did not include diesel, hybrid, plug-in, electric, or fuel cell technologies. (Note, however, that the analysis of the various companies' strategies to comply with the footprint-indexed standards does consider deployment of these technologies. See section III.A.5.4, below).

Throughout the footprint target line-fitting analysis, many dozens of approaches were analyzed. Among the approaches different statistical regression methods were used to discern the relationship between future vehicle technologies' CO_2 and vehicle footprint. Also various normalization techniques were considered to adjust for particular vehicle attributes, such as a models' relative power and mass, as the agencies considered various advanced vehicle technology packages. The general process involved starting from the baseline 2008 vehicle fleet, adjusting for the introduction of projected mainstream 2025 CO_2-reduction technologies, statistically analyzing the data for the CO_2-to-footprint ($gCO_2/mile/ft^2$) relationships, then mathematically adjusting the curves

proportionally up or down depending on the targets' overall stringency. Ultimately, the ordinary least squares regression method, the most widely used statistical line-fitting technique, was applied to best approximate the physical relationship between models' CO_2 and footprint. The data were weighted according to their vehicle sales, in order to best reflect the true consumer-demanded distribution of vehicles according to various sizes, technologies, and classes. Finally, vehicle models' density (mass divided by footprint) was normalized in setting the footprint-indexed curves, as a means to adjust for relative differences in the models' mass-efficiency. The overall logic behind these decisions was to discern the true engineering-based CO_2-to-footprint relationship for 2017-2025 target curves across all vehicle models by applying widely recognized statistical techniques to incorporate variance in the fleet.

The above steps were used to define the slopes of the curves. Further detail on the standard-setting development can be found in the federal agencies' Technical Support Document (USEPA and NHTSA, 2011c). The movement of the slopes to set the overall year-by-year stringency targets for car and trucks was determined through staff analysis and discussions with automakers In the analysis, consideration of auto companies' current and future year product plans for compliance with the 2012-2016 program standards, as well as the companies' stated capability within the first several years of the 2017-2025 program. The final step in determining the precise stringency of the footprint-indexed car and truck standards was accounting for information shared between the regulatory agencies and the automobile manufacturers, applying the agencies' historical expertise in standard-setting.

Figures III-A-5-1 and III-A-5-2 provide graphical illustrations of the proposed footprint-indexed GHG standards. Also shown in the figures are the baseline model year 2008 car and truck models. Based on staff projections for the 2025 new vehicle fleet, the car and truck models will need to, on a weighted average, reduce their GHG emissions by about 51% from 2008 levels to comply with the standards. The 2008 emission level is utilized here and above as a technology reference for all of the technology effectiveness calculations by the three agencies, because it is the most comprehensive dataset for which all data (e.g., sales, footprint, CO_2 emissions for every model) are well characterized. Compliance with the already-implemented model year 2016 standards is expected to result in a 25% reduction from the 2008 reference CO_2 level. The 2025 GHG emission target is projected to result in a 34% reduction from the model year 2016 GHG emission level. Generally the car CO_2 standard target curves move downward – i.e., become more stringent – at approximately 4.9%/year from the 2016 target line to the 2025 target line. The truck CO_2 standard target curves move downward at approximately 3.5%/year through the 2016-2021 period and about 5%/year from 2021-2025. These annual percent improvements are approximate, based on staff projections for future vehicle sales.

Figure III-A-5-1. Model year 2017-2025 car GHG standard target lines



Figure III-A-5-2. Model year 2017-2025 light-duty truck GHG standard target lines



The actual standards for each automaker are determined by target standard lines for the sales-weighted average of their vehicle fleet, as defined by particular mathematical coefficients for car and trucks and for each model year. The standard target lines for model years 2017-2025 in the figures are represented by the following mathematical expression:

$$Target\ gCO_2/mile = min(min(b,max(a,c\boldsymbol{x}+d),min(f,max(e,g\boldsymbol{x}+h))))$$

The only unknown in the expression is $\boldsymbol{x}$, which is the vehicle footprint (wheelbase times average track width), measured in ft^2. Coefficients *a* through *h* for cars and trucks for model years 2017-2025 are shown in Table III-A-5-1 below.

Table III-A-5-1. Standard-determining coefficients for model year 2017-2025 car and light-duty truck GHG standards

		Coefficient	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025
Cars	a	Min (gCO_2/mile)	206	194.7	184.9	175.3	166.1	157.2	150.2	143.3	136.8	130.5
	b	Max (gCO_2/mile)	277	262.7	250.1	238	226.2	214.9	205.5	196.5	187.8	179.5
	c	Slope (gCO_2/mi/ft^2)	4.72	4.53	4.35	4.17	4.01	3.84	3.69	3.54	3.4	3.26
	d	Intercept (gCO_2/mi)	12.7	8.92	6.54	4.2	1.89	-0.38	-1.12	-1.83	-2.52	-3.17
	e	Min (gCO_2/mile), ceiling		203.4	201.9	200.4	198.9	197.4	197.4	197.4	197.4	197.4
	f	Max (gCO_2/mile), ceiling		274.4	277	278.5	280	281.5	283	283	283	283
	g	Slope (gCO_2/mi/ft^2), ceiling		4.72	4.72	4.72	4.72	4.72	4.72	4.72	4.72	4.72
	h	Intercept (gCO_2/mi), ceiling		10.1	8.6	7.1	5.6	4.1	4.1	4.1	4.1	4.1
Trucks	a	Min (gCO_2/mile)	247	238.1	226.8	219.5	211.9	195.4	185.7	176.4	167.6	159.1
	b	Max (gCO_2/mile)	348	347.2	341.7	338.6	336.7	334.8	320.8	305.6	291	277.1
	c	Slope (gCO_2/mi/ft^2)	4.04	4.87	4.76	4.68	4.57	4.28	4.09	3.91	3.74	3.58
	d	Intercept (gCO_2/mi)	81.1	38.28	31.62	27.69	24.64	19.8	17.85	15.98	14.21	12.51
	e	Min (gCO_2/mile), ceiling		246.4	240.9	237.8	235.9	234	234	234	234	234
	f	Max (gCO_2/mile), ceiling		347.4	341.9	338.8	336.9	335	335	335	335	335
	g	Slope (gCO_2/mi/ft^2), ceiling		4.04	4.04	4.04	4.04	4.04	4.04	4.04	4.04	4.04
	h	Intercept (gCO_2/mi), ceiling		80.50	75.0	71.9	70	68.1	68.1	68.1	68.1	68.1

To calculate each automaker's fleet GHG target, first the GHG target for each test vehicle is calculated from the above formula and coefficients. A car model uses the car coefficients, and trucks use the truck coefficients. The above figures illustrate the GHG standards that result from the calculations for each model year and for the two vehicle categories. For example, a car below 41 ft^2 would get the minimum standard target (i.e., the lower, left flat part of the line), a car above 56 ft^2 would get the maximum standard target (i.e., the higher, right flat part of the line), and the rest of the car models would get a GHG target based on the linear CO_2-ft^2 relationship between 41 and 56 ft^2, as defined by the formula. Calculating the truck model targets would follow the same logic. As shown by the target lines, each model at a given footprint gets a more stringent target in each successive model year.

From all of the test vehicles' individual GHG targets, the sales-weighted average of the gCO_2/mile standard targets for each automaker, for each model year (i.e., 2017-2025), determines the standard. For compliance, each automaker's sales fleet in a given year is to have a sales-weighted gCO_2/mile that is below their sales-weighted gCO_2/mile target. Due to sales-weighting of the model-by-model results, a compliant fleet can have many particular models that are below the target line (i.e., generating credits) and many other models above the line (i.e., generating deficits). As a result of this process, the precise gCO_2e emissions/mile standard for each company is not definitively known until the final sales for that model year is known (e.g., this can be as late as April 2012 for model year 2011 sales). Within the 2017-2025 standards, banking (5-year credit carry-forward, 3-year credit carry-back to cover past deficits) and trading (between car and truck categories, between companies) are permitted.

5.2. Determination of Effect of Standard on the Fleet

The potential effect of the standards on the fleet, and on individual companies, is analyzed based on the previous section's assessment of available technologies, their potential CO_2-emission reduction, and the associated technology costs. The first step in

estimating the potential compliance costs for automakers in achieving the required CO_2 emission reductions involves the determination for each of the automakers particular gCO_2/mile targets for each model year of the standards based on the footprint-indexed standards. In other words, the GHG standard is calculated separately for each automaker for each model year based on the footprint size of its sales fleet. Then the potential compliance costs are evaluated by applying additional GHG-reduction technology to bring the fleet into compliance with incrementally lower GHG standards in future years.

Table III-A-5-2 shows the CO_2 target standards based on the California 2008 baseline fleet, the projected 2016 CO_2 targets based on federal standards, and the projected 2025 CO_2 target for each company based on their mix of cars and trucks for the proposed footprint-indexed standards. As summarized in the figure, the already adopted 2016 standards would reduce the CO_2 emissions from the fleet by 25% from 2008 to 2016 (with a range of reductions 19% to 39% for the given automakers). The proposed 2025 standards would reduce CO_2e emissions from the fleet by 34% from 2016 to 2025.

Table III-A-5-2. Summary of projected GHG targets and reductions for 2016 and 2025 standards

Company	GHG emissions (gCO_2e/mile)			Reduction in GHG emissions	
	2008 baseline	2016 target	2025 target	Change from 2008 to 2016	Change from 2016 to 2025
BMW	335	235	151	30%	35%
Chrysler-Fiat	363	260	171	28%	34%
Ford	385	264	178	31%	33%
General Motors	372	274	184	26%	33%
Honda	296	240	157	19%	35%
Hyundai-Kia	309	238	155	23%	35%
Jaguar-Land Rover	447	274	184	39%	33%
Mazda	310	235	152	24%	35%
Mercedes	368	252	165	31%	34%
Mitsubishi	313	228	146	27%	36%
Nissan	329	248	164	25%	34%
Spyker	354	230	148	35%	36%
Subaru	341	255	169	25%	34%
Suzuki	338	237	155	30%	35%
Toyota	304	248	163	19%	34%
Volvo	377	248	163	34%	34%
Volkswagen	328	226	146	31%	35%
All	336	251	166	25%	34%

Figure III-A-5-3 shows the progression of the highest volume manufacturers' GHG emission targets from 2016 through 2025 based on each company's fleet mix by category and footprint. As illustrated, the footprint-indexing of the GHG standards ultimately results in different effective standards for each automaker depending on their fleet mix. The seven automakers with projected sales fleets with the smallest average footprint have GHG emission targets of 146-155 gCO_2e/mile, whereas the four largest-footprint companies would have targets of 171-184 gCO_2e/mile. Also resulting from the

footprint-indexing of the standards, the total obligated emission reduction, by percent, from each automaker is quite similar – ranging from a 33% to a 36% GHG reduction.

Figure III-A-5-3. Projected GHG emission targets for high-volume auto manufacturers from 2016-2025



5.3. Other Greenhouse Gas Emission Crediting Provisions

A number of provisions that account in part for driving conditions beyond the customary city-highway drive cycle tailpipe emission testing are provided within the proposed 2017-2025 MY standards. The air conditioning (A/C) credit provisions that offer up to 18.8 gCO_2e/mile for cars and 24.4 gCO_2e/mile for light-duty trucks were mentioned above in section III.A.4.4 and are described in detail in Appendix R. These A/C crediting provisions would be available for prescribed technologies with credit amounts for improved A/C efficiency (indirect credits), and lower leak refrigerant systems and alternative refrigerants (direct credits). The A/C credit opportunities, although optional, are highly cost-effective and expected to be widely utilized by automakers for compliance with the fleet average standards based on staff communication with automakers and the supplier industry companies involved in the manufacture of the technologies.

For the Pavley and federal 2012-2016 MY standards, ARB and USEPA, respectively, used differing methodologies for quantifying the GHG emissions from A/C and thus differing credit schemes. However, for the 2017-2025 MY standards, ARB staff is proposing to align with the USEPA approach as it would provide a consistent program nationwide as well as regulatory continuity across the federal 2012-2016 MY and federal 2017-2025 MY regulations that California proposes to continue accepting. The proposed regulation would also incentivize employment of leakage reduction technologies for A/C systems that use a refrigerant with a GWP of 150 or less (low GWP refrigerant), which would help maintain A/C performance and efficiency by keeping proper refrigerant charge level, and would reduce the need for and therefore

potential of consumers recharging low GWP refrigerant A/C systems with less expensive and higher GWP HFC-134a.

Table III-A-5-3 shows the maximum credit available to manufacturers for applying various classes of A/C technology improvements. To qualify for A/C direct credits, an automobile manufacturer would need to conduct an engineering evaluation that demonstrates that the A/C system is designed to limit refrigerant leakage. A larger direct credit may be earned if the manufacturer uses an alternative, low GWP, refrigerant. In order to qualify for indirect credits, automakers would need to demonstrate that their efficient A/C systems can provide CO_2 reductions commensurate to the amount of indirect credits allowed. As described in detail in Appendix R, the A/C Idle Test currently in place for the 2012-2016 MY regulation does not measure the benefit of several efficiency technologies. In addition, vehicles with efficient, downsized engines have difficulty passing the test even when equipped with A/C efficiency technologies. Because downsized engines are likely to be used by manufacturers as a compliance pathway for the fleet average GHG standards, in order to maintain program flexibility, ARB staff is proposing to replace the A/C Idle Test requirement with a requirement based on a new performance-based efficiency test, the AC17. The AC17 is true performance-based efficiency test, the AC17, which may be used as an alternate test option to qualify for indirect A/C credits. This true performance-based test that evaluates all types of efficiency technologies over "real-world" driving conditions, and as such, is preferred over the current A/C Idle Test, which is limited in its ability to evaluate A/C efficiency technologies and represents only idle conditions (estimated at 13.5% of driving conditions).

Table III-A-5-3. Maximum credits available to manufacturers

Refrigerant	Emission Reduction Strategy	Max Credit (gCO_2e/mi)	
		Cars	Trucks
HFC-134a	Low Leak	6.3	7.8
	Improved Efficiency	5.0	7.2
	Total	11.3	15.0
Low GWP	Low GWP	13.8	17.2
	Improved Efficiency	5.0	7.2
	Total	18.8	24.4

The proposed AC17 test procedure was developed in concert with USEPA and US automakers, and contains the following elements: a unified dynamometer driving schedule (UDDS or LA92) preconditioning cycle, a period of solar soak (30 minutes), an

air conditioning test (SC03) drive cycle to evaluate emissions during the initial cool-down of the vehicle, and a highway fuel economy test (HFET) drive cycle to evaluate GHG emissions during steady state operation of the MVAC system and relatively steady state driving conditions. Performing these test elements under moderate temperature and humidity test cell conditions allows the efficiency of the whole MVAC system, including solar control, to be measured. For vehicle models that manufacturers are seeking to earn A/C efficiency credits, the AC17 test would be conducted to validate that the performance and efficiency of a vehicle's A/C technology is commensurate with the level of credit that is being earned. To determine whether the efficiency improvements of these technologies are being realized, the results of an AC17 test performed on a new vehicle model would be compared to a "baseline" vehicle that does not incorporate the efficiency-improving technologies. The baseline vehicle would be defined as one with characteristics that are similar to the new vehicle, only not equipped with efficiency-improving technologies (or they are de-activated).

Thus, for this rulemaking ARB is proposing to require that automobile manufacturers use the AC17 test procedure to demonstrate the effectiveness of their A/C efficiency technologies. Although USEPA will be seeking comment on the AC17 test in the Notice of Proposed Rulemaking for their 2017-2025 MY light-duty Greenhouse Gas Program that may result in some minor changes to the test procedure, staff believes that the basic procedure is sufficiently complete for ARB to propose it as a replacement for the Idle Test beginning in 2017, as a prerequisite for generating efficiency credits. Staff proposes that the LEV III/GHG regulatory proposal, as part of the Advanced Clean Cars rulemaking package, be finalized with the final federal AC17 test procedure and credit qualification requirements, provided these are substantially similar to that described herein and in Appendix R. ARB staff anticipates that USEPA will incorporate the AC17 test and associated requirements if the 2017-2025 MY rulemaking is finalized as scheduled in 2012, at which time the finalized federal regulatory language, as modified for California, would be subject to additional public comment before being incorporated into the finalized LEV III/GHG rule. If the finalized federal regulatory language cannot be incorporated into California's LEV III/GHG rule before it is finalized, ARB staff proposes that AC17 test procedure as currently proposed in the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles" (Appendix D) be used to qualify for efficiency credits, with the final federal test procedures possibly being incorporated into LEVIII through a subsequent Board action in order to promote harmonization within the national program.

Alternative fuel vehicles: ARB staff is proposing to credit electric- and hydrogen-powered vehicles according to their incremental emission impact from California-specific low-GHG upstream energy sources that are most likely in the timeframe of the regulation. Advanced electric-drive vehicles, including plug-in hybrid electric vehicle, battery electric vehicle, and fuel cell electric vehicle technology, can be driven primarily or entirely without tailpipe CO_2 emission emissions. Their associated GHG emissions are, instead, upstream from the vehicle at primary energy processing facilities, at

electricity generation plants, and throughout the fuel and electricity distribution network. In order to structure the GHG program for the long-term for a diversity of vehicle fuel types, the regulation proposes the implementation of standards that incorporate the relative GHG emissions from battery electric vehicle, plug-in hybrid electric vehicle, and fuel cell electric vehicle technologies as compared to the conventional vehicles that primarily utilize gasoline. The intent then is to establish straightforward performance-based GHG emission provisions that accurately count the upstream emissions in a technology-neutral way that provides industry certainty to plan for GHG requirements as these more advanced ultra-low-GHG technologies enter the market.

Staff notes that its proposed crediting provision for battery electric vehicle, plug-in hybrid electric vehicle, and fuel cell electric vehicle technology differs from the expected federal USEPA GHG regulatory program, which ARB intends to deem as sufficient for overall compliance. To accommodate this difference, staff is proposing two compliance options: (1) an automaker chooses to comply directly with California's standards including upstream accounting as specified here or (2) an automaker chooses to comply with the federal USEPA standards; utilizes the federal accounting provisions for battery electric vehicle, plug-in hybrid electric vehicle, and fuel cell electric vehicle technologies in the federal standards; and receives the same federal accounting for these technologies within the California regulation.

Staff's non-zero-emission accounting for these technologies' incremental upstream emissions is justified for several reasons. Primarily, the ZEV regulation already requires electric-drive vehicles in California, therefore obviating the need for special artificial crediting incentives. In addition, ARB's proposed GHG crediting more accurately depicts the science regarding known GHG impacts, more adequately sets the precedent for a future with increasingly more alternative fuel vehicles for 2025 and beyond, more assuredly protects against the environmental repercussions of foregone GHG emissions allowed from battery electric vehicle emission incentives, and better continues ARB's objective in keeping its performance standards technology-neutral. In addition, this accounting reflects California's purpose and intent to evaluate and reduce all GHG emissions – beyond tailpipe CO_2 – from all principal phases of passenger motor vehicle powering and use. Nevertheless, staff notes that accepting federal compliance (i.e., with federal upstream crediting incentives) remains valid, owing to the 50-state GHG reduction benefit greatly outweighing the California-alone GHG standard compliance, thus achieving additional emissions reductions benefiting California.

The ARB staff position on incorporating the incremental upstream emissions of electric and hydrogen fuel cell vehicles is further justified by several California-specific details that are different from the national US situation. The greater deployment of these advanced technologies in California fundamentally differentiates the State from the US context. The California ZEV regulation as proposed for amendment mandates that over 10% of the new vehicle fleet be some form of battery electric vehicle, plug-in hybrid electric vehicle, or fuel cell electric vehicle technology in 2025. In addition, California has complimentary programs (e.g., Low Carbon Fuel Standard and Renewable Portfolio Standard) that reduce upstream GHG emissions over time, rigorously track these

emissions, and provide the basis for accurate GHG emissions accounting. According to staff analysis below, for California's relatively low-GHG electricity and hydrogen, these ZEV-type vehicles will achieve very low GHG emission ratings and therefore would naturally achieve substantially lower GHG emissions than any other known vehicle technologies (e.g., hybrids) by a large margin without artificial incentives.

The GHG ratings for the three major electric-drive vehicle types involve several main factors. First, automaker vehicle testing of these vehicles' energy consumption characteristics under the customary city and highway drive cycles is required. For battery electric vehicles and plug-in hybrid electric vehicles, energy use is tested in kilowatt-hours per mile. For fuel cell electric vehicles, energy consumption is measured in kilograms of hydrogen per mile. Second, the energy consumption data are used to calculate these vehicles' relative GHG emissions, based on the projected future California-specific energy mix and related upstream GHG emission impacts. The upstream GHG factors are based on emission factors that are consistent with other known California electric grid and hydrogen production technology and policy developments for the 2020-2025 timeframe, to account for when these vehicle technologies will be entering the fleet in larger numbers. To allow for industry certainty in compliance planning, the upstream GHG emission factors are to be fixed for the entire 2017-2025 period of the GHG regulations. The GHG accounting equations, described below, that apply to these electric-drive technologies are conceptually identical to those in the federal 2012-2016 GHG rulemaking (that would be used after the initial federal incentives are utilized), but use California specific life-cycle GHG factors.

The upstream electric vehicle factors are based on the expected 33% renewable electricity mix in California, based on the implementation of 2011 California Senate Bill 2. The California grid is currently powered by an approximate 20% renewable energy mix, and the future mix in the 2020 timeframe is expected to reach 33% renewable, according to the in-development regulation of the California Public Utilities Commission. The detailed technical work from that process is utilized here to determine a consistent grid CO_2 emission rate (see EEE, 2010a; 2010b). From that analysis, the GHG emissions from future electricity use on the California grid are found to be 226 gCO_2 per generated kilowatt-hour. Upstream electricity emission factors to account for powerplant fuel transportation, feedstock, and processing GHG emissions, as well as electricity transmission and distribution efficiency losses, are taken from the Low Carbon Fuel Standard (LCFS) analysis (CARB, 2009a). After inclusion of the primary feedstock energy GHG emissions for powerplant (i.e., at 10% of overall electricity GHG) from the powerplant and the transmission and distribution losses (i.e., of 8%), the upstream electricity GHG factor is found to be 270 gCO_2e/kWh (i.e., 226 * 1.10 / 0.92) to deliver the electricity to a final vehicle user as measured at the electrical plug.

$$GHG_{EV} = (270\ gCO_2e/kWh) * E_{EV} - G_{upstream}$$

The equation is used for both the city and highway drive cycles, and E_{EV} is measured directly from each cycle for each test vehicle of battery electric vehicle technology in

units of kilowatt-hours per mile (per SAE J1634). The cycle results are combined (as for all other vehicles) for 55% city and 45% highway driving. The $G_{upstream}$ factor is applied to account for the reduction in well-to-tank gasoline GHG emissions. This adjustment factor effectively translates the lifecycle battery electric vehicle crediting into the regulation that only accounts for the direct tailpipe, or tank-to-wheels GHG emissions. Based on the LCFS lifecycle modeling of gasoline, upstream gasoline emissions are equivalent to 2211 gCO_2e/gallon of gasoline, as compared to the direct tailpipe 8887 gCO_2e/gallon as used in the regulation. As a result the equivalent gasoline emissions that are upstream can be calculated by multiplying the tailpipe GHG emissions by 25% (i.e., the upstream gasoline factor [2211], divided by direct exhaust factor [8887]). As in the federal GHG 2012-2016 regulations, this upstream gasoline adjustment is indexed to vehicles' target GHG emission rate (as described above). For example, a battery electric vehicle in California with a footprint of 42 ft^2 with a GHG emission target of 200 gCO_2/mile GHG emission target would have an upstream gasoline adjustment factor of 50 gCO_2/mile. In later years with lower GHG targets, the factor becomes lower (e.g., 40 gCO_2/mi for a 160 gCO_2/mi target).

$$G_{upstream} = (Target\ gCO_2/mile) * (0.25)$$

The GHG crediting of plug-in hybrid electric vehicles involves the measurement of electricity consumption and direct tailpipe CO_2 emissions throughout the full range of the vehicle (where it alternately uses grid electricity and consumes gasoline). Plug-in hybrid electric vehicles use the same upstream electricity GHG factor as above for their upstream electricity use during the regulatory test cycles. The fraction of their driving percent that is attributed to electricity is to be set according to the SAE J2841 utility factor, which indexes the fraction of electric miles to the amount of daily miles. This method results in a 20-mile all-electric plug-in hybrid achieving a utility factor of 0.40 and a 40-mile all-electric plug-in hybrid achieving a 0.63 utility factor, corresponding to 40% and 63% equivalent electric driving, respectively. The precise plug-in hybrid testing procedures are more complex, involving the testing through successive city and highway cycles, as described in ARB's hybrid testing procedures, and involve utility factor calculations for each subsequent successive city and highway cycles.

For fuel cell electric vehicles, the GHG crediting involves the direct test cycle measurement of hydrogen and the applicable upstream emission factors for hydrogen delivered to California vehicle users. The upstream GHG factors for hydrogen fuel are based on the expectation of 33% renewable hydrogen (based on the proposed Clean Fuels Outlet regulation, Senate Bill 1505 of 2006, and the ZEV program's fuel cell electric vehicle projections) and an upstream emission factor consistent with the Low Carbon Fuel Standard (CARB, 2009b) accounting for hydrogen fuel. Staff projects that with fuel cell electric vehicle deployment from the ZEV program, along with the provisions of the Clean Fuels Outlet regulations proposed for amendment as part of this Advanced Clean Cars package and SB1505, hydrogen will move to 33% renewable sources within the 2017-2025 timeframe. As a result, the LCFS-derived GHG emissions factor for 33% renewable hydrogen of 9,132 gCO_2e/kilogram hydrogen is applied to the rulemaking's crediting of fuel cell electric vehicles. As above for electric

vehicles, the fuel cell electric vehicle crediting equation includes the gasoline upstream adjustment factor to bring the lifecycle GHG crediting into the tank-to-wheel GHG standard. The GHG rating for fuel cell electric vehicles is calculated as follows, based on the hydrogen consumption (H_{FCV}) in kilograms of hydrogen per mile.

$$GHG_{FCV} = (9132\ gCO_2e/kg\ H_2) * H_{FCV} - G_{upstream}$$

In order to provide context for the proposed GHG crediting of battery electric vehicle, plug-in hybrid electric vehicle, and fuel cell electric vehicle technologies, approximate GHG emission ratings for three currently available models are shown here. Included are three example vehicles: an battery electric vehicle at 0.24 kWh/mile (similar to a Nissan Leaf); a plug-in hybrid electric vehicle with 0.25 kWh/mile, a 0.63 utility factor, and 177 gCO_2/mile exhaust emissions (similar to a Chevrolet Volt); and a fuel cell electric vehicle with 87 miles per kilogram hydrogen (similar to a Honda FCX Clarity). The GHG crediting of these hypothetical vehicles is shown in Table III-A-5-4. As shown all three vehicles would achieve GHG ratings that would give them substantial emission reductions within the GHG crediting framework for California described above, even after factoring in the reduced GHG of all conventional vehicles against which the three vehicles are being compared. The GHG ratings for these current electric-drive vehicle models would be 80-93% below current 2008 technology, 73-91% below 2016 technology, and 69-89% below 2020 technology, respectively. Further efficiency improvements from these current electric-drive technologies (e.g., low rolling resistance tires, mass-reduction, improved aerodynamics, improved accessory loads, low-GHG air conditioning systems), would result in greater percent GHG effectiveness than the reductions shown here when compared to conventional gasoline vehicles.

Table III-A-5-4. Example GHG emission rating from electric-drive vehicles

Technology	Electric energy use (kWh/mi)	Utility Factor	Direct CO_2 emissions (gCO_2/mi)	Hydrogen use (mi/kg)	GHG rating (gCO_2e/mi)	Reduction in GHG emissions versus average new vehicle		
						In 2008	In 2016	In 2020
Electric vehicle	0.240	-	-	-	23	93%	91%	89%
Plug-in hybrid electric vehicle (40-mile)	0.252	0.63	177	-	67	80%	73%	69%
Fuel cell vehicle	-	-	-	87	65	81%	74%	70%

Notes: Upstream GHG emissions based on California 2020 and beyond characteristics for electricity and hydrogen production, and gasoline upstream adjustment, $G_{upstream}$, of 40 gCO_2/mi is assumed for avoided equivalent upstream gasoline usage; use of air-conditioning credits not included; Average assumed new vehicle in California 336 gCO_2/mile in 2008, 251 gCO_2/mile in 2016, and 215 gCO_2/mile in 2020

Off-cycle credit: ARB staff is proposing to adopt the same off-cycle crediting provisions as USEPA at this time and revise, as needed, to maintain alignment with the federal program in future years. The federal USEPA program developed off-cycle crediting provisions for the 2012-2016 rules, and the provisions are being further developed for the 2017-2025 program. The major modification for the 2017-2025

regulations is to provide manufacturers with a list of pre-approved technologies for which USEPA can quantify a default value that would apply (unless the manufacturer demonstrates to USEPA that a different value for its technology is appropriate). The default values have been determined from the USEPA light-duty vehicle simulation tool, based on state-of-the-art full-vehicle simulation modeling of the physical principles throughout the various vehicle subsystems. The first application of the vehicle simulation model has been peer-reviewed and published (Lee et al, 2011; USEPA, 2011), and the tool is publically available. Conceptually this is similar to the "menu-driven" approach as utilized in the air conditioning provisions. Staff notes that the amount of default GHG credit allotted in these crediting provisions is conservative.

Similar to the air-conditioning credit provisions, these optional provisions can be used to offset some tailpipe emissions and thus provide additional flexibility for achieving compliance with the CO_2 standards. Any vehicle model or vehicle test family receiving off-cycle credits from the various approved technologies can receive a maximum of 10 grams CO_2 per mile in credits. This accounting reflects California's purpose and intent to evaluate and reduce all GHG emissions – beyond tailpipe CO_2 – from all principal phases of passenger motor vehicle powering and use. Through these off-cycle credit provisions, ARB staff is also integrating vehicle thermal control innovations that had formerly been considered in the Cool Cars rulemaking.

Table III-A-5-5 provides estimates for the GHG emission credits that are expected to have default credit values. With these provisions, ARB staff acknowledges the importance of off-cycle CO_2-emission reductions that verifiably occur in real world conditions but are not acknowledged in standard test-cycle CO_2 measurement. Examples of these off-cycle technologies include active grill shutters that improve aerodynamics at high vehicle speeds, solar panels that significantly offset accessory electric loads and/or charge hybrid and electric-drive batteries, and solar control glazing that reduces the load from air conditioning. ARB staff notes that these estimations for available off-cycle crediting may be further refined after USEPA's final rulemaking in 2012.

Table III-A-5-5. Estimates of off-cycle GHG credit from pre-approved technology

Technology	Car credit (gCO_2/mile)	Truck credit (gCO_2/mile)
High-efficiency headlights	1.1	1.1
Engine heat recovery	0.7	0.7
Solar roof panels	3.0	3.0
Active aerodynamic improvements	0.6	1.0
Engine stop-start	2.9	4.5
Electric heater circulation pump	1.0	1.5
Active transmission warm up	1.8	1.8
Active engine warm-up	1.8	1.8
Thermal control (e.g., solar control) and Thermal comfort (e.g., ventilated seats)	Up to 3.0	Up to 4.3

Full-Size pickup truck technology: ARB staff is proposing to adopt the USEPA full-size pickup truck incentive provisions. The full-size pick-up provisions provide special emission-reduction credit for technology innovations on the largest of pickup trucks that fall within the light-duty vehicle regulations, in order to facilitate the widespread deployment of technologies that are likely to otherwise remain in relatively small numbers. These full-size pickup crediting provisions have minimum truck capacity criteria (i.e., minimum pickup bed dimensions and minimum payload requirements), minimum company pickup truck penetration requirements, and technology-based criteria. The provisions will have two technology types (hybrid and non-hybrid performance-based) and two levels (10 and 20 gCO_2e/mile). Of the four potential mechanisms to receive the full-size pickup truck credits, no model can receive credit under more than one of the mechanisms. The pickup truck definition and the four applicable provisions are summarized in Table III-A-5-6.

Table III-A-5-6. Summary of provisions for hybrid and performance-based full-size pickup truck credits

Provision	Minimum qualifying criteria, conditions
Full-size pickup truck definition (for any qualifying pickups)	• Minimum cargo bed width between the wheelhouses of 48 inches (defined by dimension W202 in Society of Automotive Engineers Procedure J1100) • Minimum cargo bed length of 60 inches (defined by dimension L505 in Society of Automotive Engineers Procedure J1100) • Minimum towing capability (gross combined weight rating, minus gross vehicle weight rating) of 5000 lb; or minimum payload capability (gross vehicle weight rating, minus curb weight) of 1700 lb.
Performance-based full-size pickup (10 gCO_2/mi)	• Satisfy full-size pickup truck definition (see above) • Available for model years 2017-2021 • Maximum gCO_2/mile of 15% below GHG target for given year and footprint • Once test model achieves credit for given model year, it can receive credit in subsequent years, provided no increase in gCO_2/mile • The level of gCO_2/mile emission performance must be achieved on a minimum percent of all the company's full-size pickup trucks sold in each model year that it is to receive credit: 15% in 2017; 20% in 2018; 28% in 2019, 35% in 2020, 40% in 2021.
Performance-based full-size pickup (20 gCO_2/mi)	• Satisfy full-size pickup truck definition (see above) • Available for model years 2017-2025 • Maximum gCO_2/mile of 20% below GHG target for given year and footprint • Once test model achieves credit for given model year, it can receive credit for four additional model years (but not beyond model year 2025), provided no increase in gCO_2/mile • The level of gCO_2/mile emission performance must be achieved on at least 10% of all the company's full-size pickup trucks sold in each model year that it is to receive credit.
Mild hybrid full-size pickup (10 gCO_2/mi)	• Satisfy full-size pickup truck definition (see above) • Minimum recovery of 15% of the theoretical available braking energy as electrical battery energy (as determined by vehicle test weight and A, B, and C test coefficients, and USEPA equations for total net energy in to battery divided by total braking energy on FTP city cycle) • Technology must be used on a minimum percent of all the company's full-size pickup trucks sold in each model year that it is to receive credit: 30% in 2017; 40% in 2018; 56% in 2019, 70% in 2020, 80% in 2021.
Strong hybrid full-size pickup (20 gCO_2/mi)	• Satisfy full-size pickup truck definition (see above) • Minimum recovery of 75% of the theoretical available braking energy as electrical battery energy (as determined by vehicle test weight and A, B, and C test coefficients, and USEPA equations for total net energy in to battery divided by total braking energy on FTP city cycle) • Technology must be used on at least 10% of all the company's full-size pickup trucks sold in each model year that it is to receive credit

N_2O and CH_4 provisions: ARB staff is proposing to change the regulatory requirements for CH_4 and N_2O emissions. In the Pavley 2009-2016 GHG regulation, the standard was expressed as a CO_2-equivalent, including the emissions of CO_2, refrigerant HFC, and CH_4 and NO_2. These last two GHG pollutants were assigned default CO_2-equivalent emission factors that automakers could accept and include in lieu of separate certification testing for each test vehicle. As such these two pollutants were included in the baseline and in future compliance as default values (unless companies opted to submit measured data instead). Under the federal 2012-2016 rulemaking, USEPA established regulations whereby CH_4 and N_2O emissions are regulated by maximum per-vehicle emission caps with required N_2O and CH_4 emission test data submissions from model year 2015 on.

ARB staff proposes to adopt the federal USEPA model year 2016 per-vehicle regulatory caps for its 2017-2025 regulations for CH_4 and N_2O emissions. As a result, testing for these two emissions will be required from model year 2017 on by vehicle type, with full useful life certification limits of 0.030 g/mi CH_4 and 0.010 g/mi N_2O. Considering that vehicles are typically designed at about 50% below the emission limits to meet

standards for vehicle production variability and deterioration, these proposed CH_4 and N_2O standards reflect the same stringency as the existing California default standards. Under the existing California standards the default CH_4 and N_2O values would not have prevented the possibility of outlier vehicles or un-tested and un-monitored vehicles that have CH_4 and N_2O emission levels that creep up over time. This proposed mandatory testing approach more adequately protects against backsliding and the potential that high-emitting outlier vehicles could otherwise utilize ARB's default values.

ARB staff proposes to allow manufacturers to over-comply with CO_2 standards and use those over-compliance credits to offset any N_2O or CH_4 emission deficits. A manufacturer choosing this option would convert its measured N_2O and CH_4 test results that are above the applicable standards into CO_2-equivalent emissions, according to their global warming potential (GWP) values (i.e., GWP of 25 for CH_4, GWP of 298 for N_2O) to determine the amount of required CO_2 emission credits. For example, a manufacturer would use 0.25 g/mile of positive CO_2 credits to offset 0.01 g/mile of negative CH_4 credits or use 2.98 g/mile of positive CO_2 credits to offset 0.01 g/mile of negative N_2O credits.

This revised approach – unbundling the regulated GHG formula but providing credit for reducing individual vehicular GHGs – avoids having to adjust the CO_2 footprint curves to reflect the other two pollutants, as would have been required in the bundled approach that sums CO_2, N_2O, and CH_4 emissions. However, in the potential event that federal GHG standards were not being accepted for equivalent compliance, ARB staff would consider revising the GHG standards back to a bundled approach that directly sums tested CO_2, N_2O, and CH_4. This, in turn, would require the adjustment of the footprint-indexed GHG target standards from those that are proposed here.

For inventory purposes, ARB staff will convert the emission levels to CO_2-equivalent rates based on their GWP values. With a GWP of 25, the CH_4 limit equates to 0.75 gCO_2e/mile; with a GWP of 298, the N_2O limit equates to 2.98 gCO_2e/mile. For a new model year 2016 vehicle with test cycle GHG emissions of 250 gCO_2/mile, with the N_2O and CH_4 emissions at a 50% design target, the total GHG emissions from the three pollutants would be 251.87 gCO_2e/mile (i.e., 250+1.49+0.38). In this case, the contribution of the N_2O and CH_4 would be less than 1% (i.e., [1.49+0.38]/[251.87]) of the new vehicle test-cycle GHG emissions. For average new 2025 vehicles at about 166 gCO_2e/mile, N_2O and CH_4 would still amount to less than 1.5% of test cycle GHG emissions. Because these emission levels are very low, and because these particular emissions are expected to continue to be very tightly controlled as part of the LEV III SULEV 2015-2025 standards for oxides of nitrogen and hydrocarbons, staff believes it is not necessary to establish more stringent standards for these two GHG pollutants. Still, setting a cap, and maintaining a potential footprint adjustment, reflects California's purpose and intent to evaluate and reduce all GHG emissions – beyond tailpipe CO_2 – from all principal phases of passenger motor vehicle powering and use.

5.4. Compliance with the Greenhouse Gas Requirements

Staff assesses the required technology penetration and expected compliance cost based on the California vehicle fleet projection, the GHG standard and ZEV program requirements, and the available technology packages' CO_2 effectiveness and incremental prices as projected above. The GHG standards are, by design, performance standards and therefore allow many potential compliance paths to be undertaken by any company depending on their particular mix of vehicle types and technology competencies. This analysis investigates compliance paths that incur low average cost per vehicle, given the available technologies.

Fundamentally, this compliance analysis has three scenarios that are summarized here: (1) a "no new policy" baseline, (2) 2017-2025 GHG standards without new 2018-2025 ZEV requirements, and (3) 2017-2025 GHG standards with new 2018-2025 ZEV requirements. The first scenario is modeled in order to investigate the cost of the already adopted 2016 GHG standards and the existing ZEV requirements to serve as a reference from which to compare the additional technology costs from the new GHG standards and ZEV program. The second and third scenarios help show the differential cost between the GHG program alone versus the LEV III GHG standards with the ZEV program as a package. The additional compliance cost from the regulatory proposal package, then, is the third scenario minus the baseline first scenario.

The analysis of the baseline for no new LEV III and ZEV policy includes approximately constant GHG emissions for 2016 and later model years. This 2017-and-beyond baseline includes no new concerted industry action to further reduce average GHG emissions, but it does include some small changes from the slight projected car-truck shift and the requirements for model year 2017-2018 ZEV regulation compliance. Staff believes that the historical trends for automaker compliance with criteria pollutant and CAFE standards, feedback from discussions with automakers, and the effect of footprint-indexed standards make it clear a "flat" future year baseline is the highest likelihood reference scenario. For example, as indicated in the USEPA *Trends* report and other technical analyses, when model year 1986-2005 CAFE standards remained unchanged, new vehicle fuel economy also remained essentially unchanged while new technologies were utilized to improve other vehicle attributes (USEPA, 2010; Lutsey and Sperling, 2005; An and DeCicco, 2007). Similarly, staff has found no evidence of sustained over-compliance with its criteria pollutant standard regulations when standards are unchanged. From feedback from automakers, staff believes that the advent of footprint-indexed standards of 2012-2016 will make it further unlikely that there will be any significant GHG over-compliance in the absence of the proposed new GHG standards.

As indicated in the representative technology package walk-ups in Figure III-A-4-5 and III-A-4-6 above, the general progression of GHG-reduction technologies goes from early engine and transmission technologies (aerodynamics, low rolling resistance tires, dual cam phasing, 8-speed and dual clutch transmission, engine friction reduction), to mass reduction of about 10%, to turbocharged downsized direct injection engines, to cooled

exhaust gas recirculation, to more advanced mass reduction of 15-20%, to hybrids, to electric-drive technology. The increasing GHG standard stringency through the 2017-2025 standard period generally moves each automaker through this technology progression toward more advanced technologies at higher incremental cost over time. However, with the proposal for new 2018-2025 ZEV regulation requirements the strategic technology choices could be impacted to result in a greater penetration of ZEV-type vehicles, reducing the penetration of the other more incremental technologies.

The proposed changes for the ZEV regulation are posted in a separate *Initial Statement of Reasons* (ISOR) that is released concurrently with this one for LEV III. Although the proposed ZEV regulations have crediting provisions that allow for many different battery electric vehicle, plug-in hybrid electric vehicle, and fuel cell electric vehicle technology deployment strategies for compliance, the ZEV analysis has resulted in a "most likely" scenario for the projected technology mix. The basic technology shares are shown here in Table III-A-5-7, as they are analyzed in this assessment of the GHG-plus-ZEV compliance scenario. For further ZEV program details, crediting provisions, and requirements, readers are directed to the ZEV regulation *ISOR*[30].

Table III-A-5-7. Projected new vehicle technology shares of ZEV-type vehicles

Manufacturer type	Vehicle type	Existing		Proposed							
		2012-2014	2015-2017	2018	2019	2020	2021	2022	2023	2024	2025
Large volume	BEV	0.13%	0.50%	0.9%	1.7%	2.3%	2.8%	3.2%	3.6%	3.8%	3.8%
	FCV	0.06%	0.17%	0.2%	0.4%	0.6%	0.9%	1.3%	1.7%	2.1%	2.6%
	PHEV	1.5%	2.0%	3.6%	4.3%	5.0%	5.7%	6.4%	7.1%	7.9%	8.6%
Intermediate volume	PHEV	-	-	6.4%	10.0%	13.6%	17.1%	20.7%	24.3%	27.9%	31.4%

Technology penetration: Figure III-A-5-4 illustrates ARB staff's estimated technology penetration for compliance with the 2017-2025 GHG standards. Relatively low cost aerodynamic and low rolling resistance tires are adopted sooner, followed by progressive introduction of dual-clutch transmissions, turbo-downsized gasoline direct injection, mass-reduction, cooled exhaust gas recirculation, and electric-drive (including hybrid, plug-in hybrid, electric, and fuel cell) technologies. ARB staff projects that the turbo-downsized gasoline engine becomes the major engine technology over this period, with more advanced cooled EGR engines with even greater boosting emerging in the later years of the standards. For the case of the proposed GHG standards (i.e., without ZEV), the higher cost hybrid and ZEV-type technologies are needed for compliance at a level of about 12% market share by 2020 and by 16% in 2025, and about two-thirds of those vehicles are hybrids. A number of technologies like engine

[30]STAFF REPORT: INITIAL STATEMENT OF REASONS, ADVANCED CLEAN CARS, 2012 PROPOSED AMENDMENTS TO THE CALIFORNIA ZERO EMISSION VEHICLE PROGRAM REGULATIONS, Release Date December 8, 2011.

friction reduction, optimized transmission controls, improved accessory efficiency, and dual-cam-phasing, which are on most of the packages, are not shown in the figure. Although the use of a low-GWP refrigerant, like HFO-1234yf, is expected to see some deployment before the 2017-2025 period, staff projects its widespread application from 2016-2021.

Figure III-A-5-4. Technology penetration for 2017-2025 MY GHG standards (without new 2025 ZEV)



Table III-A-5-8 shows more detailed results for the technology penetration in 2016, 2020, and 2025 for the two compliance scenarios. As indicted above, compliance with the GHG standards without the ZEV program would require that hybrid and ZEV-type vehicles make up about 12% by 2020 and 16% in 2025 (with about two-thirds of those vehicles being hybrids). Under the ZEV scenario, these advanced vehicles would represent vehicle shares of 14% in 2020 and 22% in 2025 (with about two-thirds of those vehicles being ZEV-type vehicles). As a result of the impact of the additional ultra-low-GHG ZEV technologies toward GHG compliance, the required shares of incremental engine, transmission, and hybrid technologies are reduced in the 2021-2025 timeframe. For example, where the GHG-only scenario found 72% of model year 2025 vehicles would be turbocharged downsized gasoline direct injection, in the "with ZEV" scenario, that technology deployment dropped to 51%. Staff notes that the expected technology shares in an overall national US sales context is somewhere between these two scenarios, where California and ZEV-adopting states get more ZEV-heavy sales mixes and ZEVs contribute toward the GHG standard compliance of the overall US fleet.

Table III-A-5-8. Percent of new vehicles with given technology for GHG and GHG-plus-ZEV compliance scenarios

Scenario	Technology	Percent of vehicles with technology by model year		
		2016	2020	2025
GHG regulation	Aerodynamics (10%+)	61%	79%	100%
	Low RR tires (10%+)	61%	79%	100%
	Mass reduction (10%+)	11%	32%	58%
	Dual clutch transmission	38%	48%	62%
	Gasoline direct injection	33%	50%	72%
	Cooled EGR	0.2%	14%	32%
	Hybrid	4.5%	7.5%	11.3%
	Plug-in hybrid electric vehicle	1.7%	2.0%	1.9%
	Electric vehicle	0.4%	1.7%	1.8%
	Fuel cell vehicle	0.1%	0.5%	0.9%
	Alternative refrigerant	0%	100%	100%
GHG and ZEV regulations	Aerodynamics (10%+)	61%	79%	100%
	Low RR tires (10%+)	61%	79%	100%
	Mass reduction (10%+)	11%	27%	46%
	Dual clutch transmission	38%	47%	56%
	Gasoline direct injection	33%	41%	51%
	Cooled EGR	0.2%	6%	14%
	Hybrid	4.5%	5.2%	5.7%
	Plug-in hybrid electric vehicle	1.7%	5.4%	9.3%
	Electric vehicle	0.4%	2.3%	3.7%
	Fuel cell vehicle	0.1%	0.6%	2.5%
	Alternative refrigerant	0%	100%	100%

The summary results shown above in Table III-A-5-8 represent two scenarios for compliance to achieve the required regulatory GHG levels in the new California fleet. In the national US fleet context, a compliance scenario could resemble technology shares from each of those two scenarios that are shown. Automakers will be able to use ZEV-type vehicles (for California and ZEV-adopting Section 177 compliance) toward compliance with national USEPA GHG standards. California and other ZEV-adopting states[31] amount to about 29% of US light-duty vehicle sales. As a result, ZEV requirements in ZEV states alone would amount to a minimum of about 4% national US share for all ZEV types. The non-ZEV technology shares, nationally and in California, could be more similar to the "GHG only" scenario (e.g., over 70% GDI and over 10% hybrid shares). As a result, staff believes that it is possible that selling the required ZEV shares in California, along with a nationally compliant GHG fleet, could deliver some amount of over-compliance with the GHG standards within California. However, it is uncertain exactly if or how automakers might choose to differentially sell various vehicle technology types across California and the rest of the US.

Price of compliance: Due to the incremental price increases associated with the technologies that are used toward compliance, the average vehicle is projected to experience increasing vehicle prices through the vehicle rulemaking period. Assuming that all of the associated direct manufacturing and indirect cost mark-ups are passed on to consumers, Table III-A-5-9 summarizes the incremental vehicle price increase that

[31] Currently Arizona, Connecticut, Maine, Maryland, Massachusetts, New Jersey, New Mexico, New York, Oregon, Rhode Island, and Vermont.

results from the GHG emission standards over the 2017-2025 period. The GHG standards are estimated to cost approximately $1340 per vehicle by the final model year of the program, with approximately equal average per-vehicle costs across the car and truck categories. Due to the higher cost of electric vehicle technology associated with the ZEV-type vehicles, the compliance costs of the GHG-plus-ZEV scenario increase from $1340 to around $1840 per vehicle in model year 2025. Because staff estimates that the vast majority of the ZEV technology will be utilized in cars, the cost burden varies between cars and trucks, with approximately $2490 on average for cars and $810 on average in trucks by 2025. For context, as shown above on a technology basis (see section III.A.4.4) and below in consumer economic analysis, the lifetime benefits of the vehicles will on average have benefits that greatly exceed the these incremental costs.

Table III-A-5-9. Incremental vehicle technology price ($/vehicle) for 2025 GHG regulations

Scenario	Category	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025
GHG regulation	Car	-	170	330	520	720	900	1,070	1,190	1,310	1,320
	Truck	-	170	340	510	720	910	1,090	1,200	1,310	1,360
	Average	-	170	340	510	720	910	1,080	1,190	1,310	1,340
GHG and ZEV regulations	Car	-	160	460	930	1,270	1,700	2,020	2,300	2,560	2,490
	Truck	-	160	250	340	420	530	610	670	730	810
	Average	-	160	380	700	940	1,230	1,460	1,660	1,840	1,840

All value rounded to the nearest ten.

The above table represents the average costs according to the major vehicle categories. In order to arrive at those cost estimates, the analysis incorporated compliance by all the major companies with the GHG and ZEV standards, in order to investigate differences in the companies' average per-vehicle cost of compliance due to their baseline fleet characteristics. To analyze each case, after companies meet their ZEV requirements, low-GHG technology packages are added in order of their cost-effectiveness (moving up in cost per GHG reduction per mile) until companies' new vehicle fleets come into compliance with the GHG standards.

Table III-A-5-10 summarizes the incremental price increase results for major automobile manufacturers to comply with the GHG and ZEV regulations. In the table, the baseline represents a fleet without new policy, meaning compliance with 2016 GHG standards and the existing ZEV regulation. As shown in the table below, the average per-vehicle incremental price increase differs by automaker. Companies with relatively low GHG baseline fleets (e.g., Honda, Hyundai-Kia, Mazda, and Toyota) have lower-than-average incremental prices. Companies that typically have larger sales percentages of luxury and high-performance models (e.g., BMW, Jaguar-Land Rover, Mercedes, Spyker, Volvo, and Volkswagen) have higher estimated compliance costs.

Table III-A-5-10. Summary 2025 MY of increased incremental price for baseline, 2025 GHG regulation, GHG-plus-ZEV regulation scenarios

Company	Incremental price in 2025 from 2008 technology			Incremental price in 2025 from Baseline	
	Baseline	2025 GHG	2025 GHG+ZEV	2025 GHG	2025 GHG+ZEV
BMW	1,020	2,530	3,250	1,500	2,230
Chrysler-Fiat	1,270	2,350	2,870	1,080	1,600
Ford	1,260	2,710	3,220	1,440	1,960
General Motors	1,080	2,470	2,840	1,390	1,760
Honda	1,050	1,910	2,480	860	1,430
Hyundai-Kia	1,000	1,890	2,510	890	1,520
Jaguar-Land Rover *	1,670	5,410	5,870	3,740	4,200
Mazda	910	2,080	2,610	1,170	1,700
Mercedes	1,550	4,450	4,500	2,900	2,950
Mitsubishi *	720	2,900	3,940	2,180	3,230
Nissan	980	2,430	2,650	1,450	1,670
Spyker *	1,110	4,310	5,230	3,200	4,130
Subaru *	670	1,990	4,470	1,320	3,800
Suzuki *	710	2,920	3,880	2,210	3,160
Toyota	1,240	2,270	2,850	1,030	1,610
Volvo *	960	3,820	5,340	2,860	4,380
Volkswagen	1,370	3,660	3,750	2,280	2,370
Average	1,150	2,490	2,990	1,340	1,840

Notes: Costs are in the year 2025 in 2009 dollars; This baseline includes compliance with 2016 GHG standards and projected baseline ZEV requirements (i.e., before new 2018+ MY ZEV proposal) of about 2% PHEV, 1.7% BEV/FCV shares from 2017-2015; (*) indicates companies that are likely to be allowed Intermediate Volume Manufacturer (IVM) PHEV-only provisions within ZEV program

The above summary tables illustrate the incremental price to consumers in model year 2025, the final year of the proposed standards. The phase-in schedules for each of the programs are summarized above (i.e., ZEV market shares, and GHG footprint-indexed targets). Based on the phase-in schedules, the incremental technology costs (with varying levels of technology cost learning through those interim years) are analyzed through each year of the program.

Figure III-A-5-5 illustrates the summarized staff technical analysis on the incremental price increase due to the GHG and ZEV programs. As indicated in the table above, these price increases are incremental to the existing GHG and ZEV regulations. The figure shows the GHG program's incremental increase from 2016 through 2025, as well as how the higher incremental cost of ZEV technology adds additional cost due to their still relatively low manufacturing volumes. The final average incremental vehicle price increase for the GHG standards plus ZEV package is shown increasing from $0 in 2016 to $1840 in model year 2025. This average price increase shown includes the approximate 15% share of ZEVs that are higher cost (at $8000+ price premium) as well as the non-ZEVs (that more typically have an approximate $1000 price premium). In a national context, these compliance results would differ somewhat. A comparable 2017-2025 national compliance assessment would not include California's baseline ZEV regulation requirement, would not require the new proposed 2025 ZEV shares, and would involve some smaller differences in the fleet mix. However, the ZEV-type vehicles in California (and Section 177 states) will all aid in national USEPA GHG

standard compliance. As a whole, the average per-vehicle price premium overall that is associated with the 2025 federal standards is expected to be similar to the $1840 result here for California compliance.

Figure III-A-5-5. Incremental vehicle price for GHG and ZEV programs, relative to no new policies beyond model year 2016



5.5. Discussion of Differences from 2010 Joint-Agency *TAR* and this Analysis by ARB

As outlined above, there have been many updates to the technical and cost analysis since ARB, USEPA, and NHTSA jointly published their interim TAR on GHG technologies in September of 2010. This section offers a high level summary of substantial differences in the results, as well as a description of the major underlying reasons for the differing results. Essentially nearly every technical change made in our assessment of GHG-reduction technologies, including technology effectiveness, technology availability, and technology costs, was discussed jointly between the technical staffs of ARB, USEPA, and NHTSA. These changes, along with a number of California-specific assumption modifications, are summarized here.

There were numerous analytical modeling differences in this work from the TAR. One primary change has been in the CO_2 effectiveness modeling. The Ricardo vehicle simulation modeling offered a state-of-art technical analysis of emerging highly advanced powertrain technologies. The modeling ultimately indicated that a greater CO_2 effectiveness of several percentage points would result from emerging incremental technologies – in particular from more advanced direct injection engines with greater levels of turbocharging and cooled exhaust gas recirculation technologies and a number of other engine and transmission technologies.

Another modeling modification was to use results from NHTSA's new 2011 fleet safety analysis to impose constraints for per-vehicle mass-reduction across vehicle classes in

a way that was deemed "safety-neutral." As a result, smaller cars were not allowed any mass reduction, mid-size cars were allowed up to 10% mass reduction, and the trucks were allowed up to 20% mass reduction. Although the 2011 NHTSA fleet modeling showed fatality coefficients that were statistically insignificant in four out of five cases, their suggested safety modeling constraints were imposed for all vehicle classes in order to conservatively model technical compliance scenarios that minimize societal safety risks. Ultimately this safety-neutral constraint greatly reduced the total mass-reduction projected to be utilized in automaker 2025 compliance from levels of 15-30% in the TAR to approximately 9% in this updated ARB staff modeling. Based on feedback from automakers that are reducing mass across all their vehicle platforms and from various vehicle safety design studies' validation of mass-reduced advanced vehicle designs, ARB staff has found that these safety-neutrality constraints are conservative assumptions about the use of safe mass-reduction technology that will likely be utilized for compliance with the standards. Nevertheless, it is clear that the proposed regulations do not require mass reduction beyond expected manufacturer shifts.

Several changes have also been made in the provisions for evaluating the GHG crediting provisions for air conditioning system improvements. The TAR analyzed a maximum of 15 gCO_2e/mi to be utilized industry-wide in the 2020-2025 timeframe. In this analysis for the proposed standards, the available GHG credits from air-conditioning systems are higher. For this proposal the maximum available credits are higher at 18.8 gCO_2e/mi for cars and 24.4 gCO_2e/mi for trucks (for approximately 21 gCO_2e/mi on average, depending on the fleet mix). This effectively allows an additional 6 $gCO_2e/mile$ from the various refrigerant and air conditioning efficiency technologies that were not available in the TAR analysis.

A number of analytical changes have been made in this updated assessment of various technologies' incremental costs. Generally, the methods for using FEV teardown-derived costs (with agency estimates of indirect costs of the technologies) increased due to small detailed modifications to account for engineering design and testing and the potential for stranded capital costs. Also, the new FEV cost study offered some increased and some decreased costs of various hybrid components but on the whole substantially increased the incremental hybrid costs to generally $4000-$5000 over baseline 2008 technology. Mass reduction costs also increased substantially based on the agencies' assessment, thereby reducing the relative attractiveness of using optimized design and advanced materials (See Appendix Q for a related discussion). There were also minor changes in supplier cost estimates on various components. For battery electric vehicle and plug-in hybrid electric vehicle technologies, battery costs have been adjusted upward to account for safety disconnect equipment and thermal management systems. Overall the indirect cost multipliers saw adjustments in their magnitude and in the placement of technologies into the ICM categories, thus resulting in higher indirect cost mark-ups for the costs of nearly all of the technologies.

The technical and compliance cost modeling has now separately been conducted by each of the agencies with company-specific impacts examined. The company-specific modeling allows for greater detail on technologies and costs of industry compliance and

more detailed consideration by each agency for its particular regulatory requirements. The separate modeling by each of the agencies (whereas the TAR compliance modeling was led by USEPA) allows for varying agency provisions and requirements, as well as providing independent agency review and development of their respective, proposed standards. For example, the agencies have differing regulatory treatment of alternative fuel vehicles and air-conditioning credits (i.e., between NHTSA standards and the GHG standards), and California has to separately account for the requirements of the ZEV program, as discussed above.

A number of California-specific factors result in further differences from the TAR compliance results. There are some basic differences due to California-specific assumptions about the projected fleet mix. For example, even with exactly the same footprint-indexed standard lines, the California fleet has a 166 gCO_2/mile standard target, compared to the federal fleet's projected 163 gCO_2/mile target outcome. The largest factor in this difference is California's projection for 61% cars and 39% trucks versus the federal projection of 68% car and 32% truck. For context, California's fleet in model year 2008 had a 60% car share, and the recent US new vehicle fleet had a 50-53% car share in 2005-2008 and 59-60% car share in 2009-2010. The federal sales projection from the TAR incorporates a contracted industry sales projection from CSM and the US Energy Information Administration's *Annual Energy Outlook* projections. ARB's projection is based on California Department of Motor Vehicle data and statewide vehicle population and travel trends as consistent with ARB's EMFAC statewide modeling. Also, California has other small differences in the projected fleet mix, including different company percent shares and small differences in the footprint-indexed vehicle fleet size. Staff has analyzed the sensitivity of the overall GHG program outcome for shifts in these vehicle sales trends below in section III.A.5.9, finding them to be significant and important to track in future years.

California's ZEV program imposes requirements for increased sales of battery electric vehicle, plug-in hybrid electric vehicle, and fuel cell electric vehicle technology. The larger amount of ZEV technology in California, as well as other well-established low-GHG programs (e.g., Low-Carbon Fuels Standard, Renewable Portfolio Standard) tracking those upstream emissions, prompted Staff to directly consider the upstream GHG emissions of these vehicles in the fleet emission rates, whereas the TAR did not. ARB's proposal, rationale, and GHG rating equations for these ZEV-type technologies are discussed above in section III.A.5.3.

Table III-A-5-11 summarizes the results of this assessment in the context of ARB, USEPA, and NHTSA interim *TAR* analysis in September 2010. Aside from the above-mentioned differences in the modeling, there are additional differences in the assumptions applied for vehicle consumer lifetime usage and fuel price. The TAR used survival-adjusted lifetime travel assumptions that were approximately 200,000 miles per vehicle, based on national data for vehicle travel and survival rates. This assessment relies on California-specific data on vehicle travel and survival rates from the California Department of Motor Vehicles. Basic summary tables here utilize California-specific data for median vehicle lifetimes of 14 years and 186,000 miles for cars and 17 years

and 234,000 miles for trucks. Staff notes that, by definition, half of new vehicles will travel more or less than these average lifetime estimates. Also the TAR applied future gasoline prices that were approximately $3.49/gallon from the US Department of Energy's *Annual Energy Outlook*. This assessment applies projections for California fuel prices that are somewhat higher, at, for example, $4.02 in 2025 (year 2009 dollars) based on the California Energy Commission's *Integrated Energy Policy Report* (CEC, 2011).

Table III-A-5-11. Summary of the proposed standard compliance technology and cost versus joint-agency TAR findings from September 2010

Scenario	Technology Path	New Vehicle Technology Penetration in 2025					Incremental price ($/vehicle)	Average payback period (yr)	Net liftetime owner savings ($)
		Mass Reduction	Gasoline & diesel vehicles	HEV	PHEV	EV, FCV			
TAR 3%/year	Path A	15%	89%	11%	0%	0%	930	1.6	5000
	Path B	18%	97%	3%	0%	0%	850	1.5	5100
	Path C	18%	97%	3%	0%	0%	770	1.4	5200
	Path D	15%	75%	25%	0%	0%	1050	1.9	4900
TAR 4%/year	Path A	15%	65%	34%	0%	0%	1700	2.5	5900
	Path B	20%	82%	18%	0%	0%	1500	2.2	6000
	Path C	25%	97%	3%	0%	0%	1400	1.9	6200
	Path D	15%	55%	41%	0%	4%	1900	2.9	5300
Proposed regulation (4.5%/yr)	GHG	9.3%	84%	11%	1.9%	2.7%	1,340	2.1	5,900
	GHG+ZEV	8.3%	79%	5.7%	9.3%	6.2%	1,840	2.8	5,100
TAR 5%/year	Path A	15%	35%	65%	0%	1%	2500	3.1	6500
	Path B	20%	56%	43%	0%	1%	2300	2.8	6700
	Path C	25%	74%	25%	0%	0%	2100	2.5	7000
	Path D	15%	41%	49%	0%	10%	2600	3.6	5500
TAR 6%/year	Path A	14%	23%	68%	2%	7%	3500	4.1	6200
	Path B	19%	48%	43%	2%	7%	3200	3.7	6600
	Path C	26%	53%	44%	0%	4%	2800	3.1	7400
	Path D	14%	29%	55%	2%	14%	3400	4.2	5700

5.7. Analysis of Alternative GHG Regulation Stringency

In addition to the proposed GHG regulatory stringency of above, staff also analyzed alternative stringencies that delivered lower and higher GHG emission levels. The differing stringency levels were based upon the upper bounds that were chosen by USEPA, NHTSA, and CARB for use in the 2010 TAR analysis. The reduced stringency case represented a 3%/year reduction in GHG emissions from 2016-2025 to achieve 190 gCO_2e/mile; the increased stringency case represented a 6%/year GHG reduction to achieve 143 gCO_2e/mile in model year 2025.

Staff notes that NHTSA, in its Environmental Impact Statement, has decided to analyze a range of scenarios that spans from 2%/year to 7%/year in annual fuel economy increase. Staff notes that ARB's technical analysis from the TAR effectively narrowed the GHG stringency range to within 3-6%/year change in CO_2 emissions, due primarily to ARB Pavley requirements for meeting the various technical, economic, and owner-operator life-cycle cost factors. As a result the 3-6%/year range from the TAR was

maintained for this analysis of alternatives. The sufficiency of these upper and lower ranges for ARB's analysis of alternatives in its Environmental Analysis is discussed in that document, Appendix B.

In order to analyze the two alternative stringency cases, footprint-indexed GHG target lines were shifted downward from model year 2016 target lines to achieve the 3%/year (for the "lesser stringency alternative") and 6%/year (for the "greater stringency alternative") new vehicle fleet GHG emission rates for model years 2017 through 2025. Figure III-A-5-6 shows the two alternatives that were considered for lesser and greater GHG stringency. The proposal, as described above, takes the fleet from 251 gCO_2/mi in model year 2016 to 166 gCO_2/mile in 2025. The lesser stringency case, at a 3% per year reduction in GHG emissions, would result in a 191 gCO_2/mile emission rate, and the greater stringency case, at a 6% per year reduction, results in 144 gCO_2/mile.

Figure III-A-5-6. Proposed model year 2017-2025 GHG standards, with alternative stringency cases



Table III-A-5-12 shows the differing levels of technology deployment that would be projected under the lesser, proposed, and greater GHG stringency alternatives for model years 2016, 2020, and 2025. As described above, under the proposal scenario for GHG and ZEV implementation, advanced hybrid and electric-drive vehicle technologies would represent shares of 14% in 2020 and 22% in 2025. For the lesser GHG stringency case, the projected amounts of these advanced technologies would drop to 12% in 2020 and 19% in 2025. Under the greater GHG stringency case, the shares of these advanced technologies would increase to 19% in 2020 and 31% in 2025. Similarly the amounts of conventional technology (e.g., direct injection, mass reduction, cooled EGR) would be reduced in the lesser GHG stringency case and increased in the greater GHG stringency case.

Table III-A-5-12. Percent of new vehicles with given technology for proposal compliance scenario – and lesser and greater GHG stringency alternatives

Scenario	Technology	Percent of vehicles with technology by model year		
		2016	2020	2025
Alternative: Lesser stringency (3%/year) GHG regulation	Aerodynamics (10%+)	61%	77%	93%
	Low RR tires (10%+)	61%	77%	93%
	Mass reduction (10%+)	11%	13%	16%
	Dual clutch transmission	38%	43%	47%
	Gasoline direct injection	33%	30%	27%
	Cooled EGR	0.2%	1%	1%
	Hybrid	4.5%	3.8%	3.2%
	Plug-in hybrid electric vehicle	1.7%	5.4%	9.3%
	Electric vehicle	0.4%	2.3%	3.7%
	Fuel cell vehicle	0.1%	0.6%	2.5%
	Alternative refrigerant	0%	100%	100%
Proposed GHG and ZEV regulations (~4.5%/year GHG reduction from 2016-2025)	Aerodynamics (10%+)	61%	79%	100%
	Low RR tires (10%+)	61%	79%	100%
	Mass reduction (10%+)	11%	27%	46%
	Dual clutch transmission	38%	47%	56%
	Gasoline direct injection	33%	41%	51%
	Cooled EGR	0.2%	6.3%	14.5%
	Hybrid	4.5%	5.2%	5.7%
	Plug-in hybrid electric vehicle	1.7%	5.4%	9.3%
	Electric vehicle	0.4%	2.3%	3.7%
	Fuel cell vehicle	0.1%	0.6%	2.5%
	Alternative refrigerant	0%	100%	100%
Alternative: Greater stringency (6%/year) GHG regulation	Aerodynamics (10%+)	61%	81%	100%
	Low RR tires (10%+)	61%	81%	100%
	Mass reduction (10%+)	11%	39%	67%
	Dual clutch transmission	38%	50%	61%
	Gasoline direct injection	33%	55%	76%
	Cooled EGR	0.2%	18%	35%
	Hybrid	4.5%	10.0%	14.4%
	Plug-in hybrid electric vehicle	1.7%	5.4%	9.3%
	Electric vehicle	0.4%	2.7%	4.4%
	Fuel cell vehicle	0.1%	0.7%	2.6%
	Alternative refrigerant	0%	100%	100%

Figure III-A-5-7 illustrates the resulting overall incremental price increase due to the proposed regulatory GHG standards, along with the lesser and greater GHG stringency cases. The three cases incorporate the implementation of the ZEV regulation, along with conventional and hybrid gasoline technologies, to achieve compliance with the varying GHG stringency levels. The figure shows the incremental price increase from the proposed regulations from 2016 through 2025, when the total projected GHG-plus-ZEV price increase is $1840 per vehicle. Also shown is the lesser and greater stringency cases that result in approximately $1370 and $2630 incremental price increases per vehicle, respectively. These average price increases include the ZEVs that are higher cost (at a $8000+ price premium) as well as the non-ZEVs (that more typically have an approximate $1000 price premium). The staff GHG proposal, at approximately a 4.5%/year annual stringency over the 2016-2025 period, was ultimately determined based on meeting the joint statutory requirements of USEPA, NHTSA, and ARB; discussions with the automobile industry; and achievement of the maximum feasible cost-effective GHG emission reduction level.

Figure III-A-5-7. Incremental vehicle price for GHG-plus-ZEV programs for proposed regulation and two alternative GHG stringency cases (relative to no new GHG and ZEV policies beyond model year 2016)



5.8. Analysis of Vehicle Manufacturing GHG Emissions

Staff has analyzed the potential effect that the technologies promoted by the standards could have GHG impacts outside of their immediate test cycle and fuel production GHG emissions. In particular, the standards will promote a variety of mass-reduction technologies that could introduce advanced materials (e.g., high-strength steel and aluminum) that have differing manufacturing GHG emissions compared to conventional vehicle materials that are now in use. In addition, the GHG standards and the ZEV program will promote increased use of batteries and other electric-drive components that might have different manufacturing GHG impacts.

As identified above, the mass of vehicles designed to meet the standards are projected to reduce by about 9% on average in the 2020-2025 timeframe. Because of the footprint-indexed design of the standards, this level of mass-reduction is expected to result from the use of advanced materials and optimized vehicle design and without requiring vehicle shifts in size, class, or utility.

Figure III-A-5-8 shows the spread of available data on production cycle GHG emissions to manufacture vehicles of different technologies with data from three sources (Kim et al, 2010; ANL, 2007; Patterson et al, 2011). The data have been normalized to an average 3700-lb vehicle curb weight in order to represent the approximate average vehicle in the California (and US) new vehicle fleet. The amounts and types of technology considered by staff in this analysis for 2025 vehicles are generally within the "conventional mass-reduction" part of the data (primarily new steel and aluminum parts), and therefore have no clear manufacturing GHG difference from the baseline. Hybrid and electric-drive vehicles appear to potentially add several tons per vehicle of production-cycle GHG emissions.

Figure III-A-5-8. Vehicle production cycle GHG emissions from various technologies



Figure III-A-5-9 puts these manufacturing GHG emission results in context of the lifetime GHG emissions of a vehicle. The lifetime GHG emissions from the lifetime operation of a model year 2008 baseline vehicle are about 66 tons CO_2e at the vehicle tailpipe (plus another 16 tons in the upstream fuel processing upstream), as compared to their manufacturing GHG emissions at roughly 6-8 tons. Greater use of high-strength steel and aluminum to achieve the modest reductions in vehicle weight projected to comply with the proposed GHG standards may not increase production-cycle emissions, as indicated by the literature above. Although electric-drive technologies may increase manufacturing emissions by several CO_2e tons per vehicle, these technologies' substantially reduced operating emissions will more than offset the increase in manufacturing emissions, as shown in Figure III-A-5-9. The figure also includes upstream fuel production emissions based on California LCFS assumptions for gasoline and future electricity and hydrogen, as previously discussed. Although the upstream manufacturing cycle emissions are uncertain, this assessment suggests that manufacturing cycle emissions' vehicle contribution as a percentage of total vehicular GHGs could approximately increase from roughly 8% today to roughly 15% for new vehicles in 2025 (i.e., for the GHG plus ZEV scenario).

Figure III-A-5-9. Vehicle use, upstream fuel, and production cycle GHG emissions of an average mid-size vehicle



5.9. Sensitivity Analysis

One uncertainty of the GHG standard outcome is due to the inherent regulatory structure, though history suggests that appropriate safeguards can be developed to ensure projected GHG reductions. Because the standards have two categories with different standards and footprint-indexed standards for each category, different compliant 2025 fleet mixes would have substantially varying final gCO_2/mile outcomes. ARB staff has analyzed the potential for a varying outcome of the standards based on shifts in the car-truck mix and shift in the fleet-average footprint size (within the car and truck categories). These category and size trends are of interest because these factors can tend to shift over time based on fuel prices, larger economic trends, and automobile manufacturing and marketing trends. In addition, ARB staff is cognizant of the potential for strategic re-categorization of crossover vehicle models that exhibit many car-like features but could be increasingly categorized as trucks (for example based on the presence of four-wheel drive, or a third row of seats). This is an increasing potential concern over time, especially because the truck standards receive less-stringent percent GHG reductions from 2016 to 2025 than the car standards. Figure III-A-5-10 illustrates the difference in the footprint-indexed standards for cars and trucks in 2025. These standards effectively permit 29-30 gCO_2/mile less stringent standards for the smallest trucks that are primarily car-platform-derived crossover models (e.g., Honda CR-V, Toyota RAV4, Ford Escape). For example, a 45-ft^2 crossover would have a 144-gCO_2/mile standard target as a car and a 174-gCO_2/mile standard if classified as a truck.

Figure III-A-5-10. Difference between car and truck GHG standard target lines in model years 2016 and 2025



Figure III-A-5-11 summarizes the ARB staff analysis of potential fleet trends that could result from modest footprint and category shifts over the rulemaking period. To examine the potential future mix of the car-truck split, ARB considers 70% cars (the highest national car share since 1988) as a reasonable upper bound. In the other direction, ARB staff considers 55% trucks as a potential upper bound (based on 52% national light-duty truck share in 2004). There is only limited available data from 2008-2010 on average new vehicle footprint, since the footprint-indexed standards have only recently taken effect. With limited data, modest and plausible shifts in average new vehicle footprint (ft^2) by 0.2% per year are considered here in the staff analysis. The new vehicle fleet footprint and car-truck mix shifts, in turn, result in greater or lesser GHG targets, according to where the vehicle models fall on the footprint-indexed GHG target lines. The result of plausible long-term footprint and car-truck category trends would be to shift the reference case 166 gCO_2/mile 2025 standard target up to 179 gCO_2/mile (a 16% loss in GHG reductions from the 2016 level) or as low as 157 gCO_2/mile (a 11% increase in GHG reductions from the 2016 level).

Figure III-A-5-11. Potential shift in the projected fleet GHG emission outcomes based on trends in vehicle footprint and category mix



Based on this analysis, ARB staff considered various anti-backsliding provisions within the regulations. The intent of any such alternative anti-backsliding provisions would be to not allow overwhelming consumer trends (and automakers' influence on them) or automaker attempts to strategically "game" the regulation's flexibility for GHG regulatory advantage that would undermine the program's intended GHG benefit. The primary mechanisms for potential program GHG emission losses include the potential shift to a higher truck sales share and increases in average car and truck footprint. As a result, per-company anti-backsliding provisions could be structured and triggered in the event of a company surpassing threshold upsizing trends in these two areas. For example, hypothetically, if a company's fleet shifts by over a 5% truck share (e.g., from 45% truck to 50% truck) or if sales-weighted car or truck footprint shifted upward by 5% (e.g., from 40 ft^2 to 42 ft^2) the alternative standards could be triggered. The alternative anti-backsliding provisions could be structured to disallow any further GHG regulatory advantage for surpassing any such hypothetical car-truck or footprint upsizing thresholds. Such a provision would ensure the highest GHG emission scenario (i.e., with a 16% loss in intended GHG emission reduction) in the above figure could not be realized.

ARB staff is not proposing anti-backsliding provisions at this time. As a result of ARB's investigation of the potential for consumer trends and strategic re-categorization of crossover cars as trucks over time, ARB is inclined to follow these trends and categorization shifts closely in years ahead. ARB staff notes that many, but not all, automakers indicated that they are not intending to shift their sales upward in size or category over the rulemaking period through 2025. Nonetheless, the extent to which the future fleet trends move toward larger average vehicle sizes and/or more trucks than projected in this analysis could significantly undermine the expected GHG benefits. ARB staff proposes to require detailed certification data reporting on new vehicle attributes in order to closely follow these trends. Staff proposes to report to the Board on a periodic basis to the extent to which there are significant deviations from the projected fleet size and category mix. This requirement would remain even if ARB

decides to allow manufacturers to use compliance with national standards to satisfy ARB requirements in the 2017 through 2025 timeframe.

ARB staff notes that its use of GHG ratings that integrate electric-drive vehicles into the standards according to their incremental upstream GHG emissions differs from the expected federal program. The USEPA GHG program has proposed that battery electric vehicle, plug-in hybrid electric vehicle, and fuel cell electric vehicle technologies be credited for compliance purposes as if they had zero GHG emissions for model years 2017-2021, and USEPA would apply sales caps after which automakers would be required to count non-zero upstream emissions for later years. The proposed federal sales caps would allow up to 600,000 ZEV-type vehicles per manufacturer to be credited as having 0 g/mi GHG emissions in 2022-2025 model years (see USEPA and NHTSA, 2011b for details). Within a national context there are expected to be significantly lower shares of electric and fuel cell vehicles than in California, and therefore the potential for lost program GHG emission reductions due to an artificial credit incentive is lower in percentage terms. Also, there are higher national grid GHG emissions, and therefore any non-zero upstream crediting serves as a lesser relative incentive for battery electric vehicle and plug-in hybrid electric vehicle deployment than the proposed ARB GHG crediting based on California's low-GHG grid.

Therefore, crediting these vehicles at 0 gram per mile is being proposed for federal GHG regulatory purposes for 2017-2021 (without limits) and for 2022-2025 (with company-specific limits). Note that although the emissions are counted in the federal regulation as zero gCO_2e/mile for compliance purposes, the upstream emissions are accounted for separately in the full federal inventory accounting. ARB staff projects that with the successful implementation of the ZEV program in California and ZEV-adopting Section 177 states, that the federal USEPA caps for zero gCO_2e/mile crediting will be met before 2025. As described above in the development of the upstream accounting provisions, the California context (primarily due to the ZEV regulation) obviates the need for advantageous incentive crediting for these ZEV technologies.

Also, federally, these plug-in hybrid electric vehicle, battery electric vehicle, and fuel cell electric vehicle vehicles are granted additional incentives through multipliers (whereby each vehicle is counted as more than one vehicle) for 2017-2021, as shown in Table III-A-5-13. As with the zero upstream crediting, staff is not proposing to include these multiplier incentives that will be part of the federal GHG program. These multipliers would allow each of these advanced electric-drive vehicles sold to be counted as more than one vehicle for compliance accounting purposes. ARB staff proposal does not include these multipliers in the calculations for the same reasons that the 0 g/mi ZEV crediting is not utilized. In both cases, the existence of the ZEV regulation along with low California upstream emissions eliminate the need to provide such incentives that do not directly result in further GHG reductions.

Table III-A-5-13. Federal advanced electric-drive vehicle technology multiplier incentive

Technology	2017	2018	2019	2020	2021	2022-2025
Plug-in hybrid vehicle	1.6	1.6	1.6	1.45	1.3	1.0
Electric vehicle	2.0	2.0	2.0	1.75	1.5	1.0
Fuel cell vehicle	2.0	2.0	2.0	1.75	1.5	1.0

In addition, ARB staff is proposing to adopt the special pickup truck incentive credits of 10 and 20 gCO_2/mile (for hybrid and non-hybrid innovations). ARB staff has analyzed these provisions in order to evaluate the relative national GHG program losses associated with the use of these technology incentives toward automaker compliance. The 0 gCO_2/mi provision results in lost GHG emission reductions on account of the ignored upstream GHG emissions associated with the primary fuel transportation, processing, electricity generation, and distribution. The 0 gCO_2/mi provision results in increasingly greater losses in GHG reductions with greater amounts of battery electric vehicles, plug-in hybrid electric vehicles, and fuel cell electric vehicles in the fleet. The relatively low upstream GHG emissions in California reduce the extent of the loss from this provision from California vehicles. The multipliers mentioned above for these electric-drive vehicles would result in program GHG losses through the early program years, model years 2017-2021, but without any loss in the overall gCO_2/mile outcome in model year 2025. The hybrid full-size pickup credit is limited in its potential lost GHG emission reduction, because qualifying full-size pickups represent less than 10% of all the light-duty vehicles in California.

Table III-A-5-14 summarizes the extent to which the three provisions could affect the GHG program outcomes in the new California fleet. The lost GHG program emissions from the 0 g/mi battery electric vehicle/plug-in hybrid electric vehicle/ fuel cell electric vehicle incentive are estimated according to the GHG upstream emissions those vehicles would incur based on California GHG emission factors for 2020 and beyond electricity and hydrogen (both 33% renewable sourced). Due to the 0 g/mi incentives, the standards that would achieve 4.51%/year GHG emission reductions (without any such incentives), are estimated to achieve 4.34%/year, resulting in a 3.7% loss in the overall cumulative 2017-2025 GHG reductions that would have been achieved if (a) the battery electric vehicle/plug-in hybrid electric vehicle/ fuel cell electric vehicle had true upstream accounting or (b) if automakers complied without using any battery electric vehicle/plug-in hybrid electric vehicle/ fuel cell electric vehicle technology. The other two provisions, the battery electric vehicle/plug-in hybrid electric vehicle/ fuel cell electric vehicle multiplier and the pickup truck hybrid credit would have relatively minimal potential impact in eroding the intended GHG reductions from the standards over the 2017-2025 MY period.

Table III-A-5-14. Potential effect of electric and hybrid vehicle incentives on the California fleet

	Proposal without incentive provisions	Regulatory incentive provisions		
		With 0 g/mi BEV/PHEV/FCV	With 0 g/mi BEV/PHEV/FCV and multipliers	With 0 g/mi, multipliers, and pickup technology credit
Model year 2021 GHG (gCO_2e/mi)	201	203	204	204
Model year 2025 GHG (gCO_2e/mi)	166	169	169	170
Equivalent average annual GHG stringency for model years 2016-2025	4.51%	4.34%	4.31%	4.24%
Cumulative GHG program loss from 0 g/mi	-	3.7%	-	-
Cumulative GHG program loss from BEV/PHEV/FCV multiplier	-	-	0.8%	-
Cumulative GHG program loss from pickup technology credit	-	-	-	1.6%

Notes: losses from 0 g/mi are compared against the emissions that would have been counted under ZEV deployment with California upstream GHG emission factors for 2020 and beyond (i.e., 33% renewable sourced); the pickup technology credit is assumed to be utilized by 7% of the fleet for 15 gCO_2/mi credit.

5.10. Compliance with the Emission Standards

The proposed climate change emission requirements are comprised of three emission standards; a CO_2 standard, a CH_4 standard and a N_2O standard. Whereas more detail on a number of the technical provisions was given above, a simplified description of compliance with these emission standards is described here. To demonstrate compliance with these standards, manufacturers will need to report the CO_2, CH_4 and N_2O emissions of their vehicles over the combined city and highway vehicle testing drive cycles. The combined city and highway emission value is a weighted emission value determined by the following formula:

Combined city/highway emissions = 0.55 x city emissions + 0.45 x highway emissions

CO_2 Emission Standard

As described above in section III.A.5.1, the CO_2 standards are based on a set of footprint curves that assign specific CO_2 targets for each vehicle model depending on the footprint (the area described by wheelbase times the average track width of the vehicle) of the vehicle model. The CO_2 targets defined by the footprint curves become increasingly more stringent for each model year from 2017-2025. Separate sets of footprint curves have been developed for passenger cars and for light-duty trucks. The footprint-indexed target lines have "kinks," whereby all vehicles below a given size each receive the minimum target for that year and all vehicles above a given size each receive maximum targets for that year. For most vehicles (i.e., those between the GHG kinks), the CO_2 target is calculated by a simple linear expression and determined by the following formula.

$$\text{Target } gCO_2/\text{mile} = [a \times f] + b$$

Where: f is the vehicle footprint and coefficients a and b are selected from the table of coefficients for the footprint curve for either passenger cars or light-duty trucks for the applicable model year.

A manufacturer's CO_2 emission standard is determined by the sales weighted CO_2 target for a manufacturer's vehicle models and will vary between manufacturers depending on the specific mix of their vehicle models. Accordingly, a manufacturer's CO_2 standard can be expressed with the following formula:

$$CO_2 \text{ standard} = \frac{\sum_0^i CO_2 \text{ target value x model type production}}{\text{Total vehicle production}}$$

Where: i = each unique combination of model type and footprint value
Model type production = total production of model type/footprint
Total vehicle production = total production of passenger cars or light-duty trucks and medium-duty passenger vehicles, as applicable

To comply with the CO_2 standard a manufacturer may certify some vehicle models above their CO_2 target as long as their excess emissions are offset by vehicle models certifying below their CO_2 target. The sales-weighted combined test cycle CO_2 emissions must ultimately be lower than the automaker's sales-weighted CO_2 standard (based on that automaker's final sales-weighted CO_2 targets by footprint) for compliance.

Credits That Can be Applied to the CO_2 Standard

Several credits are available that a manufacturer may apply to their measured CO_2 emissions. These credits include:

1. Credits for improvements to the vehicle air conditioning system; either from the use of a low GWP refrigerant or improvements to the efficiency of the system (see Table III-A-4-11 for the maximum CO_2e credit values available for air conditioning improvements)
2. Credits for technologies that reduce CO_2 emissions but are not measured on the applicable test cycles (see Table III-A-5-5).
3. Credits for technology innovations on the largest of pickup trucks (see section III.A.5.3).

These credits would be applied to the measured CO_2 emissions for each unique combination of model type/footprint incorporating these improvements.

Methane and Nitrous Oxide Emission Standards

The CH_4 and N_2O standards are standalone standards. Accordingly, each vehicle must meet the standard.

However, manufacturers that over-comply with their CO_2 standards may generate CO_2 credits to offset any debits generated by N_2O or CH_4 emissions exceeding the applicable standard. A manufacturer choosing this option would convert its measured N_2O and CH_4 emissions that are above the applicable standards into CO_2e emissions, according to their global warming potential (GWP) values (i.e., GWP of 25 for CH_4, GWP of 298 for N_2O) to determine the amount of required CO_2 emission credits. For example, a manufacturer would use 0.25 g/mile of positive CO_2 credits to offset 0.01 g/mile of CH_4 debits or use 2.98 g/mile of positive CO_2 credits to offset 0.01 g/mile of N_2O debits.

IV. CERTIFICATION GASOLINE SPECIFICATIONS

A. PROPOSED AMENDMENTS TO THE SPECIFICATIONS FOR CALIFORNIA CERTIFICATION GASOLINE

The California certification fuel used for testing exhaust and evaporative emissions on passenger cars, light-duty trucks, medium-duty vehicles, and heavy-duty gasoline engines and vehicles currently contains the oxygenate methyl tertiary butyl ether (MTBE) in the quantity of 10.8 to 11.2 volume percent (equivalent to 2.0 percent by weight). MTBE was banned for use in California gasoline starting December 31, 2003. As a result of the ban of MTBE, ethanol became the prevalent oxygenate used in California gasoline. After the ban, refiners began adding approximately 5.7 volume percent ethanol to gasoline, which is equivalent to 2.0 weight percent. California gasoline contained 5.7 percent ethanol until the end of 2009. In 2010, California refiners transitioned to producing gasoline containing 10 percent by volume ethanol (E10). Currently, all gasoline in California contains 10 percent ethanol and will continue to contain 10 percent ethanol for the foreseeable future. While the oxygenate and oxygenate amount have changed in in-use California gasoline, the certification fuel on which emission testing is being done has not. Staff is proposing a certification fuel that contains 10 percent ethanol and is representative of current in-use fuel.

1. BACKGROUND

The USEPA reformulated gasoline (RFG) requirements mandated the use of a minimum average oxygen content (2.0 percent by weight) year-round in USEPA RFG areas. In California, fuel sold in the South Coast, San Diego, San Joaquin Valley, and the Sacramento regions must meet federal USEPA RFG requirements, but can do so through the use of California reformulated gasoline (CaRFG) because the California program produces significantly greater emission reductions than the Federal RFG program. These regions account for about 80 percent of the gasoline sold in California.

To comply with the oxygen content requirement, refiners chose to use MTBE.

Soon after the implementation of Phase 2 CaRFG, the presence of MTBE in groundwater began to be reported. An investigation and public hearings were conducted resulting in the issuance of Executive Order D-5-99 on March 25, 1999, that directed the phase-out of MTBE in California's gasoline.

In response to the Governor's Executive Order, the Board approved the CaRFG3 regulations on December 9, 1999, and amended them on July 25, 2002. The CaRFG3 regulations prohibited California gasoline produced with MTBE starting December 31, 2003; established revised CaRFG3 standards; established a CaRFG3 Predictive Model; and made various other changes. The CaRFG3 regulations also placed a conditional ban, starting December 31, 2003, on the use of any oxygenate other than ethanol, as a replacement for MTBE in California gasoline.

From December 31, 2003 to the end of 2009, California gasoline contained roughly six percent ethanol by volume. Beginning in 2010 to the present, California gasoline contains 10 percent ethanol by volume. The transition from six percent to 10 percent ethanol in California gasoline was due to two major regulations. The Energy Policy Act of 2005 (EPAct), among other things, authorized the USEPA to lift the reformulated gasoline oxygen content requirement. The removal of the two percent oxygen content requirement for USEPA RFG took effect nationwide May 6, 2006. Instead of a minimum oxygen content requirement, the EPAct established a renewable fuels standard (RFS) that requires increasing quantities of renewable fuels be consumed each year. The RFS requirements are expected to push ethanol to 10 percent by volume (E10) in gasoline nationwide by 2012.

The other regulation impacting the increase to E10 in California is the 2007 CaRFG amendments. In June 2007, ARB amended the CaRFG regulations to require the mitigation of emissions associated with permeation from ethanol in gasoline. The 2007 amendments were set to go into effect beginning December 31, 2009 and refiners found that one way to mitigate the emissions associated with permeation from ethanol in gasoline was to increase the amount of ethanol in gasoline. Increasing ethanol content in gasoline helped to decrease exhaust emissions, which helped to mitigate the emissions associated with permeation. With the impending RFS requirements increasing to 10 percent ethanol by 2012 and the 2007 CaRFG amendments requirements of mitigating emissions associated with permeation, refiners chose to go to 10 percent ethanol by volume beginning in 2010.

The current California certification gasoline properties are shown in Table IV-A-1-1, below. The current maximum ethanol content allowed in California gasoline is 10 percent by volume. California gasoline is expected to be at E10 for the foreseeable future, and the certification fuel in California needed to be updated to reflect the in-use fuel. The current certification fuel contains MTBE as the oxygenate of the fuel. Since MTBE was banned for use in California gasoline in 2003, the current certification fuel is not representative of in-use fuel. Staff has developed an E10 certification fuel representative of the current in-use fuel.

Table IV-A-1-1. Current California Certification Gasoline

Fuel Property	Limit
Sensitivity (min)	7.5
Distillation Range °F	
10 pct. point	130-150
50 pct. point	200-210
90 pct. point	290-300
Sulfur, ppm by wt	30-40
RVP, psi	6.7-7.0
Olefins, vol %	4.0-6.0
Total Aromatic Hydrocarbons, vol%	22-25
Multi-Substituted Alkyl Aromatic Hydrocarbons, vol% (max)	12-14
Benzene, vol %	0.08-1.0
Methyl tertiary-butyl ether (MTBE), vol % (max)	10.8-11.2
Ethanol, vol %	--
Total Oxygen, wt%	3.3-3.7
Octane (R+M)/2 (min)	91
Residue, vol% (max)	2.0
Phosphorous, g/gal (max)	0.005
EP, maximum	390
Lead, g/gal (max) (No lead added)	0-0.01
Additives: Sufficient to meet requirements of Title 13, CCR §2257	
Copper Corrosion	No. 1
Gum, Washed, mg/100 ml (max)	3.0
Oxidation Stability, minutes (min)	1000
Specific Gravity	Report
Heat of Combustion	Report
Carbon, wt%	Report
Hydrogen, wt%	Report

2. SUMMARY OF PROPOSED REGULATION

This section presents the staff's proposed certification gasoline and discusses the development of the proposed certification gasoline.

2.1 Proposed E10 Certification Gasoline

The proposed E10 certification gasoline specifications are shown in Table IV-A-2-1, below:

Table IV-A-2-1. Proposed E10 Certification Gasoline Properties

Fuel Property	Limit	Test Method[a]
Octane (R+M)/2	87.0-88.4[b]	D 2699-88, D 2700-88
Sensitivity (min)	7.5	D 2699-88, D 2700-88
Lead, g/gal (max) (No lead added)	0-0.01	D 3237-79[c]
Distillation Range °F 10 pct. point 50 pct. point 90 pct. point	 130-150 205-215 310-320	D 86-99aε1[c]
EP	380-420	D 86-99aε1[c]
Residue, vol% (max)	2.0	D 86-99aε1[c]
Sulfur, ppm by wt	8-11	D 2622-94 or D 5453-93[c]
Phosphorous, g/gal (max)	0.005	D 3231-73[c]
RVP, psi	6.9-7.2	D 323-58[c]
Olefins, vol %	4.0-6.0	D 6550-00[c]
Total Aromatic Hydrocarbons, vol%	19.5-22.5	D 5580-00[c]
Multi-Substituted Alkyl Aromatic Hydrocarbons, vol%	13-15	See method below[d]
Benzene, vol %	0.6-0.8	D 5580-00[c]
Methyl tertiary-butyl ether, vol % (max)	0.05	D 4815-04[c]
Ethanol, vol %	9.75-10.25	D 4815-04[c]
Total Oxygen, wt%	3.3-3.7	D 4815-04[c]
Additives: Sufficient to meet requirements of Title 13, CCR §2257		
Copper Corrosion	No. 1	D 130-88
Gum, Washed, mg/100 ml (max)	3.0	D 381-86
Oxidation Stability, minutes (min)	1000	D 525-88
Specific Gravity	Report	
Heat of Combustion	Report	
Carbon, wt%	Report	
Hydrogen, wt%	Report	

[a] ASTM specification unless otherwise noted. A test method other than that specified may be used following a determination by the Executive Officer that the other method produces results equivalent to the results with the specified method.

[b] For vehicles/engines that require the use of premium fuel as part of their warranty, the Octane ((R+M)/2) becomes a 91 minimum and the rest of the properties are the same.

[c] For ease of use, the test methods referred to in Title 13 CCR §2253.4(c) and Title 13 §2263 are labeled on this table. The actual certification fuel regulation will make references to the Title 13 CCR §2253.4(c) and Title 13 §2263 for these test methods.

[d] "Detailed Hydrocarbon Analysis of Petroleum Hydrocarbon Distillates, Reformates, and Gasoline by Single Column High Efficiency (Capillary) Column Gas Chromatography," by Neil Johansen, 1992, Boulder, CO.

There may be certain combination of properties within the proposed certification fuel ranges that may not pass the Predictive Model[32]. To prevent limiting the range of properties and to ensure the fuel is compliant with California gasoline regulations, staff is proposing that the certification fuel must also pass the Predictive Model.

2.2. Development of E10 Certification Gasoline Specifications

In order to develop a certification fuel that resembles the in-use fuel, staff used 2010 Predictive Model gasoline certifications submitted by refiners. The Predictive Model gasoline certifications represent the fuel specifications for each batch of fuel the refiner is going to produce. In California, there are eight regulated properties of gasoline: Reid vapor pressure, aromatics, benzene content, olefin content, sulfur, T50, and T90. Staff looked at the average, the standard deviation, and the range of the eight regulated gasoline properties to develop the certification fuel. Staff used the average properties as a baseline to build the fuel. Staff then entered the properties into the Predictive Model to determine ranges that would pass the Predictive Model. Staff attempted to keep the properties within the standard deviation of the average, but due to the complex relationships between the properties and emissions, some properties were forced to stray outside of their standard deviations. Table IV-A-2-2 shows a summary of the Predictive Model data used to develop the proposed certification fuel.

Staff also wanted to keep the fuel as near the pass/fail point of the Predictive Model to be true to the fuels in the market place. However, because the proposed certification fuel specifications provide allowable ranges within which fuel propertied may fall, rather than specifying a single allowable value for each property, it was very difficult to develop a set of ranges that passed the Predictive Model in all instances without making the ranges of the fuel extraordinary lenient and unrepresentative of the in-use fuel. Staff compromised and set the ranges of the proposed certification as close to the in-use data as possible, while allowing for most combinations of the properties to pass the Predictive Model. There are some combinations of fuel properties in the ranges of the proposed certification that will not pass the Predictive Model. As a result, staff has added the requirement that the certification fuel must be within the proposed ranges and must pass the Predictive Model.

[32] The Predictive Model is a set of mathematical equations that relate emission rates of exhaust hydrocarbons, oxides of nitrogen (NOx), and combined exhaust toxic species to the values of eight regulated gasoline properties. [13 CCR §2265 (and the incorporated "California Procedures for Evaluating Alternative Specifications for Phase 3 Reformulated Gasoline Using the California Predictive Model")]

Table IV-A-2-2. 2010 Predictive Model Data (Based on 586 Samples)

	RVP (psi)	Aromatics (vol%)	Benzene (vol%)	Olefins (vol%)	Sulfur (ppmw)	T50 (°F)	T90 (°F)
Average	7.14	21.11	0.79	6.91	9.01	212.10	315.40
Standard Deviation	0.62	3.50	0.12	2.22	2.90	13.26	20.33
Range	6.5-7.2	11.2-31.8	0.48-1.1	1-10	2-19	193-220	284-330

2.2.1. Octane Levels

The most common levels of octane grade on the market are 87 anti-knock index (AKI) (regular), 89 AKI (mid-grade) and 91-93 AKI (premium) [33]. The octane rating of gasoline marked "premium" or "regular" is not consistent across the country[2]. Different states define different octane grades for premium gasoline. The octane grade of premium is 93 AKI in the Federal definition and 91AKI in California. The recommended gasoline for most cars is regular octane.

Gasoline with a higher heating value (energy content) provides better fuel economy[2]. Traditionally, premium gasoline has had a slightly higher heating value than regular, and thus provides slightly better fuel economy, although that benefit is difficult to detect in normal driving. There can be even larger differences in heating value between batches of gasoline from the same refinery, between summer and winter volatility classes, or between brands of gasoline from different refineries because of compositional differences. The differences are small and there is no practical way for the consumer to identify gasoline with a higher-than-average heating value[2].

The higher the octane number in gasoline, the harder it is for the engine to "knock"—an unregulated explosion in a chamber designed for highly regulated combustion. Most modern cars, however, are designed to employ a specific compression ratio, a measure of how much room is available to the fuel/air mixture when the piston is at the bottom and the top of the cylinder. This compression ratio tolerates lower octane fuels (such as regular gasoline) without knocking[34].

Most end users prefer regular gasoline due to its lower price. According to the EIA[35], in California, among the total 5.4 million gallons per day of gasoline sold to end users in May 2011, 4.2 million gallons per day of gasoline (77%) were regular, 500 thousand gallons per day of gasoline (9%) were mid-grade, and 800 thousand gallons per day of gasoline (14%) were premium. Since the certification fuel is intended to represent in-use fuel in California, staff is basing the certification fuel on regular gasoline (87 AKI), instead of premium gasoline (91 AKI). For vehicles/engines that require the use of premium fuel as part of their warranty, the Octane ((R+M)/2) becomes a 91 AKI minimum with the other fuel properties remaining the same.

[33] http://www.api.org/aboutoilgas/gasoline/gasoline-octane.cfm
[34] http://www.scientificamerican.com/article.cfm?id=fact-or-fiction-premium-g
[35] http://www.eia.doe.gov/dnav/pet/pet_cons_refmg_c_SCA_EPMM_mgalpd_m.htm

2.2.2. Multi-substituted Alkyl-Aromatic Hydrocarbons

Staff originally proposed to remove the multi-substituted alkyl-aromatic (MSAA) specification for the certification fuel. However, stakeholders provided feedback indicating that they would prefer to see the specification remain in the certification fuel because it provided a way to ensure that specialty fuel manufactures were using refinery feedstocks rather than chemical feedstocks to produce the fuel. In order to determine MSAA, one must perform a detailed hydrocarbon analysis (DHA) on the fuel. Since DHA is not a standard part of ARB's fuels enforcement program, the DHA data on E10 fuels was limited for this specification. The limited data indicated a range of about 13-15 volume percent MSAA in the fuels sampled.

2.2.3. End Point Distillation Temperature

End point (EP) distillation temperature is another specification that is not a standard part of ARB's fuels enforcement program. Data provided by the Alliance of Automobile Manufacturers showed a California EP range of about 370-410 degrees Fahrenheit (F), with bunching around 380-390. Since measuring EP is not very accurate, staff decided to allow for a wider range of 380-420 degrees F for EP to allow for the measurement variability.

2.2.4. Sulfur

The proposed certification fuel range for sulfur is 8-11 parts per million by weight (ppmw). An upper limit of 11 ppmw was set because there was no combination of properties within the proposed ranges where a sulfur level higher than 11 ppwm would pass the Predictive Model. Staff decided to keep the minimum sulfur level at 8 ppmw because of the relationship between sulfur and expected NOx emissions. Any value below 8 ppmw in combination with properties within the proposed ranges of the certification fuel would give abnormally low predicted NOx emissions and thus, would not be representative of an in-use fuel.

2.3. E10 Certification Gasoline Application

The proposed E10 Certification Fuel changes apply only to on-road vehicles, excluding on-road motorcycles. The California on-road motorcycle regulations, California Code of Regulations (CCR), Title 13, section 1958(c), incorporate federal test procedures and federal certification exhaust test fuel requirements. The change from Federal Indolene test fuel, which is not representative of current commercial fuel, to the new E10 certification exhaust test fuel for on-road motorcycles will be accomplished in a separate, future regulatory action. As with on-road motorcycles, Board consideration of a new E10 certification test fuel for spark-ignition, off-road categories (small off-road engines, large spark-ignition engines, recreational marine spark-ignition engines, and off-highway recreational vehicles) will occur at a separate hearing.

2.4. Implementation

Staff is proposing that the phase-in requirements for E10 certification fuel be consistent with the phase-in requirements for LEV III. In addition, staff is also proposing that the E10 certification fuel would be available for optional use upon the Office of Administrative Law's filing of the LEV III rulemaking with the Secretary of State.

3. ALTERNATIVES TO THE PROPOSED E10 CERTIFICATION FUEL

This section presents an analysis of alternatives to the proposed amendments. The only alternative to the proposed certification fuel would be to leave the certification fuel unchanged with MTBE as the oxygenate. MTBE was banned for use in California gasoline starting December 31, 2003. As a result of the ban of MTBE, ethanol became the prevalent oxygenate used in California gasoline. Currently, all gasoline in California contains 10 percent ethanol and will continue to contain 10 percent ethanol for the foreseeable future. Staff determined that having engines and vehicles certified using a fuel that still contains MTBE would misrepresent the expected real-world emissions of the engines and could possibly have a negative impact on air pollution in California.[36]

V. EMISSIONS IMPACTS

A. OVERVIEW OF EMISSIONS INVENTORY METHODS

In California, the EMFAC model is used to assess emissions from on-road passenger vehicles. The latest version of the model, EMFAC2011, was released in September 2011. EMFAC2011 is comprised of three modules; the EMFAC2011-LDV module is used to calculate emissions from gasoline vehicles, diesel vehicles <14,000 pounds gross vehicle rated weight, urban transit buses, and motorhomes. EMFAC2011-LDV is informed by the latest available Department of Motor Vehicles (DMV) registration data, and vehicle miles traveled estimates from regional transportation planning agencies (RTPA). EMFAC2011-LDV estimates emissions for six vehicle classes that would be regulated under the proposed Advanced Clean Cars program, as shown in Table V-A-1.

[36] State of California, Air Resources Board, Staff Report: Initial Statement of Reasons: *Proposed 2007 Amendments to the California Reformulated Gasoline Regulations*, Release Date: April 27, 2007

Table V-A-1. EMFAC2011 Light-Duty Vehicle Categories

Vehicle Type	Vehicle Class	Gross Vehicle Weight Rating (lbs)	Curb Weight (lbs)
Passenger Car	PC or LDA		
Light-Duty Truck 1	LT1	< 6000	<3450
Light-Duty Truck 2	LT2	< 6000	>3450
Medium-Duty Vehicle	LT3 / MDV	6000 - 8500	
Medium-Duty Truck 4	MT4 / LHDT1	8500 – 10,000	
Medium-Duty Truck 5	MT5 / LHDT2	10,000 – 14,000	

In the EMFAC model, emissions are calculated as the product of a population of vehicles, the number of miles traveled per vehicle, and emission rates for each vehicle per mile. This calculation is complex, accounting for the different technologies with each model year and vehicle class, the deterioration of emission rates over time and miles driven, the difference in miles driven by vehicle class and age, and many other factors. The calculation is performed to estimate criteria pollutant emissions including reactive organic gases (ROG or NMOG), NOx, CO, and particulate matter (PM); and greenhouse gas emissions including CO_2, and CH_4. For this analysis staff used a linear regression relationship to estimate nitrous oxide (N_2O) from NOx, since N_2O is not calculated directly in EMFAC. EMFAC2011-LDV was used as the starting point for analyzing emissions for this proposed regulation. To conduct the regulatory analysis, staff used EMFAC2011-LDV output to develop several database tools to assess the potential emissions impacts of the proposed regulations on a statewide and regional basis.

The methodology used to develop database tools is based on the following equation:

Emissions = POP x TECH x ACCRL x EF

Where:

POP	Population of a vehicle of a given vehicle type and model year
TECH	The technology fraction (tech fraction) is the fraction of vehicles which meets the different emission exhaust standard categories, such as super-ultra-low-emission vehicle (SULEV), or ultra-low-emission vehicle (ULEV).
ACCRL	The annual miles that vehicles travel in a given year
EF	A measure of the amount of pollutant released per mile of travel

EMFAC2011-LDV output was separated into these components for each vehicle class, each model year (or vehicle age), and each calendar year of interest. The baseline inventory was calculated using EMFAC2011, adjusted to reflect our latest assessment of baseline technology penetration into the future, and updated with the latest available data relevant to PM emission factors. Because EMFAC2011 estimates emissions to 2035, staff also developed a long-term forecast to estimate emissions from 2035 to

2050. Benefits of the proposed regulation were calculated as the difference between the adjusted baseline inventory and regulatory scenario inventories. More details are available in Appendix T.

B. ASSESSING BENEFITS OF THE PROPOSED REGULATIONS

The proposed Advanced Clean Cars program contains many elements that will affect vehicle tailpipe emissions, including new criteria pollutant emissions standards for exhaust and evaporative emissions, new greenhouse gas emissions standards, and a mandate that manufacturers sell ZEVs. Under the proposed regulations, both criteria pollutant and greenhouse gas emissions standards are fleet average requirements. Because standards are fleet average requirements, vehicle manufacturers have the flexibility to comply using many different types of technologies in different vehicle classes. The ZEV mandate requires that ZEVs will be sold into the fleet, but the ZEVs do not provide additional emissions benefits beyond what the fleet average standards require.

To comply with the proposed Advanced Clean Cars regulations, vehicle manufacturers must sell a combination of vehicles certifying to specific emissions standards that meet a fleet-wide average regulatory target. Several new certification levels have been defined in the emissions inventory as potential compliance paths for manufacturers to meet the proposed standard. The Advanced Clean Cars program creates additional ULEV and SULEV emission certification levels in selected vehicle classes for which no testing data are available. To express these new technology groups in the database tools, staff used a ratio of standards approach. A ratio of standards approach is a technique used to estimate emission factors where no test data are available. For example, if exhaust test data are available for ULEV 50 automobiles but not for SULEV 20 automobiles, unified cycle emission factors in EMFAC for the ULEV category would be multiplied by the ratio of standards, in this case 20 mg/mi for SULEV 20 divided by 50 mg/mi for ULEV 50 to estimate SULEV 20 emission factors.

Appendix T provides the assumptions and calculation methodologies for assessing the emissions benefits of the proposed regulations.

C. ASSESSING THE IMPACT OF THE REBOUND EFFECT

The rebound effect is the phenomenon whereby consumers utilize some fraction of the energy savings from new technology to utilize a greater amount of the particular good (e.g., appliance or vehicle). In this case for vehicles, the effect would suggest that the demand for driving may marginally increase as the operating costs of the vehicle being driven are reduced. When operating costs increase, such as when fuel prices increase, driving becomes more expensive and people drive less. Conversely, if fuel prices decrease people may drive more. The overall demand for driving is a function of many factors including income, fuel prices, the distance between one's home and job, desired discretionary driving, transit options, and many other driving-related costs. Regional transportation planning agencies consider these factors that affect travel demand in the

aggregate when they estimate regional vehicle miles traveled for the EMFAC model. The proposed Advanced Clean Cars regulation would decrease vehicle operating costs of travel, as a number of the technologies that will likely be deployed to comply with the regulation would decrease the amount of fuel consumed per mile. This effect is included in the emissions inventory assessment.

The magnitude of the rebound effect is the subject of extensive academic research, which is briefly reviewed in Appendix S. Although federal agencies are applying a 10 percent rebound to their analysis, ARB's review of the literature finds the methodology developed by Hymel, Small, and van Dender (2010) to be appropriate for projecting California-specific estimates of future rebound effects. Based on this method, ARB staff estimated future projections of the rebound effect in California through CY2030 for both the baseline and policy cases ranging between 3 and 6 percent depending on the year and scenario. Staff believes that California's relatively higher income and congestion levels relative to the national average justifies the use of a different rebound assumption. California's relatively higher income and congestion levels relative to the national average justify the use of a different rebound assumption. Based on the methodology developed by Hymel, Small, and van Dender (2010) using California-specific inputs, ARB staff estimated future projections of the rebound effect through CY2030 for both the baseline and policy cases ranging between 3 and 6 percent depending on the year and scenario. Further details about the methodology and data used to estimate projected rebound levels are presented in Appendix S. These rebound effects were then translated into the percentage change in vehicle miles traveled by model year and vehicle class for new vehicles sold with and without the proposed regulation, based on the estimated percentage decrease in vehicle operating cost. The overall percentage increase in model year specific vehicle miles traveled attributable to the Advanced Clean Cars regulations ranged from between one and two percent depending on the calendar year and scenario. When these rebound rates were included in the emissions inventory, there was a loss in the regulations' overall emission reductions of around one percent.

D. EMISSION BENEFITS OF THE PROPOSED ADVANCED CLEAN CARS PROGRAM

Because the proposed Advanced Clean Cars program is in the form of emissions standards for new vehicles sold in the future, emissions benefits are initially small and increase as new vehicles replace older vehicles in the vehicle fleet. Full benefits of the program are seen over 20 years into the future as the California fleet completely turns over to Advanced Clean Cars compliant vehicles.

The Advanced Clean Cars program would provide major reductions in greenhouse gas emissions. Figure V-D-1 compares the adjusted baseline CO_2 equivalent emissions, which include benefits of the federal GHG standard compliance adopted as an option in the Pavley regulations, and the Low Carbon Fuel Standard, to estimated emissions under the proposed Advanced Clean Cars regulation. Table V-D-1 shows the greenhouse gas emission benefits in 2020, 2025, 2035, and 2050. By 2025, CO_2

equivalent emissions would be reduced by almost 14 Million Metric Tons (MMT) per year, which is 12 percent from baseline levels. The reduction increases in 2035 to 32 MMT/Yr which is a 27 percent reduction from baseline levels. By 2050 the proposed regulation will reduce emissions by more than 42 MMT/Yr, which is a reduction of 33 percent from baseline levels. Viewed cumulatively through 2050 – and assuming no further tightening of the standards after 2025 – the proposed Advanced Clean Cars regulation would reduce emissions by more than 870 Million Metric Tons CO_2 Equivalent.

Figure V-D-1. CO_2 Equivalent Emission Reductions from Advanced Clean Cars Regulations



Table V-D-1. CO_2 Equivalent (CO_2e) Emission Benefits from Advanced Clean Cars Regulations

Statewide CO_2e Emissions (Million Metric Tons / Year)				
Calendar Year	**Adjusted Baseline with Rebound**	**Proposed Regulation with Rebound**	**Benefits**	**Percent Reduction**
2020	111.2	108.1	3.1	3%
2025	109.9	96.3	13.7	12%
2035	114.8	83.2	31.5	27%
2050	131.0	88.3	42.7	33%

Table V-D-2, Table V-D-3, and Table V-D-4 provide the emission benefits (average summer day) for calendar years 2023, 2025, 2035, and 2040 for ROG, NOx, and PM2.5 respectively. Emissions benefits are initially small as the first compliant vehicles are sold into the California fleet. As time passes and more vehicles are sold, emission benefits increase. Emission benefits are fully realized in the 2035-2040 timeframe when nearly all vehicles operating in the fleet are expected to be compliant with the proposed Advanced Clean Cars standards.

By 2035 ROG emissions would be reduced by an additional 34 percent and NOx emissions by an additional 37 percent, compared to 2035 without the proposed Advanced Clean Cars rules. Under the proposed rule, the new PM2.5 standard is reduced to 3 mg/mi in 2020 and 1 mg/mi in 2028. With these standards, the net PM2.5 emissions will be essentially unchanged between 2010 and 2040 as growth in vehicle miles traveled offsets the tightening of the standard. It should be noted that the overall PM emissions from light duty vehicles are a very small fraction of the overall California PM inventory.

Table V-D-2. Statewide and Regional Emission Benefits of the Advanced Clean Cars Program (ROG)

Calendar Year	Adjusted Baseline with Rebound	Proposed Regulation with Rebound	Benefits	Percent Reduction
Statewide ROG (tons/day)				
2023	189.6	182.9	6.6	3%
2025	175.5	164.4	11.1	6%
2035	141.1	93.6	47.4	34%
South Coast Air Basin ROG (tons/day)				
2023	72.9	70.3	2.6	4%
2025	68.9	64.7	4.2	6%
2035	56.9	41.0	16.0	28%
San Joaquin Valley Air Basin ROG (tons/day)				
2023	22.4	21.7	0.7	3%
2025	21.6	20.4	1.2	5%
2035	20.2	15.3	4.9	24%

Table V-D-3. Statewide and Regional Emissions Benefits of the Advanced Clean Cars Program: NOx

Calendar Year	Adjusted Baseline with Rebound	Proposed Regulation with Rebound	Benefits	Percent Reduction
Statewide NOx (tons/day)				
2023	201.3	185.6	15.7	8%
2025	183.6	161.2	22.4	12%
2035	136.8	86.4	50.4	37%
South Coast Air Basin NOx (tons/day)				
2023	92.5	86.4	6.1	7%
2025	85.0	76.4	8.7	10%
2035	63.8	45.1	18.7	29%
San Joaquin Valley Air Basin NOx (tons/day)				
2023	31.3	29.2	2.1	7%
2025	29.0	25.9	3.1	11%
2035	23.3	16.2	7.1	30%

Table V-D-4. Statewide and Regional Emissions Benefits of the Advanced Clean Cars Program: PM2.5

Calendar Year	Adjusted Baseline with Rebound	Proposed Regulation with Rebound	Benefits	Percent Reduction
Statewide PM2.5 (tons/day)				
2023	26.7	26.0	0.6	2%
2025	27.2	26.3	0.9	3%
2035	29.7	26.8	2.9	10%
South Coast Air Basin PM2.5 (tons/day)				
2023	10.5	10.3	0.2	2%
2025	10.7	10.3	0.3	3%
2035	11.3	10.2	1.0	9%
San Joaquin Valley Air Basin PM2.5 (tons/day)				
2023	3.0	2.9	0.1	2%
2025	3.1	3.0	0.1	3%
2035	3.7	3.4	0.3	9%

E. FUEL CYCLE EMISSIONS

As projected by staff, compliance with ZEV and LEV III regulations will involve increased deployment of advanced technologies, some of which will involve alternative fuels that result in some emissions at sources associated with fueling the vehicle fleet, but that are outside the direct purview of the regulation. While such "upstream" emissions are still generally less than those associated with conventional gasoline use, a full emissions analysis accounts for them. As described in section III.A.5, the design of the LEV III GHG standards directly integrates the relative upstream GHG impacts of electricity- and hydrogen-powered vehicles compared to conventional petroleum combustion vehicles. Those regulatory provisions would mitigate the risk of unintended GHG emission increases upstream that would otherwise undermine the program GHG goals due to the increased deployment of ZEV-type vehicles. This section provides additional analysis exclusively on technologies' upstream fuel-cycle and vehicle manufacturing-cycle impacts for GHGs and criteria pollutants.

This section summarizes additional staff life-cycle analysis, with greater detail on the upstream GHG emissions and local criteria pollutants from the various vehicle technologies that are likely to be deployed for compliance with the standards. Beyond the various vehicles' direct tailpipe emissions, staff considers the lifecycle emissions that are inherent to the delivery of gasoline, electricity, and hydrogen to vehicles. Staff notes that there is the potential that other alternative fuel vehicles (e.g., vehicles that utilize diesel fuel and compressed natural gas) could be utilized to contribute toward compliance with the proposed LEV III-GHG-plus-ZEV regulatory compliance. However, staff focuses this assessment of the lifecycle emission impacts on the same primary technical compliance scenario considered above for regulatory compliance with

advanced gasoline, electric, and hydrogen fuel cell technologies. Also included in this analysis are the potential upstream impacts from vehicle production-cycle effects and the rebound effect of increased vehicle travel.

As part of California's Low Carbon Fuel Standard (LCFS), ARB staff has extensively researched the lifecycle impacts of transportation fuels. As part of the LCFS, ARB developed the CA-GREET lifecycle emission modeling tool (CARB, 2009a). The CA-GREET tool was developed from the state-of-the-art Argonne National Laboratory model that is used by researchers around the world, but the model was subsequently adapted for the particular emissions characteristics of California. From the CA-GREET tool, upstream pollutant emission factors have been extracted for this analysis in order to ensure consistent emissions assumptions across ARB's interrelated vehicle and fuel programs. This section investigates the associated upstream emission impacts of the "no new policy" and the proposed LEV III-GHG plus ZEV 2025 scenarios, with the use of emissions estimations from the CA-GREET model.

As analyzed above and illustrated in Figure V-E-1, staff's analysis projects that the California light-duty vehicle fleet will move from nearly all gasoline-fueled vehicles (including gas-electric hybrids) in 2010 to approximately 15% of new 2025 vehicles that can be powered by electricity or hydrogen (including BEVs, PHEVs, and FCVs); as such, these technologies are included here in this upstream analysis of the LEV/ZEV-compliant new vehicle fleet. This ARB staff proposal would modify existing regulations for GHG emissions, oxides of nitrogen (NO_x), hydrocarbons (specifically NMHC), and particulate matter (PM); therefore, these are the pollutants that are examined. This analysis looks at these vehicles from an overall fleet perspective, including the new 2017-2025 vehicles gradually displacing older, retiring vehicles in the fleet.

Figure V-E-1. Projected technology mix for new vehicle fleet in compliance with proposed LEV and ZEV regulations



The primary step in this analysis involves the estimation of upstream emission factors associated with each unit of fuel (i.e., gasoline, electricity, hydrogen) production. Those upstream fuel-related emission factors, which include processes of extracting, refining, and transporting the final fuel or energy carrier, are shown in Table V-E-1. The California GREET model offers estimations on urban versus non-urban emissions to help differentiate where those emissions occur (e.g., mining facilities away from population centers, versus plants and transportation effects that are within urban areas). However, staff notes that there is significant uncertainty about the extent to which the emissions are likely to occur in California or elsewhere, although they are all conservatively included in this assessment.

Table V-E-1. Fuel-related upstream (well-to-pump) emission factors assumed, 2020-2025 fuel production pathways in California

	Emission	California reformulated gasoline (g/gallon)	Electricity (g/kWh)	Hydrogen (g/kg H_2)
Total	VOC	2.82	0.02	1.42
	NOx	2.46	0.09	7.16
	PM2.5	0.29	0.02	1.74
	GHG	2655	270	9132
Urban	VOC	2.18	0.01	0.09
	NOx	0.20	0.03	0.91
	PM2.5	0.005	0.005	0.367
Non-urban	VOC	0.63	0.01	1.33
	NOx	2.26	0.06	6.25
	PM2.5	0.29	0.01	1.37

Emission factors assumed for 2020-2025, based on CA-GREET1.8b, EEE, 2010b

Staff notes several assumptions regarding its consideration here of future electricity energy sources. Although above in section III.A.5 the compliance standards for GHG emissions were based on average GHG emissions from an RPS-compliant power sector (from EEE, 2010a), this analysis assumes a more conservative (i.e., worst case, higher-emission) scenario for marginal criteria pollutant emissions from power plants. In this analysis of upstream criteria pollutant emissions, electric vehicles are all assumed to be charged from a mix of marginal power plant power sources of 67% natural gas power plants and 33% renewable (therefore not utilizing base-load large hydroelectric, nuclear, or coal plants). The various upstream criteria pollutant emission factors, transmission and distribution line losses, and energy production and extraction emissions are all based on CA-GREET modeling.

A number of assumptions were made for this analysis, along with the use of California GREET upstream criteria pollutant emission factors. Staff notes a number of caveats related to the relative lack of certainty on future California upstream emission factors. First, staff utilizes the "total" emissions as shown in the above table, whereas, the "urban" emissions may be more relevant from an inventory and public health perspective. Second, the upstream emission effects are conservatively assumed to be in California, whereas some emission impacts are in distant primary energy extraction operations around the world.

As a result of this analysis, staff recommends that the California GREET model be updated over time to include improved upstream emission factors for non-GHG pollutants that better reflect new projected hydrogen and electricity developments, as well as differentiation of whether emissions are in-state or not. At present, ARB staff has made simple, conservative assumptions for these emission factors, assuming they occur in California.

In addition to the fuel cycle emission factors, the manufacturing cycle emissions are examined. As described above the literature on vehicle manufacturing cycle GHG emissions is varied, but it suggests that incremental near-term mass reductions (up to 10-15% mass reduction) could result in no net changes upstream emission reductions; however, advanced electric drive technologies appear to be associated with greater upstream emissions than gasoline vehicles (Kim et al, 2010; Patterson et al, 2011; ANL, 2007). Table V-E-2 shows the assumed vehicle manufacturing-cycle emission factors used in this assessment. With the average 2020-2025 new gasoline vehicle having an 8-9% mass reduction (as above, for the compliance scenario analysis), these advanced gasoline vehicles are expected to have marginally lower manufacturing-related emissions; however, ZEV-type vehicles are expected to have higher manufacturing-cycle emissions. ARB staff acknowledges high uncertainty in the data for manufacturing GHG emissions, and even scarcer data on the local air pollutants associated with manufacturing various vehicle technologies. As a result, several simplifying assumptions were used (e.g., EVs were assumed to have the same upstream manufacturing criteria pollutant emissions as HEVs, due to lack of data).

Table V-E-2. Vehicle production-cycle emission factors assumed (gram/vehicle)

	Gasoline baseline	Gasoline LEV III (2017-2025)	Electric vehicle	Fuel cell vehicle
GHG	6,850,104	6,031,041	11,019,731	9,771,084
VOC/HC	1,658	1,573	1,620	1,710
NO x	6,808	6,363	7,262	10,303
PM2.5	4,481	4,154	4,668	5,187

Based on GREET 2.7 (ANL, 2007); Kim et al, 2010; Patterson et al, 2011

Figures V-E-2 and V-E-3 show NO_x and hydrocarbon (HC) emission upstream emission effects from the various processes on a ton per year basis in calendar year 2030. To emphasize, these figures are showing only upstream emissions (i.e., excluding tailpipe exhaust emissions). For hydrocarbons, volatile organic compound (VOC) emissions are tracked in GREET and are shown in the figure, whereas the similar regulated hydrocarbon pollutant in LEV III is NMOG. The vehicle manufacturing production-cycle upstream emissions are also included, as assessed in the section above, related to the use of advanced materials, EV, and FCV technologies. The figures for NO_x and HC both show similar results. From baseline 2030 upstream emissions, there are small increases in emissions due to vehicle manufacturing, electricity generation, and hydrogen production from the proposed LEV III and ZEV program. However, the reduced petroleum upstream emissions fully offset the increases from manufacturing and fuel production factors for both NO_x and HC emissions. As illustrated in the figures, the changes in upstream emissions are -11% for NO_x and -17% for HC from their baseline upstream emission levels from the fuel and vehicle production cycles.

Figure V-E-2. Potential impact on upstream NO_x emissions from vehicle and fuel production



Figure V-E-3. Potential impact on upstream hydrocarbon emissions from vehicle and fuel production



Figure V-E-4 shows the upstream PM effects (i.e., excluding tailpipe emissions) of the different factors in calendar year 2030. The impact of the upstream effects of the vehicle manufacturing production-cycle and fuel production processes is found to be relatively small, with a net impact of -4%. The same as for the NO_x and HC cases above, the largest upstream effect is the reduced upstream gasoline production PM emissions.

Figure V-E-4. Potential impact on upstream PM emissions from vehicle and fuel production in 2030



The upstream GHG emission impacts in 2030 are shown in Figure V-E-5. As was evaluated and described in the LEV III GHG compliance analysis, the GHG standards are designed to directly integrate the relative GHG impact of electric and hydrogen vehicles (versus gasoline vehicles) through straightforward provisions. This analysis in Figure V-E-5 isolates only the upstream GHG effects for the fleet in calendar year 2030.

The overall result is that the upstream GHG emission reductions from lower petroleum throughput are greater than the increases from vehicle manufacturing and electricity and hydrogen production. When just analyzing these effects that are upstream from the vehicles, the GHG emissions show an 8% GHG reduction. Staff emphasizes that the fuel-cycle GHG emissions from electricity and hydrogen production would be accounted for in the California-specific upstream compliance accounting (but would not under the proposed federal upstream 0 g/mi incentive provisions).

Figure V-E-5. Potential impact on upstream GHG emissions from vehicle and fuel production in 2030



Based on this analysis, staff finds that the regulated pollutants will have relatively small emission impacts upstream from the regulated vehicles. The upstream emission impacts are small but would result in greater emission reduction benefits than would be projected when just analyzing the vehicles. This is the result of the emission benefits of reduced petroleum upstream emissions for GHG, HC, NO_x, and PM outweighing the smaller cumulative emission increases from the vehicle manufacturing, electricity generation, and hydrogen production emissions from advanced vehicle technologies that are projected to be deployed for compliance with the proposed regulation.

Table V-E-3 summarizes the results for upstream NO_x, HC, and PM emission impacts. The analysis indicates that, in calendar year 2030, the net upstream benefits are about 31 tons/day in combined NO_x+HC reductions and about 1 ton/day of PM reduction. These upstream benefits would be in addition to those that are accounted for in the EMFAC inventory analysis above that evaluates the direct emissions from vehicle operation. The table reflects, as above, how the potential upstream benefits from the reduction in petroleum consumption more than outweigh the potential for increased manufacturing and fuel-cycle emissions from the advanced vehicle technologies that will be promoted from the proposed regulation. In addition, as discussed in the Environmental Assessment (Attachment B), these net upstream benefits would offset any emissions increase due to any unlikely delay in fleet turnover, which is not projected at this time.

Table V-E-3. Year 2030 upstream emission impacts from LEV III-GHG-ZEV scenario

Emission	Upstream emissions with no new policy (tons/day)	Effect of LEV III-GHG-ZEV regulatory package on upstream emissions (tons/day)	Upstream emission change
NOx	116.7	-13.2	-11%
HC	105.0	-17.9	-17%
PM	30.4	-1.1	-4%

These upstream emission benefits have been estimated here, outside of the EMFAC modeling in section V.D, due to the more uncertain assumptions for the upstream emission factors as outline in this section. Staff believes these upstream benefits and their underlying data basis should be studied again as more advanced vehicle technologies enter the fleet and their upstream effects become more definitively known.

For context, staff compares this section's findings for the upstream emission effects with on-road vehicle emission modeling from EMFAC. The upstream emission impacts tend to be considerably less than the on-road emissions overall, and the small upstream emission benefits found in this section would generally be an order of magnitude lower than the LEV III and ZEV vehicle programs' overall NO_x, HC, and PM emission levels. For example, the light-duty vehicle NO_x+HC emissions *at the vehicle* in calendar year 2030 from the proposed regulations were 242 tons/day, whereas the NO_x+HC net upstream emission reductions were about 31 tons/day. As a result, these upstream benefits would amount to an approximate 13% reduction from the total NO_x+HC emissions from light-duty vehicle activity in 2030. The PM net reductions of 1 tons/day in 2030 from this upstream analysis would be smaller, amounting to about a 4% reduction from the total light-duty vehicle PM emissions from the EMFAC modeling.

F. HEALTH BENEFITS ASSOCIATED WITH REDUCTIONS IN PM AND NOx EMISSIONS FROM PASSENGER VEHICLES RESULTING FROM IMPLEMENTATION OF THE LEV III AND ZEV PROGRAMS

1. OVERVIEW

Staff estimates that, statewide, implementation of the Low-Emission Vehicle (LEV III) and Zero-Emission Vehicle (ZEV) programs over the period from 2010 through 2025 will eliminate approximately 1,400 tons of PM2.5 and 40,000 tons of NO_X emissions from passenger vehicles. The estimate of the reduction of premature deaths associated with these emission reductions for both primary PM and secondary PM (produced in the atmosphere from the precursor NO_X) are presented in Table V-F-1.

Table V-F-1. Estimate of Premature Deaths from Cardiopulmonary Causes Avoided Associated with Emission Reductions from Implementation of the LEV III and ZEV Programs (2010-2025)*

Regulation	Pollutant	Avoided Premature Deaths from Cardiopulmonary Causes		
		Lower Bound (95% C.I.)	Mean	Upper Bound (95% C.I.)
LEV III and ZEV	PM2.5	140	180	230
	NO_X	190	250	300
	Total	*330*	*430*	*530*

* Health effects from primary and secondary PM are labeled PM2.5 and NO_X, respectively.

This estimate of premature deaths avoided is based on a peer-reviewed methodology used by the U.S. Environmental Protection Agency (USEPA, 2010). The methodology is fully described in ARB (2010) and is only briefly summarized in the sections below.

2. PREMATURE DEATH ESTIMATION METHODOLOGY

2.1. Overview

The incidents-per-ton (IPT) methodology is used to quantify the health benefits of directly emitted (primary) and secondary PM2.5 reductions due to regulatory controls. It is similar in concept to the methodology developed by the USEPA for similar estimations (Fann et al., 2009). The basis of the IPT methodology is the approximately linear relationship which holds between changes in emissions and estimated changes in health outcomes.

In this methodology, the number of premature deaths is estimated by multiplying emissions by a scaling factor, the IPT factor. The IPT factor is derived by calculating the number of premature deaths associated with exposure to PM2.5 from a specific source, using the C-R function described below, and dividing by the emissions of that PM2.5 source.

The IPT factors used for primary PM2.5 in this assessment were originally developed for use with diesel PM emissions, rather than emissions from the (non-diesel) passenger vehicles for which LEV III and ZEV are being proposed. However, applying diesel IPT factors to non-diesel vehicle PM emissions is justified on the grounds that emission patterns, dispersion mechanisms and loss mechanisms of primary PM from all on-road vehicular sources are expected to be similar. That is to say that a ton of PM emitted from on-road non-diesel vehicles are expected to result in the same PM2.5 exposure and health effects as a ton of emitted PM from on-road diesel trucks.

In addition to directly emitted, primary PM, motor vehicle exhaust contains NO_X, which is a precursor to nitrates, secondary PM nitrates formed in the atmosphere that can lead to an additional impact on premature death beyond those associated with directly emitted PM2.5. For secondary PM, staff calculated the health impacts resulting from the three-year average exposure to these concentrations of PM-nitrate and then associated the impacts with the basin-specific NO_X emissions to develop basin-specific factors (IPT). The basin-specific factors and emissions were applied to each air basin to estimate health benefits.

2.2. Concentration-Response Function

Calculation of the change in premature deaths associated with changes in PM2.5 exposure requires a C-R function, population data, baseline death rates, and the change in concentration of PM2.5. These data are available in a spreadsheet as part of the rulemaking package. Calculations were made based on both primary and secondary PM2.5 exposure. The sources and derivation of these parameters are described below. The equation is:

$$\Delta Y = -y_o * \left[e^{-\beta * \Delta PM} - 1\right] * pop$$

Where:

ΔY = Change in number of premature deaths associated with change in PM2.5 concentration;
y_o = Baseline all-cause death rate for age 30 and above (CDPH);
β = Beta coefficient derived from the relative risk of epidemiologic study;
ΔPM = Change in PM2.5 concentration; and
Pop = Population age 30 or above (US Census Bureau).

The spatial resolution of the underlying data is at the census tract-level with the exception of the baseline death rate, which is at the county level. Estimates of premature deaths are calculated at each census tract in California, and aggregated to county, air basin and statewide levels.

The C-R function relates changes in PM2.5 (ΔPM) exposure to changes in premature death (ΔY). The amount of change is characterized by the coefficient Beta (β). It is derived from the relative risk of deaths associated with changes in annual average PM2.5 concentration published in epidemiological studies. In this case, we are using Krewski et al. (2009), as described by USEPA (2010).

The C-R function is applied as the percent change in the all-cause death rate (y_o) per 10 $\mu g/m^3$ change in PM2.5. We use death rates by county for 7 age brackets (30-34, 35-44, 45-54, 55-64, 65-74, 75-84, 85+).

We assumed that the C-R function was linear down to a concentration of 5.7 $\mu g/m^3$ because Krewski et al. (2009) examined exposures at 5.7 $\mu g/m^3$ and above. No premature deaths were estimated in census tracts where the annual average of PM2.5 was below this threshold.

2.3. Estimating Population at the Census Tract Level

Age-resolved population data at the census tract level, for the 2000 Census, were obtained from the U.S. Census Bureau (U.S. Census Bureau). These were projected to 2006-2008 using age-resolved county population projections from the California Department of Finance (CDOF).

Age-specific population growth factors for each county, for each year, were computed from the CDOF projections by dividing each county population for the target year by the county population for the year 2000. Since each census tract lies entirely in a county, these growth factors were applied to each census tract in the county, for each age group separately. Population was projected for ten-year age groups 25-34 through 75-84, and for age 85 and older.

This method of projection reflects growth in overall county population, but does not model changes in population distribution within counties, such as expansion of urban areas into surrounding rural land.

2.4. Baseline Cardiopulmonary Death Rate

Baseline death rates (y_o) were used to calculate the estimates presented in this report. There is uncertainty in these baseline rates. Often, one must assume a baseline death rate level to be consistent throughout the city or county of interest. In addition, death rate can change over time as lifestyles, income and other factors evolve. For this analysis, we used the same baseline rates that the USEPA used. Additional information was obtained from the California Department of Health Services and the Centers for Disease Control and Prevention.

Baseline death rates vary by age bracket. Death rates were estimated separately for ten-year age groups 25-34 through 75-84, and age 85 and older. Baseline cardiopulmonary death rates were estimated at the county level from individual death records for the year 2005, obtained from the California Department of Public Health (CDPH). Cardiopulmonary death was defined as ICD9 codes 161-187 and 192-214.

The county of residence of the decedent is generally not recorded in California. However, the Federal Information Processing Standards (FIPS) city code and the ZIP code were usually recorded. The FIPS city code unambiguously identifies the county, but was sometimes invalid, unrecorded, or recorded as "unknown". When the FIPS code was not available it was sometimes possible to identify the county from the ZIP code, but ZIP codes can overlap multiple counties. In cases where 90% or more of the area of the decedent's zip code lay entirely within a county, the death was assigned to that county. A handful of records included invalid dates. The breakdown of records was as follows:

County identified by FIPS code 231,181 96.6%
County identified by ZIP code 4,196 1.8%

Unidentified or invalid 3,851 1.6%

Because the county could not be determined for 1.6% of the records, the number of deaths is slightly underestimated. No adjustment was made to compensate for excluded records.

In some cases the cardiopulmonary death incidence was extremely low, because some counties have a population of only a few thousand, and the population is further subdivided into age groups. In such cases the variability of the incidence is high. However, since this represents a very small fraction of California's population the effect on statewide death estimates is negligible. Large counties show little year-to-year variability.

Baseline death rates are subject to other sources of uncertainty. For example, the baseline death rate is treated as uniform throughout the county of interest even though it is possible that the death rate varies within a county. In addition, baseline death rates can change over time as lifestyles, health care, income, and other factors evolve.

2.5. Estimating Exposure to PM2.5

As described above, the IPT factors used for primary PM2.5 for this assessment were originally developed for use with diesel PM emissions. Thus, the value for exposure to diesel PM2.5 was applied to the C-R function to estimate the health impact. Staff estimated exposure to the primary diesel PM using monitored NO_X concentration as a surrogate, as described previously (CARB 2010). To quantify impacts from secondary PM, staff developed population-weighted PM nitrate concentrations for each air basin using data from the statewide routine monitoring network for years 2006, 2007 and 2008.

In this assessment, population-weighed exposure to primary and secondary PM2.5 was estimated based on monitor-specific concentrations. Even with an extensive air quality monitoring network, the death quantification method requires estimation of exposure between monitors across a geographic area. ARB uses a standard spatial interpolation method known as inverse distance-squared weighting (Shepard, 1968; Goodin et al., 1979). This method yields reasonable accuracy in estimating pollutant concentrations near monitoring stations, although as distance from the monitoring station increases, the uncertainty in the PM2.5 concentration also increases. This method gives accurate estimates of concentration in areas with a large number of monitors with good spatial coverage and low variability in concentration. When data are sparse, however, the assumption made about the underlying variation in PM2.5 concentration, along with the choice of interpolation method and its parameters, can be critical to avoid misleading results.

To aggregate results from census tracts to larger geographical subdivisions such as counties or air basins, we used a GIS technique called areal interpolation. Areal interpolation is a procedure for translating spatial data from one set of geographical

subdivisions to another when the boundaries do not exactly overlap. Numerous variants of the technique exist, but for the purpose of this analysis the simplest form, which uses area of polygon intersection, was employed (Goodchild and Lam, 1980; Fotheringham and Rogerson, 1994).

The precision of areal interpolation based on area of intersection depends on the relative size of the geographical subdivisions, and the homogeneity of the spatial distribution of the quantity being apportioned. In urban areas, where census tracts are small and population is distributed more evenly, areal interpolation to larger subdivisions such as air basins yields relatively precise estimates. In rural areas where the population is distributed unevenly over large census tracts, estimates are less precise.

VI. ENVIRONMENTAL IMPACTS ANALYSIS

ARB is the lead agency for the proposed regulation and has prepared an environmental analysis pursuant to its certified regulatory program. The California Environmental Quality Act (CEQA) at Public Resources Code section 21080.5 allows public agencies with regulatory programs to prepare a plan or other written document in lieu of an environmental impact report or negative declaration once the Secretary of the Resources Agency has certified the regulatory program. ARB's regulatory program has been certified by the Secretary of the Resources Agency.[37] As required by ARB's certified regulatory program for the proposed regulations, the environmental analysis is included in the Staff Report: Initial Statement of Reasons (ISOR) for the rulemaking. [38]

Appendix B to the Staff Report is an Environmental Analysis that provides an evaluation of the potential for environmental impacts associated with the proposed Advanced Clean Cars Program. The proposed Advanced Clean Cars Program consists of amendments to the following regulations: Low-Emission Vehicle (LEV III), the E10 Certification Fuel, Environmental Performance Label, On-Board Diagnostics, Zero-Emission Vehicle (ZEV), and the Clean Fuels Outlet. Three separate Regulatory Notices and Staff Reports have been prepared for these proposed amendments. A single coordinated analysis of the potential environmental impacts is analyzed in Appendix B. The Environmental Analysis assesses the potential for significant long or short term adverse environmental impacts associated with the proposed actions and an analysis of those impacts.[39] In accordance with ARB's regulations, the Environmental Analysis also describes any beneficial impacts.[40] The resource areas from the state CEQA Guidelines environmental checklist were used as a framework for assessing potentially significant impacts.[41]

If comments that are received during the public review period raise significant environmental issues, staff will summarize and respond to the comments in writing. The written responses will be included in the Final Statement of Reasons for the regulation.

---

[37] State CEQA Guidelines section 15251 (d); CCR, title 17, sections 60005-60008.)
[38] CCR section 60005.
[39] CCR section 60005, subd (b).
[40] CCR 60005, subd. (d).
[41] State CEQA Guidelines, Appendix G.

In accordance with ARB certified regulatory program, prior to taking final action on the proposed regulation, the decision maker will approve the written responses.[42] If the regulation is adopted, a Notice of Decision will be posted on ARB's website and filed with the Secretary of the Natural Resources Agency for public inspection.[43]

VII. ECONOMIC IMPACTS

The climate change regulation may impact several sectors of the economy. The steps that manufacturers will need to take to comply with the regulatory standards are expected to lead to price increases for new vehicles. Many of the technological options that manufacturers choose to comply with the greenhouse gas portion of the regulation are also expected to reduce operating costs. These two responses to the regulation have combined positive and negative impacts on California businesses and consumers. The vehicle price increase will be borne by purchasers and may negatively affect businesses. However, the operating cost savings from the use of vehicles that comply with the greenhouse gas regulation will positively impact consumers and most businesses. Based on the staff analysis, the net effect of the regulation on the economy is expected to be small but positive.

The major tool used for the analysis of the economic impact of the proposed regulation is a model of the California economy developed by the University of California, Berkeley, named the Environmental Dynamic Revenue Analysis Model (E-DRAM). This chapter explains the legal requirements for economic analysis, the methodologies employed, and the results obtained. Appendix S to this report further explains the economic impact analyses.

A. LEGAL REQUIREMENTS

The legal requirements for economic analysis are included in the Government Code and the Health and Safety Code. This section summarizes the requirements that must be satisfied for economic analyses of the proposed regulations.

Section 11346.3 of the Government Code, which applies to all agencies statewide, requires State agencies to assess the potential adverse economic impacts on California business enterprises and individuals when such agencies propose to adopt or amend any administrative regulation. The assessment shall include a consideration of the impact of the proposed regulation on California jobs, business expansion, elimination or creation, and the ability of California business to compete with businesses in other states. Additionally, climate change legislation such as AB1493 and AB32 also require greenhouse gas reduction regulations to consider the potential impacts on minority and low-income communities.

State agencies also are required to estimate the cost or savings to any State or local agency and school district, in accordance with instructions adopted by the Department

[42] CCR 60007, subd (a).
[43] CCR 60007, subd. (b).

of Finance (DOF). The estimate shall include any non-discretionary cost or savings to local agencies and the cost or savings in federal funding to the State.

Finally, Health and Safety Code section 57005 requires the Air Resources Board to perform an economic impact analysis of submitted alternatives to a proposed regulation before adopting any major regulation. A major regulation is defined as a regulation that will have a potential cost to California business enterprises in an amount exceeding ten million dollars in any single year. Because the proposal is a major regulation, we have performed an economic impact analysis, which is presented in the subsequent section.

B. SUMMARY OF COMPLIANCE COST ESTIMATES

The proposed amendments would require a combination of technologies in different vehicle classes to comply with both the criteria and greenhouse gas standards. Compliance costs will vary according to the type of emission standard, which in turn varies according to the vehicle class. As shown in Table VII-B-1, not all vehicles are subject to all aspects of the proposed amendments. Our primary analysis evaluates the combined effects of all proposed amendments.

Table VII-B-1. Summary of Vehicles Subject to Proposed Amendments

	Criteria Pollutant Standards	Greenhouse Gas Standards	ZEV Amendments
Light-duty Vehicles	Yes	Yes	Yes
Medium-duty Vehicles	Yes	Only those primarily used for passenger travel	No

As discussed previously, the new light-duty criteria pollutant standards phase in beginning with MY2015 while more stringent greenhouse gas standards do not begin until MY2017 vehicles and amendments to the ZEV program would not take effect until MY2018. Thus, the proposed near term (MY2015-2016) regulations would increase the average retail prices of light-duty vehicles by $5 to $14 per vehicle to comply with the proposed criteria pollutant standards.[44] In the mid-term (MY2017-2021) vehicle prices would increase as a result of both standards for light-duty vehicles as well as the increasing share of ZEVs required. Relative to the baseline, increases for light-duty vehicles would range from $180 to $1290 per vehicle. In the long term (MY2022-2025), the price increases for light-duty vehicles relative to the baseline would range from $1,530 to $1,910. Note that these costs do not include any state or federal financial incentives currently or expected to be offered on the purchase of new alternative fuel vehicles.

The majority of MDVs would only be subject to the criteria pollutant standards during the regulatory period. Their vehicle price increases are assumed to be fixed at $82 per

[44] Note all costs are presented in year 2009 dollars.

vehicle between MY2016 and MY2025. In the earlier model years, the near-term costs, while the standard is still phasing in, would likely be lower; however due to their relatively low volumes this simplifying assumption has a negligible (but conservative) effect on the total compliance costs. A one-time cost of $300,000 in MY2016 is also attributed to the certification costs for medium-duty SFTP compliance (See Appendix P). The incremental retail prices of the new emission-reduction technology for all affected vehicles are assumed to fall at an annual rate of 2% after MY2025 once the standard is fully phased in.

These incremental technology costs from the regulation are analyzed assuming manufacturers operate in a perfectly competitive market and pass them on to consumers in full. This section annualizes these costs and estimates the corresponding operating cost savings for an analysis of impacts on the California economy. The net impact of vehicle price increases on consumers is discussed later in this section. The new light-duty vehicles have median lifetimes of 14-17 years, over which time they will provide lower operating costs. To match the costs to the years of benefits, the incremental vehicle costs are annualized over the life of the vehicles. Few medium-duty vehicles would experience any operating cost reductions from these regulations so only net costs are annualized over their median life of 20 years for inclusion in the total cost estimates.[45] Annualized incremental costs are estimated using a real discount rate of five percent based on an average of the past ten-year interest rates for new vehicle loans.

There are no expected increases in costs associated with producing the proposed E10 certification fuel. In general, staff tried to keep the width of the property ranges for each specification the same spread of the property ranges in the current certification fuel. Only sulfur and end point have different specification spreads. The spread for sulfur decreased from a width of 10 ppmw to a width of 3 ppmw. End point went from being a maximum of 390 degrees F to a range for 380-420 degrees F. Staff consulted with specialty fuel manufacturers to see if the changes in these two properties would cause any difficulties in producing the fuel. Based on input received from the specialty fuel manufacturers, staff determined that the width of the property ranges for sulfur and end point did not cause any difficulties in producing the proposed certification fuel. Since there are no expected incremental production costs for the proposed E10 certification fuel, staff does not expect any costs to small business or consumers and therefore no additional costs for compliance with this portion of the amendments are included in the economy-wide modeling.

Annualized Costs. Table VII-B-2 provides estimates of annualized costs of the proposed Advanced Clean Cars program from 2015 to 2030. The total cost was derived by multiplying new vehicle sales by the average per vehicle price increase described above. The new vehicle sales totals are based on the projected compliance scenario fitted to new vehicle registrations estimates forecast by EMFAC2011. The

[45] Note, while these proposed amendments do not directly result in operating cost savings, concurrent federal regulations improving fuel economy of medium-duty vehicles will likely result in substantial savings that would offset these compliance costs. However, we do not include these savings in this analysis.

total costs to consumers vary each year from 2015 to 2030. Annualized costs of the proposed regulations are estimated to be approximately $390 million in 2020, $1.8 billion in 2025, and $3.4 billion in 2030. The annualized cost increases over time, due to additional sales of new cars at the higher price as multiple model years are annualized over the same period. For example, the annualized cost in 2020 of $390 million reflects the annualized costs of model years 2015 through 2020. Thus, the annualized costs for each calendar year are for cumulative sales of new cars since 2015. The $1.8 billion in annualized cost in 2025 represents the cost, in 2025, of all complying vehicles sold from 2015 through 2025.

Table VII-B-2. Estimates of Total Annualized Incremental Costs of the Proposed Advanced Clean Cars Program for 2015 through 2030 (millions of 2009 Dollars)

Year	Annualized GHG Costs to PC Consumers	Annualized GHG Costs to LDT Consumers	Annualized Criteria Pollutant Costs to LDV Consumers	Annualized Criteria pollutant Costs to MDV Consumers	Total Annualized Compliance Costs	Cumulative Annualized Incremental Cost
2015	$0	$0	$1	$0	$1	$1
2016	$0	$0	$2	$0	$2	$4
2017	$16	$9	$4	$0	$29	$33
2018	$48	$15	$5	$0	$67	$100
2019	$98	$20	$6	$0	$124	$225
2020	$134	$25	$8	$0	$166	$392
2021	$176	$32	$9	$0	$217	$609
2022	$213	$36	$10	$0	$259	$868
2023	$244	$40	$11	$0	$295	$1,163
2024	$276	$44	$12	$0	$331	$1,495
2025	$270	$49	$13	$1	$332	$1,827
2026	$264	$49	$13	$0	$325	$2,153
2027	$262	$48	$12	$0	$322	$2,475
2028	$260	$48	$12	$0	$320	$2,796
2029	$258	$48	$12	$0	$318	$3,114
2030	$256	$47	$12	$0	$316	$3,430

Note: Sum of individual columns may not match totals due to rounding.

Operating Cost Savings. Many of the technologies that reduce climate change emissions will also reduce the operating costs of light-duty vehicles. The change in criteria pollutant standards is not expected to change operating costs either positively or negatively. Lifetime maintenance costs are also expected to remain the same or decline, depending on the technologies chosen by manufacturers. For example, improved containment of air conditioning refrigerant may reduce the need for mobile air conditioning servicing and therefore reduce maintenance costs to consumers. Due to a lack of comprehensive data, however, staff assumed no change in maintenance costs for the purpose of this analysis. Estimates of the average reduction in fuel-consumption-related operating cost of the new vehicles range from about 4 percent for MY2017 vehicles to over 25 percent for MY2025 vehicles. Based on these expected operating cost reductions and the projected gasoline prices shown in Table VII-B-3, estimates of annual operating cost savings from 2015 through 2030 are provided in Table VII-B-4. Additional details on these calculations are provided in Appendix S. As

shown for every dollar spent, the regulation could save consumers about $3. These savings include the expenditures on electricity and hydrogen associated with operating the greater volume of ZEVs being proposed. In cost-effectiveness terms, every ton of greenhouse gas reduction will produce a savings of $290 in 2025, which grows to $320 per ton of reduction in 2035. Although there are no savings associated with criteria pollutant emissions, as discussed in section II-A-4.3 the costs of those reductions on a per pound basis are quite low (see Table VII-B-5). In the absence of the proposed ZEV amendments the savings to cost ratio would be even greater. Figure VII-B-1 illustrates the savings-to-cost ratio in graphical form, where the difference between the two curves is shown as the shaded area. Overall, purchasers of new vehicles in 2015 and beyond would experience a significant reduction in their operating cost as a result of the proposed regulation.

Table VII-B-3. Select Retail Gasoline Fuel Prices (2009 dollars per gallon)

Year	Price
2011	$3.68
2015	$4.06
2020	$4.06
2025	$4.02
2030	$4.17

Source: Transportation Energy Forecasts and Analyses for the 2011 Integrated Energy Policy Report, Draft Staff Report, California Energy Commission. Average of high and low cases, converted from 2010 dollars using Consumer Price Index adjustment factor.

Table VII-B-4. Estimates of Total Annual Value of New Vehicle Operating Cost Savings for Advanced Clean Cars (millions of 2009 Dollars)

Year	Cumulative Annualized Incremental Cost	Operating Cost Savings	Saving to Cost Ratio
2015	$1	$0	0.0
2016	$4	$0	0.0
2017	$33	$228	7.0
2018	$100	$487	4.9
2019	$225	$915	4.1
2020	$392	$1,438	3.7
2021	$609	$2,092	3.4
2022	$868	$2,918	3.4
2023	$1,163	$3,751	3.2
2024	$1,495	$4,671	3.1
2025	$1,827	$5,755	3.1
2026	$2,153	$6,846	3.2
2027	$2,475	$7,843	3.2
2028	$2,796	$8,803	3.1
2029	$3,114	$9,709	3.1
2030	$3,430	$10,630	3.1

Note: Operating cost savings account for increases in expenditures of electricity and hydrogen for fueling Zero-Emission Vehicles.

Table VII-B-5. Estimates of Cost Effectiveness for Advanced Clean Cars Reductions of Criteria Pollutants and Greenhouse Gases (2009 Dollars)

Year	PM2.5 ($/pound reduction)	ROG+NOx ($/pound reduction)	CO_2e ($/ton reduction)
2025	$0	$4	$290 savings
2035	$0	$3	$320 savings

Figure VII-B-1. Statewide Costs and Benefits of the Advanced Clean Cars Program (2009 dollars)



C. POTENTIAL IMPACTS ON BUSINESS CREATION, ELIMINATION, OR EXPANSION

The Advanced Clean Car regulation affects both light- and medium-duty vehicles for criteria pollutants; for greenhouse gas emissions, it only affects light-duty vehicles whose primary use is noncommercial personal transportation. Therefore, many of the medium-duty vehicles that businesses use would only be affected by the criteria pollutant portion of the proposed regulation, whose costs are expected to be minimal. However, if the businesses purchase the same light-duty vehicles as consumers, they would be expected to pay incrementally higher prices for the vehicles but save on operating costs, as is discussed in section VII.G Below. As noted in that section, staff expects that reduced operating costs will greatly outweigh the effect of the incremental vehicle price increase over the life of the vehicle.

It is very likely that savings from reduced vehicle operating costs would end up as expenditures for other goods and services. These expenditures would flow through the economy, causing expansion or creation of new businesses in several sectors. Staff's economic analysis shows that as the expenditures occur, jobs and personal income would be positively impacted. Jobs would be unaffected in 2020, increase gradually by 0.1 percent in 2025, and by 0.2 percent in 2030 compared to the baseline economy that excludes the proposed Advanced Clean Car regulatory package. Similarly, income grows by $1 billion in 2020, by $3 billion in 2025, and $6 billion 2030. Should only the LEV III (including GHG) amendments be adopted, the economic impacts would remain roughly unchanged.

The E-DRAM model was used to assess the overall impact of the regulation on California's economy. Specifically, E-DRAM was used to estimate impacts on California's output of goods and services, personal income, and employment. The estimates of the regulation's impact on these economic factors are used to assess the potential impacts on business creation, elimination, or expansion in California. The next section describes E-DRAM.

1. ENVIRONMENTAL-DYNAMIC REVENUE ANALYSIS MODEL (E-DRAM)

The overall impact of direct and indirect economic effects that may result from the proposed regulation are estimated using a computable general equilibrium (CGE) model of the California economy. A direct impact, as defined here, affects the automobile and oil industries, and their consumers. The proposed regulation may affect other economic sectors indirectly. For example, consumers are likely to redirect money from operating cost savings to spend on other sectors. In addition, the automobile industry would be expected to purchase goods and services from other sectors to comply with the proposed regulation. These expenditures caused by the regulation would indirectly affect the California economy.

A CGE model simulates various economic relationships in a market economy, where prices and production adjust in response to changes caused by regulations to establish an equilibrium in markets for all goods and services and factors of production (i.e., labor and capital). The CGE model used for this analysis is a modified version of the California Department of Finance's Dynamic Revenue Analysis Model (DRAM). The DRAM has been used for several tax policy evaluations. The modified model accounts for environmental sectors and is called Environmental-DRAM (E-DRAM). It has been used to assess the economic impacts of California's air quality State Implementation Plans, the AB32 Scoping Plan, reformulated gasoline regulations, vehicle greenhouse gas standards, and other regulations. A previous version of E-DRAM was peer reviewed as part of the Scoping Plan process and did not reveal any significant concerns. Additional details about E-DRAM can be found in Appendix S.

Economic Impacts: Higher vehicle prices provide a means to estimate the direct expenditures that will be incurred by California businesses, governments, and individuals to meet the requirements of the proposed Advanced Clean Cars program.

These expenditures would in turn bring about additional (indirect) changes in the California economy that may change the overall costs of the regulation to the economy. Increased vehicle prices, for example, may result in a reduction of demand for other goods and services as consumers use more of their money to pay for the price increase. California firms may respond by cutting back production and decreasing employment. On the other hand, in response to the proposed regulations automobile manufacturers are expected to choose technologies that reduce vehicle operating costs, leaving consumers with additional money to spend on products and services. This would, in turn, induce firms supplying those products and services to expand their production and increase their hiring of workers. A third type of effect occurs when purchase of the new vehicles directly lowers demand for the petroleum refining and gasoline distribution sectors.

The changes caused by the proposed regulations will affect industries both negatively and positively. The net effect on the California economy of these activities hinges on the extent to which products and services are obtained locally. Using the E-DRAM model of the California economy, staff estimated the net effects of these activities on affected industries and the overall economy. The California industries and individuals affected most by the proposed Advanced Clean Cars program are those engaged in the production, distribution, sales, service, and use of light- and medium-duty vehicles as well as the refining and distribution of gasoline.

Table VII-C-1, Table VII-C-2, and Table VII-C-3 summarize the impacts of the proposed climate change regulations on the California economy for forecast years 2020, 2025, and 2030 respectively. The results of the E-DRAM simulation show that the changes caused by the proposed regulations would increase the California economic output by roughly $2 billion (0.1 percent) in 2020, $8 billion (0.2 percent) in 2025, and $14 billion (0.3 percent) in 2030. Personal income would increase more gradually, remaining almost unchanged in 2020 but increasing by roughly $3 billion (0.1 percent) in 2025, and $6 billion (0.2 percent) in 2030. As a result, California net employment impacts due to the proposed regulation would also remain about constant in 2020, but increase slightly by 21,000 jobs (0.1 percent) in 2025, and 37,000 jobs (0.2 percent) in 2030.

Table VII-C-1. Economic Impacts of the Proposed Advanced Clean Cars (ACC) Regulations on the California Economy in Fiscal Year 2020 (2009 dollars)

California Economy	Without ACC Regulations	With ACC Regulations	Difference	% of Total
Output (Billions)	$3,600	$3,602	$2	0.1
Personal Income (Billions)	$2,171	$2,172	$1	0.0
Employment (thousands)	17,913	17,919	6	0.0

Note: Difference of individual columns may not match due to rounding.

Table VII-C-2. Economic Impacts of the Proposed Advanced Clean Cars Regulations on the California Economy in Fiscal Year 2025 (2009 dollars)

California Economy	Without ACC Regulations	With ACC Regulations	Difference	% of Total
Output (Billions)	$4,170	$4,178	$8	0.2
Personal Income (Billions)	$2,525	$2,528	$3	0.1
Employment (thousands)	18,966	18,987	21	0.1

Note: Difference of individual columns may not match due to rounding.

Table VII-C-3. Economic Impacts of the Proposed Advanced Clean Cars Regulations on the California Economy in Fiscal Year 2030 (2009 dollars)

California Economy	Without ACC Regulations	With ACC Regulations	Difference	% of Total
Output (Billions)	$4,881	$4,895	$14	0.3
Personal Income (Billions)	$2,962	$2,968	$6	0.2
Employment (thousands)	20,179	20,216	37	0.2

Note: Difference of individual columns may not match due to rounding.

These results indicate that higher vehicle prices cause consumers to redirect their expenditures. Consumers would spend more on the purchase of motor vehicles, thus having less money to spend on the purchase of other goods and services. Since most automobile manufacturing occurs outside of the State, the increased consumer expenditures on motor vehicles would reduce California economic activity. However, the reduction in operating costs resulting from improved vehicle technology would reduce consumer fuel expenditures, leaving California consumers with more disposable income to spend on other goods and services. Businesses that serve local markets are most likely to benefit from the increase in consumer expenditures. The increase would in turn boost the California economy slightly, resulting in the creation of some additional jobs.

The output from E-DRAM is based on the assumption that the future structure of California's economy remains similar to current existing conditions. These results are thus only illustrative of the potential macroeconomic effects that might occur with the implementation of the proposed amendments as opposed to a forecast of future economic growth. The relatively small percentage change in this context means that the uncertainty of future economic structures may offset some of these positive effects. However staff believes it is unlikely that the proposed amendments *per se* would result in significant negative economic impacts. In fact, the technology-forcing nature of the program could stimulate growth in certain sectors, which would not be reflected in the model's existing linkages between sectors. For instance, electric vehicle manufacturers and clean energy companies that have recently been established in the state would have the potential of expanding their businesses and exporting their products to other

parts of the country or the world, though conservatively such positive impacts are not assumed in the modeling.

2. AFFILIATED BUSINESSES

The E-DRAM results reflect the overall impacts to the statewide economy. While positive at the aggregate level, some individual sectors may experience negative impacts. As the directly regulated automotive manufacturing sector currently has a limited presence in California, indirect effects on affiliated businesses are likely to be of greater interest. Potential effects are discussed qualitatively here and in a more quantitative fashion in section VIII.C.5 and Appendix S for affiliated businesses located in low-income cities.

The oil and gas industry, fuel providers, and service stations are likely to be the most adversely affected by the proposed Advanced Clean Cars program due to the substantial reductions in demand for gasoline – exceeding $1 billion beginning in 2020 and increasing to over $10 billion in 2030. Some jobs could be transferred from refineries or fuel providers to the electricity generation or hydrogen production sectors or other unaffiliated businesses. Likewise, some service stations may be able to transition to providing alternative fuel types to offset these losses. However, a net loss to these businesses would be expected overall.

Vehicle dealers may also be affected due to changes in vehicle sales. In 2010, 55 percent of average new vehicle dealership revenue was generated by new vehicle sales and another 24 percent from used vehicle sales.[46] The effect of the proposed program on vehicle price increases and subsequently on new and used vehicle sales are further discussed in section IX.A and IX.B. Those analyses suggest that new vehicle sales in California would increase slightly as a result of the proposed amendments, which would in turn increase dealer revenues due to the higher sales volume as well as the higher vehicle prices. However, the higher new vehicle sales may reduce populations of older vehicles, which could reduce business for the parts and servicing departments at dealerships (and independent repair shops). On the other hand, the greater penetration of new advanced vehicle technologies may result in servicing needs that can only be fulfilled at the dealership. Additionally, dealers may need to provide training to sales and servicing staff to familiarize them with many of the new ZEV technologies anticipated to be offered as a result of the proposed program.

The effects on used vehicle dealers (or the used vehicle department at a new vehicle dealership) are more ambiguous. Higher sales volumes of new vehicles do not necessarily imply that used vehicle sales must fall. A vehicle can be sold only once new and some are never resold while others might be resold numerous times. New vehicle buyers frequently trade in an existing vehicle, generating both a new and used vehicle sale. In addition, assuming that the higher price of new vehicles translates into

[46] California New Car Dealers Association 2011 Economic Impact Report, http://www.cncda.org/secure/GetFile.aspx?ID=2106 (Accessed November 2, 2011)

proportionally higher used vehicle prices, this increase in revenue could offset some or all of the losses from reduced sales volumes.

3. ECONOMIC IMPACTS OUTSIDE OF CALIFORNIA

Although State rulemaking law does not require evaluation of economic impacts outside of California, the significant compliance costs imposed by both the LEV III and ZEV amendments warrants some consideration of the potential impacts at a broader level. ARB's standard economic analysis assesses the per vehicle price increases on vehicles sold in California as applied by manufacturers located outside of the State. As described in section IX.A and IX.B, staff believes the proposed Advanced Clean Cars program could have a small positive effect on new vehicle sales in California, which in turn could imply growth for that sector and affiliated sectors. However, staff does not have the capability to evaluate quantitatively the effects of the proposed program on the broader economy surrounding those sectors. E-DRAM is not a suitable model for evaluating these potential effects as it treats everything outside of California as the "rest of the world" and makes no distinction between other states or other countries.

However, as concurrent federal light-duty vehicle greenhouse gas emission regulations are expected to be promulgated in concert with the proposed Advanced Clean Cars program, an economic impact analysis at the national level would provide insights on the potential economy-wide impacts for other states besides California. Although no such analysis was conducted as part of the recent Notice of Proposed Rulemaking for 2017 and Later Model Year Light-Duty Vehicle Greenhouse Gas Emissions and Corporate Average Fuel Economy Standards, an exploratory economy-wide impact analysis of the impacts of greenhouse gas tailpipe standards was undertaken by U.S. EPA as part of their MY2012-2016 rule[47], which is indicative of the types of effects to expect from the MY2017-2025 National Program.

In its MY2012-2016 analysis, U.S. EPA used the Intertemporal General Equilibrium Model (IGEM), which is an economy-wide computable general equilibrium model for the United States economy. Based on changes in vehicle technology costs, fuel consumption, and fuel prices that would be expected from the MY2012-2016 rule, IGEM estimates changes in U.S. gross domestic product (GDP) and household consumption. Note that the value of additional private or societal benefits are not included in the modeling. The results show that U.S. GDP would increase for all years analyzed, on the order of 0.5 percent in 2020, 0.77 percent in 2030, and continuing to increase to 0.9 percent in 2050. On the consumption side, households would decrease consumption by about 0.01 percent at the beginning of the rule due to the higher vehicle prices, but fuel savings would accumulate with time so that consumption would increase by 0.36 percent in 2020, 0.92 percent in 2030, and reaching 1.5% in 2050.

Due to the similar nature of the proposed MY2017-2025 National Program, similar small, positive effects on U.S. GDP and household consumption would be expected as

[47] Memorandum to Docket, "Economy-Wide Impacts of Proposed Greenhouse Gas Tailpipe Standards for the Final Rulemaking," March 4, 2010, Document ID: EPA-HQ-OAR-2009-0472-11467

those for the prior rule. While such effects are unlikely to be perfectly distributed uniformly across all states, it is even more unlikely that these positive benefits occur only in California, with none occurring in the remaining 49 states. Indeed, like Californians, consumers in many other states would be expected to experience reductions in operating costs resulting from improved vehicle technology, leaving them with more disposable income to spend on other goods and services in their local markets.

D. POTENTIAL IMPACT ON CALIFORNIA BUSINESS COMPETITIVENESS

Automobile manufacturing in California represents a small fraction of the State's economy, less than 0.5 percent.[48] The California businesses impacted by this regulation tend to be affiliated businesses such as gasoline service stations, automobile dealers, and automobile repair shops, as discussed above in section VII.C.2. Affiliated businesses are mostly local businesses. These businesses compete within the State and generally are not subject to competition from out-of-state businesses. Therefore, the proposed regulations are not expected to impose significant competitive disadvantages on affiliated businesses.

Additionally, the GHG component of the LEV III amendments is being proposed in coordination with the MY2017-2025 National Program, which will impose similar impacts on businesses in other states. Therefore, affiliated businesses in California would be selling, repairing, and fueling similar vehicles as their competitors in other parts of the country, so there would be no benefit to relocating. For all other businesses that purchase new light-duty vehicles, vehicle prices would also be similar to those their competitors face in other states. As other countries adopt more stringent GHG standards, the same would be true of their global counterparts. These businesses would also experience similar operating cost savings as ordinary consumers, which can be reinvested back into the businesses and potentially increase their competitiveness.

E. ANCILLARY BENEFITS

The economic impacts described above only consider the private benefits associated with reduced expenditures for operating future new vehicles that comply with the proposed Advanced Clean Cars program. However, the proposed regulations would also produce other societal benefits. Although these societal benefits are not monetized for inclusion in a formal benefit-cost analysis or incorporated into the cost effectiveness calculations, they are discussed here for completeness.

1. SOCIAL COST OF CARBON

The social cost of carbon (SCC) is a monetary estimate of future damages resulting from the emission of one additional metric ton of carbon dioxide in a specific year.[49]

[48] Based on the share of output from the vehicle manufacturing sector assumed in E-DRAM.
[49] SCC values discussed in this section apply only to carbon dioxide emissions. Values for other greenhouse gases (GHGs) are under development.

Given the consensus that climate change caused by anthropogenic emissions of carbon dioxide, (CO_2), and other GHGs will result in widespread, long-term environmental and economic damage, it would be inconsistent to assign a zero value to the reduction of climate change emissions. Regulations that reduce future CO_2 emissions benefit the environment and the economy by preventing damages. Recognizing the need to assign value to the social costs of GHG emissions, ARB staff monetizes the social benefits of the proposed rule's reduction of CO_2 emissions using global SCC values published by the U.S. government. Due to the provisional and uncertain nature of these estimates however, ARB staff calculates these values for illustrative purposes but does include them in the primary economic impact analysis or cost-effectiveness estimates.

Federal agencies have developed and applied a range of global SCC values in regulatory impact analyses (RIAs) since 2008. The U.S. government is committed to periodically reviewing and updating SCC values. Its current SCC values result from averaging the outputs of three peer-reviewed integrated assessment models (IAMs).[50] The interagency group selected four different values for the social cost of CO_2 emissions in any given year: three values based on the average SCC across models and socio-economic and emissions scenarios, discounted at 2.5%, 3% and 5% rates; and a fourth value – the 95th percentile of model estimates -- to represent higher-than-expected or catastrophic damages. (See Table VII-E-1-1.) Taking one example from the table, $33 represents the stream of future damages caused by the emission of one additional metric ton of CO_2 in the year 2030, when those post-2030 damages are discounted at 3%. To estimate the social benefits of an entire regulatory program, SCC values ($) for all impacted years are multiplied by annual CO_2 emission reductions (MT CO_2), converted to a net present value using the same discount rate (3%) and summed. Additional details related to the estimation, selection and application of the social cost of carbon can be found in Appendix S.

[50] "Social Cost of Carbon for Regulatory Impact Analysis under Executive Order 12866," February 2010, EPA-HQ-OAR-2009-0472 See pages 5-11 for discussion of the three integrated assessment models.

Table VII-E-1-1. SCC Values: Federal Interagency Working Group

Global Social Cost of CO_2 Emitted in 2020, 2025, 2030, & 2040 (2009$/Metric Ton)[51]				
Discount Rate	5%	3% "Central Value"	2.5%	3%
Emissions Year	Avg., 3 models	Avg., 3 models	Avg., 3 models	95th percentile
2020	$7	$27	$43	$84
2025	$8	$31	$47	$94
2030	$10	$34	$52	$103
2040	$13	$41	$60	$123

Source: Social Cost of Carbon for Regulatory Impact Analysis under Executive Order 12866, U.S. Interagency Working Group on Social Cost of Carbon, 2010

Future damages from climate change are discounted to reflect society's marginal rate of substitution between consumption in the present and in the future. The working group emphasizes the use of a range of SCC values to reflect the uncertainties of estimating the future benefits of reducing CO_2 emissions, but identifies the value discounted at 3% as its "central value." Discount rates of 3% and 7% are often used for social discounting in the context of Federal regulatory programs, however, the Office of Management and Budget's Circular A-4 suggests using a lower, but still positive discount rate when considering inter-generational costs.[52]

Despite the use of discounting to calculate the net present value of future benefits, the interagency group's annual unit SCC values increase over time. Future emissions are expected to become more damaging as physical and economic systems become more stressed in response to increased climatic change.

The proposed rule will substantially reduce combustion, distribution, refining and extraction of gasoline for an extended period. The private economic benefits that accrue to vehicle owners as a result of the rule, (fuel savings, e.g.), are quantified and discussed in the economic impact analysis in section VII-B.

Additional economic benefits – social benefits – can be attributed to the global climate change impacts of reducing fuel production, distribution and combustion. Applying global SCC values to the emission reductions of carbon dioxide estimated from the proposed Advanced Clean Cars program results in the SCC benefits shown in Table VII-D-1-2. Amounts are expressed in billions of 2009 dollars and represent the net

[51] Table values differ marginally from those in the U.S. EPA Preamble (76 Fed.Reg. No. 231, December 1, 2001, Table III-70, p. 75128) because U.S. EPA uses a GDP price index rather than a consumer price index to adjust for inflation.

[52] Executive Office of the President, Office of Management and Budget, Circular A4, Regulatory Analysis, September 17, 2003. See Section E, Identifying and Measuring Benefits and Costs, Discount Rates, 4. Intergenerational Discounting. Accessed 11/17/11 at: http://www.whitehouse.gov/omb/circulars_a004_a-4/#e

present value of climate change damages avoided as a result of CO_2 emission reductions in the specified year(s). For the "Central Value," which discounts future benefits at 3% annually, the proposed regulation would avoid $20 billion of climate change damages through 2040.

Table VII-D-1-2. Social Benefits of Projected Advanced Clean Cars CO_2 Emission Reductions

Global Social Benefits of ACC CO_2 Reductions, (Billions of 2009$) in Selected Years and Cumulated through 2040				
Discount Rate	5%	3% "Central Value"	2.5%	3%
Emissions Year	Avg., 3 models	Avg., 3 models	Avg., 3 models	95th percentile
2020	$0.03	$0.10	$0.16	$0.30
2025	$0.13	$0.49	$0.75	$1.5
2030	$0.28	$0.95	$1.4	$2.9
2040	$0.56	$1.7	$2.6	$5.2
2017-2040	**$5.9**	**$20**	**$30**	**$59**

Combining the estimated social benefits of projected CO_2 emission reduction with the private economic benefits discussed in section VII.B improves the overall benefit-cost ratio of the proposed rule. However, the social benefits of CO_2 emission reduction were not considered in setting the stringency of the proposed ACC-GHG standards.

Had SCC been integrated with the primary economic impact analysis for the proposed program, its inclusion would not have significantly impacted ACC's overall benefit-cost ratio as seen in Figure VII-D-1-1, below. This is because the private value of fuel exceeds the estimated social cost of the GHG-related externality associated with its combustion.

Figure VII-D-1-1. Benefit-Cost Ratios of ACC through 2040 with and without Social Cost of Carbon (Millions of 2009$)



2. ADDITIONAL ANCILLIARY BENEFITS

The avoidance of future damages from carbon dioxide emissions as represented by the social cost of carbon is one of many ancillary benefits that are not included in the primary economic impact analysis. Other benefits not monetized nor included are:

- Valuation of avoided morbidity and mortality impacts from criteria pollutant emission reductions;
- Consumer surplus from additional vehicle miles traveled;
- Upstream reduction of criteria pollutant emissions from fuel distribution;
- Refueling Time Savings;
- California's contribution to national energy security benefits.

The 2017 and Later Model Year Light-Duty Vehicle Greenhouse Gas Emissions and Corporate Average Fuel Economy Standards proposed by U.S. EPA and NHTSA offers energy security benefits by reducing the risk of national macroeconomic disruptions caused by oil price volatility.[53] California's implementation of the proposed Advanced Clean Cars program and subsequent reductions in petroleum-based fuel consumption would contribute to similar energy security benefits after 2016.

[53] Preamble, 76 Fed.Reg. No. 231, December 1, 2011, Table III-75, p. 75137.

Some ancillary benefits, such as refueling time savings, are uncertain because they depend on future automobile design choices. Others would incur related dis-benefits. For example, incremental VMT would increase accidents, traffic congestion and noise as well as consumer surplus. Nonetheless, when estimated and monetized at the federal level by the USEPA in the context of the National Program for MY2017-2025, the benefit of increased travel outweighs the associated dis-benefits.[54]

If all these additional ancillary impacts of California's proposed regulations were quantified and monetized using the methods applied by U.S. EPA for the National Program, estimated net program benefit would increase, and the overall benefit-cost ratio would further improve.

F. POTENTIAL COSTS TO LOCAL AND STATE AGENCIES

Fiscal impacts on local and State agencies would not occur within the next three fiscal years. However, due to the potential magnitude of impacts in future fiscal years, they are discussed here to illustrate the possible scale of the problem. Lower fuel consumption by the new complying vehicles would affect gasoline and vehicle sales tax revenues. Gasoline taxes include fixed State and federal excise taxes, and the State sales tax. If tax rates remain at current levels, staff estimates that the Advanced Clean Cars program could result in gasoline excise and sales tax revenues declines of about $250 million in 2020 (compared to the no regulation scenario), of which about half could be offset by increased sales taxes from higher priced vehicles. In 2025, fuel-related tax revenues could decline by more than $1 billion compared to a no regulation scenario, of which about $250 million could be offset by increased vehicle sales tax revenues. By 2030, fuel-related tax revenues could decrease by as much as $1.9 billion while vehicle-related Sales tax revenues would continue to be about $230 million more, leading to a net shortfall of $1.7 billion. In the absence of any adjustments by the Legislature to generate additional revenues, shortfalls of these magnitudes could lead to significant underfunding of road maintenance, transit funding, and other government services. Although not quantified, it is expected that a considerable percentage of the fuel savings resulting from the proposed regulations will be redirected towards goods and services subject to sales tax, in which case some of the tax revenues, in addition to increased vehicle sales taxes, would be recouped. However, there is no guarantee that these revenues would be dedicated to transportation-related purposes as would be the case with state and federal excise tax revenue.

California Energy Commission analysis of the Department of Motor Vehicle database for 2009 shows there were about 300,000 light-duty vehicles registered to State and local agencies in California. EMFAC 2011 estimates the total population of light-duty vehicles in 2009 at about 22.8 million, meaning that government owned vehicles comprise about 1.3 percent of the total state fleet. The data also show that governments owned about 11,000 MY2009 vehicles. Taken as a proxy for annual purchases, this represents about 1.3 percent of all MY2009 light-duty vehicles

[54] Preamble, 76 Fed.Reg. No. 231, December 1, 2001, Table III-83, p. 75147.

estimated in EMFAC2011. Government fleets are thus a small share of the total California market and would not be expected to bear a significant portion of the compliance costs. Furthermore, the staff analysis below for individual consumers indicates that the increased initial price is more than offset by operating cost savings over the life of the vehicle. Assuming that typical agency-owned vehicles are driven similar amounts as those owned by California households, staff expects that the same would hold true for public agencies—savings from the lower operating costs of the proposed regulation would outweigh the higher price that the State and local agencies would pay for vehicles in 2017 and later. In cases where government vehicles are driven more or less than typical household vehicles, the savings would accrue faster or slower, but still pay back within the lifetime of the vehicle. While these proposed amendments would not yield fuel savings for MY2015 and MY2016 vehicles, these vehicles would still have reductions in operating costs resulting from prior rulemakings that would far exceed the minimal compliance costs associated with the early phases of the tightened criteria pollutant standards.

G. POTENTIAL IMPACT ON MONTHLY LOAN PAYMENT AND OPERATING SAVINGS FOR NEW VEHICLES

To provide a perspective on the potential impact of the proposed regulations on the monthly cash flow for typical purchasers of new vehicles, staff considered a vehicle-financing period of five years at an interest rate of 5 percent. Table VII-G-1 provides estimates of potential increases in monthly loan payments and decreases in operating costs based on the average increases to vehicle prices when the regulation is fully phased-in (MY2025). Fuel savings are estimated based on the EMFAC2011 model estimates of the annual average vehicle miles traveled (VMT) in the vehicle's first five years of life with additional VMT added to account for the rebound effect. Overall, light-duty vehicles are estimated to travel on the order of 17,000 miles annually during their first five years. See Appendix S for additional details on payback and savings calculations.

As shown in Table VII-G-1, the proposed Advanced Clean Cars program is expected to increase the price of new MY2025 average fleet vehicle by about $1,900. For vehicles that are financed, this would increase the average monthly payment for a typical consumer about $35. Concurrently, typical consumers would benefit from monthly fuel savings of about $48 producing a net monthly savings of about $12 and net lifetime savings of roughly $4,000. These savings would pay back the initial increase in vehicle purchase price in less than three years.

Table VII-G-1. Potential Impact on Monthly Loan Payment and Operating Savings for New 2025 MY Vehicles (2009 dollars)

Description	Advanced Clean Cars Program
Average Increase in New Vehicle Price	$1,900
Increase in Monthly Loan Payment	$35
Net Lifetime Savings	$4,000
Monthly Operating Savings	$48
Net Monthly Savings	**$12**
Payback Period (Years)	**2.9**

Note: Estimates have been rounded. Costs and savings include ZEVs and their additional expenditures on electricity and hydrogen.

In the event that only the proposed LEV III (including GHG) amendments are adopted, average new vehicle prices would increase by only $1,400, which translates to increases in monthly payments of $26 assuming the entire incremental vehicle price has been financed. At the same time, consumers on average would reduce fuel expenditures by $50 each month, for a net monthly savings of $24. Over the life of the vehicle, net fuel savings would total $4,800 after accounting for the higher initial purchase price. The lower compliance cost and greater fuel savings would reduce the payback period to only two years.

It should be noted here that most vehicles still retain about half of their original value after a five-year financing period. These values would effectively reduce the increase in monthly payments if they were realized after the completion of the loan payments. Even without the realization of the residual value, monthly savings from new vehicle operations exceed the increase in monthly loan payments for both the passenger car and light-duty truck categories.

H. JUSTIFICATION FOR ADOPTING REGULATIONS DIFFERENT FROM FEDERAL REGULATIONS

To the extent California's regulations differ from current federal requirements affecting the same pollutants, California has authority to set its own standards to reduce emissions further to meet federal and state ambient air quality standards and climate change requirements and goals, and to require additional and separate reporting. The differing state requirements proposed are necessary to achieve additional benefits for human health, public welfare, and the environment as envisioned by authorizing legislation.

I. CONCLUSION

The proposed Advanced Clean Cars program has a small, net positive impact on the State's economy. The regulation may lead to a small, net creation or expansion of businesses, and could increase jobs in California. Because affected businesses are

primarily local, there will not be any impact on the ability of California businesses to compete with businesses in other states. State and local agencies will not be adversely impacted and are likely to realize a net reduction in their cost of fleet operations. Consumers would likewise quickly recoup the additional vehicle costs through savings in operating costs.

VIII. IMPACTS ON MINORITY AND LOW-INCOME COMMUNITIES

This section provides information on ARB's activities to reach out to minority and low-income communities in the development of the Advanced Clean Cars regulations. Staff also has assessed whether the regulation would impose economic or environmental impacts on minority or low-income communities.

A. ARB ENVIRONMENTAL JUSTICE POLICY

ARB has made the consideration of environmental justice an integral part of its activities. State law defines environmental justice as the fair treatment of people of all races, cultures, and incomes with respect to the development, adoption, implementation, and enforcement of environmental laws, regulations, and policies.

The Board approved Environmental Justice Policies and Actions (Policies) on December 13, 2001. These Policies establish a framework for incorporating environmental justice into ARB's programs consistent with the directives of State law. The Policies apply to all communities in California, but recognize that environmental justice issues have been raised more in the context of low-income and minority communities.

1. AB 1493 REQUIREMENTS

Assembly Bill 1493 emphasizes the importance of considering the economic impacts of the climate change regulations on communities in an environmental justice context. The bill specifically directs ARB to, "consider the impact the regulations may have on the economy of the State, including, but not limited to...the ability of the State to maintain and attract businesses in communities with the most significant exposure to air contaminants, localized air contaminants, or both, including, but not limited to, communities with minority populations or low-income populations, or both."

The bill also recognizes the importance of engaging these communities throughout the regulatory development process and includes specific requirements that ARB "conduct public workshops in the State, including, but not limited to, public workshops in three of the communities in the state with the most significant exposure to air contaminants or localized air contaminants, or both, including, but not limited to, communities with minority populations or low-income populations, or both."

2. AB 32 REQUIREMENTS

Assembly Bill 32 also includes specific language regarding communities in an environmental justice context. The bill specifically directs ARB to, "coordinate with State agencies, as well as consult with the environmental justice community, industry sectors, business groups, academic institutions, environmental organizations, and other stakeholders in implementing this division." It also recognizes the importance of engaging these communities throughout the regulatory development process and includes specific requirements that ARB "shall conduct a series of public workshops to give interested parties an opportunity to comment on the plan. The State board shall conduct a portion of these workshops in regions of the State that have the most significant exposure to air pollutants, including, but not limited to, communities with minority populations, communities with low-income populations, or both."

AB 32 also requires, "that activities undertaken to comply with the regulations do not disproportionately impact low-income communities" and that "the State board shall ensure that the greenhouse gas emission reduction rules, regulations, programs, mechanisms, and incentives under its jurisdiction, where applicable and to the extent feasible, direct public and private investment toward the most disadvantaged communities in California and provide an opportunity for small businesses, schools, affordable housing associations, and other community institutions to participate in and benefit from statewide efforts to reduce greenhouse gas emissions."

Finally, AB 32 requires ARB, before including any market-based compliance mechanism, to "Consider the potential for direct, indirect, and cumulative emission impacts from these mechanisms, including localized impacts in communities that are already adversely impacted by air pollution."

3. OUTREACH TO MINORITY AND LOW-INCOME COMMUNITIES

Staff conducted workshops in communities with environmental justice concerns. The dates of all the workshops were as follows:

Date	Location
July 12, 2011	Fresno
July 19, 2011	Pacoima
July 26, 2011	Oakland

Each of the three workshops included an expert panel with opening remarks from a local community leader. The panels included one expert that focused on background information and environmental impacts of air pollution, one expert in the medical field that focused on the health impacts of air pollution, one expert from the American Lung Association of California that discussed their report titled "The Road to Clean Air," and in some areas we also had an expert speak about local concerns. For instance in Fresno we had a speaker address agriculture. Having local community members and leaders participate in the workshops was greatly appreciated and added value and a

local context to ARB's presence in these communities. After community members heard from the panel members, staff presented information about the Advanced Clean Cars regulations and the CEQA scoping process (as discussed in Appendix B).

There were a number of different comments and concerns expressed at each workshop and staff was able to engage in a good dialogue with attendees about many air quality and climate change related issues.

In general, community leaders and community members were very supportive of the work ARB is doing to take steps to reduce emissions from passenger cars and light-duty trucks.

B. POTENTIAL ENVIRONMENTAL IMPACTS

The Advanced Clean Cars regulations provide many air quality benefits to communities with environmental justice concerns. In addition to improved air quality from cleaner cars, there are upstream benefits associated with reduced petroleum shipping and refining and retail fuel distribution. Many of the related shipping and processing facilities are located in or near low-income and minority communities. Importation and distribution of petroleum takes place in ports and along freeway corridors near communities often identified with environmental justice concerns. Staff therefore has not identified any mechanisms by which the Advanced Clean Cars regulation would result in a disproportionate or negative impact on low-income or minority communities. As indicated above in section V.E., overall fuel-related activities will result in a decrease in such upstream emissions. As a result, these upstream emission reductions are likely to provide benefits to these communities.

C. POTENTIAL ECONOMIC IMPACTS

Staff has evaluated the economic effects of the Advanced Clean Cars program on low-income households. For those households that purchase new vehicles, the economic effects of the regulations would be no different than on any other consumer. However, because residents in low-income communities tend to purchase used vehicles at a higher rate than residents in middle- and high- income communities, staff evaluated the effects of the regulation on the used vehicle market and, more specifically, on low-income households that purchase used vehicles. Effects on employment and businesses in low-income communities are also discussed. Staff invites comment on other possible economic impacts.

1. POTENTIAL IMPACT ON A TYPICAL LOW-INCOME HOUSEHOLD

The proposed Advanced Clean Cars regulations are likely to require changes in vehicle technology that will increase the price of new vehicles sold in California. This increase in turn is expected to increase the price of used vehicles. Low-income households often purchase used vehicles. In this analysis, California households of three members with an annual family income of roughly $18,500 or less are considered to be economically

disadvantaged.[55] According to the 2009 National Household Travel Survey[56] low-income households with an average annual income below $20,000 (closest bracket to poverty level of $18,500) tend to own vehicles with an average age of 11 to 13 years.

The impact on low-income used car buyers was assessed by considering the annual vehicle price increase as a percent of income. The analyses showed that the proposed regulations should not have a significant impact on low-income households that purchase used cars.

2. APPROACH

The approach used to assess the potential impact of the proposed regulations on typical low-income purchasers of used vehicles is outlined here:

(1) Changes in the average price of used vehicles caused by the proposed Advanced Clean Cars program were estimated using historical used vehicle values from the National Automobile Dealers Association. For example, a $500 increase in the price of a new vehicle belonging to the passenger car category would be expected to increase the price of a 10-year-old vehicle by $100 assuming a residual value of 20 percent.

(2) Changes in prices of used vehicles were annualized over the remaining life of the vehicles. For example, an $100 increase in the price of a 10- year-old used passenger car is equivalent to a $23 annual cost increase for the vehicle over its median remaining useful life of 6 years.

(3) The annualized cost increase was compared with the median income of typical low-income households to assess the extent of the impact on typical low-income household purchasers of used vehicles.

3. ASSUMPTIONS

The following assumptions were used to estimate the potential economic impacts of the proposed regulations on typical low-income households:

(1) The proposed regulations would increase the fleet average price of a new vehicle by about $1900 when the regulation is fully phased in MY 2025. This price increase includes ZEV technologies that tend to be more expensive. To the degree that low-income households would be more likely to purchase vehicles with conventional technologies, the use of the fleet average price increase would overestimate their costs.

---

[55] Based on U.S. Department of Labor and U.S. Department of Health and Human Services, 2011 Poverty Guidelines (http://aspe.hhs.gov/poverty/11poverty.shtml, Accessed September 22, 2011)
[56] http://nhts.ornl.gov/index.shtml, Accessed September 22, 2011

(2) Most low-income households purchase vehicles that are at least 10 years old. This assumption is based on the information obtained from the 2009 National Household Travel Survey.

(3) A 10-year-old used passenger car has a retention value of about 20 percent. A 10-year-old light-duty truck has a retention value of about 29 percent. The average 10-year-old light-duty vehicle has a retention value of 23%.[57]

(4) A real discount rate of 10 percent was used for this analysis even though the interest rate on used car loans averaged around 9 percent in the past 10 years[58]. Given the unusually low recent interest rates, this rate was rounded upward upwards to 10 percent to be closer to pre-recession levels.

(5) New passenger cars are expected to have median useful life of 14 years, and new large trucks and minivans have a median useful life of 17 years.[59] Based on the data from EMFAC, a 10- year-old car has a median remaining useful life of 6 years and a 10-year old truck has a median remaining useful life of 9 years.[60]

(6) According to the 2011 Federal Poverty Guidelines, California households of three with an annual family income of $18,500 or less are considered to be economically disadvantaged.

4. RESULTS

Typical California low-income households are affected by the proposed Advanced Clean Cars program to the extent that the implementation of the regulations would alter their annual disposable income. Using the previously stated assumptions, staff estimated that the increase in annual costs of used vehicles represents about 0.5 percent of the annual family income of $18,500 for a low-income household, as shown in Table VIII-C-4-1. This represents a minor change in the average income of typical low-income households. Larger households are considered economically disadvantaged at higher income levels so their poverty guideline income level is higher In cases where they are purchasing similarly priced 10-year old vehicles, the annual cost increases would represent an even smaller percentage of their annual income (i.e. dividing the same incremental price by a higher income level).

The analysis discussed here assumes that low-income households would be able to finance the increase in used car prices either from their own income or from borrowing. As shown in Table VIII-C-4-1, the average increase in used vehicle prices would be $440 for a 10-year-old MY2025 vehicle (in calendar year 2035). It is possible that some

[57] Analysis of National Automobile Dealers Association Used Vehicle Values for 1994-2004.
[58] US Federal Reserve Historical Car Loan Data http://www.federalreserve.gov/releases/g20/hist/fc_hist_tc.txt (Accessed September 20, 2011)
[59] Based on the age when the EMFAC2011 survival probability is less than 50%.
[60] Based on the age when the EMFAC2011 survival probability is less than 50% of the survival probability of a 10-year-old vehicle, e.g. a 10-year-old passenger car has a survival probability of 76%, the age of a vehicle with a survival probability less than 38% is 16 years old.

low-income households may have difficulty raising this amount in additional funds to purchase their vehicles. However, staff notes that this average price increase includes a sizeable share of zero-emission vehicles with greater incremental costs. Isolating only conventional vehicle technology, the average increase of used vehicles is significantly lower, on the order of $200 per vehicle which translates to an annualized cost of $40 over seven years and represents only 0.2 percent of the annual family income of $18,500.

Table VIII-C-4-1. Potential Impacts of Proposed Advanced Clean Cars Program on Low-Income Households (2009 dollars)

Description	Advanced Clean Cars Program
Average Increase in New 2025 MY Vehicle Prices	$1,900
Average Increase in Used 2025 MY Vehicle Prices	$440
Median Remaining useful life (years)	7
Annualized Cost of Used Vehicle	$90
Poverty Guideline Income Level	$18,500
Share of Annual Income	**0.5%**

Note: Table values have been rounded and may not reproduce exactly using assumptions described.

The proposed GHG standards directly consider the importance of the lowest cost vehicles via the construction of the footprint-indexed standards. The footprint-indexed standards intentionally utilize a modification to the otherwise linear CO_2-to-size relationship to accommodate the difficulties of applying costly technologies to smaller relatively low cost vehicle classes such as subcompact and compact cars. The standard targets intentionally do not require the same percent reductions in CO_2 emissions for cars less than 41 ft^2 with the "kink" in the standard target line at that size. These target lines effectively make it so that cars smaller than that threshold do not receive more stringent standards (see Figure III-A-3-2 and Figure III-A-5-1 above). These lowest-cost subcompact and compact cars typically are priced in the $14,000 to $16,000 range. To the extent that low-income purchasers are purchasing new cars, these lowest-cost, smaller vehicles have less stringent standards and therefore would have less additional new technology and lower incremental cost than the average values used in this analysis.

The Advanced Clean Cars program may cause vehicle prices to increase, however like other consumers who pay higher prices for their vehicle, they will also see a significant reduction in vehicle operating costs. The savings far outweigh the annualized cost of purchasing the vehicle (price increase spread over the years of ownership). Purchase prices may increase by a small percentage of their income, but will be more than offset by the operating cost savings, as discussed in the next section.

4.1. Potential Impact on Monthly Loan Payment and Operating Savings

To assess the potential impact of the proposed regulations on the monthly cash flow of typical low-income purchasers of used vehicles, we consider a vehicle financing period of three years at an interest rate of 10 percent. Although recent average used vehicle loan periods are closer to 5 years, we assume three years as a more conservative assumption given that these vehicles may be approaching the end of their life. Table VIII-C-4-2 below provides estimates of the potential increases in monthly payments and decreases in operating cost savings. As shown in the table, the proposed Advanced Clean Cars program is expected to increase the monthly payment for an average 10-year-old MY2025 vehicle (i.e., in the year 2035) by about $14. Concurrently, typical low-income consumers would benefit from monthly operating cost savings of about $36, resulting in a net monthly savings of around $20. The vehicle miles traveled (VMT) are estimated using EMFAC2011 age-specific accrual rates, which for 10-year-old vehicles average around 12,000 miles per year. Over the remaining life of the vehicle, the vehicle would generate $2,000 of net savings after factoring in the additional $440 average price increase. Households with higher or lower VMT would accrue greater or fewer net savings. The fuel savings would payback the initial costs in less than one year.

Table VIII-C-4-2. Potential Impact on Monthly Loan Payment and Operating Cost Savings for Used 2025 Vehicles Resulting from Advanced Clean Cars Program (2009 dollars)

Description	Advanced Clean Cars Program
Average Increase of Used MY2025 Vehicle Price in 2035	$440
Increase in Monthly Loan Payment	$14
Net Lifetime Savings	$2,000
Monthly Operating Cost Savings	$36
Net Monthly Savings	**$22**
Payback Period (years)	**0.9**

As previously discussed, the average price increase includes a sizeable share of zero-emission vehicles with greater incremental costs. Assuming that low-income households would be more likely to purchase conventional vehicle technologies, the average increase for a used MY2025 vehicle would be closer to $200. If this entire amount were financed, monthly loan payments would increase on average by $7, however these consumers would save almost $30 each month in operating costs for a net savings of $23. Over the life of the vehicle, net savings would average around $1,700 and pay back the higher purchase price in about half a year.

It should be noted here that most used vehicles continue to retain a portion of their value after a three-year financing period. These values tend to effectively reduce the increase in monthly payments if the vehicle is resold after completion of the loan payments. Even without the realization of the residual value, monthly savings from vehicles impacted by the regulation exceed the increase in monthly loan payments.

5. ECONOMIC IMPACT ASSESSMENT ON AFFILIATED BUSINESSES IN LOW-INCOME CITIES OF CALIFORNIA

This section evaluates potential economic impacts that the proposed Advanced Clean Cars program may have on low-income cities in California, defined as cities whose poverty levels were at or over 13.2 percent. The low-income cities were home to approximately 15 million Californians or about 41 percent of the California population in 2009. Of these 15 million Californians, 2.9 million or 19 percent were considered to be low-income. Figure VIII-C-5-1 shows the locations of low-income cities on the California map.

Figure VIII-C-5-1. Low-Income Cities in California



Section 43018.5 (e) of the California Health and Safety code requires an assessment of the impact of the proposed clean car regulations on businesses affiliated with the auto industry, especially those located in low-income communities. These businesses fall into twenty-three standard industrial classifications (SIC). ARB staff identified 37,144 businesses in low-income cities in California. These businesses employed over 210,000 people and generate about $27 billion in annual sales. On average, a typical

affiliated business generated about $722,000 in revenues per year or about $127,000 per employee. (See Appendix S for additional details)

Affiliated businesses in low-income cities are affected by the proposed Advanced Clean Cars program to the extent that implementation of the regulations would change their profitability. Using the assumptions described in Appendix S, staff estimated the impact on profitability of affiliated businesses. The impact on profitability would be the most severe for gasoline service stations. The affected service stations would experience an estimated decline of almost $740 million in revenues and about $6.4 million in profits. The profitability impact on manufacturers of automotive parts and bodies would be positive but that on auto repair shops would be negative. As a result, service stations are expected to lose approximately 2,300 jobs and auto repair shops about 2,200 jobs as a result of an assumed decrease in older vehicles. These job losses, however, are likely to be offset partially by the creation of 350 jobs by manufacturers of auto body and parts. No change is expected on the profitability or employment of new automotive dealers. The gain in profit associated with the 5 percent increase in sales volume is estimated to be roughly equivalent with the decrease in profit associated with the assumed 5 percent reduction in used vehicle sales.

Based on the change in revenues and the average revenue per business, the proposed regulations are estimated to result in the equivalent elimination of 324 service stations, 112 used car and parts dears, and 669 auto repair shops in low-income cities in California while 21 auto body and parts manufacturers are created. The loss of these businesses would reduce the number of businesses in low-income cities by less than 0.1 of one percent of the over 1.2 million total businesses in low-income cities in California in 2009.[61] The proposed regulations are also expected to result in the creation or expansion of numerous unaffiliated businesses, depending upon where the consumers redirect their savings from the reduction in fuel consumption and repair costs. Affiliated businesses are mostly local businesses. These businesses mostly compete against each other and are not subject to competition from out-of-state businesses. Therefore, the proposed regulations are not expected to impose significant competitive disadvantages on affiliated businesses.

Note that this analysis represents a static approach that assumes no growth in population, employment, VMT, etc. Although this approach usually tends to overestimate the immediate impact a regulation, these simplifying assumptions are appropriate for this type of analysis when the economy-wide impact of a regulation is small. Section V shows that the proposed amendments could lead to a very slight increase in demand for travel that would increase the demand for gasoline and reduce the impact on service stations from what is anticipated here. Additionally, our analysis represents a partial equilibrium evaluation of the impact of the proposed regulations on affiliated businesses only. The analysis does not include the positive impact of the proposed regulations on unaffiliated businesses. As described in Section VII, the reduction in fuel consumption is expected to save consumers a significant amount of money. Part of the consumer savings is likely to be spent on non-liquid fuel such as

[61] Based on Dunn and Bradstreet Market Insight (subscription data).

electricity and the balance will be spent on other consumer products and services. Depending upon where the consumers direct their expenditures, many unaffiliated businesses will benefit from the proposed regulations. Because of higher average economic multipliers of unaffiliated sectors relative to service stations and repair shops, staff believes the numbers of jobs created by these businesses significantly exceed the number of jobs lost from service stations and auto repair shops.

IX. OTHER CONSIDERATIONS

A. CONSUMER RESPONSE EFFECTS ON EMISSIONS AND STATE ECONOMY

ARB's Advanced Clean Cars program will increase new vehicle prices, starting with model year 2015. In addition to an increase in price, however, it is expected that many of the technologies that manufacturers employ to lower GHG emissions to comply with the regulation (including the production of Zero-Emission Vehicles) will, as an outgrowth, result in vehicles with lower operating costs than comparable pre-regulation vehicles. AB 1493 requires ARB to evaluate such operating costs as a component of owner or operator life-cycle costs, and AB 32 requires ARB to design its regulations seeking to maximize total benefits to California and consider overall societal benefits.

Changes in vehicle prices and other attributes may affect consumer purchase decisions. For example, not all consumers would be willing to pay more for the vehicle that they might have otherwise purchased. Some may purchase a different vehicle commensurate with their budget, including a used vehicle instead of a new vehicle. Others may wait until the following year, or respond in some other way. Still other consumers may be willing to pay the additional up front cost for greater future reductions in operating cost, in which case the vehicle would be more attractive. Such decision changes, referred to as consumer response, can affect the California vehicle fleet mix and possibly emissions. ARB estimates show that even if there is a consumer response to potential price increases and changes in operating costs, the staff proposal—the Advanced Clean Cars program as a whole—would continue to have a positive effect on tailpipe criteria pollutant emissions.

1. BACKGROUND

A model known as CARBITS, was used to estimate consumer response (i.e., the estimated change in the type and number of vehicles sold) to changes in new vehicle attributes. The model is explained in greater detail in Appendix S. The attribute changes considered are the vehicle price increases necessary to cover the estimated compliance costs of the criteria pollutant and climate change regulations, and the reduction in vehicle operating costs which is an outgrowth of some of the technologies employed to reduce GHG emissions. Other attributes such as the size or performance of a vehicle are assumed to remain unchanged in order to comply with the proposed amendments, which is consistent with the constraints on such vehicle attributes modeled by Ricardo and in the technology assessment in section III. Additionally, the compliance cost estimates explicitly factor in the costs to maintain these attributes at

current levels, e.g. downsized engines have direct injection and turbocharging to preserve performance characteristics, which further justifies this modeling assumption.

The CARBITS model is a consumer choice model based on discrete choice modeling theory and was developed by the Institute of Transportation Studies at the University of California, Davis. The ultimate objective of the modeling effort is to investigate the potential fleet mix changes resulting from the proposed amendments which may contribute to any criteria pollutant impact. A panel of independent academics reviewed the methodology and inputs employed by this model and concluded it to be an appropriate tool for this rulemaking. (See Appendix S for additional modeling details.)

Consumer response may manifest itself in different ways. The consumer response to the regulations is defined as the difference in the California fleet mix between the forecasted baseline and the regulation scenarios. The baseline scenario is a depiction of the passenger vehicle fleet in the absence of the proposed emissions regulation. While vehicle prices are likely to go up with respect to the regulatory scenarios, the operating costs are expected to be lower. As a consequence of the price increase, consumers could respond by purchasing fewer new vehicles and holding on to their current vehicles a bit longer. Such a shift in vehicle holdings would lead to aging of the vehicle fleet. The aging of the fleet could result in older, relatively higher polluting cars staying in service longer than they would have remained otherwise. Some may assert that this delay in fleet turnover could slow the progress that California is making in reducing criteria pollutant emissions from mobile sources. However, under these proposed amendments, criteria pollutant standards are concurrently being tightened so that the reduced emissions levels of new vehicles may offset any increases from prolonged operation of older vehicles. Additionally, the reduction in operating cost could make new vehicles more attractive, creating a factor that would increase new vehicle sales and turn the fleet over faster. Together, tighter criteria pollutant standards and an accelerated fleet turnover would lessen and potentially more than offset the impact of any price effects.[62] The purpose of the CARBITS model is to quantitatively investigate the possible magnitude and direction of such changes.

The focus of this analysis is on the light-duty vehicle fleet, which comprises the majority of the on-road fleet and vehicle purchases made by households. While medium-duty vehicles are also affected by the proposed regulations, compliance costs for criteria pollutant standards are expected to be minimal and only a few vehicle configurations are subject to the greenhouse gas standards that would result in any substantial vehicle price increases. Therefore, staff believes the emissions effects of consumer response related to medium-duty vehicles to be minimal.

2. IMPACTS ON VEHICLE PRICES AND OPERATING COSTS

Based on the cost estimates from sections II.A.4 and III.A.6 of this report, staff developed a regulatory scenario to use as inputs to CARBITS in an effort to estimate

[62] Note additional offsetting criteria pollutant emissions are projected to result from reduced fuel throughput, as described in the Environmental Analysis, Appendix B.

consumer response to changes in price and operating cost. The latest version of CARBITS uses individual vehicle configuration level data. Future baseline vehicle prices were first adjusted to account for the increases associated with the National Program for MY2012-2016 and the existing ZEV requirements for each of the vehicle configurations in the database. The fleet average price increases shown in Table IX-A-2-1 were then added to the baseline prices to cover manufacturer compliance costs for the entire Advanced Clean Cars package. Table IX-A-2-2 shows the average price increase in percentage terms relative to baseline vehicle purchase prices. Prices are assumed to decrease at an annual rate of only 2 percent once the standards have fully phased in after the 2025 model year due to assumed learning and economies of scale. Appendix S shows additional sensitivity analyses for alternative methods for adjusting vehicle prices, including at a more detailed vehicle class level.

Table IX-A-2-1. Advanced Clean Cars, Fleet Average Vehicle Price Changes for MY2015-2025 Vehicles Relative to Baseline Vehicles (2009 dollars)

Model Year	Incremental Price
2015	$5
2016	$14
2017	$179
2018	$408
2019	$740
2020	$984
2021	$1,288
2022	$1,525
2023	$1,722
2024	$1,913
2025	$1,910

Table IX-A-2-2. Clean Cars, Fleet Average Percentage Change in Vehicle Price for MY2015-2025 Vehicles Relative to Baseline Vehicle Prices

Model Year	% Price Increase
2015	0.0%
2016	0.0%
2017	0.5%
2018	1.1%
2019	2.0%
2020	2.7%
2021	3.6%
2022	4.2%
2023	4.8%
2024	5.3%
2025	5.3%

Section VII presented data on operating cost reductions due to the proposed regulation. Due to existing variability in vehicle operating costs, the reductions were applied to baseline operating costs on a percentage basis, as shown in Table IX-A-2-3, as opposed to assuming all vehicles have the same absolute operating costs that would be implied by the standards. Although energy prices are an important component of operating costs, these percentage reductions reflect only vehicle technology improvements because future fuel prices are kept constant and assumed to be unaffected by the proposed amendments. Appendix S shows additional sensitivity analyses for alternative methods for adjusting vehicle operating costs.

Table IX-A-2-3. Advanced Clean Cars, Percentage Reduction in Fuel-related Operating Cost of MY2015-2025 Vehicles Compared to Baseline Vehicles

Model Year	Passenger Cars	Light-Duty Trucks
2015	0%	0%
2016	0%	0%
2017	3%	4%
2018	5%	6%
2019	7%	8%
2020	9%	10%
2021	11%	13%
2022	13%	16%
2023	15%	18%
2024	17%	20%
2025	21%	24%

These percentage operating cost savings translate into the following average cents per mile savings for a new vehicle, as shown in Table IX-A-2-4.

Table IX-A-2-4. Advanced Clean Cars, Operating Cost Savings of MY2015-2025 Vehicles compared to Baseline Vehicles (Cents Per Mile, 2009 dollars)[63]

Model Year	Passenger Cars	Light-Duty Trucks
2015	0	0
2016	0	0
2017	0.4	0.5
2018	0.6	0.8
2019	0.8	1.1
2020	1.0	1.4
2021	1.3	1.8
2022	1.5	2.1
2023	1.7	2.4
2024	1.9	2.7
2025	2.2	3.2

3. IMPACTS ON VEHICLE SALES, FLEET SIZE, AND AVERAGE AGE

The impacts of the proposed regulation were assessed by forecasting a baseline future fleet mix that assumes that, absent the proposed amendments, vehicle prices and operating costs change only in response to the existing National Program requirements for MY2012-2016. This baseline is then compared to a regulatory scenario that takes into account the estimated price and operating cost changes resulting from the Advanced Clean Cars program. Figures IX-A-3-1, IX-A-3-2, and IX-A-3-3 show the totals and changes in vehicle sales, the size of the fleet, and the average age of the fleet resulting from the proposed program relative to the baseline.

[63] Savings only for first year of ownership as savings will vary with fuel price. See Appendix S for fuel price schedule.

Figure IX-A-3-1. New Vehicle Sales for Advanced Clean Cars Program



Figure IX-A-3-2. Total Fleet Size for Advanced Clean Cars Program



Figure IX-A-3-3. Average Vehicle Age for Advanced Clean Cars Program



In the initial years of the regulation there is a negligible decrease in sales due to compliance with the criteria pollutant standards while there is no concurrent reduction in operating costs resulting from these proposed amendments. However, once the greenhouse gas standards begin to phase in during MY2017, the reduced operating costs of new vehicles makes them more attractive to consumers and total sales begin to increase relative to the baseline. Sales continue to grow over the baseline until the standards have been fully phased-in in MY2025. After this point, new vehicles no longer offer any significant advantage in operating costs over used vehicles that become increasingly available on the market. Thus, the change in sales begins to decline, though these levels still represent a relative increase over baseline totals. As a result of these sales, the fleet continues to grow slowly with time, making the regulation scenario fleet larger in all years compared to the baseline fleet. These sales increases also contribute to decreasing the average age of the fleet, implying that households are not holding onto their older vehicles longer than they would have in the absence of the proposed program.

The assumptions for this analysis do not consider other reductions in ownership costs that may be associated with the regulation such as the potential elimination of a mobile air conditioning service event through improved refrigerant containment strategies that manufacturers may choose to employ. Due to a lack of comprehensive data, however, staff assumed no change in maintenance costs for the purpose of this analysis.

Likewise, the value of potential reductions in refueling time are not included in this analysis. Further, the model does not explicitly consider other more intangible vehicle attributes associated with the proposed program that consumers may value, such as environmental or energy security benefits.

In addition, the sales projections from CARBITS are based on consumer preferences for vehicles that were actually available in the market. For past regulations that resulted in relatively transparent modifications to conventional vehicle types, this data limitation did not impose a significant restriction. Due to the recent introduction of certain advanced vehicle technologies that are still unknown or unfamiliar to vehicle buyers, though, the applicability of these same consumer preferences for these vehicle types is uncertain. However, the price adjustments reflect the costs associated with complying with the entire proposed Advanced Clean Cars program, which conservatively imposes a higher cost on the consumers being modeled. Thus, while the sales projections presented here technically reflect only the internal combustion or conventional hybrid vehicle fleets, staff assumes that other vehicle technologies produced for the ZEV amendments will displace some of these sales, though resulting in the same overall light-duty vehicle sales levels.

Finally, these sales projections are generated for the purpose of policy analysis as opposed to market forecasting. Vehicle sales volumes and distributions are influenced by a host of factors, notably other vehicle attributes, fuel prices and broader economic conditions. In this analysis, these other factors are assumed to remain unchanged with and without the proposed amendments in order to isolate the effects of the policies. Such conditions are unlikely to exist in reality so that actual sales volumes are likely to deviate from these projections. Thus, the differential between the two cases serves as the most relevant metric for assessing the scale and direction of the impacts.

4. IMPACTS ON CRITERIA EMISSIONS

Changes in the fleet size and average age would affect criteria emissions. Newer cars emit less and will produce steady declines in most vehicle pollutants as new vehicles replace existing ones. As discussed previously, the CARBITS results indicate a slight acceleration in fleet turnover where the ACC fleet is generally larger but younger than the baseline fleet. However newer vehicles tend to be driven more intensively than older vehicles, which combined with the rebound effect might increase vehicle miles traveled sufficiently to offset the expected emissions reductions from improvements in emission controls. ARB staff used the fleet composition generated by CARBITS in a modified emissions inventory tool to estimate the changes in criteria pollutant emissions shown in Figure IX-A-4-1.

In all calendar years between 2015 and 2030, all criteria pollutant emissions remain lower for the policy case than the baseline even when accounting for any possible increases due to changes in consumer purchasing patterns. The results without consumer response are analogous to the emissions benefits described in in Section V-

D.[64] These curves (dashed lines, open markers) reflect the changes only from improvements in tailpipe emission rates and assume there are no changes in fleet composition, though do account for any emissions increases due to the rebound effect.

An additional change due to a different fleet mix yields the results with consumer response (solid line, closed markers). In this case, the distribution of vehicles not only includes a greater share of newer vehicles but also more vehicles total to result in a larger total fleet. Total emissions are a function of both the vehicle emission rates and the number of miles that vehicles are driven. While newer vehicles will have lower emission rates, separate from the expected increase in VMT due to the rebound effect resulting from the lower operating costs, newer vehicles also tend to be driven more intensively in their younger years. Thus, having a greater proportion of newer vehicles and a larger total fleet size would generate additional VMT as an artifact of the modeling methodology. As a result, consumer responses to new vehicle offerings could reduce some of the expected emission reductions of PM2.5 (circles) as a result of an increase in VMT. However these same forces could further enhance emission reductions of ROG (triangles) and have essentially no effect on NOx (squares). For all pollutants the Advanced Clean Cars program would continue to produce net benefits when allowing for changes in fleet composition.

[64] The CARBITS population reflects only twenty vintages of light-duty vehicles in any calendar year which represents a subset of the EMFAC population used for the emission reductions presented in Section V-D. The emissions estimates from the two models are therefore not necessarily expected to match exactly, however the CARBITS subset covers an overwhelming majority of vehicles in the on-road fleet and their associated VMT.

Figure IX-A-4-1. Advanced Clean Cars, Changes in ROG, NOx, and PM2.5 Emissions due to Consumer Response (percent)



In the event that total fleetwide VMT is solely a function of the rebound effect, renormalizing VMT to account only for those effects but maintaining the changes in fleet composition would result in similar changes to the percent reductions without consumer response. (See Appendix T for emission calculation methodologies and Appendix S for more detailed emission results.)

Overall, staff believes that consumer response to new vehicle offerings would not negate any of the positive effects on criteria pollutant emissions that are expected to result from the Advanced Clean Cars program, including resultant upstream emission reductions (as discussed in section V).

B. ALTERNATIVE APPROACH TO ASSESSING CONSUMER RESPONSE

The CARBITS model considers many factors at a detailed household and vehicle level in a bottom-up approach to project changes in fleet composition that may result from the Advanced Clean Cars program. Staff also used an alternative approach similar to the one used by USEPA for their MY2012-2016 National Program; this method uses an aggregate sales response factor, known as the price elasticity of demand, to produce a top-down estimate of potential consumer response. The price elasticity of demand is

defined as the ratio of the percentage change in sales to the percentage change in price and is a frequently used measure of consumers' sensitivity to price. A typical value used in the literature and policy analysis is -1, meaning that the percentage decrease in new vehicle sales is equal to the percentage increase in vehicle price or vice versa.

Staff first estimated the percentage change in average new vehicle prices. Assuming that all compliance costs are passed onto consumers, this increase will have additional financial implications for new vehicle buyers. Higher vehicle prices will result in an increase in loan payments for consumers who finance their purchases as well as higher insurance premiums and registration fees. However, higher new vehicle prices also generally results in higher resale values, which may offset some or all of the increases. For all model years, this adjusted incremental vehicle price is less than $1,500. Additionally, vehicle owners would also benefit from operating cost savings that effectively reduce the cost of vehicle ownership. The adjustments that factor in these savings for the first five years of ownership ultimately yield the net price changes shown in Table IX-B-1 (see Appendix S for additional details on adjustments). The negative values imply that the operating cost savings and higher resale values after five years far outweigh ownership costs and any additional compliance costs.

Table IX-B-1. Advanced Clean Cars Price Elasticity of Demand

MY	Net Adjusted Price Change (2009 dollars)	% Price Change	% New Sales Change
2015	$0	0.0%	0.0%
2016	$6	0.0%	0.0%
2017	-$268	-0.9%	0.9%
2018	-$341	-1.1%	1.1%
2019	-$434	-1.4%	1.4%
2020	-$536	-1.7%	1.7%
2021	-$701	-2.2%	2.2%
2022	-$833	-2.7%	2.7%
2023	-$965	-3.1%	3.1%
2024	-$1,090	-3.5%	3.5%
2025	-$1,546	-4.9%	4.9%

As a result of the net savings, the price of new vehicles declines with time relative to a base MY2015 new vehicle. Applying the elasticity value of -1 to the resulting percentage change in vehicles prices implies that new vehicle sales would increase by 0 to 4.9 percent from MY2015 to MY2025 as shown in Table IX-B-1. These percentage changes in new vehicle sales are within the same range as those projected by CARBITS relative to MY2015 sales levels, as shown in Figure IX-B-1. Sensitivity analyses described in Appendix S show that even assuming only three years' worth of operating cost savings would not reduce sales below MY2015 levels. Unlike the CARBITS approach, this simplified approach applies only to new vehicle sales and does

not provide any insights into the changes in fleet size or average vehicle age that could occur from the regulations. Additionally, this elasticity approach does not take into consideration any of the variation in consumer preferences or household characteristics or the availability of used vehicles that may influence demand for new vehicles, hence why the changes are smoother than those produced by CARBITS.

Figure IX-B-1. Comparison of Approaches to Estimate Percent Change in New Vehicle Sales



C. ENERGY COST AND DEMAND FOR NEW VEHICLES

Both of the previous sections suggest that consumers will be willing to trade off the future operating savings against the higher upfront cost of new vehicles so that demand for new vehicles will remain constant if not increasing slightly. However, given these clear private economic benefits, why then have consumers historically not demanded – and automakers not supplied – vehicles that would supposedly be in their own best interests? This issue is often described as an example of the "energy paradox" (Metcalf and Hassett 1999; Tietenberg 2009), as one would expect consumers to make these seemingly-profitable investments to lower operating costs, and yet they do not.

There are several possible explanations for why consumers might not behave as expected. One potential reason is that these consumers are effectively more concerned with the upfront costs over the future fuel savings than might otherwise be expected. Automobile manufacturers appear to believe that consumers only pay attention to the

first three years of fuel savings, despite consumers holding on to vehicles for substantially longer than that on average (Helfand and Wolverton 2011). In other words, consumers may demand a very short payback period or a very high rate of return (discount rate) when they invest in vehicles with lower operating costs, but are content to accept a longer payback period or a lower rate of return for other investments. Indeed, recent literature provides evidence on both sides as to whether consumers are currently fully valuing fuel savings (Helfand and Wolverton (2011); Allcott and Wozny (2011); and Busse, Knittel, and Zettelmeyer (2011).

Other explanations include imperfect information about fuel economy, other biases in decision-making, and capital market imperfections (i.e., the difficulty in obtaining sufficient credit to invest in low emission vehicle technology) (Gillingham, Newell, Palmer 2009; Allcott and Wozny 2011). For example, consumers may demand shorter payback periods because they are loss averse, meaning that the additional investment in the new vehicle may not pay back if the owner needs/wants a different vehicle after just a few years or the price of fuel suddenly drops (e.g. Metcalf and Hassett 1999). Additionally, there is a considerable array of new vehicles available on the market. Rather than evaluate each option systematically and individually, consumers may succumb to inertia by simply replacing a vehicle with its current incarnation or use other shortcuts to whittle down the options, resulting in an "irrational" choice.

Additionally, although payback periods and net monthly fuel expenditures may be routine calculations as part of the rulemaking process, consumers may not actually perform similar computations. Vehicle prices are determined by a variety of factors. Increases may represent additional vehicle content or may simply reflect currency exchange rates, commodity prices, or inflation. Even if consumers could distinguish between the different causes, vehicles are sold as bundled goods whereby buyers cannot pick and choose which attributes to include on their purchase for a clearly marked price. Rarely do consumers have the choice between two vehicles that are exactly identical except for operating cost and purchase price. Instead, a particular vehicle might offer reduced operating cost at a slightly higher initial price while a somewhat similar alternative vehicle might provide a separate set of attributes though have a slightly lower purchase price and higher operating costs. Selecting the alternative vehicle for whatever attribute(s) it offers – cargo room, comfort, safety features, towing capacity, Bluetooth connectivity, styling, etc. – does not automatically imply an unwillingness to pay for reduced operating costs; simply that the consumer exhibits a very high willingness to pay (which could include the ongoing higher operating costs) for these other attributes.

Auto manufacturers operate in a highly competitive market and may themselves be risk averse. Despite the wide assortment of vehicle types, attributes, styles, and amenities of new vehicle models each year, there still exists a considerable level of substitutability between the different offerings. Due to consumers' apparent ambiguity regarding fuel savings, a single manufacturer that attempts to differentiate its products through reduced operating costs or lower emissions might be risking market share. Only when manufacturers are assured that their competitors are also operating under the same

constraints would they provide these attributes; the proposed program in essence levels the playing field.

Reductions in operating costs might in fact be welcomed by the consumer if such an option were available that continued to provide the original desired attribute(s). Most consumers do not derive utility from consuming fuel or producing emissions per se, but from the services and amenities that are associated with those actions. If those same services and amenities can be provided using less fuel and producing fewer emissions, consumers would be better off. Indeed, ARB staff believes that compliance with the Advanced Clean Cars program will not require manufacturers to reduce other attributes from their current levels and the compliance costs explicitly include the costs to preserve them. For conventional vehicles, the compliance costs are based on technology packages that would be largely invisible to a consumer. The footprint basis of the standard and the separate car/truck targets eliminate the incentives for manufacturers to reduce the diversity of vehicle sizes and body styles, thus preserving consumer choice. So long as the attributes that consumers value most remain unchanged as a result of the proposed amendments, the reductions in operating costs would improve consumer welfare even if they were not salient enough to be of high priority in the selection criterion at the time of purchase.

Here again, if consumers would be willing to purchase such a vehicle, why then do manufacturers not provide them? Indeed there are many vehicles that consumers might wish to buy that are not available for purchase. In some case, these vehicles have yet to be invented or proven feasible concepts. More practically, even for vehicles that could be produced using current technology, consumers have highly diverse tastes and preferences and manufacturing vehicles to order for each individual buyer is not possible. Automakers must therefore attempt to select the suite of attributes that is most likely to appeal to the broadest swath of consumers, which might not provide low operating costs. Those on the margins must settle for their "next best" option. To the degree that these consumers value fuel savings and their next best options would be improved along this dimension as a result of the policy, their welfare would be improved.

In the event that some future improvements in vehicles are foregone for the sake of regulatory compliance, it is unclear whether this would necessarily reduce consumer welfare. Today's vehicles are markedly better along almost every dimension compared to vehicles from decades past. Do today's vehicle buyers consider themselves to be significantly better off than their historic counterparts? To the degree that consumer welfare from a new vehicle is derived as it relates to other vehicles on the road, a suspension or slower growth rate in further improvements would not represent as great a welfare loss as if welfare is derived purely based on the value of the attributes themselves.

ARB staff believes that whether or not the valuation of fuel savings played any role in a consumer's purchase decision is a separate issue from that of how the consumer is better off as a result of the policy. Consumers who purchase new vehicles will benefit from lower operating costs and will now have more money in their pockets. The value

of this money is not diminished if they neither intended nor desired these savings. Consumers will continue to purchase those vehicles that maximize their utility. Due to the flexible nature of the proposed Advanced Clean Cars program, manufacturers will continue to be able to produce a diverse array of vehicles demanded by the market. Staff does not believe that compliance will not come at the expense of other attributes, as has been the case to date for compliance with MY2009-2011 light-duty vehicle GHG standards in California and this assumption has been incorporated into the vehicle cost estimates for the proposed amendments. In the event that some consumers might experience some welfare loss through a change in their vehicle selection, this would be offset by gains from the considerable fuel savings as well as the broader societal and environmental benefits generated by the proposed program.

D. MANUFACTURER RESPONSE TO INCREASED VEHICLE PRICES

The majority of the economic analysis has assumed that manufacturers operate in a fully competitive market that allows them to pass on the full cost of compliance to consumers. While the previous sections largely suggest that consumers would be willing to accept such price increases in exchange for the reduced operating costs (in the absence of any other changes in vehicle attributes or market conditions), those conclusions are primarily based on using vehicle averages and representative consumers. In reality both consumers and vehicles vary widely in their characteristics and it is not feasible to model the entire array.

In the event that some consumers would not be willing to accept the full cost of compliance, manufacturers would be required to find strategies to maintain a vehicle's appeal or risk losing market share to competitors who may be able to produce a similar (or better) vehicle for a lower price. Manufacturers may therefore choose not to pass on the full compliance costs in various ways. While an automaker might absorb compliance costs of certain vehicles for a limited number of years, this tactic may not be a viable long-term solution. However, manufacturers could cross-subsidize vehicles within their fleet by increasing vehicle prices of some models beyond their individual compliance costs in order to offset some of the increase of other vehicles. Additionally, the flexibility mechanisms allowing for banking and trading of credits could allow manufacturers to distribute costs over different vehicles as well as over time. Although it is possible that costs could fall in the future as a result of learning, economies of scale, or innovation, overcompliance in early years while the standard is still phasing-in and costs are relatively low could also reduce compliance burdens in later years.

Lastly, it is unlikely that vehicle attributes will remain constant across all dimensions as has been assumed in the modeling exercises above. Although useful for policy analysis, limiting changes to only operating costs and vehicle prices is not necessarily representative of future market offerings. These changes in operating costs and vehicle prices are likely to be bundled with other changes in styling, safety, and amenities as opposed to being selected "à la carte" by new vehicle buyers. As a result, the relevant metric for determining vehicle sales will be the consumer's willingness to pay for the entire bundle and not the single attribute in isolation.

E. EFFECT OF INCREASED FUEL PRICE

Many of the measures that manufacturers will employ to achieve greenhouse gas emission reductions will result in reduced vehicle operating costs, due to the fact that the vehicles will be more efficient. These operating cost savings in turn feed into the staff analysis of the economic impact of the regulation and its cost-effectiveness.

The dollar value to consumers of a given motor vehicle GHG reduction and any associated increase in vehicle efficiency will vary depending on the price of fuel. Throughout the staff report analysis the staff has assumed a retail gasoline price around $4 per gallon (2009 dollars) between 2015 and 2030 based on the average of the values used in the California Energy Commission (CEC) *Integrated Energy Policy Report* (CEC, 2011). Staff's values are roughly consistent with current California conditions. However, given the volatility in fuel prices, staff also replicated relevant portions of the analysis using fuel prices that were 30 percent higher to assess the extent to which its findings and conclusions depend on fuel price assumptions.

The primary staff analysis concluded that at a fuel price of $4 per gallon in 2025 the GHG reduction technologies would more than pay for themselves over the life of the vehicle, and the regulation as a whole would have small but overall positive effects on the California economy. As would be expected, if fuel prices were assumed to increase to a range of $5-6 per gallon rather than $4 per gallon, net benefits increase both for individual consumers and for the State as a whole. Hydrogen and electricity prices are assumed to remain constant. The specific impacts are summarized in Table IX-F-1 and then discussed below.

Table IX-F-1. Effect of Increased Fuel Price on Economic Impacts of Advanced Clean Cars Regulation (2009 dollars)

	Fuel Price Assumption	
	CEC Average	**30% Above Avg**
Consumer Impacts, MY2025		
Net Monthly Difference, New Vehicle	$12 savings	$28 savings
Net Monthly Difference, Used Vehicle	$22 savings	$34 savings
California Economy, CY2030		
Annualized Savings	$11 Billion	$14 Billion
Change in Output	$14 Billion	$18 Billion
Change in Personal Income	$6 Billion	$8 Billion
Change in Employment	37,000	54,000

Section VII shows the effect of the regulation on monthly expenses for purchasers of new vehicles. That analysis looked at the increase in monthly loan payment, assuming a 5-year loan that would result from the fleet average increase in new vehicle prices

associated with the fully phased-in regulation. The analysis then factored in the monthly decrease in operating expenses associated with the various vehicle technologies. The analysis concluded that the average net monthly cost for purchasers of new vehicles would increase by about $35 but result in average monthly savings in operating costs during that same period of almost $50, for a net savings of $12. As is shown in Table IX-F-1, if future fuel prices average over $5 per gallon, then the monthly cash flow is more than doubly positive, yielding net monthly savings of almost $30.

For purchasers of used vehicles the staff analysis calculated the increase in loan payment assuming a three-year loan. The analysis concluded that purchasers of used vehicles would have a monthly net benefit of about $20. If future fuel prices average $5.23 per gallon the monthly net benefit will increase to nearly $35.

F. SUMMARY AND CONCLUSIONS

In this section, staff assessed what the consequences would be if one assumes that the changes in vehicle attributes do affect sales, in contrast to the economic impact analysis previously presented in section VII. Staff analyzed the potential effect of price and operating cost changes on sales, fleet size, and fleet age using a consumer choice model, CARBITS, developed by researchers at the University of California, Davis. The results show that the net effect of increased new vehicle prices and lower operating costs is a tendency to increase sales during the period when the stringency of the standard is tightening; sales then begin to decline after the standard has fully phased-in, though levels remain higher than baseline. This effect had no significant net impact on mobile source criteria pollutant emissions in any model year during the phase-in of the standards or afterwards through 2030, a result obtained before analyzing any additional upstream criteria pollutant emission reductions from decreased fuel throughput.

Generally, the economic impacts of the proposed Advanced Clean Cars program tend to be positive. Staff believes that manufacturers can continue to offer the wide array of new vehicles that appeal to a diverse consumer base while also complying with the proposed program and preserving or improving consumer welfare. The magnitude of positive effects for individual vehicle owners and for the economy as a whole will increase if future fuel prices exceed recent historical averages.

X. SUMMARY AND STAFF RECOMMENDATION

A. SUMMARY OF STAFF PROPOSAL

In response to the continued need to reduce emissions from light-duty vehicles in order to achieve State and federal ambient air quality standards and provide a healthful environment to the citizens of California, staff has presented a number of proposals for the Board's consideration. Considered as a whole, these proposals constitute a comprehensive program designed to achieve significant reductions of criteria and greenhouse gas emissions and, in conjunction with the proposed modifications to the

Zero-Emission Vehicle and Clean Fuels Outlet programs, also part of this rulemaking, lay the groundwork for sustainable transportation in the future.

In addition, staff has attempted to structure the proposals to make them consistent with federal programs currently under development for criteria and GHG emissions while retaining those provisions needed to meet California's unique emission reduction requirements.

To summarize, staff has proposed:

- Significant reductions of exhaust and evaporative emissions
- Significant reductions of greenhouse gas emissions well into the future
- Modifications to California certification fuel to better reflect in-use gasoline
- Modifications to the Environmental Performance Label to more accurately reflect the emission performance of vehicles and make it more useful to the consumer when considering a vehicle purchase
- Minor revisions to the On-Board Diagnostic requirements to assure the development of more robust systems

B. STAFF RECOMMENDATION

For the reasons stated above, staff recommends the Board adopt the proposals set forth in this staff report

LIST OF ACRONYMS AND ABBREVIATIONS

AC:	Air conditioning
ACEff :	Air conditioning efficiency
AERO:	Aerodynamic drag reduction
A/F:	Air/Fuel
AFS:	Air fuel ratio sensor
AIS:	Air intake system
ARB:	California Air Resources Board
ASL:	Aggressive shift logic
AT:	Automatic transmission
AT-PZEV:	Advanced technology partial zero-emission vehicles
ATKCS:	Atkinson cycle engine with cam switching
BC:	Black carbon
BEV:	Battery electric vehicle
BISG:	Higher voltage stop-start/belt integrated starter generator
BWC:	Butane working capacity
CAFÉ:	Corporate Average Fuel Economy
CCP:	Coupled cam phasing
CCR:	California Code of Regulations
cEGR:	Cooled exhaust gas recirculation
CEQA:	California Environmental Quality Act
CFC:	Chlorofluorocarbon
CFR:	Code of Federal Regulations
CGE:	Computable general equilibrium
CH_4:	Methane
CO:	Carbon monoxide
CO_2:	Carbon dioxide
CO_2e:	CO_2- equivalent
cpsi:	Cells per square inch
CVT:	Continuously variable transmission
CVVL:	Continuous variable valve lift
DCP:	Dual cam phasing
DCT:	Dual clutch or automated shift manual transmissions
DEAC:	Cylinder deactivation
DOHC:	Dual overhead cam
DRAM:	California Department of Finance's Dynamic Revenue Analysis Model
dVA:	Digital valve actuation
DVVL:	Discrete variable valve lift
E10:	Fuel that contains a mix of 10% ethanol and 90% gasoline
E-DRAM:	Environmental-DRAM
EFR:	Reduction of engine friction losses
EGR:	Exhaust-gas recirculation
EHPS:	Electro-hydraulic power steering
EMFAC:	ARB Emission Factors model (EMFAC2011)
EPS:	Electric power steering

EV:	Electric vehicle
EV(XX):	Electric vehicle (XX miles of electric range)
EVOH:	Ethylene vinyl alcohol
FCV:	Fuel cell electric vehicle
FEL:	Family Emission Limit
FTP:	Federal Test Procedure
GDI:	Gasoline direct injection
GHG:	Greenhouse gas
g/mi:	Grams per mile
GPF:	Gasoline particulate filter
GVWR:	Gross vehicle weight rating
GWP:	Global Warming Potential
HC:	Hydrocarbons
HCFC:	Hydrochlorofluorocarbon
HEG:	High-efficiency gearbox
HEV:	Hybrid electric vehicle
HFC:	Hydrofluorocarbon
IACC:	Improved Accessories
IATC:	Improved automatic transmission controls
ICM:	Indirect cost multiplier
IPCC:	Intergovernmental Panel on Climate Change
ISO:	International Organization for Standardization
Lbs.:	Pounds
LCFS:	Low carbon fuel standard
LDB:	Low-drag brakes
LDT:	Light-Duty truck
LDT1:	Light-duty truck with a loaded vehicle weight of 0-3750 pounds
LDT2:	Light-duty truck with a loaded vehicle weight of 3751 pounds to a gross vehicle weight rating of 8500 pounds
LDV:	Light-duty vehicle
LEV:	Low-emission vehicle
LHD:	Light heavy-duty
LNT:	Lean NOx trap
LowLeak:	Air conditioning low refrigerant leak
LRRT:	Low rolling resistance tires
LUB:	Low-friction lubricants
LVW	Loaded vehicle weight
Mass:	Mass reduction
MDPV:	Medium-duty passenger vehicle
MDV:	Medium-duty vehicle
mg/mi:	Milligrams per mile
MHEV:	12-volt micro-hybrid
MMT:	Million metric tons
MON:	Motor octane number
MTBE:	Methyl tertiary butyl ether
MY:	Model year

NEV:	Neighborhood electric vehicle
NF_3:	Nitrogen Trifluoride
NGV:	Natural gas vehicles
NHTSA:	National Highway Traffic Safety Administration
NMHC:	Non-methane hydrocarbons
NMOG:	Non-methane organic gas
NMVOC:	Non-methane volatile organic compound
N_2O:	Nitrous oxide
NOx:	Oxides of nitrogen
O_3:	Ozone
OBD:	Onboard diagnostic
OEM:	Original equipment manufacturer
OHV:	Overhead valve
ORVR:	Onboard Refueling Vapor Recovery
PC:	Passenger car
PFC:	Perfluorocarbon
PFI:	Port Fuel Injection
PHEV:	Plug-in hybrid electric vehicle
P2HEV:	Parallel type hybrid electric vehicle
PM:	Particulate matter
PMP:	Particulate Measurement Programme
PSHEV:	Power-split hybrid electric vehicle
PZEV:	Partial zero-emission vehicle, as defined in the "California Exhaust Emission Standards and Test Procedures for 2009 and Subsequent Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes"
REEV(XX):	Range-extender electric vehicle (XX miles of electric capability)
ROG:	Reactive organic gas
ROLL:	Low-rolling-resistance tires
RON:	Research octane number
RPE:	Retail price equivalent factor
RR:	Rolling resistance
RTPA:	Regional transportation planning agencies
SAE:	Society of Automotive Engineers
SAX:	Front or secondary axle disconnect for four-wheel drive systems
SC03:	A test procedure designed to determine emissions associated with the use of an air conditioner; A/C test procedure
SCR:	Selective catalyst reduction
SF_6:	Sulfur Hexafluoride
SFTP:	California Supplemental Federal Test Procedure
SGDI:	Stoichiometric gasoline direct-injection technology
SO_2:	Sulfur dioxide
SPN:	Solid particle number
SULEV:	Super-ultra-low-emission vehicle
TAR:	Technology Assessment Report
TBDS:	Turbocharging and downsizing

TDS:	Turbocharged downsized
UC:	Unified Cycle; a dynamometer driving schedule that is similar to the US06 test cycle, but with less aggressive speeds and acceleration
ULEV:	Ultra-low-emission vehicle
USEPA:	United States Environmental Protection Agency
US06:	A high-speed, high-acceleration, test procedure designed to measure off-cycle emissions
US06 Bag 2:	A test procedure comprised of the middle portion of the US06 cycle
V6:	Vee-formation six-cylinder
VOC:	Volatile organic compounds
VVT:	Variable valve timing
ZEV:	Zero-emission vehicle
2MHEV:	2-mode hybrid electric vehicle
6MAN:	Manual 6-speed transmission
6sp DCT:	6 speed dual clutch transmission

REFERENCES

SECTION II

EXHAUST CRITERIA EMISSIONS

Society of Automotive Engineers, 2011. SAE 2011-01—0296, "Development of Advanced Zone-Coated Three-Way Catalysts"

Society of Automotive Engineers, 2011. SAE 2011-01-0301, "Investigation of LEV-III Aftertreatment Designs"

Society of Automotive Engineers, 2008. SAE 2008-01-0812, "Advanced Washcoat Technology for PZEV Application"

Society of Automotive Engineers, 2009. SAE 2009-01-1070, "Low Rhodium Catalyst Technology for Gasoline and FFV Applications"

Society of Automotive Engineers, 2009. SAE 2009-01-1068, "Development of Third Generation of Gasoline P-ZEV Technology"

Society of Automotive Engineers, 2008. SAE 2008-01-0449, "Development of a Diesel Emission Catalyst System for Meeting US SULEV Standards"

Rogozhin, A., M. Gallaher, W. McManus, 2009. Automobile Industry Retail Price Equivalent and Indirect Cost Multipliers. Prepared for USEPA. EPA-410-09-003. February.

Rogozhin, A., M. Gallaher, G. Helfand, W. McManus, 2010. Using indirect cost multipliers to estimate the total cost of adding new technology in the automobile industry. *International Journal of Production Economics* **124**. 360–368

US Environmental Protection Agency and National Highway Traffic Safety Administration (USEPA and NHTSA), 2011. *Draft Joint Technical Support Document: Proposed Rulemaking for 2017-2025 Light-Duty Vehicle Greenhouse Gas Emission Standards and Corporate Average Fuel Economy Standards.* EPA-420-D-11-901. November.

SFTP EMISSIONS

California Air Resources Board: Supplemental Federal Test Procedure (SFTP) Test Program. Contact – David Eiges, Mobile Source Control Division, California Air Resources Board.

California Air Resources Board: LEV III PM Test Program. Contact – Sherry Zhang, Monitoring and Laboratory Division, California Air Resources Board.

California Air Resources Board, 1997: California Air Resources Board, Public Hearing to Consider Adoption of New Certification Tests and Standards to Control Exhaust Emissions from Aggressive Driving and Air-Conditioner Usage for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles Under 8,501 Pounds Gross Vehicle Weight Rating, July 1997 (Staff Report).
http://www.arb.ca.gov/regact/offcycle/staffrep.pdf

California Air Resources Board, 1997: California Air Resources Board, Public Hearing to Consider Adoption of New Certification Tests and Standards to Control Exhaust Emissions from Aggressive Driving and Air-Conditioner Usage for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles Under 8,501 Pounds Gross Vehicle Weight Rating, July 1997 (Technical Support Document).
http://www.arb.ca.gov/regact/offcycle/tsd.pdf. Last accessed August 8, 2011.

California Air Resources Board, 2006: California Air Resources Board. EMFAC2007. Available at: http://www.arb.ca.gov/msei/onroad/latest_version.htm. Last accessed August 8, 2011.

EVAPORATIVE EMISSIONS

Clontz, R., M. Elum, P. McCrae, R. Williams. 2007. Effects of Low –Purge Vehicle Applications and Ethanol-Containing Fuels on Evaporative Emissions Canister Performance. SAE Paper No. 2007-01-1929, pp. 1716-1717

Haskew, H.M., T.F. Liberty, D. McClement. 2006. Fuel Permeation from Automotive Systems: E0, E6, E10, E20, and E85 Final Report. CRC report E-65-3, pg. 23

Nulman, M., A. Olejnik, M. Samus, E. Fead, G. Rossi. 2001. Fuel Permeation Performance of Polymeric Materials. SAE Paper No. 2001-01-1999, table II

Thomas, E.W. 2009. Fluoroelastomer Compatibility with Bioalcohol Fuels. SAE Paper No. 2009-01-0994, pp. 462-472

Williams, R.S., C.R. Clontz. 2001. Impact and Control of Canister Bleed Emissions. SAE Paper No. 2001-01-0733, pp. 2-8

ON-BOARD DIAGNOSTICS

Society of Automotive Engineers. SAE J1979-DA "Digital Annex of E/E Diagnostic Test Modes", October 2011.

Staff Report: Initial Statement of Reasons (ISOR): Technical Status and Revisions to Malfunction and Diagnostic System Requirements for Heavy-Duty Engines (HD OBD) and Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles and Engines (OBD II), April 10, 2009.

SECTION III

CLIMATE CHANGE

IPCC. (2007a). Climate Change 2007: Synthesis Report. Contribution of Working Groups I, II and III to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change. Cambridge University Press. http://www.ipcc.ch/pdf/assessment-report/ar4/syr/ar4_syr.pdf

Climate Action Team (CAT 2010) Report to the Governor and Legislature. t http://www.energy.ca.gov/2010publications/CAT-1000-2010-004/CAT-1000-2010-004.pdf

IPCC. (2007b). Technical Summary: Climate Change 2007: The Physical Science Basis, Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change. Cambridge University Press. https://www.ipcc-wg1.unibe.ch/publications/wg1-ar4/ar4-wg1-ts.pdf

IPCC (2000), Special Report on Emissions Scenarios (SRES). http://www.ipcc.ch/pdf/special-reports/spm/sres-en.pdf.

IPCC (2007c), Synthesis report. http://www.ipcc.ch/pdf/assessment-report/ar4/syr/ar4_syr_spm.pdf

Zhao, C., A. E. Andrews, L. Bianco, J. Eluszkiewicz, A. Hirsch, C. MacDonald, T. Nehrkorn, and M. L. Fischer (2009). Atmospheric inverse estimates of methane emissions from Central California, J. Geophys. Res., 114, D16302, doi:10.1029/2008JD011671.

Ramanathan, V. and G. Carmichael (2008) Global and regional climate changes due to black carbon. Nature Geoscience 156, 221-227.

IPCC (2007d), Working Group I: The Physical Science Basis, Chapter 2: Changes in Atmospheric Constituents and in Radiative Forcing. http://www.ipcc.ch/pdf/assessment-report/ar4/wg1/ar4-wg1-chapter2.pdf

Office of Environmental Health Hazard Assessment. Environmental Protection Indicators for California (EPIC), 2009. http://oehha.ca.gov/multimedia/epic/pdf/ClimateChangeIndicatorsApril2009.pdf

Lee, J., S. De Gryze, J. Six. (2009). Effect of Climate Change on Field Crop Production in the Central Valley of California. California Energy Commission. CEC-500-2009-041-F. http://www.energy.ca.gov/2009publications/CEC-500-2009-041/CEC-500-2009-041-F.pdf

Westerling, A.L., B. P. Bryant, H.K. Preisler, H G. Hidalgo, and T. Das. (2009). Climate Change, Growth, and California Wildfire. California Energy Commission. CEC-500-2009-046-F. http://www.energy.ca.gov/2009publications/CEC-500-2009-046/CEC-500-2009-046-F.pdf

Vicuna, S.R. Leonardson, M. Hanemann, L. Dale, and J. Dracup. (2008). "Climate change impact on high elevation hydropower generation in California's Sierra Nevada: A case study in the upper American River." Climatic Change **87**:S123–S137.

Hadley, O.L., C.E. Corrigan, T.W. Kirchstetter, S.S. Cliff, and V. Ramanathan (2010). Measured black carbon deposition on the Sierra Nevada snow pack and implication for snow pack retreat, Atmos. Chem. Phys., 10, 7505-7513, doi:10.5194/acp-10-7505.

The future is now: An update on climate change science impacts and response options for California (2008). Publication # CEC-500-2008-071. http://www.energy.ca.gov/2008publications/CEC-500-2008-071/CEC-500-2008-071.pdf

GREENHOUSE GAS EMISSIONS

An, F., and DeCicco, J.M., 2007. Trends in Technical Efficiency Trade-Offs for the U.S. Light Vehicle Fleet. Society of Automotive Engineers. 2007-01-1325.

California Senate, 2006. *SB 1505 Senate Bill; Fuel Hydrogen Alternative Fuel.* Lowenthal. http://www.leginfo.ca.gov/pub/05-06/bill/sen/sb_1501-1550/sb_1505_bill_20060930_chaptered.html. Accessed July 14, 2010.

California Air Resources Board (CARB), 2008a. *Climate Change Scoping Plan: A Framework for Change.* December.

California Air Resources Board (CARB), 2008b. *Concept Paper: Environmental and Energy Standards for Hydrogen Production Senate Bill 1505.* http://www.arb.ca.gov/msprog/hydprod/1505concepts.pdf. April 3.

California Air Resources Board (CARB), 2009a. *Detailed California-Modified GREET Pathway for California Average and Marginal Electricity.* Version 2.1. February 27.

California Air Resources Board (CARB), 2009b. *Detailed California Modified GREET Pathway for Compressed Gaseous Hydrogen from North American Natural Gas.* Version 2.1. February 27.

California Air Resources Board (CARB), 2010b. *Proposed Regulation for a California Renewable Electricity Standard Staff Report: Initial Statement of Reasons*. Appendix D. Supporting Documentation for the Environmental Analysis. June.

California Energy Commission (CEC), 2011. *Transportation Fuel Price and Demand Forecasts: Inputs and Methods for the 2011 Integrated Energy Policy Report - FINAL STAFF REPORT*. Publication # CEC-600-2011-001. *http://www.energy.ca.gov/2011publications/CEC-600-2011-001/CEC-600-2011-001.PDF*

Energy and Environmental Economics, Inc., (EEE), 2010a. *Greenhouse Gas Modeling of California's Electricity Sector to 2020: Updated Results of the GHG Calculator Version 3b Update.* Prepared for California Public Utilities Commission. October.

Energy and Environmental Economics, Inc., (EEE), 2010b. GHG Calculator Version 3c. *http://www.ethree.com/documents/GHG%20update/GHG%20Calculator%20version%203c_Oct2010.zip*. October.

FEV, 2011. Light-Duty Technology Cost Analysis Power-split and P2 HEV Case Studies. Prepared for USEPA.

FEV, 2010. Light-Duty Technology Cost Analysis: Report on Additional Case Studies. Prepared for USEPA. EPA-420-R-10-010. April.

FEV, 2009. Light-Duty Technology Cost Analysis Pilot Study. Prepared for USEPA. EPA-420-R-09-020. December.

Lee, S., B. Lee, H. Zheng, C. Sze, L. Quinones, and J. Sanchez, 2011. Development of Greenhouse Gas Emissions Model for 2014-2017 Heavy- and Medium-Duty Vehicle Compliance, SAE 2011 Commercial Vehicle Engineering Congress, Chicago, September 2011, SAE Paper 2011-01-2188.

Lotus Engineering, Inc., 2010, *An Assessment of Mass reduction Opportunities for a 2017 – 2020 Model Year Vehicle Program"*, Rev 006A.

Lutsey, N., 2010. *Review of Technical Literature and Trends Related to Automobile Mass-Reduction Technology.* Institute of Transportation Studies, University of California, Davis. UCD-ITS-RR-10-10.

Lutsey, N. and D. Sperling, 2005. Energy efficiency, fuel economy, and policy implications. Transportation Research Record. 1941: 8-17.

Lutsey, N. and D. Sperling, 2010. Toward integration of vehicle and fuel regulation: California case study. Transportation Research Record. 2191: 100-110.

National Research Council (NRC). 2011. *Assessment of Fuel Economy Technologies*

for Light-Duty Vehicles. Washington D.C.

Nelson, P.A., K.G. Gallagher, I. Bloom, and D.W. Dees, 2011. *Modeling the Performance and Cost of Lithium-Ion Batteries for Electric-Drive Vehicles.* Final Report Submitted to the Environmental Protection Agency. Argonne National Laboratory. July 15.

Northeast States Center for a Clean Air Future (NESCCAF), 2004. *Reducing Greenhouse Gas Emissions from Light-Duty Motor Vehicles.* September 2004.

Ricardo, Inc., 2011. *Computer Simulation of Light-Duty Vehicle Technologies for Greenhouse Gas Emission Reduction in the 2020-2025 Timeframe.* Prepared for U.S. Environmental Protection Agency.

Rogozhin, A., M. Gallaher, W. McManus, 2009. Automobile Industry Retail Price Equivalent and Indirect Cost Multipliers. Prepared for USEPA. EPA-410-09-003. February.

Rogozhin, A., M. Gallaher, G. Helfand, W. McManus, 2010. Using indirect cost multipliers to estimate the total cost of adding new technology in the automobile industry. *International Journal of Production Economics* **124**. 360–368

Santini, D., K. Gallagher, and P. Nelson, 2010. Modeling of Manufacturing Costs of Lithium-Ion Batteries for HEVs, PHEVs, and EVs. *Electric Vehicle Symposium* (EVS25). Shenzhen, China. November 5-9.

Society of Automotive Engineers, Cancelled 2002. J1634: Electric Vehicle Energy Consumption and Range Test Procedure. http://standards.sae.org/j1634_200210 (and see http://standards.sae.org/wip/j1634).

Society of Automotive Engineers, 2008. J2727: HFC-134a Mobile Air Conditioning System Refrigerant Emission Chart. http://standards.sae.org/j2727_200808.

Society of Automotive Engineers, 2010. J1711: Recommended Practice for Measuring the Exhaust Emissions and Fuel Economy of Hybrid-Electric Vehicles, Including Plug-in Hybrid Vehicles. http://standards.sae.org/j1711_201006.

Society of Automotive Engineers, 2010. J2841: Utility Factor Definitions for Plug-In Hybrid Electric Vehicles Using Travel Survey Data. http://standards.sae.org/j2841_201009.

US Environmental Protection Agency (USEPA), 2011. Peer Review of the Greenhouse gas Emissions Model (GEM) and EPA's Response to Comments, Docket # EPA-HQ-OAR-2010-0162-3418, Publication Number: EPA-420-R-11-007. July.

U.S. Environmental Protection Agency and National Highway Traffic Safety

Administration (USEPA and NHTSA), 2010. *Light-Duty Vehicle Greenhouse Gas Emission Standards and Corporate Average Fuel Economy Standards; Final Rule.*

U.S. Environmental Protection Agency (USEPA), 2010. *Light-duty automotive technology, carbon dioxide emissions, and fuel economy trends: 1975 Through 2010.* EPA420-R-10-023.

U.S. Environmental Protection Agency (USEPA), National Highway Traffic Safety Administration (NHTSA), and California Air Resources Board (CARB), 2010. *Interim Technical Assessment Report: Light-Duty Vehicle Greenhouse Gas Emission Standards and Corporate Average Fuel Economy Standards in Model Years 2017-2025.* http://www.epa.gov/otaq/climate/regulations/ldv-ghg-tar.pdf. September.

U.S. Environmental Protection Agency and National Highway Traffic Safety Administration (US EPA and NHTSA), 2011a. 2017–2025 Model Year Light-Duty Vehicle GHG Emissions and CAFE Standards: Supplemental Notice of Intent. Federal Register. Vol. 76, No. 153. August 9.

US Environmental Protection Agency and National Highway Traffic Safety Administration (USEPA and NHTSA), 2011b. *2017 and Later Model Year Light-Duty Vehicle Greenhouse Gas Emissions and Corporate Average Fuel Economy Standards; Proposed Rule.* Prepublication Draft. November 16.

US Environmental Protection Agency and National Highway Traffic Safety Administration (USEPA and NHTSA), 2011c. *Draft Joint Technical Support Document: Proposed Rulemaking for 2017-2025 Light-Duty Vehicle Greenhouse Gas Emission Standards and Corporate Average Fuel Economy Standards.* EPA-420-D-11-901. November.

Yeh, S., N. Lutsey, N. Parker, 2009. Assessment of technologies to meet a low carbon fuel standard. *Environmental Science & Technology* **43**(18): 6907-6914.

SECTION IV

U.S. Energy Information Administration. "Refiner Motor Gasoline Sales Volumes." *Petroleum & Other Liquids.* 1 August 2011. Online 8 August 2011. http://www.eia.doe.gov/dnav/pet/pet_cons_refmg_c_SCA_EPMM_mgalpd_m.htm

SECTION V

FUEL CYCLE EMISSIONS

Argonne National Laboratory (ANL), 2007. GREET 2.7 Vehicle Cycle Model. *http://greet.es.anl.gov/greet_2_series*.

California Air Resources Board (CARB), 2009. *CA-GREET 1.8b.* http://www.arb.ca.gov/fuels/lcfs/lcfs.htm. December.

Energy and Environmental Economics, Inc., (EEE), 2010a. *Greenhouse Gas Modeling of California's Electricity Sector to 2020: Updated Results of the GHG Calculator Version 3b Update.* Prepared for California Public Utilities Commission. October.

Energy and Environmental Economics, Inc., (EEE), 2010b. GHG Calculator Version 3c. http://www.ethree.com/documents/GHG%20update/GHG%20Calculator%20version%203c_Oct2010.zip. October.

Kim,H-J, C. McMillan, G.A. Keoleian, and S.J. Skerlos, 2010. Greenhouse Gas Emissions Payback for Lightweighted Vehicles Using Aluminum and High-Strength Steel. *Journal of Industrial Ecology* **14**(6): 929-946.

Patterson, J., M. Alexander, and A. Gurr, 2011. Preparing for a Life Cycle CO_2 Measure. Prepared for Low-Carbon Vehicle Partnership. May 20.

REBOUND EFFECT

Hymel, K., K. Small, and K. Van Dender (2010) Induced Demand and Rebound Effects in Road Transport, *Transportation Research B*, 44(10): 1220-1241.

HEALTH EFFECTS

CARB 2010 Appendix J of Staff Report, Initial Statement of Reasons for Proposed Rulemaking, "Proposed Amendments to the Truck and Bus Regulation, the Drayage Truck Regulation and the Tractor-Trailer Greenhouse Gas Regulation" (2010)

CDOF. California Department of Finance population projection web site. Available at: http://www.dof.ca.gov/research/demographic/reports/view.php
(File: Compiled Health Tables ACC 2dec11.xls)

CDPH. California Department of Public Health statistics web site. Available at: http://www.cdph.ca.gov/data/statistics/Pages/default.aspx
(File: Compiled Health Tables ACC 2dec11.xls)

Fann N, Fulcher CM and Hubbell BJ. 2009. The influence of location, source, and emission type in estimates of the human health benefits of reducing a ton of air pollution Air Quality. Atmosphere & Health. 2:169-176.

Fotheringham S and Rogerson P, editors. 1994. Spatial Analysis and GIS. London. Taylor and Francis. Chapter 7, pp 121-145.

Goodchild M and Lam N. 1980. Areal interpolation: a variant of the traditional spatial problem. Geo-processing, 1: 297-312.

Goodin WR, McRae GJ and Seinfeld JH. 1979. A Comparison of Interpolation Methods for Sparse Data: Application to Wind and Concentration Fields. J Applied Meteor. 18:761-771.

Krewski D, Jerrett M, Burnett RT, Ma R, Hughes E, Shi Y, Turner MC, Pope CA III, Thurston G, Calle EE and Thun MJ. 2009. Extended follow-up and spatial analysis of the American Cancer Society study linking particulate air pollution and mortality. HEI Research Report, 140, Health Effects Institute, Boston, MA.

Shepard D. 1968. A two-dimensional interpolation function for irregularly-spaced data. Proceedings of the 1968 ACM National Conference. Pp. 517–524.
US Census Bureau. American Fact Finder web site. Available at: http://factfinder.census.gov/home/saff/main.html?_lang=en

US Census Bureau. American Fact Finder web site. Available at: http://factfinder.census.gov/home/saff/main.html?_lang=en
(File: Compiled Health Tables ACC 2dec11.xls)

US EPA. 2010. Quantitative Health Risk Assessment for Particulate Matter Available at: http://www.epa.gov/ttn/naaqs/standards/pm/data/PM_RA_FINAL_June_2010.pdf

SECTION IX

ECONOMIC ANALYSIS

Allcott, H. and N. Wozny (2011) Gasoline Prices, Fuel Economy, and the Energy Paradox, MIT Working Paper.

Busse, Meghan, Christopher Knittel, and Florian Zettelmeyer (2011) Pain at the Pump: How Gasoline Prices Affect Automobile Purchasing, NBER Working Paper #15590.

California Energy Commission (2011) Transportation Energy Forecasts and Analyses for the 2011 Integrated Energy Policy Report, Draft Staff Report. CEC-600-2011-007-SD.

Gillingham, K., R. Newell, and K. Palmer (2009) Energy Efficiency Economics and Policy, *Annual Review of Resource Economics*, 1: 597-619

Helfand, G. and A. Wolverton (2011) Evaluating the Consumer Response to Fuel Economy: A Review of the Literature, *International Review of Environmental and Resource Economics*, 5(2): 103-146

Metcalf, G., and K. Hassett (1999) Measuring the Energy Savings From Home Improvement Investments: Evidence From Monthly Billing Data, *The Review of Economics and Statistics*, 81(3): 516-528.

Tietenberg, T. (2009). "Reflections – Energy Efficiency Policy: Pipe Dream or Pipeline to the Future?" *Review of Environmental Economics and Policy* 3 (2): 304 -320.

APPENDICES

APPENDIX A: Proposed Regulation Order
APPENDIX B: Environmental Analysis for the Advanced Clean Cars Program
APPENDIX C: Proposed Amendments to the "California Exhaust Emission Standards and Test Procedures for 2001 and Subsequent Model Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles"
APPENDIX D: Proposed New "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles"
APPENDIX E: Proposed Amendments to the " California Non-Methane Organic Gas Test Procedures"
APPENDIX F: Proposed Amendments to the "California Evaporative Emission Standards and Test Procedures for 2001 and Subsequent Model Motor Vehicles"
APPENDIX G: Proposed Amendments to the "California Refueling Emission Standards and Test Procedures for 2001 and Subsequent Model Motor Vehicles"
APPENDIX H: Proposed Amendments to the "Specifications for Fill Pipes and Openings of Motor Vehicle Fuel Tanks"
APPENDIX I: Proposed New "Specifications for Fill Pipes and Openings of 2015 and Subsequent Motor Vehicle Fuel Tanks"
APPENDIX J: Proposed Amendments to the "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Otto-Cycle Engines"
APPENDIX K: Proposed Amendments to the "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Diesel Engines and Vehicles"
APPENDIX L: Proposed Amendments to the "California Environmental Performance Label Specifications for 2009 and Subsequent Model Year Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles "
APPENDIX M: Proposed Amendments to the "California Test Procedure for Evaluating Substitute Fuels and New Clean Fuels "
APPENDIX N: Proposed New "California Test Procedure for Evaluating Substitute Fuels and New Clean Fuels in 2015 and Subsequent Years"
APPENDIX O: Technical Support Document - Development of Supplemental Federal Test Procedures Standards
APPENDIX P: Technical Support Document - Development of PM Standards
APPENDIX Q: Technical Support Document - Development of LEV III Greenhouse Gas Standards
APPENDIX R: Technical Support Document - GHG Non-Test Cycle Provisions
APPENDIX S: Technical Support Document - Economic Analysis
APPENDIX T: Technical Support Document - Emissions Benefit Analysis
APPENDIX U: Technical Support Document - Climate Change Impacts of Black Carbon Particles

APPENDIX A - PROPOSED REGULATION ORDER

Amendments to Sections 1900, 1956.8, 1960.1, 1961, 1961.1, 1965, 1968.2, 1968.5, 1976, 1978, 2037, 2038, 2062, 2112, 2139, 2140, 2145, 2147, 2235, and 2317, and
Adoption of new Sections 1961.2 and 1961.3,
Title 13, California Code of Regulations

Set forth below are the proposed amendments to title 13 of the California Code of Regulations. Amendments to existing section proposed and subject to comment in this rulemaking are shown in underline to indicate additions and ~~strikeout~~ to indicate deletions. Subsections for which no changes are proposed in this rulemaking are indicated with [No change] or "* * * *". Sections 1961.2 and 1961.3 are new sections, shown without underline for easier reading.

TABLE OF CONTENTS

Section Page No.

1. Section 1900 1
2. Section 1956.8. 4
3. Section 1960.1 10
4. Section 1961 15
5. Section 1961.1. 26
6. Section 1961.2. 35
7. Section 1961.3. 68
8. Section 1965 110
9. Section 1968.2. 111
10. Section 1968.5. 126
11. Section 1976 129
12. Section 1978 139
13. Section 2037 142
14. Section 2038. 143
15. Section 2062 144
16. Section 2112 145
17. Section 2139 146
18. Section 2140 148
19. Section 2145 149
20. Section 2147 150
21. Section 2235 151
22. Section 2317 152

1. Amend title 13, CCR, section 1900 to read as follows:

§ 1900. Definitions.

* * * *

(b) In addition to the definitions incorporated under subdivision (a), the following definitions shall govern the provisions of this chapter.

* * * *

(9) "Intermediate volume manufacturer" means any pre-2001 model year manufacturer with California sales between 3,001 and 60,000 new light- and medium-duty vehicles per model year based on the average number of vehicles sold by the manufacturer each model year from 1989 to 1993; any 2001 through 2002 model year manufacturer with California sales between 4,501 and 60,000 new light- and medium-duty vehicles per model year based on the average number of vehicles sold by the manufacturer each model year from 1989 to 1993; ~~and~~ any 2003 ~~and subsequent~~ through 2017 model year manufacturer with California sales between 4,501 and 60,000 new light- and medium-duty vehicles based on the average number of vehicles sold for the three previous consecutive model years for which a manufacturer seeks certification; and any 2018 and subsequent model year manufacturer with California sales between 4,501 and 20,000 new light- and medium-duty vehicles based on the average number of vehicles sold for the three previous consecutive model years for which a manufacturer seeks certification. For a manufacturer certifying for the first time in California, model year sales shall be based on projected California sales. A manufacturer's California sales shall consist of all vehicles or engines produced by the manufacturer and delivered for sale in California, except that vehicles or engines produced by the manufacturer and marketed in California by another manufacturer under the other manufacturer's nameplate shall be treated as California sales of the marketing manufacturer.

For purposes of applying the 2005 ~~and subsequent~~ through 2017 model year zero-emission vehicle requirements for intermediate-volume manufacturers under section 1962(b) or 1962.1(b), as applicable, the annual sales from different firms shall be aggregated in the case of (1) vehicles produced by two or more firms, each one of which either has a greater than 50% equity ownership in another or is more than 50% owned by another; or (2) vehicles produced by any two or more firms if a third party has equity ownership of greater than 50% in each firm.

For purposes of applying the 2009 ~~and subsequent~~ through 2016 model year Greenhouse Gas requirements for intermediate volume manufacturers under section 1961.1, the annual sales from different firms shall be aggregated in the

following situations: (1) vehicles produced by two or more firms, each one of which either has a greater than 10% equity ownership in another or is more than 10% owned by another; or (2) vehicles produced by any two or more firms if a third party has equity ownership of greater than 10% in each firm.

For the 2018 and subsequent model years, the annual sales from different firms shall be aggregated in the following situations: (1) vehicles produced by two or more firms, one of which is 33.4% or greater part owned by another; or (2) vehicles produced by any two or more firms if a third party has equity ownership of 33.4% or more in each of the firms; or (3) vehicles produced by two or more firms having a common corporate officer(s) who is (are) responsible for the overall direction of the companies; or (4) vehicles imported or distributed by any firms where the vehicles are manufactured by the same entity and the importer or distributor is an authorized agent of the entity.

* * * *

(22) "Small volume manufacturer" means, with respect to the 2001 and subsequent model-years, a manufacturer with California sales less than 4,500 new passenger cars, light-duty trucks, medium-duty vehicles, heavy-duty vehicles and heavy-duty engines based on the average number of vehicles sold for the three previous consecutive model years for which a manufacturer seeks certification as a small volume manufacturer; however, for manufacturers certifying for the first time in California model-year sales shall be based on projected California sales. A manufacturer's California sales shall consist of all vehicles or engines produced by the manufacturer and delivered for sale in California, except that vehicles or engines produced by the manufacturer and marketed in California by another manufacturer under the other manufacturer's nameplate shall be treated as California sales of the marketing manufacturer. Except as provided in the next paragraph, ~~beginning with~~ for the 2009 through 2017 model years, the annual sales from different firms shall be aggregated in the following situations: (1) vehicles produced by two or more firms, one of which is 10% or greater part owned by another; or (2) vehicles produced by any two or more firms if a third party has equity ownership of 10% or more in each of the firms; or (3) vehicles produced by two or more firms having a common corporate officer(s) who is (are) responsible for the overall direction of the companies; or (4) vehicles imported or distributed by ~~all~~ any firms where the vehicles are manufactured by the same entity and the importer or distributor is an authorized agent of the entity.

For purposes of compliance with the zero-emission vehicle requirements, heavy-duty vehicles and engines shall not be counted as part of a manufacturer's sales. For purposes of applying the 2005 ~~and subsequent~~ through 2017 model year zero-emission vehicle requirements for small-volume manufacturers under sections 1962(b) and 1962.1(b), the annual sales from different firms shall be aggregated in the case of (1) vehicles produced by two or more firms, each one

of which either has a greater than 50% equity ownership in another or is more than 50% owned by another; or (2) vehicles produced by any two or more firms if a third party has equity ownership of greater than 50% in each firm.

For the 2018 and subsequent model years, the annual sales from different firms shall be aggregated in the following situations: (1) vehicles produced by two or more firms, one of which is 33.4% or greater part owned by another; or (2) vehicles produced by any two or more firms if a third party has equity ownership of 33.4% or more in each of the firms; or (3) vehicles produced by two or more firms having a common corporate officer(s) who is (are) responsible for the overall direction of the companies; or (4) vehicles imported or distributed by any firms where the vehicles are manufactured by the same entity and the importer or distributor is an authorized agent of the entity.

NOTE: Authority cited: Sections 39600, 39601, 43013, 43018, 43101, and 43104 Health and Safety Code. Reference: Sections 39002, 39003, 39010, 39500, 40000, 43000, 43013, 43018.5, 43100, 43101, 43101.5, 43102, 43103, 43104, 43106, and 43204, Health and Safety Code.

2. Amend title 13, CCR, section 1956.8 to read as follows:

§ 1956.8. Exhaust Emission Standards and Test Procedures - 1985 and Subsequent Model Heavy-Duty Engines and Vehicles.

* * * *

(b) The test procedures for determining compliance with standards applicable to 1985 and subsequent model heavy-duty diesel engines and vehicles and the requirements for participating in the averaging, banking and trading programs, are set forth in the "California Exhaust Emission Standards and Test Procedures for 1985 through 2003 Model Heavy-Duty Diesel-Engines and Vehicles, " adopted April 8, 1985, as last amended December 12, 2002, the "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Diesel Engines and Vehicles," adopted December 12, 2002, as last amended ~~October 12, 2011~~ [insert date of amendment for this rulemaking], and the "California Interim Certification Procedures for 2004 and Subsequent Model Hybrid-Electric Vehicles, in the Urban Bus and Heavy-Duty Vehicle Classes," adopted October 24, 2002, which are incorporated by reference herein.

* * * *

(c)(1)(B) The exhaust emissions from new 2005 and subsequent model heavy-duty Otto-cycle engines, except for Otto-cycle medium- and heavy-duty engines subject to the alternative standards in 40 CFR §86.005-10(f), shall not exceed:

California Emission Standards for 2005 and Subsequent Model Heavy-Duty Otto-Cycle Engines[A]
(in g/bhp-hr)

Model Year	*Emission Category*	*NMHC + NOx*	*NMHC*	*NOx*	*CO[FG]*	*HCHO*	*PM*
Standards for Heavy-Duty Otto-Cycle Engines Used in 2005 through 2019 Model Incomplete Medium-Duty Vehicles 8,501 to 10,000 ~~14,000~~ pounds GVW[B] and 2005 and Subsequent Model Incomplete Medium-Duty Vehicles 10,001 to 14,000 pounds GVW[C]							
2005 through 2007	ULEV	1.0[C,E]	n/a	n/a	14.4	0.05	n/a
	SULEV	0.5	n/a	n/a	7.2	0.025	n/a
2008 and subsequent	ULEV	n/a	0.14[E]	0.20[E]	14.4	0.01	0.01
	SULEV	n/a	0.07[E]	0.10[E]	7.2	0.005	0.005
Standards for Heavy-Duty Otto-Cycle Engines Used In Heavy-Duty Vehicles Over 14,000 pounds GVW							
2005 through 2007	n/a	1.0[C,ED,F]	n/a	n/a	37.1	0.05[DE]	n/a
2008 and subsequent	n/a	n/a	0.14[E]	0.20[E]	14.4	0.01	0.01

[A] These standards apply to petroleum-fueled, alcohol-fueled, liquefied petroleum gas-fueled and natural gas-fueled Otto-cycle engines.

[B] For the 2020 and subsequent model years, medium-duty vehicles 8,501 to 10,000 pounds GVW must certify to the primary emission standards and test procedures for complete vehicles specified in section 1961.2, title 13, CCR.

[~~B~~C] A manufacturer of engines used in incomplete medium-duty vehicles may choose to comply with these standards as an alternative to the primary emission standards and test procedures for complete vehicles specified in section 1961 or 1961.2, title 13, CCR. A manufacturer that chooses to comply with these optional heavy-duty engine standards and test procedures shall specify, in the Part I application for certification, an in-use compliance test procedure, as provided in section 2139(c), title 13 CCR.

[CD] A manufacturer may request to certify to the Option 1 or Option 2 federal NMHC + NOx standards as set forth in 40 CFR § 86.005-10(f). However, for engines used in medium-duty vehicles, the formaldehyde level must meet the standard specified above.

[DE] This standard only applies to methanol-fueled Otto-cycle engines.

[EF] A manufacturer may elect to include any or all of its medium- and heavy-duty Otto-cycle engine families in any or all of the emissions ABT programs for HDEs, within the restrictions described in section I.15 of the "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Otto-Cycle Engines," incorporated by reference in section 1956.8(d). For engine families certified to the Option 1 or 2 federal standards, the FEL must not exceed 1.5 g/bhp-hr. If a manufacturer elects to include engine families certified to the 2005 and subsequent model year standards, the NOx plus NMHC FEL must not exceed 1.0 g/bhp-hr. For engine families certified to the 2008 and subsequent model year standards, the FEL is the same as set forth in 40 CFR 86.008-10(a)(1).

[FG] Idle carbon monoxide: For all Otto-cycle heavy-duty engines utilizing aftertreatment technology, and not certified to the on-board diagnostics requirements of section 1968, et seq, as applicable, the CO emissions shall not exceed 0.50 percent of exhaust gas flow at curb idle.

---

* * * *

(3) *Optional Standards for Complete Heavy-Duty Vehicles that Use Heavy-Duty Otto-Cycle Engines.* Manufacturers may request to group complete heavy-duty Otto-cycle vehicles into the same test group as Otto-cycle vehicles certifying to the LEV III exhaust emission standards and test procedures specified in title 13, CCR, §1961.2, so long as those complete heavy-duty Otto-cycle vehicles meet the most stringent LEV III standards to which any vehicle within that test group certifies.

* * * *

(d) The test procedures for determining compliance with standards applicable to 1987 and subsequent model heavy-duty Otto-cycle engines and vehicles are set forth in the "California Exhaust Emission Standards and Test Procedures for 1987 through 2003 Model Heavy-Duty Otto-Cycle Engines and Vehicles," adopted April 25, 1986, as last amended December 27, 2000, the "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Otto-Cycle Engines," adopted December 27, 2000, as last amended ~~September 27, 2010~~ [insert date of amendment for this rulemaking], the "California Non-Methane Organic Gas Test Procedures," adopted July 12, 1991, as last amended ~~July 30, 2002~~ [insert date of amendment for this rulemaking], and the "California Interim Certification Procedures for 2004 and Subsequent Model Hybrid-Electric Vehicles, in the Urban Bus and Heavy-Duty Vehicle Classes," adopted October 24, 2002, which are incorporated by reference herein.

* * * *

(h) The exhaust emissions from new:

* * * *

(2) 1992 and subsequent model diesel engines used in medium-duty low-emission vehicles, ultra-low-emission vehicles and super-ultra-low-emission vehicles shall not exceed:

Exhaust Emission Standards for Engines Used in 1992 through 2004 Model Incomplete Otto-Cycle Medium-Duty Low-Emission Vehicles, Ultra-Low-Emission Vehicles, and Super Ultra-Low-Emission Vehicles, and ~~for~~ 1992 and Subsequent Model Diesel Engines Used in Medium-Duty Low-Emission Vehicles, Ultra-Low-Emission Vehicles, and Super Ultra-Low-Emission Vehicles[A,F]

(grams per brake horsepower-hour)

Model Year	*Vehicle Emissions Category*[B]	*Carbon Monoxide*	*NMHC + NOx*[C]	*Non-Methane Hydrocarbons*	*Oxides of Nitrogen*	*Formaldehyde*	*Particulates*[D]
1992[E] - 2001	LEV	14.4	3.5[K]	n/a	n/a	0.050	0.10[K]
2002-2003[E]	LEV	14.4	3.0[K]	n/a	n/a	0.050	0.10[K]
1992-2003[E,H]	ULEV	14.4	2.5[K]	n/a	n/a	0.050	0.10[K]
2004-2006 ~~and subsequent~~[L]	ULEV - Opt A	14.4	2.5[I,J,K]	n/a	n/a	0.050	0.10[J,K]
2004-2006 ~~and subsequent~~[L]	ULEV - Opt. B	14.4	2.4[I,J,K]	n/a	n/a	0.050	0.10[J,K]
2007 and subsequent[D] (diesel only)	ULEV	15.5	n/a	0.14	0.20	0.050	0.01
1992-2006 ~~and subsequent~~[L]	SULEV	7.2	2.0[K]	n/a	n/a	0.025	0.05[K]
2007 and subsequent[D] (diesel only)	SULEV	7.7	n/a	0.07	0.10	0.025	0.005

[A] This set of standards is optional. For the 1992 through 2019 model years, m~~M~~anufacturers of engines used in incomplete medium-duty vehicles or diesel engines used in medium-duty vehicles from 8501-10,000 ~~14,000~~ pounds gross vehicle weight rating may choose to comply with these standards as an alternative to the primary emission standards and test procedures specified in section 1960.1, ~~or~~ section 1961, or section 1961.2 Title 13, California Code of Regulations. For the 1992 and subsequent model years, manufacturers of engines used in incomplete medium-duty vehicles or diesel engines used in medium-duty vehicles from 10,001-14,000 pounds gross vehicle weight rating may choose to comply with these standards as an alternative to the primary emission standards and test procedures specified in section 1960.1, section 1961, or section 1961.2 Title 13, California Code of Regulations. For the 2020 and subsequent model years, both incomplete medium-duty vehicles and medium-duty vehicles that use a diesel engine 8,501 to 10,000 pounds GVW must certify to

the primary emission standards and test procedures for complete vehicles specified in section 1961.2, title 13, CCR. Manufacturers that choose to comply with these optional heavy-duty standards and test procedures shall specify, in the application for certification, an in-use compliance test procedure, as provided in section 2139(c), Title 13, California Code of Regulations.

B "LEV" means low-emission vehicle.
"ULEV" means ultra-low-emission vehicle.
"SULEV" means super ultra-low-emission vehicle.

C This standard is the sum of the individual non-methane hydrocarbon emissions and oxides of nitrogen emissions. For methanol-fueled engines, non-methane hydrocarbons shall mean organic material hydrocarbon equivalent ("OMHCE").

D These standards apply only to diesel engines and vehicles.

E Manufacturers may certify engines used in incomplete medium-duty vehicles or diesel engines used in medium-duty vehicles to these standards to meet the requirements of section 1956.8(g), Title 13, California Code of Regulations.

F In-use compliance testing shall be limited to vehicles or engines with fewer than 90,000 miles.

G [Reserved]

H For engines certified to the 3.5 grams per brake horsepower-hour (g/bhp-hr) LEV standards, the in-use compliance standard shall be 3.7 g/bhp-hr for the first two model years of introduction. For engines certified to the 2002 and 2003 model year LEV standards, the in-use compliance standard shall be 3.2 g/bhp-hr. For engines certified to the 1992 through 2003 model year ULEV standards, the in-use compliance standard shall be 2.7 g/bhp-hr for the first two model years of introduction. For engines certified to the 1992 and subsequent SULEV standards, the in-use compliance standard shall be 2.2 g/bhp-hr for the first two model years of introduction.

I Manufacturers have the option of certifying to either option A or B. Manufacturers electing to certify to Option A must demonstrate that the NMHC emissions do not exceed 0.5 g/bhp-hr.

J Emissions averaging may be used to meet these standards for diesel engines, using the requirements for participation in averaging, banking and trading programs, as set forth in the "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Diesel Engines and Vehicles," incorporated by reference in section 1956.8 (b), above.

K Engines of 1998 and subsequent model years may be eligible to generate averaging, banking and trading credits based on these standards according to the requirements of the averaging, banking and trading programs described in the "California Exhaust Emission Standards and Test Procedures for 1985 through 2003 Model Heavy-Duty Engines and Vehicles" and the "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Diesel Engines and Vehicles," incorporated by reference in section 1956.8(b), above.

L For the 2005 and 2006 model years, these emission standards only apply to diesel engine and vehicles. ~~For 2007 and subsequent model year diesel engines used in medium-duty vehicles, these emission standards are not applicable.~~

---

* * * *

(5) *Optional Standards for Complete Heavy-Duty Vehicles that Use Heavy-Duty Diesel Engines.* Manufacturers may request to group complete heavy-duty diesel vehicles into the same test group as medium-duty diesel vehicles certifying to the LEV III exhaust emission standards and test procedures specified in title 13, CCR, §1961.2, so long as those complete heavy-duty diesel vehicles meet the most stringent LEV III standards to which any vehicle within that test group certifies.

NOTE: Authority cited: Sections 39500, 39600, 39601, 43013, 43018, 43100, 43101, 43102, 43104, 43105, 43106, 43107 and 43806, Health and Safety Code; and Section 28114, Vehicle Code. Reference: Sections 39002, 39003, 39500, 39667, 43000, 43009.5, 43013, 43017, 43018, 43100, 43101, 43101.5, 43102, 43104, 43105, 43106, 43107, 43202, 43204, 43205, 43205.5, 43206, 43210, 43211, 43212, 43213, and 43806, Health and Safety Code; and Section 28114, Vehicle Code.

3. Amend title 13, CCR, section 1960.1 to read as follows:

§ 1960.1. Exhaust Emission Standards and Test Procedures - 1981 through 2006 Model Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles.

* * * *

(r) *4000-Mile Supplemental FTP Emission Standards.* The Supplemental Federal Test Procedure (SFTP) standards in this section are ~~represent~~ the maximum SFTP exhaust emissions at 4,000 miles ± 250 miles or at the mileage determined by the manufacturer for emission-data vehicles in accordance with the "California Exhaust Emission Standards and Test Procedures for 1988 Through 2000 Model Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," as incorporated by reference in section 1960.1(k), and with the "California 2001 through 2014 Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and ~~for 2001~~ 2009 through 2016 ~~and Subsequent~~ Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," as incorporated by reference in section 1961(d). The SFTP exhaust emission levels from new 2001 through 2020 ~~and subsequent~~ model low-emission vehicles, ultra-low-emission vehicles and super-ultra-low-emission vehicles in the passenger car and light-duty truck class certifying to the LEV II exhaust emission standards in section 1961, and new 2003 through 2020 model ~~and subsequent~~ low-emission vehicles, ultra-low-emission vehicles, and super-ultra-low-emission vehicles in the medium-duty class certifying to the LEV II exhaust emission standards in section 1961, shall not exceed:

SFTP EXHAUST EMISSION STANDARDS FOR LOW-EMISSION VEHICLES, ULTRA-LOW-EMISSION VEHICLES, AND SUPER-ULTRA-LOW-EMISSION VEHICLES IN THE PASSENGER CAR, LIGHT-DUTY TRUCK, AND MEDIUM-DUTY VEHICLE CLASSES

(grams per mile) 5,6,7,8,9,10,~~11~~

Vehicle Type[1]	Gross Vehicle Weight Rating (lbs.)	~~Loaded Vehicle~~ Test Weight (lbs.)[2]	US06 Test[1]		A/C Test[1,~~11~~]	
			NMHC[3,4] + NOx[1]	CO[1]	NMHC[3,4] + NOx[1]	CO[1]
PC	All	All Vehicles in this category are tested at their loaded vehicle weight (curb weight plus 300 lbs.)	0.14	8.0	0.20	2.7
LDT ~~LDT~~	< 6,000 lbs.	0-3750 Vehicles in this category are tested at their loaded vehicle weight (curb weight plus 300 lbs.)	0.14	8.0	0.20	2.7
		3751-5750 Vehicles in this category are tested at their loaded vehicle weight (curb weight plus 300 lbs.)	0.25	10.5	0.27	3.5
MDV ~~MDV~~	6,001-8,500 lbs.[2]	3751-5750 Vehicles in this category are tested at their adjusted loaded vehicle weight (average of curb weight and GVWR)	0.40	10.5	0.31	3.5
		5751-8500 Vehicles in this category are tested at their adjusted loaded vehicle weight (average of curb weight and GVWR)	0.60	11.8	0.44	4.0

[1] *Abbreviations and Definitions.* For the purposes of this SFTP standards table only, the following abbreviations and definitions apply:
"PC" means passenger car.
"LDT" means light-duty truck, defined as any motor vehicle rated at 6,000 pounds gross vehicle weight or less, which is designed primarily for purposes of transportation of property or is a derivative of such a vehicle, or is available with special features enabling off-street or off-highway operation and use.

"MDV" means medium-duty truck, defined as any motor vehicle having a manufacturer's gross vehicle weight rating of greater than 6,000 pounds and less than 14,001 pounds, except passenger cars.
"NMHC+NOx" means non-methane hydrocarbon plus oxides of nitrogen emissions.
"CO" means carbon monoxide emissions.
"US06" means the test cycle designed to evaluate emissions during aggressive and microtransient driving.
"A/C" means air-conditioning.

~~2 For MDVs, "Loaded Vehicle Weight" shall mean "Test Weight," which is the average of the vehicle's curb weight and gross vehicle weight.~~

2 3 Vehicles with a gross vehicle weight rating over 8,500 pounds are exempted from the requirements of this subsection.

3 4 *Non-Methane Hydrocarbon Emissions.* Hydrocarbon emissions shall be measured in accordance with Part B (Determination of Non-Methane Hydrocarbon Mass Emissions by Flame Ionization Detection) of the "California Non-Methane Organic Gas Test Procedures" as incorporated by reference in section 1960.1(g)(1), note (3). For alcohol-fueled vehicles certifying to these standards, including flexible-fuel vehicles when certifying on methanol or ethanol, "Non-Methane Hydrocarbons" shall mean "Organic Material Non-Methane Hydrocarbon Equivalent."

4 5 *A/C-on Specific Calibrations.* A/C-on specific calibrations (e.g. air to fuel ratio, spark timing, and exhaust gas recirculation), may be used which differ from A/C-off calibrations for given engine operating conditions (e.g., engine speed, manifold pressure, coolant temperature, air charge temperature, and any other parameters). Such calibrations must not unnecessarily reduce the NMHC+NOx emission control effectiveness during A/C-on operation when the vehicle is operated under conditions which may reasonably be expected to be encountered during normal operation and use. If reductions in control system NMHC+NOx effectiveness do occur as a result of such calibrations, the manufacturer shall, in the Application for Certification, specify the circumstances under which such reductions do occur, and the reason for the use of such calibrations resulting in such reductions in control system effectiveness.

A/C-on specific "open-loop" or "commanded enrichment" air-fuel enrichment strategies (as defined below), which differ from A/C-off "open-loop" or "commanded enrichment" air-fuel enrichment strategies, may not be used, with the following exceptions: cold-start and warm-up conditions, or, subject to Executive Officer approval, conditions requiring the protection of the vehicle, occupants, engine, or emission control hardware. Other than these exceptions, such strategies which are invoked based on manifold pressure, engine speed, throttle position, or other engine parameters shall use the same engine parameter criteria for the invoking of this air-fuel enrichment strategy and the same degree of enrichment regardless of whether the A/C is on or off.

"Open-loop" or "commanded" air-fuel enrichment strategy is defined as enrichment of the air to fuel ratio beyond stoichiometry for the purposes of increasing engine power output and the protection of engine or emissions control hardware. However, "closed-loop biasing," defined as small changes in the air-fuel ratio for the purposes of optimizing vehicle emissions or driveability, shall not be considered an "open-loop" or "commanded" air-fuel enrichment strategy. In addition, "transient" air-fuel enrichment strategy (or "tip-in" and "tip-out" enrichment), defined as the temporary use of an air-fuel ratio rich of stoichiometry at the beginning or duration of rapid throttle motion, shall not be considered an "open-loop" or "commanded" air-fuel enrichment strategy.

5 6 *SFTP.* SFTP means the additional test procedure designed to measure emissions during aggressive and microtransient driving, as described in section 86.159-00, Title 40, Code of Federal Regulations, as adopted October 22, 1996, over the US06 cycle, and also the test procedure designed to measure urban driving emissions while the vehicle's air conditioning system is operating, as described in section 86.160-00, Title 40, Code of Federal

Regulations, as adopted October 22, 1996, over the SC03 cycle, except the test weight shall be that specified in this subsection 1960.1(r), regardless of what may be specified in the Code of Federal Regulations. These sections of the Code of Federal Regulations are incorporated herein by reference.

~~6~~7 *Applicability to Alternative Fuel Vehicles.* These SFTP standards do not apply to vehicles certified on fuels other than gasoline and diesel fuel, but the standards do apply to the gasoline and diesel fuel operation of flexible-fuel vehicles and dual-fuel vehicles.

~~7~~8 *Air to Fuel Ratio Requirement.* With the exception of cold-start conditions, warm-up conditions and rapid-throttle motion conditions ("tip-in" or "tip-out" conditions), the air to fuel ratio shall not be richer at any time than, for a given engine operating condition (e.g., engine speed, manifold pressure, coolant temperature, air charge temperature, and any other parameters), the leanest air to fuel mixture required to obtain maximum torque (lean best torque), with a tolerance of six percent of the fuel consumption. The Executive Officer may approve a manufacturer's request for approval to use additional enrichment in subsequent testing if the manufacturer demonstrates that additional enrichment is needed to protect the vehicle, occupants, engine, or emission control hardware.

~~8~~9 *"Lean-On-Cruise" Calibration Strategies.* In the Application for Certification, the manufacturer shall state whether any "lean-on-cruise" strategies are incorporated into the vehicle design. A "lean-on-cruise" air-fuel calibration strategy is defined as the use of an air-fuel ratio significantly greater than stoichiometry, during non-deceleration conditions at speeds above 40 mph. "Lean-on-cruise" air-fuel calibration strategies shall not be employed during vehicle operation in normal driving conditions, including A/C-usage, unless at least one of the following conditions is met:

1. Such strategies are substantially employed during the FTP or SFTP, or

2. Such strategies are demonstrated not to significantly reduce vehicle NMHC+NOx emission control effectiveness over the operating conditions in which they are employed, or

3. Such strategies are demonstrated to be necessary to protect the vehicle, occupants, engine, or emission control hardware.

If the manufacturer proposes to use a "lean-on-cruise" calibration strategy, the manufacturer shall specify the circumstances under which such a calibration would be used, and the reason or reasons for the proposed use of such a calibration.

The above provisions shall not apply to vehicles powered by "lean-burn" engines or Diesel-cycle engines. A "lean-burn" engine is defined as an Otto-cycle engine designed to run at an air-fuel ratio significantly greater than stoichiometry during the large majority of its operation.

~~9~~10 *Phase-In Requirements.* For the purposes of this 1960.1(r) section only, each manufacturer's PC and LDT fleet shall be defined as the total projected number of low-emission and ultra-low-emission PCs and LDTs from 0-5750 pounds loaded vehicle weight sold in California. Each manufacturer's MDV fleet shall be defined as the total projected number of low-emission, ultra-low-emission, and super-ultra-low-emission MDVs less than 8501 pounds gross vehicle weight rating sold in California.

a. For the 2001 through 2014 model years, mManufacturers of PCs, LDTs, and MDVs, except small volume manufacturers, shall certify a minimum percentage of their PC and LDT fleet, and a minimum percentage of their MDV fleet, according to the following phase-in schedule.

	Percentage	
Model Year	PC, LDT	MDV
2001	25	NA
2002	50	NA
2003	85	25
2004	100	50
2005 through 2014 ~~and subsequent~~	100	100

b. Manufacturers may use an "Alternative or Equivalent Phase-in Schedule" to comply with the phase-in requirements. An "Alternative Phase-in" is one that achieves at least equivalent emission reductions by the end of the last model year of the scheduled phase-in. Model-year emission reductions shall be calculated by multiplying the percent of vehicles (based on the manufacturer's projected California sales volume of the applicable vehicle fleet) meeting the new requirements per model year by the number of model years implemented prior to and including the last model year of the scheduled phase-in. The "cumulative total" is the summation of the model-year emission reductions (e.g., a four model-year 25/50/85/100 percent phase-in schedule would be calculated as: (25%*4 years) + (50%*3 years) + (85%*2 years) + (100%*1 year) = 520). Any alternative phase-in that results in an equal or larger cumulative total than the required cumulative total by the end of the last model year of the scheduled phase-in shall be considered acceptable by the Executive Officer under the following conditions: 1) all vehicles subject to the phase-in shall comply with the respective requirements in the last model year of the required phase-in schedule and 2) if a manufacturer uses the optional phase-in percentage determination in section 1960.1(q) note (9), the cumulative total of model-year emission reductions as determined only for PCs and LDTs certified to this section 1960.1(r) must also be equal to or larger than the required cumulative total by end of the 2004 model year. Manufacturers shall be allowed to include vehicles introduced before the first model year of the scheduled phase-in (e.g., in the previous example, 10 percent introduced one year before the scheduled phase-in begins would be calculated as: (10%*5 years) and added to the cumulative total).

c. Small volume manufacturers of PCs, LDTs, and MDVs shall certify 100% of their PC and LDT fleet in the 2004 through 2014 ~~and subsequent~~ model years, and 100% of their MDV fleet in the 2005 through 2014 ~~and subsequent~~ model years.

104 *Single-Roll Electric Dynamometer Requirement.* For all vehicles certified to the SFTP standards, a single-roll electric dynamometer or a dynamometer which produces equivalent results, as set forth in the "California Exhaust Emission Standards and Test Procedures for 1988 Through 2000 ~~and Subsequent~~ Model Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles" as incorporated by reference in section 1960.1(k) or the "California 2001 through 2014 Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2009 through 2016 Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," as incorporated by reference in section 1961(d), as applicable, must be used for all types of emission testing to determine compliance with the associated emission standards.

NOTE: Authority cited: Sections 39600, 39601, 43013, 43018, 43101, 43104, and 43105, Health and Safety Code. Reference: Sections 39002, 39003, 39667, 43000, 43009.5, 43013, 43018, 43100, 43101, 43101.5, 43102, 43103, 43104, 43105, 43106, 43107, and 43204-43205.5, Health and Safety Code.

4. Amend title 13, CCR, section 1961 to read as follows:

§ 1961. Exhaust Emission Standards and Test Procedures - 2004 through 2019 ~~and Subsequent~~ Model Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles.

Introduction. This section 1961 contains the California "LEV II" exhaust emission standards for 2004 through 2019 ~~and subsequent~~ model passenger cars, light-duty trucks and medium-duty vehicles. A manufacturer must demonstrate compliance with the exhaust standards in section 1961(a) applicable to specific test groups, and with the composite phase-in requirements in section 1961(b) applicable to the manufacturer's entire fleet. Section 1961(b) also includes the manufacturer's fleet-wide composite phase-in requirements for the 2001 - 2003 model years.

* * * *

(a) *Exhaust Emission Standards.*

(1) *"LEV II" Exhaust Standards.* The following standards are ~~represent~~ the maximum exhaust emissions for the intermediate and full useful life from new 2004 through 2019 ~~and subsequent~~ model-year "LEV II" LEVs, ULEVs, and SULEVs, including fuel-flexible, bi-fuel and dual fuel vehicles when operating on the gaseous or alcohol fuel they are designed to use:

LEV II Exhaust Mass Emission Standards for New 2004 through 2019 ~~and Subsequent~~ Model LEVs, ULEVs, and SULEVs in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes

Vehicle Type	*Durability Vehicle Basis (mi)*	*Vehicle Emission Category*	*NMOG (g/mi)*	*Carbon Monoxide (g/mi)*	*Oxides of Nitrogen (g/mi)*	*Formaldehyde (mg/mi)*	*Particulates (g/mi)*
All PCs; LDTs 8500 lbs. GVWR or less Vehicles in this category are tested at their loaded vehicle weight	50,000	LEV	0.075	3.4	0.05	15	n/a
		LEV, Option 1	0.075	3.4	0.07	15	n/a
		ULEV	0.040	1.7	0.05	8	n/a
	120,000	LEV	0.090	4.2	0.07	18	0.01
		LEV, Option 1	0.090	4.2	0.10	18	0.01
		ULEV	0.055	2.1	0.07	11	0.01
		SULEV	0.010	1.0	0.02	4	0.01
	150,000	LEV	0.090	4.2	0.07	18	0.01

Date of Release: December 7, 2011; 45-day Notice Version
Date of Hearing: January 26, 2012

	(Optional)	LEV, Option 1	0.090	4.2	0.10	18	0.01
		ULEV	0.055	2.1	0.07	11	0.01
		SULEV	0.010	1.0	0.02	4	0.01
MDVs 8501 - 10,000 lbs. GVWR Vehicles in this category are tested at their adjusted loaded vehicle weight	120,000	LEV	0.195	6.4	0.2	32	0.12
		ULEV	0.143	6.4	0.2	16	0.06
		SULEV	0.100	3.2	0.1	8	0.06
	150,000 (Optional)	LEV	0.195	6.4	0.2	32	0.12
		ULEV	0.143	6.4	0.2	16	0.06
		SULEV	0.100	3.2	0.1	8	0.06
MDVs 10,001-14,000 lbs. GVWR Vehicles in this category are tested at their adjusted loaded vehicle weight	120,000	LEV	0.230	7.3	0.4	40	0.12
		ULEV	0.167	7.3	0.4	21	0.06
		SULEV	0.117	3.7	0.2	10	0.06
	150,000 (Optional)	LEV	0.230	7.3	0.4	40	0.12
		ULEV	0.167	7.3	0.4	21	0.06
		SULEV	0.117	3.7	0.2	10	0.06

* * * *

(3) *LEV II NMOG Standards for Bi-Fuel, Fuel-Flexible and Dual-Fuel Vehicles Operating on Gasoline.* For fuel-flexible, bi-fuel, and dual-fuel PCs, LDTs and MDVs, compliance with the NMOG exhaust mass emission standards shall be based on exhaust emission tests both when the vehicle is operated on the gaseous or alcohol fuel it is designed to use, and when the vehicle is operated on gasoline. A manufacturer must demonstrate compliance with the applicable exhaust mass emission standards for NMOG, CO, NO_x, and formaldehyde set forth in the table in section 1961(a)(1) when certifying the vehicle for operation on the gaseous or alcohol fuel.

The following standards are ~~represent~~ the maximum NMOG emissions when the vehicle is operating on gasoline. A manufacturer shall not apply a reactivity adjustment factor to the exhaust NMOG mass emission result when operating on gasoline. A manufacturer may measure NMHC in lieu of NMOG when fuel-flexible, bi-fuel, and dual-fuel vehicles are operated on gasoline, in accordance with the test procedures incorporated by reference in section 1961(d). Testing at 50°F is not required for fuel-flexible, bi-fuel, and dual-fuel vehicles when operating on gasoline. The applicable CO, NO_x, and formaldehyde standards are set forth in section 1961(a)(1).

LEV II NMOG Standards for Bi-Fuel, Fuel-Flexible, and Dual-Fuel Vehicles Operating on Gasoline (g/mi)			
Vehicle Type	*Vehicle Emission Category*	*Durability Vehicle Basis*	
		50,000 mi	*120,000 mi*
All PCs; LDTs, 0-8500 lbs. GVWR	LEV	0.125	0.156
	ULEV	0.075	0.090
	SULEV	0.010	0.040
MDVs, 8501-10,000 lbs. GVWR	LEV	n/a	0.230
	ULEV	n/a	0.167
	SULEV	n/a	0.117
MDVs, 10,001-14,000 lbs. GVWR	LEV	n/a	0.280
	ULEV	n/a	0.195
	SULEV	n/a	0.143

(4) *LEV II 50°F Exhaust Emission Standards.* All LEV II light- and medium-duty LEVs, ULEVs, and SULEVs must demonstrate compliance with the following exhaust emission standards for NMOG and formaldehyde (HCHO) measured on the FTP (40 CFR, Part 86, Subpart B) conducted at a nominal test temperature of 50°F, as modified by Part II, Section C of the "California 2001 through 2014 Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and ~~for~~ 2009 through 2016 ~~and Subsequent~~ Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles" incorporated by reference in section 1961(d). The NMOG mass emission result shall be multiplied by the applicable reactivity adjustment factor, if any, prior to comparing to the applicable adjusted 50,000 mile certification standards set forth below. A manufacturer may demonstrate compliance with the NMOG and HCHO certification standards contained in this subparagraph by measuring NMHC exhaust emissions or issuing a statement of compliance for HCHO in accordance with Section D.1, subparagraph (p) and Section G.3.1.2, respectively, of the "California 2001 through 2014 Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and ~~for~~ 2009 through 2016 ~~and Subsequent~~ Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles" incorporated by reference in section 1961(d). Emissions of CO and NOx measured at 50°F shall not exceed the standards set forth in §1961(a)(1) applicable to vehicles of the same emission

category and vehicle type subject to a cold soak and emission test at 68° to 86°F. Natural gas and diesel-fueled vehicles are exempt from the 50°F test requirements.

Vehicle Weight Class	*Vehicle Emission Category (g/mi)*					
	LEV		*ULEV*		*SULEV*	
	NMOG	*HCHO*	*NMOG*	*HCHO*	*NMOG*	*HCHO*
PCs; LDTs 0-8500 lbs. GVWR	0.150	0.030	0.080	0.016	0.020	0.008
MDVs 8501-10,000 lbs. GVWR	0.390	0.064	0.286	0.032	0.200	0.016
MDVs 10,001-14,000 lbs. GVWR	0.460	0.080	0.334	0.042	0.234	0.020

(5) *LEV II Cold CO Standard.* The following standards are ~~represent~~ the 50,000 mile cold temperature exhaust carbon monoxide emission levels from new 2001 through 2019 ~~and subsequent~~ model-year LEV II passenger cars, light-duty trucks, and medium-duty vehicles:

2001 THROUGH 2019 ~~AND SUBSEQUENT~~ MODEL-YEAR COLD TEMPERATURE CARBON MONOXIDE EXHAUST EMISSIONS STANDARDS FOR LEV II PASSENGER CARS, LIGHT-DUTY TRUCKS, AND MEDIUM-DUTY VEHICLES

(grams per mile)

Vehicle Type	*Carbon Monoxide*
All PCs, LDTs 0-3750 lbs. LVW;	10.0
LDTs, 3751 lbs. LVW - 8500 lbs. GVWR; LEV I and Tier 1 MDVs 8500 lbs. GVWR and less	12.5

These standards are applicable to vehicles tested at a nominal temperature of 20°F (-7°C) in accordance with 40 CFR Part 86 Subpart C, as amended by the "California 2001 through 2014 Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and ~~for~~ 2009 through 2016 ~~and Subsequent~~ Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles" incorporated by reference in section 1961(d). Natural gas, diesel-fueled, and zero-emission vehicles are exempt from these standards.

* * * *

(7) *Supplemental Federal Test Procedure (SFTP) Off-Cycle Emission Standards.* The SFTP exhaust emission levels from new 2004 through 2019 ~~and subsequent~~ model LEV II LEVs, ULEVs, and SULEVs shall not exceed the standards set forth in section 1960.1(r).

(8) *Requirements for Vehicles Certified to the Optional 150,000 Mile Standards.*

* * * *

(B) *Requirement to Generate a Partial ZEV Allowance.* A vehicle that is certified to the 150,000 mile SULEV standards shall also generate a partial ZEV allocation according to the criteria set forth in section C.3 of the "California Exhaust Emission Standards and Test Procedures for 2005 through 2008 ~~and Subsequent~~ Model Zero-Emission Vehicles, and 2001 through 2008 ~~and Subsequent~~ Model Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck, and Medium-Duty Vehicle Classes," incorporated by reference in section 1962, the "California Exhaust Emission Standards and Test Procedures for 2009 through 2017 Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck, and Medium-Duty Vehicle Classes," incorporated by reference in section 1962.1, or the "California Exhaust Emission Standards and Test Procedures for 2018 and Subsequent Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck, and Medium-Duty Vehicle Classes," incorporated by reference in section 1962.2,as applicable.

* * * *

(14) *When a Federally-Certified Vehicle Model is Required in California.*

(A) *General Requirement.* Whenever a manufacturer federally-certifies a 2004 through 2014 ~~or subsequent~~ model-year passenger car, light-duty truck or medium-duty vehicle model to the standards for a particular emissions bin that are more stringent than the standards for an applicable California emission category, the equivalent California model may only be certified to (i) the California standards for a vehicle emissions category that are at least as stringent as the standards for the corresponding federal emissions bin, or (ii) the exhaust emission standards to which the federal model is certified. However, where the federal exhaust emission standards for the particular emissions bin and the California standards for a vehicle emissions category are equally stringent, the California model may only be certified to either the California standards for that vehicle emissions category or more stringent California standards. The federal emission bins are those contained in Tables S04-1 and S04-2 of 40 CFR §86.1811-04(c) as adopted February 10, 2000. The criteria for

applying this requirement are set forth in Part I. Section H.1 of the "California 2001 through 2014 Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and ~~for~~ 2009 through 2016 ~~and Subsequent~~ Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," as incorporated by reference in section 1961(d).

* * * *

(b) *Emission Standards Phase-In Requirements for Manufacturers.*

(1) *Fleet Average NMOG Requirements for Passenger Cars and Light-Duty Trucks.*

(A) The fleet average non-methane organic gas exhaust mass emission values from the passenger cars and light-duty trucks certified to the Tier 1, LEV I, and LEV II standards that are produced and delivered for sale in California each model year from 2001 through 2014 by a manufacturer other than a small volume manufacturer or an independent low volume manufacturer shall not exceed:

FLEET AVERAGE NON-METHANE ORGANIC GAS EXHAUST MASS EMISSION REQUIREMENTS FOR LIGHT-DUTY VEHICLE WEIGHT CLASSES (50,000 mile Durability Vehicle Basis)		
Model Year	*Fleet Average NMOG (grams per mile)*	
	All PCs; LDTs 0-3750 lbs. LVW	*LDTs 3751 lbs. LVW - 8500 lbs. GVW*
2001	0.070	0.098
2002	0.068	0.095
2003	0.062	0.093
2004	0.053	0.085
2005	0.049	0.076
2006	0.046	0.062
2007	0.043	0.055
2008	0.040	0.050
2009	0.038	0.047
2010 through 2014~~+~~	0.035	0.043

(B) *Calculation of Fleet Average NMOG Value.*

1. *Basic Calculation.*

* * * *

Date of Release: December 7, 2011; 45-day Notice Version
Date of Hearing: January 26, 2012

c. The applicable emission standards to be used in the above equations are as follows:

Model Year	*Emission Category*	*Emission Standard Value*	
		All PCs; LDTs 0-3750 lbs. LVW	*LDTs 3751-5750 lbs. LVW*
2001 through 2014 ~~and subsequent~~ (§1960.5 "AB 965" vehicles only)	All	Federal Emission Standard to which Vehicle is Certified	Federal Emission Standard to which Vehicle is Certified
2001 - 2003 (§1960.1(f)(2))	Tier 1	0.25	0.32
2001 - 2006 model year vehicles certified to the "LEV I" standards in §1960.1(g)(1) (For TLEVs, 2001 - 2003 model years only)	TLEVs	0.125	0.160
	LEVs	0.075	0.100
	ULEVs	0.040	0.050
Model Year	Emission Category	All PCs; LDTs 0-3750 lbs. LVW	LDTs 3751 lbs. LVW - 8500 lbs. GVW
2004 through 2014 ~~and subsequent~~ model year vehicles certified to the "LEV II" standards in §1961(a)(1)	LEVs	0.075	0.075
	ULEVs	0.040	0.040
	SULEVs	0.01	0.01
2004 through 2014 ~~and subsequent~~ model year vehicles certified to the optional 150,000 mile "LEV II" standards for PCs and LDTs in 1961(a)(1)	LEVs	0.064	0.064
	ULEVs	0.034	0.034
	SULEVs	0.0085	0.0085

* * * *

3. *Federally-Certified Vehicles.* A vehicle certified to the federal standards for a federal exhaust emissions bin in accordance with Section H.1 of the "California 2001 through 2014 Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and ~~for~~ 2009 through 2016 ~~and Subsequent~~ Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," as incorporated by reference in section 1961(d), shall use the corresponding intermediate useful life NMOG standard to which the vehicle is deemed certified in the fleet average calculation.

(C) *Requirements for Small Volume Manufacturers.*

1. In 2001 through 2006 model years, a small volume manufacturer shall not exceed a fleet average NMOG value of 0.075 g/mi for PCs and LDTs from 0-3750 lbs. LVW or 0.100 g/mi for LDTs from 3751-5750 lbs. LVW calculated in accordance with section 1961(b)(1)(B). In 2007 through 2014 ~~and subsequent~~ model years, a small volume manufacturer shall not exceed a fleet average NMOG value of 0.075 for PCs and LDTs from 0-3750 lbs. LVW or 0.075 for LDTs from 3751 lbs. LVW - 8500 lbs. GVW calculated in accordance with section 1961(b)(1)(B).

* * * *

(D) *Phase-in Requirements for Independent Low Volume Manufacturers.* In 2001 through 2006 model years, an independent low volume manufacturer shall not exceed a fleet average NMOG value of 0.075 g/mi for PCs and LDTs from 0-3750 lbs. LVW or 0.100 g/mi for LDTs from 3751-5750 lbs. LVW calculated in accordance with section 1961(b)(1)(B). In 2007 through 2014 ~~and subsequent~~ model years, an independent low volume manufacturer shall not exceed a fleet average NMOG value of 0.060 for PCs and LDTs from 0-3750 lbs. LVW or 0.065 g/mi for LDTs from 3751 lbs. LVW - 8500 lbs. GVW calculated in accordance with section 1961(b)(1)(B).

* * * *

(3) *Medium-Duty Vehicle Phase-In Requirements.*

(A) A manufacturer of MDVs, other than a small volume manufacturer, shall certify an equivalent percentage of its MDV fleet according to the following phase-in schedule:

Model Year	*Vehicles Certified to §1960.1(h)(1), (h)(2), and §1961(a)(1) (%)*		*Vehicles Certified to §1956.8(g) or (h) (%)*		
	LEV	*ULEV*	*Tier 1*	*LEV*	*ULEV*
2001	80	20	100	0	0
2002	70	30	0	100	0
2003	60	40	0	100	0
2004 through 2014 +	40	60	0	0	100

(B) *Phase-In Requirements for LEV II MDVs.* For the 2004 through 2006 model years, a manufacturer, other than a small volume manufacturer must phase-in at least one test group per model year to the MDV LEV II standards. All 2007 through 2014 ~~and subsequent~~ model year MDVs, including those produced by a small volume manufacturer, are subject to the LEV II MDV standards. Beginning in the 2005 model year, all medium-duty engines certified to the optional medium-duty engine standards in title 13, CCR §1956.8(c) or (h), including those produced by a small volume manufacturer, must meet the standards set forth in title 13, CCR §1956.8(c) or (h), as applicable. A manufacturer that elects to certify to the Option 1 or Option 2 federal standards as set forth in 40 CFR §86.005-10(f) is not subject to these phase-in requirements.

(C) *Identifying a Manufacturer's MDV Fleet.* For the 2001 through 2014 ~~and subsequent~~ model years, each manufacturer's MDV fleet shall be defined as the total number of California-certified MDVs produced and delivered for sale in California. The percentages shall be applied to the manufacturers' total production of California-certified medium-duty vehicles delivered for sale in California. For the 2005 through 2014 ~~and subsequent~~ model years, a manufacturer that elects to certify to the optional medium-duty engine standards in title 13, CCR, §1956.8(c) or (h) shall not count those engines in the manufacturer's total production of California-certified medium-duty vehicles for purposes of this subsection.

* * * *

(E) For a manufacturer that elects to certify to the optional medium-duty engine standards in title 13, CCR §1956.8(c) or (h), all such 2005 through 2014 ~~and subsequent~~ model year MDVs, including those produced by a small volume manufacturer, shall be subject to the emissions averaging provisions applicable to heavy-duty diesel or Otto-cycle engines as set forth in the

"California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Otto-Cycle Engines," or the "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Diesel Engines, incorporated by reference in §1956.8(b) or (d), as applicable.

(c) *Calculation of NMOG Credits/Debits*

(1) *Calculation of NMOG Credits for Passenger Cars and Light-Duty Trucks.* In 2001 through 2014 ~~and subsequent~~ model years, a manufacturer that achieves fleet average NMOG values lower than the fleet average NMOG requirement for the corresponding model year shall receive credits in units of g/mi NMOG determined as:

> [(Fleet Average NMOG Requirement) - (Manufacturer's Fleet Average NMOG Value)] x
> (Total No. of Vehicles Produced and Delivered for Sale in California, Including ZEVs and HEVs).

A manufacturer with 2001 through 2014 ~~and subsequent~~ model year fleet average NMOG values greater than the fleet average requirement for the corresponding model year shall receive debits in units of g/mi NMOG equal to the amount of negative credits determined by the aforementioned equation. For the 2001 through 2014 ~~and subsequent~~ model years, the total g/mi NMOG credits or debits earned for PCs and LDTs 0-3750 lbs. LVW, for LDTs 3751-5750 lbs. LVW and for LDTs 3751 lbs. LVW - 8500 lbs. GVW shall be summed together. The resulting amount shall constitute the g/mi NMOG credits or debits accrued by the manufacturer for the model year.

(2) *Calculation of Vehicle Equivalent NMOG Credits for Medium-Duty Vehicles.*

(A) In 2001 through 2014 ~~and subsequent~~ model years, a manufacturer that produces and delivers for sale in California MDVs in excess of the equivalent requirements for LEVs, ULEVs and/or SULEVs certified to the exhaust emission standards set forth in section 1961(a)(1) or to the exhaust emission standards set forth in Title 13, CCR, Section 1956.8(h) shall receive "Vehicle-Equivalent Credits" (or "VECs") calculated in accordance with the following equation, where the term "produced" means produced and delivered for sale in California:

* * * *

(3) *Procedure for Offsetting Debits.*

(A) A manufacturer shall equalize emission debits by earning g/mi NMOG emission credits or VECs in an amount equal to the g/mi NMOG debits or VEDs, or by submitting a commensurate amount of g/mi NMOG credits or VECs

to the Executive Officer that were earned previously or acquired from another manufacturer. For 2001 through 2003 and for 2007 through 2014 ~~and subsequent~~ model years, manufacturers shall equalize emission debits by the end of the following model year. For 2004 through 2006 model years, a manufacturer shall equalize NMOG debits for PCs and LDTs and LEV II MDVs within three model years and prior to the end of the 2007 model year. If emission debits are not equalized within the specified time period, the manufacturer shall be subject to the Health and Safety Code section 43211 civil penalty applicable to a manufacturer which sells a new motor vehicle that does not meet the applicable emission standards adopted by the state board. The cause of action shall be deemed to accrue when the emission debits are not equalized by the end of the specified time period. For the purposes of Health and Safety Code section 43211, the number of passenger cars and light-duty trucks not meeting the state board's emission standards shall be determined by dividing the total amount of g/mi NMOG emission debits for the model year by the g/mi NMOG fleet average requirement for PCs and LDTs 0-3750 lbs. LVW applicable for the model year in which the debits were first incurred and the number of medium-duty vehicles not meeting the state board's emission standards shall be equal to the amount of VEDs incurred.

* * * *

(d) *Test Procedures.* The certification requirements and test procedures for determining compliance with the emission standards in this section are set forth in the "California 2001 through 2014 Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and ~~for~~ 2009 through 2016 ~~and Subsequent~~ Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," as amended ~~September 27, 2010~~ [INSERT DATE OF AMENDMENT], ~~and~~ the "California Non-Methane Organic Gas Test Procedures," as amended ~~July 30, 2002~~ [INSERT DATE OF AMENDMENT], which are incorporated herein by reference. In the case of hybrid electric vehicles and on-board fuel-fired heaters, the certification requirements and test procedures for determining compliance with the emission standards in this section are set forth in the "California Exhaust Emission Standards and Test Procedures for 2005 through 2008 Model Zero-Emission Vehicles, and 2001 through 2008 Model Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," incorporated by reference in section 1962, ~~and~~ the "California Exhaust Emission Standards and Test Procedures for 2009 through 2017 ~~and Subsequent~~ Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," incorporated by reference in section 1962.1, and the "California Exhaust Emission Standards and Test Procedures for 2018 and Subsequent Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes" incorporated by reference in section 1962.2.

* * * *

NOTE: Authority cited: Sections 39500, 39600, 39601, 43013, 43018, 43101, 43104, 43105, and 43106, Health and Safety Code. Reference: Sections 39002, 39003, 39667, 43000, 43009.5, 43013, 43018, 43100, 43101, 43101.5, 43102, 43104, 43105, 43106, 43204, and 43205, Health and Safety Code.

5. Amend title 13, CCR, section 1961.1 to read as follows:

§ 1961.1. Greenhouse Gas Exhaust Emission Standards and Test Procedures - 2009 through 2016 ~~and Subsequent~~ Model Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles.

(a) *Greenhouse Gas Emission Requirements.* The greenhouse gas emission levels from new 2009 through 2016 ~~and subsequent~~ model year passenger cars, light-duty trucks, and medium-duty passenger vehicles shall not exceed the following requirements. Light-duty trucks from 3751 lbs. LVW – 8500 lbs. GVW that are certified to the Option 1 LEV II NOx Standard in section 1961(a)(1) are exempt from these greenhouse gas emission requirements, however, passenger cars, light-duty trucks 0-3750 lbs. LVW, and medium-duty passenger vehicles are not eligible for this exemption.

(1) *Fleet Average Greenhouse Gas Requirements for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles.*

(A)(i) The fleet average greenhouse gas exhaust mass emission values from passenger cars, light-duty trucks, and medium-duty passenger vehicles that are produced and delivered for sale in California each model year by a large volume manufacturer shall not exceed:

FLEET AVERAGE GREENHOUSE GAS EXHAUST MASS EMISSION REQUIREMENTS FOR PASSENGER CAR, LIGHT-DUTY TRUCK, AND MEDIUM-DUTY PASSENGER VEHICLE WEIGHT CLASSES[1] (4,000 mile Durability Vehicle Basis)		
Model Year	*Fleet Average Greenhouse Gas Emissions (grams per mile CO_2-equivalent)*	
	All PCs; LDTs 0-3750 lbs. LVW	*LDTs 3751 lbs. LVW - 8500 lbs. GVW; MDPVs*
2009	323	439
2010	301	420
2011	267	390
2012	233	361
2013	227	355
2014	222	350
2015	213	341
2016+	205	332

[1] Each manufacturer shall demonstrate compliance with these values in accordance with section 1961.1(a)(1)(B).

1. For each model year, a manufacturer must demonstrate compliance with the fleet average requirements in this section 1961.1(a)(1)(A) based on one of two options applicable throughout the model year, either:

Option 1: the total number of passenger cars, light-duty trucks, and medium-duty passenger vehicles that are certified to the California exhaust emission standards in this section 1961.1, and are produced and delivered for sale in California; or

Option 2: the total number of passenger cars, light-duty trucks, and medium-duty passenger vehicles that are certified to the California exhaust emission standards in this section 1961.1, and are produced and delivered for sale in California, the District of Columbia, and all states that have adopted California's greenhouse gas emission standards for that model year pursuant to Section 177 of the federal Clean Air Act (42 U.S.C. § 7507).

a. For the 2009 and 2010 model years, a manufacturer that selects compliance Option 2 must notify the Executive Officer of that selection, in writing, within 30 days of the effective date of the amendments to this section (a)(1)(A)1 or must comply with Option 1.

b. For the 2011 through 2016 ~~and later~~ model years, a manufacturer that selects compliance Option 2 must notify the Executive Officer of that selection, in writing, prior to the start of the applicable model year or must comply with Option 1.

c. When a manufacturer is demonstrating compliance using Option 2 for a given model year, the term "in California" as used in subsections 1961.1(a)(1)(B)3. and 1961.1 (b) means California, the District of Columbia, and all states that have adopted California's greenhouse gas emission standards for that model year pursuant to Section 177 of the federal Clean Air Act (42 U.S.C. § 7507).

d. A manufacturer that selects compliance Option 2 must provide to the Executive Officer separate values for the number of vehicles produced and delivered for sale in the District of Columbia and for each individual state within the average.

(A)(ii) For the 2012 through 2016 model years, a manufacturer may elect to demonstrate compliance with this section 1961.1 by demonstrating compliance with the 2012 through 2016 MY National greenhouse gas program as follows:

1. A manufacturer that selects compliance with this option 1961.1(a)(1)(A)(ii) must notify the Executive Officer of that selection, in writing, prior to the start of the applicable model year or must comply with 1961.1(a)(1)(A)(i).

2. The manufacturer must submit to ARB a copy of the Model Year CAFE report that it submitted to EPA as required under 40 CFR §86.1865-12 (May 7, 2010) ~~(as proposed at 74 Fed. Reg. 49454, 49760 (September 28, 2009) and adopted by EPA on April 1, 2010, 75 Fed. Reg. [insert page] (April [insert date], 2010)~~, for demonstrating compliance with the 2012 through 2016 MY National greenhouse gas program and the EPA determination of compliance. These must be submitted within 30 days of receipt of the EPA determination of compliance, for each model year that a manufacturer selects compliance with this option 1961.1(a)(1)(A)(ii).

3. The manufacturer must provide to the Executive Officer separate values for the number of vehicles produced and delivered for sale in California, the District of Columbia, and each individual state that has adopted California's greenhouse gas emission standards for that model year pursuant to Section 177 of the federal Clean Air Act (42 U.S.C. § 7507). and

~~3~~4. If a manufacturer has outstanding greenhouse gas debits at the end of the 2011 model year, as calculated in accordance with 1961.1(b), the manufacturer must submit to the Executive Officer a plan for offsetting all outstanding greenhouse gas debits by using greenhouse gas credits earned under the 2012 through 2016 MY National greenhouse gas program before applying those credits to offset any 2012 through 2016 MY National greenhouse gas program debits. Upon approval of the plan by the Executive Officer, the manufacturer may demonstrate compliance with this section 1961.1 by demonstrating compliance with the 2012 through 2016 MY National greenhouse gas program. Any California debits not offset by the end of the 2016 model year National greenhouse gas program reporting period are subject to penalties as provided in this Section 1961.1.

* * * *

(C) *Requirements for Intermediate Volume Manufacturers.*

* * * *

3. In the 2016 ~~and subsequent~~ model years, an intermediate volume manufacturer shall either:

a. not exceed a fleet average greenhouse gas emissions value of 233 g/mi for PCs and LDT1s and 361 g/mi for LDT2s and MDPVs, or

b. not exceed a fleet average greenhouse gas value of 0.75 times the baseline fleet average greenhouse gas value for PCs and LDT1s and 0.82 times the baseline fleet average greenhouse gas value for LDT2s and MDPVs, as calculated in section 1961.1(a)(1)(C)2.

* * * *

(D) *Requirements for Small Volume Manufacturers and Independent Low Volume Manufacturers.*

* * * *

3. In the 2016 ~~and subsequent~~ model years, a small volume manufacturer and an independent low volume manufacturer shall either:

a. not exceed the fleet average greenhouse gas emissions value calculated for each GHG vehicle test group for which a comparable vehicle is sold by a large volume manufacturer, in accordance with section 1961.1(a)(1)(D)2; or

b. not exceed a fleet average greenhouse gas emissions value of 233 g/mi for PCs and LDT1s and 361 g/mi for LDT2s and MDPVs; or

c. upon approval of the Executive Officer, if a small volume manufacturer demonstrates a vehicle model uses an engine, transmission, and emission control system that is identical to a configuration certified for sale in California by a large volume manufacturer, those small volume manufacturer vehicle models are exempt from meeting the requirements in paragraphs 3.a. and b. of this section.

* * * *

(b) *Calculation of Greenhouse Gas Credits/Debits.*

(1) *Calculation of Greenhouse Gas Credits for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles.*

* * * *

(B) In 2009 through 2016 ~~and subsequent~~ model years, a manufacturer that achieves fleet average Greenhouse Gas values lower than the fleet average Greenhouse Gas requirement for the corresponding model year shall receive credits in units of g/mi Greenhouse Gas determined as:

[(Fleet Average Greenhouse Gas Requirement) - (Manufacturer's Fleet Average
Greenhouse Gas Value)] x (Total No. of Vehicles Produced and Delivered for Sale in California, Including ZEVs and HEVs).

(2) A manufacturer with 2009 through 2016 ~~and subsequent~~ model year fleet average Greenhouse Gas values greater than the fleet average requirement for the corresponding model year shall receive debits in units of g/mi Greenhouse Gas equal to the amount of negative credits determined by the aforementioned equation. For the 2009 through 2016 ~~and subsequent~~ model years, the total g/mi Greenhouse Gas credits or debits earned for PCs and LDT1s and for LDT2s and MDPVs shall be summed together. The resulting amount shall constitute the g/mi Greenhouse Gas credits or debits accrued by the manufacturer for the model year.

(3) *Procedure for Offsetting Greenhouse Gas Debits.*

* * * *

(B) Greenhouse Gas emission credits earned in the 2000 through 2008 model years shall be treated as if they were earned in the 2011 model year and shall retain full value through the 2012 model year. Greenhouse Gas emission credits earned in the 2009 through 2016 ~~and subsequent~~ model years shall retain full value through the fifth model year after they are earned. The value of any credits earned in the 2000 through 2008 model years that are not

used to equalize debits accrued in the 2009 through 2012 model years shall be discounted by 50% at the beginning of the 2013 model year, shall be discounted to 25% of its original value if not used by the beginning of the 2014 model year, and will have no value if not used by the beginning of the 2015 model year. Any credits earned in the 2009 through 2016 ~~and subsequent~~ model years that are not used by the end of the fifth model year after they are accrued shall be discounted by 50% at the beginning of the sixth model year after being earned, shall be discounted to 25% of its original value if not used by the beginning of the seventh model year after being earned, and will have no value if not used by the beginning of the eighth model year after being earned.

(c) *Test Procedures.* The certification requirements and test procedures for determining compliance with the emission standards in this section are set forth in the "California 2001 through 2014 Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and ~~for 2001~~ 2009 through 2016 ~~and Subsequent~~ Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," incorporated by reference in section 1961(d). In the case of hybrid electric vehicles and on-board fuel-fired heaters, the certification requirements and test procedures for determining compliance with the emission standards in this section are set forth in the "California Exhaust Emission Standards and Test Procedures for 2009 through 2017 ~~2005 and Subsequent~~ Model Zero-Emission Vehicles~~,~~ and ~~2001 and Subsequent Model~~ Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," incorporated by reference in section 1962.1.

* * * *

(e) *Definitions Specific to this Section.* The following definitions apply to this section 1961.1:

* * * *

(7) "2012 through 2016 MY National greenhouse gas program" means the national program that applies to new 2012 through 2016 model year passenger cars, light-duty trucks, and medium-duty passenger vehicles as ~~proposed by the U.S. Environmental Protection Agency at 74 Fed.Reg. 49454 (September 28, 2009) and~~ adopted by the U.S. Environmental Protection Agency at ~~EPA on April 1, 2010,~~ 75 Fed.Reg. 25324 ~~[insert page]~~, (May 7, 2010) ~~April [insert date], 2010~~, as incorporated in and amended by the " California 2001 through 2014 Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and ~~for 2001~~ 2009 through 2016 ~~and Subsequent~~ Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles."

Date of Release: December 7, 2011; 45-day Notice Version
Date of Hearing: January 26, 2012

* * * *

(9) "Optional GHG Test Vehicle Configuration" means any GHG vehicle configuration that is selected for testing by the manufacturer as allowed by section G.2.3 of the "California 2001 through 2014 Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and ~~for 2001~~ 2009 through 2016 ~~and Subsequent~~ Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," other than the worst-case configuration.

* * * *

NOTE: Authority cited: Sections 39500, 39600, 39601, 43013, 43018, 43018.5, 43101, 43104 and 43105, Health and Safety Code. Reference: Sections 39002, 39003, 39667, 43000, 43009.5, 43013, 43018, 43018.5, 43100, 43101, 43101.5, 43102, 43104, 43105, 43106, 43204, 43205, and 43211, Health and Safety Code.

6. Adopt new title 13, CCR, section 1961.2 to read as follows: (Note: the entire text of section 1961.2 set forth below is new language proposed to be added to the California Code of Regulations.)

§ 1961.2. Exhaust Emission Standards and Test Procedures - 2015 and Subsequent Model Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles.

Introduction. This section 1961.2 contains the California "LEV III" exhaust emission standards for 2015 and subsequent model year passenger cars, light-duty trucks, and medium-duty vehicles. A manufacturer must demonstrate compliance with the exhaust standards in subsection (a) applicable to specific test groups, and with the composite phase-in requirements in subsection (b) applicable to the manufacturer's entire fleet.

Before the 2015 model year, a manufacturer that produces vehicles that meet the standards in subsection (a) has the option of certifying the vehicles to those standards, in which case the vehicles will be treated as LEV III vehicles for purposes of the fleet-wide phase-in requirements. Similarly, 2015 - 2019 model-year vehicles may be certified to the "LEV II" exhaust emission standards in subsection 1961(a)(1), in which case the vehicles will be treated as LEV II vehicles for purposes of the fleet-wide phase-in requirements.

A manufacturer has the option of certifying engines used in incomplete and diesel medium-duty vehicles with a gross vehicle weight rating of greater than 10,000 lbs. GVW to the heavy-duty engine standards and test procedures set forth in title 13, CCR, subsections 1956.8(c) and (h). All medium-duty vehicles with a gross vehicle weight rating of less than or equal to 10,000 lbs. GVW, including incomplete otto-cycle medium-duty vehicles and medium-duty vehicles that use diesel cycle engines, must be certified to the LEV III chassis standards and test procedures set forth in this section 1961.2.

(a) *Exhaust Emission Standards.*

(1) *"LEV III" Exhaust Standards.* The following standards are the maximum exhaust emissions for the full useful life from new 2015 and subsequent model year "LEV III" passenger cars, light-duty trucks, and medium-duty vehicles, including fuel-flexible, bi-fuel and dual fuel vehicles when operating on the gaseous or alcohol fuel they are designed to use:

LEV III Exhaust Mass Emission Standards for New 2015 and Subsequent Model Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles						
Vehicle Type	*Durability Vehicle Basis (mi)*	*Vehicle Emission Category*[2]	*NMOG + Oxides of Nitrogen (g/mi)*	*Carbon Monoxide (g/mi)*	*Formaldehyde (mg/mi)*	*Particulates*[1] *(g/mi)*
All PCs; LDTs 8500 lbs. GVWR or less; MDPVs Vehicles in this category are tested at their loaded vehicle weight	150,000	LEV160	0.160	4.2	4	0.01
		ULEV125	0.125	2.1	4	0.01
		ULEV70	0.070	1.7	4	0.01
		ULEV50	0.050	1.7	4	0.01
		SULEV30	0.030	1.0	4	0.01
		SULEV20	0.020	1.0	4	0.01
MDVs 8501 - 10,000 lbs. GVWR Vehicles in this category are tested at their adjusted loaded vehicle weight	150,000	LEV395	0.395	6.4	6	0.12
		ULEV340	0.340	3.2	6	0.06
		ULEV250	0.250	2.6	6	0.06
		ULEV200	0.200	2.6	6	0.06
		SULEV170	0.170	1.5	6	0.06
		SULEV150	0.150	1.5	6	0.06
MDVs 10,001-14,000 lbs. GVWR Vehicles in this category are tested at their adjusted loaded vehicle weight	150,000	LEV630	0.630	7.3	6	0.12
		ULEV570	0.570	3.7	6	0.06
		ULEV400	0.400	3.0	6	0.06
		ULEV270	0.270	3.0	6	0.06
		SULEV230	0.230	1.7	6	0.06
		SULEV200	0.200	1.7	6	0.06

[1] These standards shall apply only to vehicles not included in the phase-in of the particulate standards set forth in subsection (a)(2).

[2] The numeric portion of the category name is the NMOG+NOx value in thousandths of grams per mile.

(2) *Particulate Standards.*

(A) *Particulate Standards for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles.* Beginning in the 2017 model year, a manufacturer, except a small volume manufacturer, shall certify a percentage of its passenger car, light-duty truck, and medium-duty vehicle fleet to the following particulate standards according to the following phase-in schedule. These standards are the maximum particulate emissions allowed at full useful life. All vehicles certifying to these particulate standards must certify to the LEV III exhaust emission standards set forth in subsection (a)(1).

LEV III Particulate Emission Standard Values and Phase-in for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles		
Model Year	**% of vehicles certified to a 3 mg/mi standard**	**% of vehicles certified to a 1 mg/mi standard**
2017	10	0
2018	20	0
2019	40	0
2020	70	0
2021	100	0
2022	100	0
2023	100	0
2024	100	0
2025	75	25
2026	50	50
2027	25	75
2028 and subsequent	0	100

(B) *Particulate Standards for Medium-Duty Vehicles Other than Medium-Duty Passenger Vehicles.* Beginning in the 2017 model year, a manufacturer, except a small volume manufacturer, shall certify a percentage of its medium-duty vehicle fleet to the following particulate standards according to the following phase-in schedule. These standards are the maximum particulate emissions allowed at full useful life. All vehicles certifying to these particulate standards must certify to the LEV III exhaust emission standards set forth in subsection (a)(1). This subsection (a)(2)(B) shall not apply to medium-duty passenger vehicles.

LEV III Particulate Emission Standard Values and Phase-in for Medium-Duty Vehicles Other than Medium-Duty Passenger Vehicles			
Vehicle Type	**Model Year**	**% of vehicles certified to a 8 mg/mi standard**	**% of vehicles certified to a 10 mg/mi standard**
MDVs 8501 - 10,000 lbs. GVWR, excluding MDPVs	2017	10	n/a
	2018	20	n/a
	2019	40	n/a
	2020	70	n/a
Vehicles in this category are tested at their adjusted loaded vehicle weight	2021 and subsequent	100	n/a
MDVs 10,001 - 14,000 lbs. GVWR	2017	n/a	10
	2018	n/a	20
	2019	n/a	40
	2020	n/a	70
Vehicles in this category are tested at their adjusted loaded vehicle weight	2021 and subsequent	n/a	100

(C) *Particulate Standards for Small Volume Manufacturers.* In the 2021 through 2027 model years, a small volume manufacturer shall certify 100 percent of its passenger car, light-duty truck, and medium-duty passenger vehicle fleet to the 3 mg/mi particulate standard. In the 2028 and subsequent model years, a small volume manufacturer shall certify 100 percent of its passenger car, light-duty truck, and medium-duty passenger vehicle fleet to the 1 mg/mi particulate standard. In the 2021 and subsequent model years, a small volume manufacturer shall certify 100 percent of its medium-duty vehicles 8501 - 10,000 lbs. GVWR, excluding MDPVs, to the 8 mg/mi particulate standard. In the 2021 and subsequent model years, a small volume manufacturer shall certify 100 percent of its medium-duty vehicles 10,001 - 14,000 lbs. GVWR to the 10 mg/mi particulate standard. These standards are the maximum particulate emissions allowed at full useful life. All vehicles certifying to these particulate standards must certify to the LEV III exhaust emission standards set forth in subsection (a)(1).

(3) *NMOG+NOx Standards for Bi-Fuel, Fuel-Flexible, and Dual-Fuel Vehicles.* For fuel-flexible, bi-fuel, and dual-fuel PCs, LDTs and MDVs, compliance with the NMOG+NOx exhaust mass emission standards must be based on exhaust emission tests both when the vehicle is operated on the gaseous or alcohol fuel it is designed to use, and when the vehicle is operated on gasoline. A manufacturer must demonstrate compliance with the applicable exhaust mass emission standards for NMOG+NOx, CO, and formaldehyde set

forth in the table in subsection (a)(1) when certifying the vehicle for operation on the gaseous or alcohol fuel, as applicable, and on gasoline or diesel, as applicable.

A manufacturer may measure NMHC in lieu of NMOG when fuel-flexible, bi-fuel and dual-fuel vehicles are operated on gasoline, in accordance with the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles." Testing at 50°F is not required for fuel-flexible, bi-fuel, and dual-fuel vehicles when operating on gasoline.

(4) *50°F Exhaust Emission Standards.* All passenger cars, light-duty trucks, and medium-duty vehicles, other than natural gas and diesel-fueled vehicles, must demonstrate compliance with the following exhaust emission standards for NMOG+NOx and formaldehyde (HCHO) measured on the FTP (40 CFR, Part 86, Subpart B) conducted at a nominal test temperature of 50°F, as modified by Part II, Section C of the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles." A manufacturer may demonstrate compliance with the NMOG+NOx and HCHO certification standards contained in this subparagraph by measuring NMHC exhaust emissions or issuing a statement of compliance for HCHO in accordance with Section D.1, subparagraph (p) and Section G.3.1.2, respectively, of the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles." Emissions of CO measured at 50° F shall not exceed the standards set forth in subsection (a)(1) applicable to vehicles of the same emission category and vehicle type subject to a cold soak and emission test at 68° to 86° F.

(A) *Standards for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles Certified to the LEV III Standards.*

50°F Exhaust Emission Standards for LEV III Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles			
Vehicle Emission Category	*NMOG + NOx (g/mi)*		*HCHO (g/mi)*
	Gasoline	Alcohol Fuel	Both Gasoline and Alcohol Fuel
LEV160	0.320	0.320	0.030
ULEV125	0.250	0.250	0.016
ULEV70	0.140	0.250	0.016
ULEV50	0.100	0.140	0.016
SULEV30	0.060	0.125	0.008
SULEV20	0.040	0.075	0.008

(B) *Standards for Medium-Duty Vehicles (Excluding MDPVs) Certified to the LEV III Standards.*

50°F Exhaust Emission Standards for LEV III Medium-Duty Vehicles (Excluding MDPVs)			
Vehicle Emission Category	*NMOG + NOx (g/mi)*		*HCHO (g/mi)*
	Gasoline	Alcohol Fuel	Both Gasoline and Alcohol Fuel
LEV395	0.790	0.790	0.064
ULEV340	0.680	0.680	0.032
ULEV250	0.500	0.500	0.032
ULEV200	0.400	0.500	0.016
SULEV170	0.340	0.425	0.016
SULEV150	0.300	0.375	0.016
LEV630	1.260	1.260	0.080
ULEV570	1.140	1.140	0.042
ULEV400	0.800	0.800	0.042
ULEV270	0.540	0.675	0.020
SULEV230	0.460	0.575	0.020
SULEV200	0.400	0.500	0.020

(5) *Cold CO Standard*. The following standards are the 50,000 mile cold temperature exhaust carbon monoxide emission levels from new 2015 and subsequent model-year passenger cars, light-duty trucks, and medium-duty passenger vehicles:

2015 AND SUBSEQUENT MODEL-YEAR COLD TEMPERATURE CARBON MONOXIDE EXHAUST EMISSIONS STANDARDS FOR PASSENGER CARS, LIGHT-DUTY TRUCKS, AND MEDIUM-DUTY PASSENGER VEHICLES
(grams per mile)

Vehicle Type	*Carbon Monoxide*
All PCs, LDTs 0-3750 lbs. LVW;	10.0
LDTs, 3751 lbs. LVW - 8500 lbs. GVWR; MDPVs 10000 lbs. GVWR and less	12.5

These standards apply to vehicles tested at a nominal temperature of 20°F (-7°C) in accordance with 40 CFR Part 86 Subpart C, as amended by the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles." Natural gas, diesel-fueled and zero-emission vehicles are exempt from these standards.

(6) *Highway NMOG + NOx Standard.* The maximum emissions of non-methane organic gas plus oxides of nitrogen measured on the federal Highway Fuel Economy Test (HWFET; 40 CFR 600 Subpart B, as modified by the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," must not be greater than the applicable LEV III NMOG+NOx standard set forth in subsection (a)(1). Both the sum of the NMOG+NOx emissions and the HWFET standard must be rounded in accordance with ASTM E29-67 to the nearest 0.01 g/mi before being compared.

(7) *Supplemental Federal Test Procedure (SFTP) Off-Cycle Emission Standards.*

(A) *SFTP NMOG+NOx and CO Exhaust Emission Standards for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles.* Manufacturers shall certify 2015 and subsequent model year LEVs, ULEVs, and SULEVs in the PC, LDT, and MDPV classes to either the *SFTP NMOG+NOx and CO Stand-Alone Exhaust Emission Standards* set forth in subsection (a)(7)(A)1, or in accordance with the *SFTP NMOG+NOx and CO Composite Exhaust Emission Standards and Fleet-Average Requirements* set forth in subsection (a)(7)(A)2. The manufacturer shall notify the Executive Officer of its selected emission standard type in the Application for Certification of the first test group

certifying to SFTP NMOG+NOx and CO emission standards on a 150,000 mile durability basis. Once an emission standard type for NMOG+NOx and CO is selected for a fleet, and the Executive Officer is notified of such selection, the selection must be kept through the 2025 model year for the entire fleet, which includes LEV II vehicles if selecting to comply with subsection (a)(7)(A)2. The manufacturer may not change its selection until the 2026 model year. Test groups not certifying to the 150,000-mile SFTP NMOG+NOx and CO emission standards pursuant to this subsection (a)(7)(A) shall be subject to the 4,000-mile SFTP NMOG+NOx and CO emission standards set forth in subsection 1960.1(r).

1. *SFTP NMOG+NOx and CO Exhaust Stand-Alone Emission Standards*. The following standards are the maximum SFTP NMOG+NOx and CO exhaust emissions through full useful life from 2015 and subsequent model-year LEV III LEVs, ULEVs, and SULEVs when operating on any gaseous or liquid fuel they use for FTP certification.

SFTP NMOG+NOx and CO Stand-Alone Exhaust Emission Standards for 2015 and Subsequent Model LEV III Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles

Vehicle Type	*Durability Vehicle Basis (mi)*	*Vehicle Emission Category*[1]	US06 Test *(g/mi)*		*SC03 Test (g/mi)*	
			NMHC + NOx	*CO*	*NMHC + NOx*	*CO*
All PCs; LDTs 0- 8,500 lbs. GVWR; and MDPVs Vehicles in these categories are tested at their loaded vehicle weight (curb weight plus 300 pounds).	150,000	LEV	0.140	9.6	0.100	3.2
		ULEV	0.120	9.6	0.070	3.2
		SULEV (Option A)[2]	0.060	9.6	0.020	3.2
		SULEV	0.050	9.6	0.020	3.2

[1] *Vehicle Emission Category*. Manufacturers must certify all vehicles, which are certifying to a LEV III FTP emission category on a 150,000-mile durability basis, to the emission standards of the equivalent, or a more stringent, SFTP emission category set forth on this table. That is, all LEV III LEVs certified to 150,000-mile FTP emission standards shall comply with the SFTP LEV emission standards in this table, all LEV III ULEVs certified to 150,000-mile FTP emission standards shall comply with the SFTP ULEV emission standards in this table, and all LEV III SULEVs certified to 150,000-mile FTP emission standards shall comply with the SFTP SULEV emission standards in this table.

[2] *Optional SFTP SULEV Standards.* A manufacturer may certify light-duty truck test groups from 6,001 to 8,500 lbs. GVWR and MDPV test groups to the SULEV, option A, emission standards set forth in this table for the 2015 through 2020 model year, only if the vehicles in the test group are equipped with a particulate filter and the manufacturer extends the particulate filter emission warranty mileage to 200,000 miles. Passenger cars and light-duty trucks 0-6,000 lbs. GVWR are not eligible for this option.

2. *SFTP NMOG+NOx and CO Composite Exhaust Emission Standards*. For the 2015 and subsequent model years, a manufacturer selecting this option must certify LEV II and LEV III LEVs, ULEVs, and SULEVs, such that the manufacturer's sales-weighted fleet-average NMOG+NOx composite emission value, does not exceed the applicable NMOG+NOx composite emission standard set forth in the following table. In addition, the CO composite emission value of any LEV III test group shall not exceed the CO composite emission standard set forth in the following table. SFTP compliance shall be demonstrated using the same gaseous or liquid fuel used for FTP certification.

For each test group subject to this subsection, manufacturers shall calculate a Composite Emission Value for NMOG+NOx and, for LEV III test groups, a separate Composite Emission Value for CO, using the following equation:

Composite Emission Value = 0.28 x US06 + 0.37 x SC03 + 0.35 x FTP [Eq. 1]

where "US06" = the test group's NMOG+NOx or CO emission value, as applicable, determined through the US06 test;
"SC03" = the test group's NMOG+NOx or CO emission value, as applicable, determined through the SC03 test; and
"FTP" = the test group's NMOG+NOx or CO emission value, as applicable, determined through the FTP test.

If no vehicles in a test group have air conditioning units, the FTP cycle emission value can be used in place of the SC03 cycle emission value in Equation 1. To determine compliance with the SFTP NMOG+NOx composite emission standard applicable to the model year, manufacturers shall use a sales-weighted fleet average of the NMOG+NOx composite emission values of every applicable test group. The sales-weighted fleet average shall be calculated using a combination of carry-over and new certification SFTP composite emission values (converted to NMOG+NOx, as applicable). LEV II test groups will use their emission values in the fleet average calculation but will not be considered LEV III test groups. Compliance with the CO composite emission standard cannot be demonstrated through fleet averaging. The NMOG+NOx sales-weighted fleet-average composite emission value for the fleet and the CO composite emission value for each test group shall not exceed:

SFTP NMOG+NOx and CO Composite Emission Standards for 2015 and Subsequent Model Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles (g/mi)[1]

Model Year	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025+
All PCs; LDTs 8,500 lbs. GVWR or less; and MDPVs[3]	***Sales-Weighted Fleet Average NMOG+NOx Composite Exhaust Emission Standards***[2,4,5,6]										
	0.140	0.110	0.103	0.097	0.090	0.083	0.077	0.070	0.063	0.057	0.050
Vehicles in this category are tested at their loaded vehicle weight (curb weight plus 300 pounds).	***CO Composite Exhaust Emission Standard***[7]										
	4.2										

[1] *Mileage for Compliance.* All test groups certifying to LEV III FTP emission standards on a 150,000-mile durability basis shall also certify to the SFTP on a 150,000-mile durability basis, as tested in accordance with the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles."

[2] *Determining NMOG+NOx Composite Emission Values of LEV II Test Groups.* For carry-over test groups certified to LEV II FTP emission standards, SFTP emission values shall be converted to NMOG+NOx and projected out to 120,000 miles or 150,000 miles., In lieu of deriving a deterioration factor specific to SFTP test cycles, carry-over test groups may use the applicable deterioration factor from the FTP cycle in order to determine the carry-over composite emission values for the purpose of the NMOG+NOx sales-weighted fleet-average calculation.

[3] MDPVs are excluded from SFTP NMOG+NOx and CO emission standards and the sales-weighted fleet average until they are certified to LEV III FTP 150,000-mile NMOG+NOx and CO requirements.

[4] Test groups shall certify to bins in increments of 0.010 g/mi. Beginning with the 2018 model year, vehicles may not certify to bin values above a maximum of 0.180 g/mi.

[5] *Calculating the sales-weighted average for NMOG+NOx.* For each model year, the manufacturer shall calculate its sales-weighted fleet-average NMOG+NOx composite emission value as follows.

$$\frac{\left[\sum_{i=1}^{n}\left(number\ of\ vehicles\ in\ the\ test\ group\right)_i \times \left(composite\ value\ of\ bin\right)_i\right]}{\sum_{i=1}^{n}\left(number\ of\ vehicles\ in\ the\ test\ group\right)_i} \qquad \text{[Eq. 2]}$$

where "n" = a manufacturer's total number of PC, LDT, and, if applicable, MDPV certification bins, in a given model year including carry-over certification bins, certifying to SFTP composite emission standards in that model year;

"number of vehicles in the test group" = the number of vehicles produced and delivered for sale in California in the certification test group; and

"Composite Value of Bin" = the numerical value selected by the manufacturer for the certification bin that serves as the emission standard for the vehicles in the test group with respect to all testing for test groups certifying to SFTP on a 150,000-mile durability basis, and the SFTP carry-over composite emission value, as described in footnote 7 of this table, for carry-over LEV II test groups.

[6] *Calculation of Fleet Average Total NMOG+NOx Credits or Debits.* A manufacturer shall calculate the total NMOG+NOx credits or debits, as follows:

[(NMOG+NOx Composite Emission Standard) – (Manufacturer's Sales-Weighted Fleet-Average Composite Emission Value)]
x (Total Number of Vehicles Produced and Delivered for Sale in California in the 0-8,500 lbs GVWR plus MDPVs classes, if applicable) [Eq. 3]

A negative number constitutes total NMOG+NOx debits, and a positive number constitutes total NMOG+NOx credits accrued by the manufacturer for the given model year. Total NMOG+NOx credits earned in a given model year retain full value through the fifth model year after they are earned. At the beginning of the sixth model year, the total NMOG+NOx credits have no value. A manufacturer may trade credits with other manufacturers

A manufacturer shall equalize total NMOG+NOx debits within three model years after they have been incurred by earning NMOG+NOx credits in an amount equal to the total NMOG+NOx debits. If total NMOG+NOx debits are not equalized within the three model-year period, the manufacturer is subject to the Health and Safety Code section 43211 civil penalty applicable to a manufacturer which sells a new motor vehicle that does not meet the applicable emission standards adopted by the state board. The cause of action shall be deemed to accrue when the total NMOG+NOx debits are not equalized by the end of the specified time period. For the purposes of Health and Safety Code section 43211, the number of vehicles not meeting the state board's emission standards is determined by dividing the NMOG+NOx debits for the model year by the NMOG+NOx composite emission standard in effect during the model year in which the debits were incurred.

[7] *Calculating the CO composite emission value.* Composite emission values for CO shall be calculated in accordance with Equation 1 above. Unlike the NMOG+NOx composite emission standards, manufacturers would not be able to meet the proposed CO composite emission standard through fleet averaging: each individual test group must comply with the standard. Test groups certified to 4,000-mile SFTP emission standards are not subject to this CO emission standard.

(B) *SFTP PM Exhaust Emission Standards for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles.* The following standards are the maximum PM exhaust emissions through the full useful life from 2017 and subsequent model-year LEV III LEVs, ULEVs, and SULEVs in the PC, LDT, and MDPV classes when operating on any gaseous or liquid fuel they use for FTP certification. Manufacturers must certify LEVs, ULEVs, and SULEVs in the PC, LDT, and MDPV classes, which are certifying to LEV III FTP PM emission standards in subsection (a)(2) on a 150,000-mile durability basis, to the *SFTP PM Exhaust Emission Standards* set forth in this subsection (a)(7)(B).

SFTP PM Exhaust Emission Standards for 2017 and Subsequent Model LEV III Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles[1]

Vehicle Type	*Test Weight*	*Mileage for Compliance*	*Test Cycle*	*PM (mg/mi)*
All PCs; LDTs 0-6,000 lbs GVWR	Loaded vehicle weight	150,000	US06	10.0
LDTs 6,001-8,500 lbs GVWR; MDPVs	Loaded vehicle weight	150,000	US06	20.0

[1] All PCs, LDTs, and MDPVs certified to LEV III FTP PM emission standards in subsection (a)(2) on a 150,000-mile durability basis shall comply with the SFTP PM Exhaust Emission Standards in this table.

(C) *SFTP II NMOG+NOx and CO Exhaust Emission Standards for Medium-Duty Vehicles.* The following standards are the maximum NMOG+NOx and CO composite emission values for full useful life of 2016 and subsequent model-year medium-duty LEV III ULEVs and SULEVs from 8,501 through 14,000 pounds GVWR when operating on any gaseous or liquid fuel they use for FTP certification. The following composite emission standards do not apply to MDPVs subject to the emission standards presented in subsections (a)(7)(A) and (a)(7)(B).

SFTP NMOG+NOx and CO Composite Exhaust Emission Standards for 2016 and Subsequent Model ULEVs and SULEVs in the Medium-Duty Vehicle Class

Vehicle Type	*Mileage for Compliance*	*HP/GVWR*[2]	*TestCycle*[3,4]	*Vehicle Emission Category*[5]	*Composite Emission Standard*[1] *(g/mi)*	
					NMOG + NOx	*Carbon Monoxide*
MDVs 8,501 - 10,000 lbs GVWR	150,000	≤ 0.024	US06 Bag 2, SC03, FTP	ULEV	0.550	22.0
				SULEV	0.350	12.0
		> 0.024	Full US06, SC03, FTP	ULEV	0.800	22.0
				SULEV	0.450	12.0
MDVs 10,001-14,000 lbs GVWR	150,000	n/a	UC (LA92), SC03, FTP	ULEV	0.550	6.0
				SULEV	0.350	4.0

[1] Manufacturers shall use Equation 1 in subsection (a)(7)(A)2 to calculate SFTP Composite Emission Values for each test group subject to the emission standards in this table. For MDVs 10,001-14,000 lbs. GVWR, the emission results from the UC test shall be used in place of results from the US06 test.

[2] *Power to Weight Ratio.* If all vehicles in a test group have a power to weight ratio at or below a threshold of 0.024, they may opt to run the US06 Bag 2 in lieu of the full US06 cycle. The cutoff is determined by using a ratio of the engine's horsepower to the vehicle's GVWR in pounds and does not include any horsepower contributed by electric motors in the case of hybrid electric or plug-in hybrid electric vehicles. Manufacturers may opt to test to the full cycle regardless of the calculated ratio; in such case, manufacturers shall meet the emission standards applicable to vehicles with power-to-weight ratios greater than 0.024.

[3] *Test Weight.* Medium-duty vehicles are tested at their adjusted loaded vehicle weight (average of curb weight and GVWR).

[4] *Road Speed Fan.* Manufacturers have the option to use a road speed modulated fan as specified in § 86.107–96(d)(1) instead of a fixed speed fan for MDV SFTP testing.

[5] *Vehicle Emission Categories.* For MDVs 8,501-10,000 lbs. GVWR, for each model year, the percentage of MDVs certified to an SFTP emission category set forth in this section 1961.2 shall be equal to or greater than the total percentage certified to the FTP ULEV250, ULEV200, SULEV170, and SULEV150 emission categories; of these vehicles, the percentage of MDVs certified to an SFTP SULEV emission category shall be equal to or greater than the total percentage certified to both the FTP SULEV170 and SULEV150 emission categories. For MDVs 10,001-14,000 lbs. GVWR, for each model year, the percentage of MDVs certified to an SFTP emission category set forth in this section 1961.2 shall be equal to or greater than the total percentage certified to the FTP ULEV400, ULEV270, SULEV230, and SULEV200 emission categories; of these vehicles, the percentage of MDVs certified to an SFTP SULEV emission category shall be equal to or greater than the total percentage certified to both the FTP SULEV230 and SULEV200 emission categories.

(D) *SFTP PM Exhaust Emission Standards for Medium-Duty Vehicles.* The following standards are the maximum PM composite emission values for the full useful life of 2017 and subsequent model-year LEV III LEVs, ULEVs, and SULEVs when operating on any gaseous or liquid fuel they use for FTP certification. The following composite emission standards do not apply to MDPVs subject to the emission standards set forth in subsections (a)(7)(A) and (a)(7)(B).

SFTP PM Exhaust Emission Standards for 2017 and Subsequent Model Medium-Duty Vehicles[1]

Vehicle Type	*Test Weight*	*Mileage for Compliance*	*Hp/GVWR*[2]	*Test Cycle*[3,4]	*PM (mg/mi)*
MDVs 8,501-10,000 lbs GVWR	Adjusted loaded vehicle weight	150,000	≤ 0.024	US06 Bag 2	7.0
			>0.024	US06	10.0
MDVs 10,001-14,000 lbs GVWR	Adjusted loaded vehicle weight	150,000	n/a	UC (LA92)	7.0

[1] Except for MDPVs subject to the emission standards set forth in subsection (a)(7)(B), MDVs certified to 150,000-mile FTP PM emission standards in subsection (a)(2) shall comply with the SFTP PM Exhaust Emission Standards in this table.

[2] *Power to Weight Ratio.* If all vehicles in a test group have a power to weight ratio at or below a threshold of 0.024, they may opt to run the US06 Bag 2 in lieu of the full US06 cycle. The cutoff is determined by using a ratio of the engine's horsepower to the vehicle's GVWR in pounds and does not include any horsepower contributed by electric motors in the case of hybrid electric or plug-in hybrid electric vehicles. Manufacturers may opt to test to the full cycle regardless of the calculated ratio; in such case, manufacturers shall meet the emission standards applicable to vehicles with power-to-weight ratios greater than 0.024.

[3] *Road Speed Fan.* Manufacturers have the option to use a road speed modulated fan as specified in § 86.107–96(d)(1) instead of a fixed speed fan for MDV SFTP testing.

[4] Manufacturers shall use Equation 1 above to calculate SFTP Composite PM Emission Values for each test group subject to the emission standards in this table. For MDVs 8,501-10,000 lbs. GVWR certifying to the US06 Bag 2 PM emission standard, the emission results from the US06 Bag 2 test shall be used in place of results from the full US06 test. For MDVs 10,001-14,000 lbs. GVWR, the emission results from the UC test shall be used in place of results from the US06 test.

(8) *Interim In-Use Compliance Standards.*

(A) *LEV III NMOG+NOx Interim In-Use Compliance Standards.* The following interim in-use compliance standards shall apply for the first two model years that a test group is certified to the LEV III standards.

1. *NMOG+NOx Interim In-Use Compliance Standards for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles.* For the 2015 through 2019 model years, these standards shall apply.

Emission Category	Durability Vehicle Basis (miles)	LEV III PCs, LDTs, and MDPVs
		NMOG + NOx (g/mi)
LEV160	150,000	n/a
ULEV125	150,000	n/a
ULEV70	150,000	0.100
ULEV50	150,000	0.070
SULEV30	150,000	0.040[1]
SULEV20	150,000	0.030[1]

[1]not applicable to test groups that receive PZEV credits

2. *NMOG+NOx Interim In-Use Compliance Standards for Medium-Duty Vehicles, Excluding Medium-Duty Passenger Vehicles.* For the 2015 through 2020 model years, these standards shall apply.

Emission Category	Durability Vehicle Basis (miles)	LEV III MDVs (excluding MDPVs) 8,501 - 10,000 lbs. GVW	LEV III MDVs 10,001 - 14,000 lbs. GVW
		NMOG + NOx (g/mi)	NMOG + NOx (g/mi)
LEV395	150,000	n/a	n/a
ULEV340	150,000	n/a	n/a
ULEV250	150,000	0.370	n/a
ULEV200	150,000	0.300	n/a
SULEV170	150,000	0.250	n/a
SULEV150	150,000	0.220	n/a
LEV630	150,000	n/a	n/a
ULEV570	150,000	n/a	n/a
ULEV400	150,000	n/a	0.600
ULEV270	150,000	n/a	0.400
SULEV230	150,000	n/a	0.340
SULEV200	150,000	n/a	0.300

(B) *LEV III Particulate Interim In-Use Compliance Standards.* The following interim in-use compliance standards shall apply for the first two model years that a test group is certified to the LEV III standards.

1. *LEV III Particulate Interim In-Use Compliance Standards for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles.* For the 2017 through 2020 model years, the interim in-use compliance standard for vehicles certifying to the 3 mg/mi particulate standard is 6 mg/mi. For the 2025 through 2028 model years, the interim in-use compliance standard for vehicles certifying to the 1 mg/mi particulate standard is 2 mg/mi.

2. *LEV III Particulate Interim In-Use Compliance Standards for Medium-Duty Vehicles, excluding Medium-Duty Passenger Vehicles.* For the 2017 through 2020 model years, the interim in-use compliance standard for vehicles certifying to the 8 mg/mi particulate standard shall be 16 mg/mi and the interim in-use compliance standard for vehicles certifying to the 10 mg/mi particulate standard shall be 20 mg/mi.

(C) SFTP *Interim In-Use Compliance Standards.*

1. Test groups certified prior to the 2020 model year may use an in-use compliance standard for NMOG+NOx for the first two model years that they are certified to new standards.

a. For light-duty vehicle test groups and medium-duty passenger vehicle test groups certifying to the standards in subsection (a)(7)(A)1, in-use compliance emission standards for NMOG+NOx shall be 1.4 times the applicable certification standard.

b. For light-duty vehicle test groups and medium-duty passenger vehicle test groups certifying to the standards in subsection (a)(7)(A)2, in-use compliance emission standards for NMOG+NOx shall be 1.4 times the Composite Value of the bin to which a test group is certified.

c. For medium-duty vehicle tests groups certifying to the standards in subsection (a)(7)(C), in-use compliance emission standards for NMOG+NOx shall be 1.4 times the applicable certification standard.

2. Test groups certified prior to the 2020 model year will be allowed an in-use compliance standard for PM for the first five model years that they are certified to the SFTP PM standard.

a. For light-duty vehicle test groups and medium-duty passenger vehicle test groups certifying to SFTP PM exhaust emission

standards in subsection (a)(7)(B), in-use compliance emission standards for PM shall be 5.0 mg/mi higher than the applicable certification standard.

b. For medium-duty vehicle test groups certifying to SFTP PM Exhaust Emission Standards in subsection (a)(7)(D), in-use compliance emission standards for PM shall be 5.0 mg/mi higher than the applicable certification standard.

(9) *Requirement to Generate Additional NMOG+NOx Fleet Average Credit.* For a vehicle that is certified to the LEV III standards in subsection (a)(1), which does not generate a partial ZEV allocation according to the criteria set forth in section C.3 of the "California Exhaust Emission Standards and Test Procedures for 2009 through 2017 Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes" and the "California Exhaust Emission Standards and Test Procedures for 2018 and Subsequent Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," a manufacturer may subtract 5 mg/mi from the NMOG+NOx emission standards value set forth in subsection (b)(1)(B)1.c when calculating the manufacturer's fleet average, provided that the manufacturer extends the performance and defects warranty period to 15 years or 150,000 miles, whichever occurs first.

(10) *Requirement to Generate a Partial ZEV Allowance.* For the 2015 through 2017 model years, a manufacturer that certifies to the LEV III SULEV30 or the LEV III SULEV20 standards shall also generate a partial ZEV allocation according to the criteria set forth in section C.3 of the "California Exhaust Emission Standards and Test Procedures for 2009 through 2017 Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes."

(11) *NMOG Credit for Direct Ozone Reduction Technology.* A manufacturer that certifies vehicles equipped with direct ozone reduction technologies shall be eligible to receive NMOG credits that can be applied to the NMOG exhaust emissions of the vehicle when determining compliance with the standard. In order to receive credit, the manufacturer must submit the following information for each vehicle model for which it gets credit, including, but not limited to:

(A) a demonstration of the airflow rate through the direct ozone reduction device and the ozone-reducing efficiency of the device over the range of speeds encountered in the Unified Cycle Driving Schedule;

(B) an evaluation of the durability of the device for the full useful life of the vehicle; and

(C) a description of the on-board diagnostic strategy for monitoring the performance of the device in-use.

Using the above information, the Executive Officer shall determine the value of the NMOG credit based on the calculated change in the one-hour peak ozone level using an approved airshed model.

(12) *When a Federally-Certified Vehicle Model is Required in California.*

(A) *General Requirement.* Whenever a manufacturer federally-certifies a 2015 or subsequent model-year passenger car, light-duty truck, or medium-duty vehicle model to the standards for a particular emissions bin that are more stringent than the standards for an applicable California emission category, the equivalent California model may only be certified to (i) the California standards for a vehicle emissions category that are at least as stringent as the standards for the corresponding federal emissions bin, or (ii) the exhaust emission standards to which the federal model is certified. However, where the federal exhaust emission standards for the particular emissions bin and the California standards for a vehicle emissions category are equally stringent, the California model may only be certified to either the California standards for that vehicle emissions category or more stringent California standards. The federal emission bins are those contained in Tables S04-1 and S04-2 of 40 CFR §86.1811-04(c) as adopted February 10, 2000. The criteria for applying this requirement are set forth in Part I. Section H.1 of the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles."

(B) *Exception for clean fuel fleet vehicles.* Subsection (a)(12)(A) does not apply in the case of a federally-certified vehicle model that is only marketed to fleet operators for applications that are subject to clean fuel fleet requirements established pursuant to section 246 of the federal Clean Air Act (42 U.S.C. sec. 7586). In addition, the Executive Officer shall exclude from the requirement a federally-certified vehicle model where the manufacturer demonstrates to the Executive Officer's reasonable satisfaction that the model will primarily be sold or leased to clean fuel fleet operators for such applications, and that other sales or leases of the model will be incidental to marketing to those clean fuel fleet operators.

(13) *Emission Standard for a Fuel-Fired Heater.* Whenever a manufacturer elects to utilize an on-board fuel-fired heater on any passenger car, light-duty truck or medium-duty vehicle, the fuel-fired heater must meet ULEV125 standards for passenger cars and light-duty trucks less than 8,500 pounds GVWR as set forth in subsection 1961(a)(1). The exhaust emissions from the fuel-fired heater shall be determined in accordance with the ""California Exhaust Emission Standards and Test Procedures for 2009 through 2017 Model Zero-

Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes" or the "California Exhaust Emission Standards and Test Procedures for 2018 and Subsequent Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," as applicable. If the on-board fuel-fired heater is capable of operating at ambient temperatures above 40°F, the measured emission levels of the on-board fuel-fired heater shall be added to the emissions measured on the FTP (40 CFR, Part 86, Subpart B), as amended by the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles" to determine compliance with the exhaust emission standards in subsection (a)(1).

(b) *Emission Standards Phase-In Requirements for Manufacturers.*

(1) *Fleet Average NMOG + NOx Requirements for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles.*

(A) The fleet average non-methane organic gas plus oxides of nitrogen exhaust mass emission values from the passenger cars, light-duty trucks, and medium-duty passenger vehicles that are produced and delivered for sale in California each model year by a manufacturer other than a small volume manufacturer shall not exceed:

FLEET AVERAGE NON-METHANE ORGANIC GAS PLUS OXIDES OF NITROGEN EXHAUST MASS EMISSION REQUIREMENTS FOR PASSENGER CARS, LIGHT-DUTY TRUCKS, AND MEDIUM-DUTY PASSENGER VEHICLES (150,000 mile Durability Vehicle Basis)		
Model Year	*Fleet Average NMOG + NOx (grams per mile)*	
	All PCs; LDTs 0-3750 lbs. LVW	*LDTs 3751 lbs. LVW - 8500 lbs. GVWR; All MDPVs*
2015	0.100	0.119
2016	0.093	0.110
2017	0.086	0.101
2018	0.079	0.092
2019	0.072	0.083
2020	0.065	0.074
2021	0.058	0.065
2022	0.051	0.056
2023	0.044	0.047
2024	0.037	0.038
2025+	0.030	0.030

1. *Pooling Provision.*

a. For each model year, a manufacturer must demonstrate compliance with the fleet average requirements in this subsection (b)(1)(A) based on one of two options applicable throughout the model year, either:

Option 1: the total number of passenger cars, light-duty trucks, and medium-duty passenger vehicles that are certified to the California exhaust emission standards in subsection (a) and subsection 1961(a)(1), and are produced and delivered for sale in California; or

Option 2: the total number of passenger cars, light-duty trucks, and medium-duty passenger vehicles that are certified to the California exhaust emission standards in subsection (a) and subsection 1961(a)(1), and are produced and delivered for sale in California, the District of Columbia, and all states that have adopted California's criteria pollutant emission standards set forth in this section

1961.2 for that model year pursuant to section 177 of the federal Clean Air Act (42 U.S.C. § 7507).

b. A manufacturer that selects compliance Option 2 must notify the Executive Officer of that selection in writing prior to the start of the applicable model year or must comply with Option 1.

c. When a manufacturer is demonstrating compliance using Option 2 for a given model year, the term "in California" as used in this section 1961.2 means California, the District of Columbia, and all states that have adopted California's criteria pollutant emission standards set forth in this section 1961.2 for that model year pursuant to Section 177 of the federal Clean Air Act (42 U.S.C. § 7507).

d. A manufacturer that selects compliance Option 2 must provide to the Executive Officer separate values for the number of vehicles produced and delivered for sale in the District of Columbia and for each individual state within the average.

2. *PZEV Anti-Backsliding Requirement.* In the 2018 and subsequent model years, a manufacturer must produce and deliver for sale in California a minimum percentage of its passenger car and light-duty truck fleet that certifies to SULEV30 and SULEV20 standards. This minimum percentage must be equal to the average percentage of PZEVs produced and deliver for sale in California for that manufacturer based for the 2015 through 2017 model year. For the 2018 model year, a manufacturer may calculate this average percentage using the projected sales for the 2017 model year in lieu of actual sales.

(B) *Calculation of Fleet Average NMOG + NOx Value.*

1. *Basic Calculation.*

a. Each manufacturer's PC and LDT1 fleet average NMOG + NOx value for the total number of PCs and LDT1s produced and delivered for sale in California shall be calculated as follows:

(Σ [Number of vehicles in a test group x applicable emission standard] +
Σ [Number of off-vehicle charge capable hybrid electric vehicles in a test group x HEV NMOG+NOx contribution factor]) ÷
Total Number of PCs plus LDT1s Produced and Delivered for sale in California, Including ZEVs and HEVs

b. Each manufacturer's LDT2 and MDPV fleet average NMOG+NOx value for the total number of LDT2s and MDPVs produced and delivered for sale in California shall be calculated as follows:

(Σ [Number of vehicles in a test group x applicable emission standard] + Σ [Number of hybrid electric vehicles in a test group x HEV NMOG factor]) ÷ Total Number of LDT2s plus MDPVs Produced and Delivered for sale in California, Including ZEVs and HEVs

c. The applicable emission standards to be used in the above equations are as follows:

Model Year	**Emission Category**	**Emission Standard Value[1] (g/mi)**	
		All PCs; LDTs 0-3750 lbs. LVW	**LDTs 3751-5750 lbs. LVW; All MDPVs**
2015 and subsequent (AB 965 vehicles only)[2]	All	Sum of the NMOG and NOx Federal Emission Standards to which Vehicle is Certified	Sum of the NMOG and NOx Federal Emission Standards to which Vehicle is Certified
Model Year	**Emission Category**	**All PCs; LDTs 0-3750 lbs. LVW**	**LDTs 3751 lbs. LVW - 8500 lbs. GVWR; All MDPVs**
2015 through 2019 model year vehicles certified to the "LEV II" standards in subsection 1961(a)(1); 2015 and subsequent model year vehicles certified to the "LEV III" standards in subsection 1961.2(a)(1)	LEV II LEVs; LEV160s	0.160	0.160
	LEV II ULEVs; LEV125s	0.125	0.125
	ULEV70s	0.070	0.070
	ULEV50s	0.050	0.050
	LEV II SULEVs; SULEV30s	0.030	0.030
	SULEV20s	0.020	0.020
	LEV395s	n/a	0.395
	ULEV340s	n/a	0.340
	ULEV250s	n/a	0.250
	ULEV200s	n/a	0.200
	SULEV170s	n/a	0.170
	SULEV150s	n/a	0.150

[1] For LEV III vehicle test groups that meet the extended emission warranty requirements in subsection (a)(9), the applicable emission standard value shall be the emission standard value set forth in this table minus 5 mg/mi.

[2] "AB 965 vehicles" are those certified in accordance with the "Guidelines for Certification of 2003 and Subsequent Model-Year Federally Certified Light-Duty Motor Vehicles for Sale in California," incorporated by reference in section 2062.

2. *NMOG+NOx Contribution Factor for Off-vehicle Charge Capable HEVs.* The HEV NMOG+NOx contribution factor for light-duty off-vehicle charge capable hybrid electric vehicles is calculated as follows:

LEV160 HEV Contribution Factor = 0.160 - [(Zero-emission VMT Allowance) x 0.035]
ULEV125 HEV Contribution Factor = 0.125 - [(Zero-emission VMT Allowance) x 0.055]
ULEV70 HEV Contribution Factor = 0.070 - [(Zero-emission VMT Allowance) x 0.020]
ULEV50 HEV Contribution Factor = 0.050 - [(Zero-emission VMT Allowance) x 0.020]
SULEV30 HEV Contribution Factor = 0.030 - [(Zero-emission VMT Allowance) x 0.010]
SULEV20 HEV Contribution Factor = 0.020 - [(Zero-emission VMT Allowance) x 0.020]

where the Zero-emission VMT Allowance for off-vehicle charge capable HEVs is determined in accordance with section C.3 of the "California Exhaust Emission Standards and Test Procedures for 2009 through 2017 Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes" and the "California Exhaust Emission Standards and Test Procedures for 2018 and Subsequent Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," as applicable. This subsection (b)(1)(B)2 shall only apply to off-vehicle charge capable HEVs certified to the LEV III standards set forth in subsection (a)(1).

3. *Federally-Certified Vehicles.* A vehicle certified to the federal standards for a federal exhaust emissions bin in accordance with section H.1 of the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles" shall use the sum of the corresponding LEV II NMOG and NOx emission category value set forth in subsection (b)(1)(B)1.c for the fleet average calculation. If a vehicle is certified to 150,000 mile standards for a federal exhaust emission bin and the corresponding California NMOG+NOx emission category is a LEV III category, it may use the emission standard value for that LEV III category as set forth in subsection (b)(1)(B)1.c.

(C) Phase-In *Requirements for Small Volume Manufacturers.*

1. In the 2015 through 2019 model years, a small volume manufacturer shall not exceed a fleet average NMOG+NOx value of 0.160 g/mi for PCs and LDTs from 0-3750 lbs. LVW or 0.160 g/mi for LDTs from 3751-5750 lbs. LVW calculated in accordance with subsection (b)(1)(B). In 2020 through 2024 model years, a small volume manufacturer shall not exceed a fleet average NMOG+NOx value of 0.125 g/mi for PCs and LDTs from 0-3750 lbs. LVW or 0.125 g/mi for LDTs from 3751 lbs. LVW - 8,500 lbs. GVW and MDPVs calculated in accordance with subsection (b)(1)(B). In 2025 and subsequent model years, a small volume manufacturer shall not exceed a fleet average NMOG+NOx value of 0.070 g/mi for PCs and LDTs from 0-3750 lbs. LVW or 0.070 g/mi for LDTs from 3751 lbs. LVW - 8,500 lbs. GVW and MDPVs calculated in accordance with subsection (b)(1)(B).

2. If a manufacturer's average California sales exceeds 4500 units of new PCs, LDTs, MDVs, heavy-duty vehicles, and heavy-duty engines based on the average number of vehicles sold for the three previous consecutive model years, the manufacturer shall no longer be treated as a small volume manufacturer. If this is the first time the manufacturer exceeds the 4500 unit sales limit, the manufacturer must comply with the fleet average requirements applicable to a large volume manufacturer, as specified in subsection (b)(1)(A) beginning with the fourth model year after the last of the three consecutive model years. If during this four year lead time period the manufacturer's sales drop below the 4500 unit sales limit and then increase again above the 4500 unit sales limit, the four year lead time period shall be calculated based on the first model year in which the manufacturer again exceeds the 4500 unit sales limit. Except as noted above – i.e., if this is not the first time the manufacturer has exceeded the 4500 unit sales limit – the manufacturer shall comply with the fleet average requirements applicable to larger manufacturers as specified in subsection (b)(1)(A) beginning with the following model year after the last of the three consecutive model years.

3. If a manufacturer's average California sales fall below 4500 units of new PCs, LDTs, MDVs and heavy duty engines based on the average number of vehicles sold for the three previous consecutive model years, the manufacturer shall be treated as a small volume manufacturer and shall be subject to the requirements for small volume manufacturers beginning with the next model year.

(D) *Treatment of ZEVs.* ZEVs classified as LDTs (>3750 lbs. LVW) that have been counted toward the ZEV requirement for PCs and LDTs (0-3750 lbs. LVW) as specified in sections 1962 and 1962.1 shall be included as LDT1s in the calculation of a fleet average NMOG value.

(2) *LEV III Phase-In Requirement for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles.* Beginning in the 2015 model year, the LEV II SULEV emission standards set forth in section 1961(a)(1) that are applicable to PCs, LDTs, and MDPVs shall only apply to those PCs, LDT1s, LDT2s, and MDPVs that receive partial ZEV allowances in accordance with the "California Exhaust Emission Standards and Test Procedures for 2009 through 2017 Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes" or the "California Exhaust Emission Standards and Test Procedures for 2018 and Subsequent Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," as applicable. A manufacturer shall certify 100 percent of its PC, LDT, and MDPV fleet to the LEV III standards in subsection (a)(1) in 2020 and subsequent model years.

(3) *LEV III Phase-In Requirements for Medium-Duty Vehicles, Other than Medium-Duty Passenger Vehicles.*

(A) A manufacturer of MDVs, other than a small volume manufacturer, shall certify at least the following percentage of its MDV fleet according to the following phase-in schedule:

Model Year	*Vehicles Certified to §1961.2(a)(1) (%)*				*Vehicles Certified to §1956.8(c) or (h) (%)*
	LEV II LEV; LEV III LEV395 or LEV630	LEV II ULEV; LEV III ULEV340 or ULEV570	LEV III ULEV250 or ULEV400	LEV III SULEV170 or SULEV230	ULEV
2015	40	60	0	0	100
2016	20	60	20	0	100
2017	10	50	40	0	100
2018	0	40	50	10	100
2019	0	30	40	30	100
2020	0	20	30	50	100
2021	0	10	20	70	100
2022 +	0	0	10	90	100

(B) *Requirements for Small Volume Manufacturers.* In the 2015 through 2017 model years, a small volume manufacturer shall certify, produce,

and deliver for sale in California vehicles or engines certified to the MDV LEV II LEV standards or to the LEV III LEV395 or LEV III LEV630 standards, as applicable, in a quantity equivalent to 100% of its MDV fleet. In the 2018 through 2021 model years, a small volume manufacturer shall certify, produce, and deliver for sale in California vehicles or engines certified to the MDV LEV II ULEV standards or to the LEV III ULEV340 or LEV III ULEV570 standards, as applicable, in a quantity equivalent to 100% of its MDV fleet. In the 2022 and subsequent model years, a small volume manufacturer shall certify, produce, and deliver for sale in California vehicles or engines certified to the MDV LEV III ULEV250 or LEV III ULEV400 standards, as applicable, in a quantity equivalent to 100% of its MDV fleet. Engines certified to these MDV standards are not eligible for emissions averaging.

(C) *Identifying a Manufacturer's MDV Fleet.* Each manufacturer's MDV fleet shall be defined as the total number of California-certified MDVs produced and delivered for sale in California. The percentages shall be applied to the manufacturers' total production of California-certified medium-duty vehicles delivered for sale in California. A manufacturer that elects to certify to the optional medium-duty engine standards in subsections 1956.8(c) or (h) shall not count those engines in the manufacturer's total production of California-certified medium-duty vehicles for purposes of this subsection.

(D) For a manufacturer that elects to certify to the optional medium-duty engine standards in title 13, CCR subsections 1956.8(c) or (h), all such MDVs, including those produced by a small volume manufacturer, shall be subject to the emissions averaging provisions applicable to heavy-duty diesel or Otto-cycle engines as set forth in the "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Otto-Cycle Engines," or the "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Diesel Engines, incorporated by reference in subsections 1956.8(b) or (d), as applicable.

(4) *SFTP Phase-In Requirements.*

(A) *Phase-In Requirement for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles.* A test group certifying to LEV III FTP emission categories on a 150,000-mile durability basis shall also certify to SFTP requirements on a 150,000-mile durability basis.

Manufacturers shall have two options for phase in to the SFTP NMOG+NOx and CO emission standards.

1. Under Option 1, beginning with the 2015 model year, a manufacturer shall certify its PCs, LDTs, and MDPVs to the SFTP NMOG+NOx and CO emission standards in subsection (a)(7)(A)1 when the

vehicles are also certifying to a LEV III FTP emission category at 150,000-mile durability.

2. Under Option 2, for 2015 and subsequent model years, a manufacturer shall certify its fleet of PCs, LDTs, and MDPVs such that the manufacturer's sales-weighted fleet-average NMOG+NOx composite emission value does not exceed the composite emission standard in effect for that model year. During the 150,000-mile durability phase-in, the sales-weighted fleet-average NMOG+NOx composite emission value shall be calculated using a combination of carry-over values and new-certification values. Carry-over test groups shall convert values to NMOG+NOx and may use the applicable deterioration factor from the FTP cycle in lieu of deriving a deterioration factor specific to SFTP test cycles. Any vehicle certified to SFTP requirements on a 150,000-mile durability basis shall be subject to the applicable emission standards for the full useful life of that vehicle. Compliance with the CO composite emission standard cannot be demonstrated through fleet averaging.

Beginning with the 2017 model year, a manufacturer shall certify its PCs, LDTs, and MDPVs certifying to LEV III FTP PM emission standards on a 150,000-mile durability basis to the SFTP PM emission standards in subsection (a)(7)(B).

(B) *Phase-In Requirements for Medium-Duty Vehicle Manufacturers.* Phase-in for NMOG+NOx and CO emission standards begins with the 2016 model year. For MDVs 8,501-10,000 lbs. GVWR, for each model year, the percentage of MDVs certified to an SFTP emission category set forth in this section 1961.2 shall be equal to or greater than the total percentage certified to the FTP ULEV250, ULEV200, SULEV170, and SULEV150 emission categories; of these vehicles, the percentage of MDVs certified to an SFTP SULEV emission category shall be equal to or greater than the total percentage certified to both the FTP SULEV170 and SULEV150 emission categories. For MDVs 10,001-14,000 lbs. GVWR, for each model year, the percentage of MDVs certified to an SFTP emission category set forth in this section 1961.2 shall be equal to or greater than the total percentage certified to the FTP ULEV400, ULEV270, SULEV230, and SULEV200 emission categories; of these vehicles, the percentage of MDVs certified to an SFTP SULEV emission category shall be equal to or greater than the total percentage certified to both the FTP SULEV230 and SULEV200 emission categories.

In addition, 2017 and subsequent model MDVs certifying to LEV III FTP PM emission standards on a 150,000-mile durability basis must also certify to the SFTP emission standards set forth in subsection (a)(7)(D).

(C) *Identifying a Manufacturer's Medium-Duty Vehicle Fleet.* For the 2016 and subsequent model years, each manufacturer's MDV fleet shall be defined as the total number of California-certified MDVs, other than MDPVs,

produced and delivered for sale in California. For 2016 and subsequent model years, a manufacturer that elects to certify engines to the optional medium-duty engine emission standards in subsections 1956.8(c) or (h) shall not count those engines in the manufacturer's total production of California-certified medium-duty vehicles for purposes of this subparagraph.

(c) *Calculation of NMOG + NOx Credits/Debits*

(1) *Calculation of NMOG+NOx Credits and Debits for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles.*

(A) In 2015 and subsequent model years, a manufacturer shall calculate its credits or debits using the following equation.

[(Fleet Average NMOG+NOx Requirement) - (Manufacturer's Fleet Average NMOG+NOx Value)] x
(Total No. of Vehicles Produced and Delivered for Sale in California, Including ZEVs and HEVs).

(B) In 2015 and subsequent model years, a manufacturer that achieves fleet average NMOG+NOx values lower than the fleet average NMOG+NOx requirement for the corresponding model year shall receive credits in units of g/mi NMOG + NOx . A manufacturer with 2015 and subsequent model year fleet average NMOG+NOx values greater than the fleet average requirement for the corresponding model year shall receive debits in units of g/mi NMOG + NOx equal to the amount of negative credits determined by the aforementioned equation. The total g/mi NMOG+NOx credits or debits earned for PCs and LDTs 0-3750 lbs. LVW, for LDTs 3751-5750 lbs. LVW and for LDTs 3751 lbs. LVW - 8500 lbs. GVWR shall be summed together. The resulting amount shall constitute the g/mi NMOG+NOx credits or debits accrued by the manufacturer for the model year.

(2) *Calculation of Vehicle-Equivalent NMOG + NOx Credits for Medium-Duty Vehicles Other than MDPVs.*

(A) In 2015 and subsequent model years, a manufacturer that produces and delivers for sale in California MDVs, other than MDPVs, in excess of the equivalent requirements for LEV III vehicles certified to the exhaust emission standards set forth in subsection (a)(1), shall receive "Vehicle-Equivalent Credits" (or "VECs") calculated in accordance with the following equation, where the term "produced" means produced and delivered for sale in California:

{[(1.2) x (No. of ULEV340s and ULEV570s Produced excluding HEVs) +
(No. of ULEV340 HEVs x HEV VEC factor for ULEV340s) +
(No. of ULEV570 HEVs x HEV VEC factor for ULEV570s)] –
(Equivalent No. of ULEV340s and ULEV570s Required to be Produced)} +

{[(1.4) x (No. of ULEV250s and ULEV400s Produced excluding HEVs) +
(No. of ULEV250 HEVs x HEV VEC factor for ULEV250s) +
(No. of ULEV400 HEVs x HEV VEC factor for ULEV400s)] -
[(1.4) x (Equivalent No. of ULEV250s and ULEV270s Required to be Produced)]} +

{[(1.5) x (No. of ULEV200s and ULEV270s Produced excluding HEVs) +
(No. of ULEV200 HEVs x HEV VEC factor for ULEV200s) +
(No. of ULEV270 HEVs x HEV VEC factor for ULEV270s)] -
[(1.5) x (Equivalent No. of ULEV200s and ULEV270s Required to be Produced)]} +

{[(1.6) x (No. of SULEV170s and SULEV230s Produced excluding HEVs) +
(No. of SULEV170 HEVs x HEV VEC factor for SULEV170s) +
(No. of SULEV230 HEVs x HEV VEC factor for SULEV230s)] -
[(1.6) x [(Equivalent No. of SULEV170s and SULEV230s Required to be Produced)]} +

{[(1.7) x (No. of SULEV150s and SULEV200s Produced excluding HEVs) +
(No. of SULEV150 HEVs x HEV VEC factor for SULEV150s) +
(No. of SULEV200 HEVs x HEV VEC factor for SULEV200s)] -
[(1.7) x [(Equivalent No. of SULEV150s and SULEV200s Required to be Produced)]} +

[(2.0) x (No. of ZEVs Certified and Produced as MDVs)].

(B) *MDV HEV VEC factor.* The MDV HEV VEC factor is calculated as follows:

For ULEV340s:

$$1+\left[\frac{(ULEV340\ standard-ULEV250\ standard)\times Zero-emission\ VMT\ Allowance}{ULEV340\ standard}\right];$$

For ULEV250s:

$$1+\left[\frac{(ULEV250\ standard-ULEV200\ standard)\times Zero-emission\ VMT\ Allowance}{ULEV250\ standard}\right];$$

For ULEV200s:

$$1+\left[\frac{(ULEV200\ standard-SULEV170\ standard)\times Zero-emission\ VMT\ Allowance}{ULEV3200\ standard}\right];$$

For SULEV170s:

$$1+\left[\frac{(SULEV170\ standard-SULEV150\ standard)\times Zero-emission\ VMT\ Allowance}{SULEV170\ standard}\right];$$

For SULEV150s: $$1+\left[\frac{(SULEV150\ standard-ZEV\ standard)\times Zero-emission\ VMT\ Allowance}{SULEV150\ standard}\right];$$

For ULEV570s:

$$1+\left[\frac{(ULEV570\ standard-ULEV400\ standard)\times Zero-emission\ VMT\ Allowance}{ULEV570\ standard}\right];$$

For ULEV400s:

$$1+\left[\frac{(ULEV400\ standard-ULEV270\ standard)\times Zero-emission\ VMT\ Allowance}{ULEV400\ standard}\right];$$

For ULEV270s:

$$1+\left[\frac{(ULEV270\ standard-SULEV230\ standard)\times Zero-emission\ VMT\ Allowance}{ULEV270\ standard}\right];$$

For SULEV230s:

$$1+\left[\frac{(SULEV230\ standard-SULEV200\ standard)\times Zero-emission\ VMT\ Allowance}{SULEV230\ standard}\right]$$

For SULEV200s: $$1+\left[\frac{(SULEV200\ standard-ZEV\ standard)\times Zero-emission\ VMT\ Allowance}{SULEV200\ standard}\right]$$

where "Zero-emission VMT Allowance" for an HEV is determined in accordance with section C of the "California Exhaust Emission Standards and Test Procedures for 2009 through 2017 Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," incorporated by reference in section 1962.1, or the "California Exhaust Emission Standards and Test Procedures for 2018 and Subsequent Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," incorporated by reference in section 1962.2, as applicable.

(C) A manufacturer that fails to produce and deliver for sale in California the equivalent quantity of MDVs certified to LEV III exhaust emission standards, shall receive "Vehicle-Equivalent Debits" (or "VEDs") equal to the amount of negative VECs determined by the equation in subsection (c)(2)(A).

(D) Only ZEVs certified as MDVs and not used to meet the ZEV requirement shall be included in the calculation of VECs.

(3) *Procedure for Offsetting Debits.*

(A) A manufacturer shall equalize emission debits by earning g/mi NMOG+NOx emission credits or VECs in an amount equal to the g/mi NMOG+NOx debits or VEDs, or by submitting a commensurate amount of g/mi NMOG+NOx credits or VECs to the Executive Officer that were earned previously or acquired from another manufacturer. A manufacturer shall equalize NMOG+NOx debits for PCs, LDTs, and MDPVs and VEC debits for MDVs within three model years. If emission debits are not equalized within the specified time period, the manufacturer shall be subject to the Health and Safety Code §43211 civil penalty applicable to a manufacturer which sells a new motor vehicle that does not meet the applicable emission standards adopted by the state board. The cause of action shall be deemed to accrue when the emission debits are not equalized by the end of the specified time period. A manufacturer demonstrating compliance under Option 2 in subsection (b)(1)(A)1.a, must calculate the emission debits that are subject to a civil penalty under Health and Safety Code section 43211 separately for California, the District of Columbia, and for each individual state that is included in the fleet average greenhouse gas requirements in subsection (b)(1)(A)1.a. The manufacturer must calculate these emission debits separately for California, the District of Columbia, and each individual state using the formula in subsections (c)(1) and (c)(2), except that the "Total No. of Vehicles Produced and Delivered for Sale in California, Including ZEVs and HEVs" shall be calculated separately for the District of Columbia and each individual state.

For the purposes of Health and Safety Code §43211, the number of passenger cars, light-duty trucks, and medium-duty passenger vehicles not meeting the state board's emission standards shall be determined by dividing the total amount of g/mi NMOG+NOx emission debits for the model year by the g/mi NMOG+NOx fleet average requirement for PCs and LDTs 0-3750 lbs. LVW and for LDTs 3751 lbs. LVW - 8500 lbs. GVW and MDPVs applicable for the model year in which the debits were first incurred; and the number of medium-duty vehicles not meeting the state board's emission standards shall be equal to the amount of VEDs incurred.

(B) The emission credits earned in any given model year shall retain full value through five subsequent model years. Credits will have no value if not used by the beginning of the sixth model year after being earned.

(4) *Changing NMOG Credits and Debits to NMOG+NOx Credits and Debits.* The value of any emission credits that have not been used prior to the start of the 2015 model year and any emission debits that have not been equalized prior to the start of the 2015 model year earned shall be converted to NMOG+NOx credits at the start of the 2015 model year by multiplying their values by a factor of 3.0. These credits and debits are subject to the provisions in subsection 1961(c)(3).

(d) *Test Procedures.* The certification requirements and test procedures for determining compliance with the emission standards in this section are set forth in the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," as adopted [INSERT DATE OF ADOPTION], the "California Non-Methane Organic Gas Test Procedures," as amended [INSERT DATE OF AMENDMENT], which are incorporated herein by reference. In the case of hybrid electric vehicles and on-board fuel-fired heaters, the certification requirements and test procedures for determining compliance with the emission standards in this section are set forth in the "California Exhaust Emission Standards and Test Procedures for 2009 through 2017 Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," incorporated by reference in section 1962.1, and the "California Exhaust Emission Standards and Test Procedures for 2018 and Subsequent Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," incorporated by reference in section 1962.2.

(e) *Abbreviations.* The following abbreviations are used in this section 1961.2:

"ALVW" means adjusted loaded vehicle weight.
"ASTM" means American Society of Testing and Materials.
"CO" means carbon monoxide.
"FTP" means Federal Test Procedure.
"g/mi" means grams per mile.
"GVW" means gross vehicle weight.
"GVWR" means gross vehicle weight rating.
"HEV" means hybrid-electric vehicle.
"LDT" means light-duty truck.
"LDT1" means a light-duty truck with a loaded vehicle weight of 0-3750 pounds.
"LDT2" means a light-duty truck with a loaded vehicle weight of 3751 pounds to a gross vehicle weight rating of 8500 pounds.
"LEV" means low-emission vehicle.
"LPG" means liquefied petroleum gas.
"LVW" means loaded vehicle weight.
"MDPV" means medium-duty passenger vehicle.
"MDV" means medium-duty vehicle.
"NMHC" means non-methane hydrocarbons.
"mg/mi" means milligrams per mile.
"NMHC" means non-methane hydrocarbons.
"Non-Methane Organic Gases" or "NMOG" means the total mass of oxygenated and non-oxygenated hydrocarbon emissions.

"NOx" means oxides of nitrogen.
"PC" means passenger car.
"SULEV" means super-ultra-low-emission vehicle.
"ULEV" means ultra-low-emission vehicle.
"VEC" means vehicle-equivalent credits.
"VED" means vehicle-equivalent debits.
"VMT" means vehicle miles traveled.
"ZEV" means zero-emission vehicle.

Note: Authority cited: Sections 39500, 39600, 39601, 43013, 43018, 43101, 43104, 43105, and 43106, Health and Safety Code. Reference: Sections 39002, 39003, 39667, 43000, 43009.5, 43013, 43018, 43100, 43101, 43101.5, 43102, 43104, 43105, 43106, 43204, and 43205, Health and Safety Code.

7. Adopt new title 13, CCR, section 1961.3 to read as follows: (Note: the entire text of section 1961.3 set forth below is new language proposed to be added to the California Code of Regulations.)

§ 1961.3. Greenhouse Gas Exhaust Emission Standards and Test Procedures - 2017 and Subsequent Model Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles.

Introduction. This section 1961.3 sets the greenhouse gas emission levels from new 2017 and subsequent model year passenger cars, light-duty trucks, and medium-duty passenger vehicles. Light-duty trucks from 3751 lbs. LVW – 8500 lbs. GVW that are certified to the Option 1 LEV II NOx Standard in section 1961(a)(1) are exempt from these greenhouse gas emission requirements, however, passenger cars, light-duty trucks 0-3750 lbs. LVW, and medium-duty passenger vehicles are not eligible for this exemption.

Emergency vehicles may be excluded from these greenhouse gas emission requirements. The manufacturer must notify the Executive Officer that they are making such an election, in writing, prior to the start of the applicable model year or must comply with this section 1961.3.

(a) *Greenhouse Gas Emission Requirements.*

(1) *Fleet Average Carbon Dioxide Requirements for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles.* For the purpose of determining compliance with this subsection (a)(1), the applicable fleet average CO_2 mass emission standards for each model year is the sales-weighted average of the calculated CO_2 exhaust mass emission target values for each manufacturer. For each model year, the sales-weighted fleet average CO_2 mass emissions value shall not exceed the sales-weighted average of the calculated CO_2 exhaust mass emission target values for that manufacturer.

(A) *Fleet Average Carbon Dioxide Target Values for Passenger Cars.* The fleet average CO_2 exhaust mass emission target values for passenger cars that are produced and delivered for sale in California each model year shall be determined as follows:

1. For passenger cars with a footprint of less than or equal to 41 square feet, the gram per mile CO_2 target value shall be selected for the appropriate model year from the following table:

Date of Release: December 7, 2011; 45-day Notice Version
Date of Hearing: January 26, 2012

Model Year	*CO_2 Target Value (grams/mile)*
2017	195.0
2018	185.0
2019	175.0
2020	166.0
2021	157.0
2022	150.0
2023	143.0
2025	137.0
2025 and subsequent	131.0

2. For passenger cars with a footprint of greater than 56 square feet, the gram per mile CO_2 target value shall be selected for the appropriate model year from the following table:

Model Year	*CO_2 Target Value (grams/mile)*
2017	263.0
2018	250.0
2019	238.0
2020	226.0
2021	215.0
2022	205.0
2023	196.0
2025	188.0
2025 and subsequent	179.0

3. For passenger cars with a footprint that is greater than 41 square feet and less than or equal to 56 square feet, the gram per mile CO_2 target value shall be calculated using the following equation and rounded to the nearest 0.1 grams/mile:

$$\text{Target } gCO_2/\text{mile} = [a \times f] + b$$

Where: f is the vehicle footprint and
coefficients a and b are selected from the following table for the applicable model year.

Date of Release: December 7, 2011; 45-day Notice Version
Date of Hearing: January 26, 2012

Model year	*a*	*b*
2017	4.53	8.9
2018	4.35	6.5
2019	4.17	4.2
2020	4.01	1.9
2021	3.84	-0.4
2022	3.69	-1.1
2023	3.54	-1.8
2024	3.4	-2.5
2025 and subsequent	3.26	-3.2

(B) *Fleet Average Carbon Dioxide Target Values for Light-Duty Trucks and Medium-Duty Passenger Vehicles.* The fleet average CO_2 exhaust mass emission target values for light-duty trucks and medium-duty passenger vehicles that are produced and delivered for sale in California each model year shall be determined as follows:

1. For light-duty trucks and medium-duty passenger vehicles with a footprint of less than or equal to 41 square feet, the gram per mile CO_2 target value shall be selected from the following table:

Model Year	*CO_2 Target Value (grams/mile)*
2017	238.0
2018	227.0
2019	220.0
2020	212.0
2021	195.0
2022	186.0
2023	176.0
2025	168.0
2025 and subsequent	159.0

2. For light-duty trucks and medium-duty passenger vehicles with a footprint of greater than 41 square feet and less than or equal to the maximum footprint value specified in the table below for each model year, the gram/mile CO_2 target value shall be calculated using the following equation and rounded to the nearest 0.1 grams/mile:

Target gCO_2/mile = [*a* x *f*] + *b*

Where: *f* is the vehicle footprint and
coefficients *a* and *b* are selected from the following table for the applicable model year.

Model year	*Maximum Footprint*	*a*	*b*
2017	50.7	4.87	38.3
2018	60.2	4.76	31.6
2019	66.4	4.68	27.7
2020	68.3	4.57	24.6
2021	73.5	4.28	19.8
2022	74.0	4.09	17.8
2023	74.0	3.91	16.0
2024	74.0	3.74	14.2
2025 and subsequent	74.0	3.58	12.5

3. For light-duty trucks and medium-duty passenger vehicles with a footprint that is greater than the minimum footprint value specified in the table below and less than or equal to the maximum footprint value specified in the table below for each model year, the gram/mile CO_2 target value shall be calculated using the following equation and rounded to the nearest 0.1 grams/mile:

Target gCO_2/mile = [*a* x *f*] + *b*

Where: *f* is the vehicle footprint and
coefficients *a* and *b* are selected from the following table for the applicable model year.

Model year	*Minimum Footprint*	*Maximum Footprint*	*a*	*b*
2017	50.7	66.0	4.04	80.5
2018	60.2	66.0	4.04	75.0

4. For light-duty trucks and medium-duty passenger vehicles with a footprint that is greater than the minimum value specified in the

table below for each model year, the gram/mile CO_2 target value shall be selected for the applicable model year from the following table:

Model year	*Minimum Footprint*	*CO_2 target value (grams/mile)*
2017	66.0	347.0
2018	66.0	342.0
2019	66.4	339.0
2020	68.3	337.0
2021	73.5	335.0
2022	74.0	321.0
2023	74.0	306.0
2024	74.0	291.0
2025 and subsequent	74.0	277.0

(C) *Calculation of Manufacturer-Specific Carbon Dioxide Fleet Average Standards.* For each model year, each manufacturer must comply with fleet average CO_2 standards for passenger cars and for light-duty trucks plus medium-duty passenger vehicles, as applicable, calculated for that model year as follows. For each model year, a manufacturer must calculate separate fleet average CO_2 values for its passenger car fleet and for its combined light-duty truck plus medium-duty passenger vehicle fleet using the CO_2 target values in subsection (a)(A). These calculated CO_2 values are the manufacturer-specific fleet average CO_2 standards for passenger cars and for light-duty trucks plus medium-duty passenger vehicles, as applicable, which apply for that model year.

1. A CO_2 target value shall be calculated in accordance with subparagraph (a)(1)(A) or (a)(1)(B), as applicable, for each unique combination of model type and footprint value.

2. Each CO_2 target value, determined for each unique combination of model type and footprint value, shall be multiplied by the total production of that model type/footprint combination for the applicable model year.

3. The resulting products shall be summed, and that sum shall be divided by the total production of passenger cars or total combined

production of light-duty trucks and medium-duty passenger vehicles, as applicable, in that model year. The result shall be rounded to the nearest whole gram per mile. This result shall be the applicable fleet average CO_2 standard for the manufacturer's passenger car fleet or its combined light-duty truck and medium-duty passenger vehicle fleet, as applicable.

(2) *Nitrous Oxide (N_2O) and Methane (CH_4) Exhaust Emission Standards for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles.* Each manufacturer's fleet of combined passenger automobile, light-duty trucks, and medium-duty passenger vehicles must comply with N_2O and CH_4 standards using either the provisions of subsection (a)(2)(A), subsection (a)(2)(B), or subsection (a)(2)(C). Except with prior approval of the Executive Officer, a manufacturer may not use the provisions of both subsection (a)(2)(A) and subsection (a)(2)(B) in the same model year. For example, a manufacturer may not use the provisions of subsection (a)(2)(A) for their passenger automobile fleet and the provisions of subsection (a)(2)(B) for their light-duty truck and medium-duty passenger vehicle fleet in the same model year. The manufacturer may use the provisions of both subsections (a)(2)(A) and (a)(2)(C) in the same model year. For example, a manufacturer may meet the N_2O standard in subsection (a)(2)(A)1 and an alternative CH_4 standard determined under subsection (a)(2)(C).

(A) *Standards Applicable to Each Test Group.*

1. Exhaust emissions of N_2O shall not exceed 0.010 grams per mile at full useful life, as measured on the FTP (40 CFR, Part 86, Subpart B), as amended by the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures Passenger Cars, Light Duty Trucks, and Medium Duty Vehicles." Manufacturers may optionally determine an alternative N_2O standard under subsection (a)(2)(C).

2. Exhaust emissions of CH_4 shall not exceed 0.030 grams per mile at full useful life, as measured on the FTP (40 CFR, Part 86, Subpart B), as amended by the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles." Manufacturers may optionally determine an alternative CH_4 standard under subsection (a)(2)(C).

(B) *Including N_2O and CH_4 in Fleet Averaging Program.* Manufacturers may elect to not meet the emission standards in subsection (a)(2)(A). Manufacturers making this election shall measure N_2O and CH_4 emissions for each unique combination of model type and footprint value on

both the FTP test cycle and the Highway Fuel Economy test cycle at full useful life, multiply the measured N_2O emissions value by 298 and the measured CH_4 emissions value by 25, and include both of these adjusted N_2O and CH_4 full useful life values in the fleet average calculations for passenger automobiles and light-duty trucks plus medium-duty passenger vehicles, as calculated in accordance with subsection (a)(2)(A)(D).

(C) *Optional Use of Alternative N_2O and/or CH_4 Standards.* Manufacturers may select an alternative standard applicable to a test group, for either N_2O or CH_4, or both. For example, a manufacturer may choose to meet the N_2O standard in subsection (a)(2)(A)1 and an alternative CH_4 standard in lieu of the standard in subsection (a)(2)(A)2. The alternative standard for each pollutant must be less stringent than the applicable exhaust emission standard specified in subsection (a)(2)(A). Alternative N_2O and CH_4 standards apply to emissions as measured on the FTP (40 CFR, Part 86, Subpart B), as amended by the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," for the full useful life, and become the applicable certification and in-use emission standard(s) for the test group. Manufacturers using an alternative standard for N_2O and/or CH_4 must calculate emission debits according to the provisions of subsection (a)(2)(D) for each test group/alternative standard combination. Debits must be included in the calculation of total credits or debits generated in a model year as required under subsection (b)(1)(B). Flexible fuel vehicles (or other vehicles certified for multiple fuels) must meet these alternative standards when tested on all applicable test fuel type.

(D) *CO_2-Equivalent Debits.* CO_2-equivalent debits for test groups using an alternative N_2O and/or CH_4 standard as determined under (a)(2)(C) shall be calculated according to the following equation and rounded to the nearest whole gram per mile:

$$\text{Debits} = \text{GWP} \times (\text{Production}) \times (\text{AltStd} - \text{Std})$$

Where:

Debits = N_2O or CH_4 CO_2-equivalent debits for a test group using an alternative N_2O or CH_4 standard;

GWP = 25 if calculating CH_4 debits and 298 if calculating N_2O debits;

Production = The number of vehicles of that test group produced and delivered for sale in California;

AltStd = The alternative standard (N_2O or CH_4) selected by the manufacturer under (a)(2)(C); and

Std = The exhaust emission standard for N_2O or CH_4 specified in (a)(2)(A).

(3) *Alternative Fleet Average Standards for Manufacturers with Limited U.S. Sales.* Manufacturers meeting the criteria in this subsection (a)(3) may request that the Executive Officer establish alternative fleet average CO_2 standards that would apply instead of the standards in subsection (a)(1).

(A) *Eligibility for Alternative Standards.* Eligibility as determined in this subsection (a)(3) shall be based on the total sales of combined passenger cars, light-duty trucks, and medium-duty passenger vehicles. The terms "sales" and "sold" as used in this subsection (a)(3) shall mean vehicles produced and delivered for sale (or sold) in the states and territories of the United States. For the purpose of determining eligibility the sales of related companies shall be aggregated according to the provisions of section 1900. To be eligible for alternative standards established under this subsection (a)(3), the manufacturer's average sales for the three most recent consecutive model years must remain below 5,000. If a manufacturer's average sales for the three most recent consecutive model years exceeds 4,999, the manufacturer will no longer be eligible for exemption and must meet applicable emission standards as follows.

1. If a manufacturer's average sales for three consecutive model years exceeds 4,999, and if the increase in sales is the result of corporate acquisitions, mergers, or purchase by another manufacturer, the manufacturer shall comply with the emission standards described in subsections (a)(1) and (a)(2), as applicable, beginning with the first model year after the last year of the three consecutive model years.

2. If a manufacturer's average sales for three consecutive model years exceeds 4,999 and is less than 50,000, and if the increase in sales is solely the result of the manufacturer's expansion in vehicle production (not the result of corporate acquisitions, mergers, or purchase by another manufacturer), the manufacturer shall comply with the emission standards described in subsections (a)(1) and (a)(2), as applicable, beginning with the second model year after the last year of the three consecutive model years.

(B) *Requirements for New Entrants into the U.S. Market.* New entrants are those manufacturers without a prior record of automobile sales in the United States and without prior certification to (or exemption from, under 40 CFR §86.1801-12(k)) greenhouse gas emission standards in 40 CFR §86.1818-12 or greenhouse gas standards in section 1961.1. In addition to the eligibility requirements stated in subsection (a)(3)(A), new entrants must meet the following requirements:

1. In addition to the information required under subsection (a)(3)(D), new entrants must provide documentation that shows a clear intent by the company to actually enter the U.S. market in the years for which alternative standards are requested. Demonstrating such intent could include providing documentation that shows the establishment of a U.S. dealer network, documentation of work underway to meet other U.S. requirements (e.g., safety standards), or other information that reasonably establishes intent to the satisfaction of the Executive Officer.

2. Sales of vehicles in the U.S. by new entrants must remain below 5,000 vehicles for the first two model years in the U.S. market and the average sales for any three consecutive years within the first five years of entering the U.S. market must remain below 5,000 vehicles. Vehicles sold in violation of these limits will be considered not covered by the certificate of conformity and the manufacturer will be subject to penalties on an individual-vehicle basis for sale of vehicles not covered by a certificate. In addition, violation of these limits will result in loss of eligibility for alternative standards until such point as the manufacturer demonstrates two consecutive model years of sales below 5,000 automobiles.

3. A manufacturer with sales in the most recent model year of less than 5,000 automobiles, but where prior model year sales were not less than 5,000 automobiles, is eligible to request alternative standards under subsection (a)(3). However, such a manufacturer will be considered a new entrant and subject to the provisions regarding new entrants in this subsection (a)(3), except that the requirement to demonstrate an intent to enter the U.S. market in subsection (a)(3)(B)(1) shall not apply.

(C) *How to Request Alternative Fleet Average Standards.* Eligible manufacturers may petition for alternative standards for up to five consecutive model years if sufficient information is available on which to base such standards.

1. To request alternative standards starting with the 2017 model year, eligible manufacturers must submit a completed application no later than July 30, 2013.

2. To request alternative standards starting with a model after 2017, eligible manufacturers must submit a completed request no later than 36 months prior to the start of the first model year to which the alternative standards would apply.

3. The request must contain all the information required in subsection (a)(3)(D), and must be signed by a chief officer of the

company. If the Executive Officer determines that the content of the request is incomplete or insufficient, the manufacturer will be notified and given an additional 30 days to amend the request.

(D) *Data and Information Submittal Requirements.* Eligible manufacturers requesting alternative standards under subsection (a)(3) must submit the following information to the California Air Resources Board. The Executive Officer may request additional information as s/he deems appropriate. The completed request must be sent to the California Air Resources Board at the following address: Chief, Mobile Source Operations Division, California Air Resources Board, 9480 Telstar Avenue, Suite 4, El Monte, California 91731.

1. *Vehicle Model and Fleet Information.*

a. The model years to which the requested alternative standards would apply, limited to five consecutive model years.

b. Vehicle models and projections of production volumes for each model year.

c. Detailed description of each model, including the vehicle type, vehicle mass, power, footprint, and expected pricing.

d. The expected production cycle for each model, including new model introductions and redesign or refresh cycles.

2. *Technology Evaluation Information.*

a. The CO_2 reduction technologies employed by the manufacturer on each vehicle model, including information regarding the cost and CO_2 -reducing effectiveness. Include technologies that improve air conditioning efficiency and reduce air conditioning system leakage, and any "off-cycle" technologies that potentially provide benefits outside the operation represented by the FTP and the HWFET.

b. An evaluation of comparable models from other manufacturers, including CO_2 results and air conditioning credits generated by the models. Comparable vehicles should be similar, but not necessarily identical, in the following respects: vehicle type, horsepower, mass, power-to-weight ratio, footprint, retail price, and any other relevant factors. For manufacturers requesting alternative standards starting with the 2017 model year, the analysis of comparable vehicles should include vehicles from the 2012 and 2013

model years, otherwise the analysis should at a minimum include vehicles from the most recent two model years.

c. A discussion of the CO_2-reducing technologies employed on vehicles offered outside of the U.S. market but not available in the U.S., including a discussion as to why those vehicles and/or technologies are not being used to achieve CO_2 reductions for vehicles in the U.S. market.

d. An evaluation, at a minimum, of the technologies projected by the California Air Resources Board in the "Staff Report: Initial Statement of Reasons for Proposed Rulemaking, Public Hearing to Consider the "LEV III" Amendments to The California Greenhouse Gas and Criteria Pollutant Exhaust and Evaporative Emission Standards and Test Procedures and to the On-Board Diagnostic System Requirements for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles, and to the Evaporative Emission Requirements for Heavy-Duty Vehicles" and the appendices to this report, released on December 7, 2011, as those technologies likely to be used to meet greenhouse gas emission standards and the extent to which those technologies are employed or projected to be employed by the manufacturer. For any technology that is not projected to be fully employed, the manufacturer must explain why this is the case.

3. *Information Supporting Eligibility.*

a. U.S. sales for the three previous model years and projected sales for the model years for which the manufacturer is seeking alternative standards.

b. Information regarding ownership relationships with other manufacturers, including details regarding the application of the provisions of 40 CFR §86.1838–01(b)(3) and section 1900 regarding the aggregation of sales of related companies.

(E) *Alternative Standards.* Upon receiving a complete application, the Executive Officer will review the application and determine whether an alternative standard is warranted. If the Executive Officer judges that an alternative standard is warranted, the following standards shall apply. For the purposes of this subsection (a)(3)(E), an "ultra-small volume manufacturer" shall mean a manufacturer that meets the requirements of subsection (a)(3).

1. At the beginning of the model year that is three model years prior to the model year for which an alternative standard is requested, each ultra-small volume manufacturer shall identify all vehicle models from

the model year that is four model years prior to the model year for which an alternative standard is requested, certified by a large volume manufacturer that are comparable to that small volume manufacturer's vehicle models for the model year for which an alternative standard is requested, based on model type and footprint value. The ultra-small volume manufacturer shall demonstrate to the Executive Officer the appropriateness of each comparable vehicle model selected. Upon approval of the Executive Officer, s/he shall provide to the ultra-small volume manufacturer the target grams CO_2 per mile for each vehicle model type and footprint value that is approved. The ultra-small volume manufacturer shall calculate its fleet average CO_2 standard in accordance with subsection (a)(1)(C) based on these target grams CO_2 per mile values provided by the Executive Officer.

2. In the 2017 and subsequent model years, an ultra-small volume manufacturer shall either:

a. not exceed its fleet average CO_2 standard calculated in accordance with subsection (a)(1)(C) based on the target grams CO_2 per mile values provided by the Executive Officer; or

b. upon approval of the Executive Officer, if an ultra-small volume manufacturer demonstrates a vehicle model uses an engine, transmission, and emission control system and has a footprint value that are identical to a configuration certified for sale in California by a large volume manufacturer, those ultra-small volume manufacturer vehicle models are exempt from meeting the requirements in paragraph 2.a of this subsection.

(F) *Restrictions on Credit Trading.* Manufacturers subject to alternative standards approved by the Executive Officer under this subsection (a)(3) may not trade credits to another manufacturer. Transfers of credits between a manufacturer's car and truck fleets are allowed.

(4) *Greenhouse Gas Emissions Values for Electric Vehicles, "Plug-In" Hybrid Electric Vehicles, and Fuel Cell Vehicles.*

(A) *Electric Vehicle Calculations.*

1. For each unique combination of model type and footprint value, a manufacturer shall calculate the City CO_2 Value using the following formula:

$$\textit{City } CO_2 \textit{ Value} = (270\ gCO_2e/kWh) * E_{EV} - 0.25 * GHG_{target}$$

Date of Release: December 7, 2011; 45-day Notice Version
Date of Hearing: January 26, 2012

Where E_{EV} is measured directly from each cycle for each test vehicle of battery electric vehicle technology in units of kilowatt-hours per mile (per SAE J1634, incorporated herein by reference).

2. For each unique combination of model type and footprint value, a manufacturer shall calculate the Highway CO_2 Value using the following formula:

Highway CO_2 Value = *(270 gCO_2e/kWh)* * E_{EV} – 0.25 * GHG_{target}

Where E_{EV} is measured directly from each cycle for each test vehicle of battery electric vehicle technology in units of kilowatt-hours per mile (per SAE J1634, incorporated herein by reference).

(B) *"Plug-In" Hybrid Electric Vehicle Calculations.* For each unique combination of model type and footprint value, a manufacturer shall calculate the City CO_2 Value and the Highway CO_2 Value using the following formulas:

City CO_2 Value = GHG_{urban}

and

Highway CO_2 Value = $GHG_{highway}$

Where GHG_{urban} and $GHG_{highway}$ are measured in accordance with section G.12 of the "California Exhaust Emission Standards and Test Procedures for 2009 through 2017 Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes" or the "California Exhaust Emission Standards and Test Procedures for 2018 and Subsequent Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," as applicable.

(C) *Fuel Cell Vehicle Calculations.* For each unique combination of model type and footprint value, a manufacturer shall calculate the City CO_2 Value and the Highway CO_2 Value using the following formulas:

City CO_2 = GHG_{FCV} = (9132 $gCO_2e/kg\ H_2$) * H_{FCV} – $G_{upstream}$

and

Highway CO_2 = GHG_{FCV} = (9132 $gCO_2e/kg\ H_2$) * H_{FCV} – $G_{upstream}$

Where H_{FCV} means hydrogen consumption in kilograms of hydrogen per mile, measured for the applicable test cycle, in accordance with SAE J2572 (published October 2008), incorporated herein by reference.

(5) *Calculation of Fleet Average Carbon Dioxide Value.*

(A) For each unique combination of model type and footprint value, a manufacturer shall calculate a combined city/highway CO_2 exhaust emission value as follows:

0.55 x City CO_2 Value + 0.45 x Highway CO_2 Value

"City" CO_2 exhaust emissions shall be measured using the FTP test cycle (40 CFR, Part 86, Subpart B), as amended by the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures Passenger Cars, Light Duty Trucks, and Medium Duty Vehicles." "Highway" CO_2 exhaust emission shall be measured using the using the Highway Fuel Economy Test (HWFET; 40 CFR 600 Subpart B).

(B) Each combined city/highway CO_2 exhaust emission, determined for each unique combination of model type and footprint value, shall be multiplied by the total production of that model type/footprint combination for the applicable model year.

(C) The resulting products shall be summed, and that sum shall be divided by the total production of passenger cars or total combined production of light-duty trucks and medium-duty passenger vehicles, as applicable, in that model year. The result shall be rounded to the nearest whole gram per mile. This result shall be the manufacturer's actual sales-weighted fleet average CO_2 value for the manufacturer's passenger car fleet or its combined light-duty truck and medium-duty passenger vehicle fleet, as applicable.

(D) For each model year, a manufacturer must demonstrate compliance with the fleet average requirements in section (a)(1) based on one of two options applicable throughout the model year, either:

Option 1: the total number of passenger cars, light-duty trucks, and medium-duty passenger vehicles that are certified to the California exhaust emission standards in section 1961.3, and are produced and delivered for sale in California; or

Option 2: the total number of passenger cars, light-duty trucks, and medium-duty passenger vehicles that are certified to the California exhaust emission standards in this section 1961.3, and are produced and delivered for sale in California, the District of Columbia, and all states that have adopted California's greenhouse gas emission standards for that model year pursuant to Section 177 of the federal Clean Air Act (42 U.S.C. § 7507).

1. A manufacturer that selects compliance Option 2 must notify the Executive Officer of that selection, in writing, prior to the start of the applicable model year or must comply with Option 1.

2. When a manufacturer is demonstrating compliance using Option 2 for a given model year, the term "in California" as used in section 1961.3 means California, the District of Columbia, and all states that have adopted California's greenhouse gas emission standards for that model year pursuant to Section 177 of the federal Clean Air Act (42 U.S.C. § 7507).

3. A manufacturer that selects compliance Option 2 must provide to the Executive Officer separate values for the number of vehicles produced and delivered for sale in the District of Columbia and for each individual state within the average.

(6) *Credits for Reduction of Air Conditioning Direct Emissions.* Manufacturers may generate A/C Direct Emissions Credits by implementing specific air conditioning system technologies designed to reduce air conditioning direct emissions over the useful life of their vehicles. A manufacturer may only use an A/C Direct Emissions Credit for vehicles within a model type upon approval of the A/C Direct Emissions Credit for that model type by the Executive Officer. The conditions and requirements for obtaining approval of an A/C Direct Emissions Credit are described in (A) through (F), below.

(A) Applications for approval of an A/C Direct Emissions Credit must be organized by model type. The applications must also include:

- vehicle make and
- number of vehicles within the model type that will be equipped with the air conditioning system to which the leakage credit shall apply.

Separate applications must be submitted for any two configurations of an A/C system with differences other than dimensional variation.

(B) To obtain approval of the A/C Direct Emissions Credit, the manufacturer must demonstrate through an engineering evaluation that the A/C system under consideration reduces A/C direct emissions. The demonstration must include all of the following elements:

- the amount of A/C Direct Emissions Credit requested, in grams of CO_2-equivalent per mile (gCO_2e/mi);
- the calculations identified in section (a)(6)(C) justifying that credit amount;
- schematic of the A/C system;

- specifications of the system components with sufficient detail to allow reproduction of the calculation; and
- a justification that the number of fittings and joints has been minimized and components have been optimized to minimize leakage.

Calculated values must be carried to at least three significant figures throughout the calculations, and the final credit value must be rounded to one tenth of a gram of CO_2-equivalent per mile (gCO_2e/mi).

(C) The calculation of A/C Direct Emissions Credit depends on the refrigerant or type of system, and is specified in paragraphs 1, 2, and 3 of this subsection.

1. HFC-134a vapor compression systems

For A/C systems that use HFC-134a refrigerant, the A/C Direct Emissions Credit is calculated using the following formula:

$$A/C\ Direct\ Credit = Direct\ Credit\ Baseline \times (1 - \frac{LR}{Avg\ LR})$$

Where:

Direct Credit Baseline = 12.6 gCO_2e/mi for passenger cars;
Direct Credit Baseline = 15.6 gCO2e/mi for light-duty trucks and medium-duty passenger vehicles;
Avg LR = 16.6 grams/year for passenger cars;
Avg LR = 20.7 grams/year for light-duty trucks and medium-duty passenger vehicles;

LR = the larger of *SAE LR* or *Min LR*;

Where:

SAE LR = initial leak rate evaluated using SAE International's Surface Vehicle Standard SAE J2727 (Revised August 2008), incorporated by reference, herein;
Min LR = 8.3 grams/year for passenger car A/C systems with belt-driven compressors;
Min LR = 10.4 grams/year for light-duty truck and medium-duty passenger vehicle A/C systems with belt-driven compressors;
Min LR = 4.1 grams/year for passenger car A/C systems with electric compressors;
Min LR = 5.2 grams/year for light-duty truck and medium-duty passenger vehicle A/C systems with electric compressors.

Note: Initial leak rate is the rate of refrigerant leakage from a newly manufactured A/C system in grams of refrigerant per year. The Executive

Officer may allow a manufacturer to use an updated version of the August 2008 version of SAE J2727 or an alternate method if s/he determines that the updated SAE J2727 or the alternate method provides more accurate estimates of the initial leak rate of A/C systems than the August 2008 version of SAE J2727 does.

2. Low-GWP vapor compression systems

For A/C systems that use a refrigerant having a GWP of 150 or less, the A/C Direct Emissions Credit shall be calculated using the following formula:

$$A/C\ Direct\ Credit = Low\ GWP\ Credit - High\ Leak\ Penalty$$

Where:

$$Low\ GWP\ Credit = Max\ Low\ GWP\ Credit \times (1 - \frac{GWP}{1{,}430}),$$

and

$$High\ Leak\ Penalty = \begin{cases} Max\ High\ Leak\ Penalty, & \text{if } SAE\ LR > Avg\ LR; \\ Max\ High\ Leak\ Penalty \times \frac{SAE\ LR - Min\ LR}{Avg\ LR - Min\ LR}, & \text{if } Min\ LR < SAE\ LR \leq Avg\ LR; \\ 0, & \text{if } SAE\ LR \leq Min\ LR. \end{cases}$$

Where:

Max Low GWP Credit = 13.8 gCO_2e/mi for passenger cars;

Max Low GWP Credit = 17.2 gCO_2e/mi for light-duty trucks and medium-duty passenger vehicles;

GWP = the global warming potential of the refrigerant over a 100-year horizon, as specified in section (a)(6)(F);

Max High Leak Penalty = 1.8 gCO_2e/mi for passenger cars;

Max High Leak Penalty = 2.1 gCO_2e/mi for light-duty trucks and medium-duty passenger vehicles;

Avg LR = 13.1 g/yr for passenger cars;

Avg LR = 16.6 g/yr for light-duty trucks and medium-duty passenger vehicles;

and where:

SAE LR = initial leak rate evaluated using SAE International's Surface Vehicle Standard SAE J2727 (Revised August 2008);

Min LR = 8.3 g/yr for passenger cars;

Min LR = 10.4 g/yr for light-duty trucks and medium-duty passenger vehicles.

Note: Initial leak rate is the rate of refrigerant leakage from a newly manufactured A/C system in grams of refrigerant per year. The Executive Officer may allow a manufacturer to use an updated version of SAE J2727 or an alternate applicable test method if s/he finds the update or the alternate method provides more accurate estimates of the initial leak rate of A/C systems than the August 2008 version of SAE J2727 does.

3. Other A/C systems

For an A/C system that uses a technology other than vapor compression cycles, an A/C Direct Emissions Credit may be approved by the Executive Officer. The amount of credit requested must be based on demonstration of the reduction of A/C direct emissions of the technology using an engineering evaluation that includes verifiable laboratory test data, and cannot exceed 13.8 gCO_2e/mi for passenger cars and 17.2 gCO_2e/mi for light-duty trucks and medium-duty passenger vehicles.

(D) The total leakage reduction credits generated by the air conditioning system shall be calculated separately for passenger cars, and for light-duty trucks and medium-duty passenger vehicles, according to the following formula:

$$Total\ Credits\ (g/mi) = A/C\ Direct\ Credit \times Production$$

Where:

A/C Direct Credit is calculated as specified in subsection (a)(6)(C).

Production = The total number of passenger cars or light-duty trucks plus medium-duty passenger vehicles, whichever is applicable, produced and delivered for sale in California, with the air conditioning system to which the *A/D Direct Credit* value from subsection (a)(6)(C) applies.

(E) The results of subsection (a)(6)(D), rounded to the nearest whole gram per mile, shall be included in the manufacturer's credit/debit totals calculated in subsection (b)(1)(B).

(F) The following values for refrigerant global warming potential (GWP), or alternative values as determined by the Executive Officer, shall be used in the calculations of this subsection (a)(6). The Executive Officer shall determine values for refrigerants not included in this subsection (a)(6)(F) upon request by a manufacturer, based on findings by the Intergovernmental Panel on Climate Change (IPCC) or from other applicable research studies.

Refrigerant	*GWP*
HFC–134a	1,430
HFC–152a	124
HFO–1234yf	4
CO_2	1

(7) *Credits for Improving Air Conditioning System Efficiency.* Manufacturers may generate CO_2 credits by implementing specific air conditioning system technologies designed to reduce air conditioning-related CO_2 emissions over the useful life of their passenger cars, light-duty trucks, and/or medium-duty passenger vehicles. Credits shall be calculated according to this subsection (a)(7) for each air conditioning system that the manufacturer is using to generate CO_2 credits. The eligibility requirements specified in subsection (a)(7)(E) must be met before an air conditioning system is allowed to generate credits.

(A) Air conditioning efficiency credits are available for the following technologies in the gram per mile amounts indicated for each vehicle category in the following table:

Date of Release: December 7, 2011; 45-day Notice Version
Date of Hearing: January 26, 2012

Air Conditioning Technology	*Passenger Cars (g/mi)*	*Light-Duty Trucks and Medium-Duty Passenger Vehicles (g/mi)*
Reduced reheat, with externally-controlled, variable-displacement compressor (*e.g.* a compressor that controls displacement based on temperature setpoint and/or cooling demand of the air conditioning system control settings inside the passenger compartment).	1.5	2.2
Reduced reheat, with externally-controlled, fixed-displacement or pneumatic variable displacement compressor (*e.g.* a compressor that controls displacement based on conditions within, or internal to, the air conditioning system, such as head pressure, suction pressure, or evaporator outlet temperature).	1.0	1.4
Default to recirculated air with closed-loop control of the air supply (sensor feedback to control interior air quality) whenever the ambient temperature is 75 °F or higher: Air conditioning systems that operated with closed-loop control of the air supply at different temperatures may receive credits by submitting an engineering analysis to the Administrator for approval.	1.5	2.2
Default to recirculated air with open-loop control air supply (no sensor feedback) whenever the ambient temperature is 75 °F or higher. Air conditioning systems that operate with open-loop control of the air supply at different temperatures may receive credits by submitting an engineering analysis to the Administrator for approval.	1.0	1.4
Blower motor controls which limit wasted electrical energy (*e.g.* pulse width modulated power controller).	0.8	1.1
Internal heat exchanger (*e.g.* a device that transfers heat from the high-pressure, liquid-phase refrigerant entering the evaporator to the low-pressure, gas-phase refrigerant exiting the evaporator).	1.0	1.4
Improved condensers and/or evaporators with system analysis on the component(s) indicating a coefficient of performance improvement for the system of greater than 10% when compared to previous industry standard designs).	1.0	1.4
Oil separator. The manufacturer must submit an engineering analysis demonstrating the increased improvement of the system relative to the baseline design, where the baseline component for comparison is the version which a manufacturer most recently had in production on the same vehicle design or in a similar or related vehicle model. The characteristics of the baseline component shall be compared to the new component to demonstrate the improvement.	0.5	0.7

(B) Air conditioning efficiency credits are determined on an air conditioning system basis. For each air conditioning system that is eligible for a credit based on the use of one or more of the items listed in subsection (a)(7)(A), the total credit value is the sum of the gram per mile values listed in subsection (a)(7)(A) for each item that applies to the air conditioning system.

However, the total credit value for an air conditioning system may not be greater than 5.0 grams per mile for any passenger car or 7.2 grams per mile for any light-duty truck or medium-duty passenger vehicle.

(C) The total efficiency credits generated by an air conditioning system shall be calculated separately for passenger cars and for light-duty trucks plus medium-duty passenger vehicles according to the following formula:

$$Total\ Credits\ (g/mi) = Credit \times Production$$

Where:

Credit = the CO_2 efficiency credit value in grams per mile determined in subsection (a)(7)(B) or (a)(7)(E), whichever is applicable.

Production = The total number of passenger cars or light-duty trucks plus medium-duty passenger vehicles, whichever is applicable, produced and delivered for sale in California, with the air conditioning system to which to the efficiency credit value from subsection (a)(7)(B) applies.

(D) The results of subsection (a)(7)(C), rounded to the nearest whole gram per mile, shall be included in the manufacturer's credit/debit totals calculated in subsection (b)(1)(B).

(E) For the purposes of this subsection (a)(7)(E), the AC17 Test Procedure shall mean the AC17 Air Conditioning Efficiency Test Procedure set forth in the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles."

1. For each air conditioning system selected by the manufacturer to generate air conditioning efficiency credits, the manufacturer shall perform the AC17 Test Procedure.

2. Using good engineering judgment, the manufacturer must select the vehicle configuration to be tested that is expected to result in the greatest increased CO_2 emissions as a result of the operation of the air conditioning system for which efficiency credits are being sought. If the air conditioning system is being installed in passenger cars, light-duty trucks, and medium-duty passenger vehicles, a separate determination of the quantity of credits for passenger cars and for light-duty trucks and medium-duty passenger vehicles must be made, but only one test vehicle is required to represent the air conditioning system, provided it represents the worst-case impact of the system on CO_2 emissions.

3. For each air conditioning system selected by the manufacturer to generate air conditioning efficiency credits, the manufacturer shall perform the AC17 Test Procedure according to the following requirements. Each air conditioning system shall be tested as follows:

a. Perform the AC17 test on a vehicle that incorporates the air conditioning system with the credit-generating technologies.

b. Perform the AC17 test on a vehicle which does not incorporate the credit-generating technologies. The tested vehicle must be similar to the vehicle tested under subsection (a)(7)(E)(3)a.

c. Subtract the CO_2 emissions determined from testing under subsection (a)(7)(E)(3)a from the CO_2 emissions determined from testing under subsection (a)(7)(E)(3)b and round to the nearest 0.1 grams/mile. If the result is less than or equal to zero, the air conditioning system is not eligible to generate credits. If the result is greater than or equal to the total of the gram per mile credits determined under subsection (a)(7)(B), then the air conditioning system is eligible to generate the maximum allowable value determined under subsection (a)(7)(B). If the result is greater than zero but less than the total of the gram per mile credits determined under subsection (a)(7)(B), then the air conditioning system is eligible to generate credits in the amount determined by subtracting the CO_2 emissions determined from testing under subsection (a)(7)(E)(3)a from the CO_2 emissions determined from testing under subsection (a)(7)(E)(3)b and rounding to the nearest 0.1 grams/mile.

4. For the first model year for which an air conditioning system is expected to generate credits, the manufacturer must select for testing the highest-selling subconfiguration within each vehicle platform that uses the air conditioning system. Credits may continue to be generated by the air conditioning system installed in a vehicle platform provided that:

a. The air conditioning system components and/or control strategies do not change in any way that could be expected to cause a change in its efficiency;

b. The vehicle platform does not change in design such that the changes could be expected to cause a change in the efficiency of the air conditioning system; and

c. The manufacturer continues to test at least one sub-configuration within each platform using the air conditioning system, in

each model year, until all sub-configurations within each platform have been tested.

5. Each air conditioning system must be tested and must meet the testing criteria in order to be allowed to generate credits. Using good engineering judgment, in the first model year for which an air conditioning system is expected to generate credits, the manufacturer must select for testing the highest-selling subconfiguration within each vehicle platform using the air conditioning system. Credits may continue to be generated by an air conditioning system in subsequent model years if the manufacturer continues to test at least one sub-configuration within each platform on annually, as long as the air conditioning system and vehicle platform do not change substantially.

(8) *Off-Cycle Credits.* Manufacturers may generate credits for CO_2-reducing technologies where the CO_2 reduction benefit of the technology is not adequately captured on the FTP and/or the HWFET. These technologies must have a measurable, demonstrable, and verifiable real-world CO_2 reduction that occurs outside the conditions of the FTP and the HWFET. These optional credits are referred to as "off-cycle" credits. Off-cycle technologies used to generate emission credits are considered emission-related components subject to applicable requirements, and must be demonstrated to be effective for the full useful life of the vehicle. Unless the manufacturer demonstrates that the technology is not subject to in-use deterioration, the manufacturer must account for the deterioration in their analysis. The manufacturer must use one of the three options specified in this subsection (a)(8) to determine the CO_2 gram per mile credit applicable to an off-cycle technology. The manufacturer should notify the Executive Officer in its pre-model year report of its intention to generate any credits under this subsection (a)(8).

(A) *Credit available for certain off-cycle technologies.*

1. The manufacturer may generate a CO_2 gram/mile credit for certain technologies as specified in the following table, provided that each technology is applied to the minimum percentage of the manufacturer's total U.S. production of passenger cars, light-duty trucks, and medium-duty passenger vehicles specified in the table in each model year for which credit is claimed. Technology definitions are in subsection (e).

Off-Cycle Technology	Passenger Cars (g/mi)	Light-Duty Trucks and Medium-Duty Passenger Vehicles (g/mi)	Minimum Total Percent of U.S. Production
Active aerodynamics	0.6	1.0	10
High efficiency exterior lighting	1.1	1.1	10
Engine heat recovery	0.7 per 100W of capacity	0.7 per 100W of capacity	10
Engine start-stop (idle-off)	2.9	4.5	10
Active transmission warm-up	1.8	1.8	10
Active engine warm-up	1.8	1.8	10
Electric heater circulation pump	1.0	1.5	n/a
Solar roof panels	3.0	3.0	n/a
Thermal control	≤3.0	≤4.3	n/a

a. Credits may also be accrued for thermal control technologies as defined in subsection (e) in the amounts shown in the following table:

Thermal Control Technology	Credit value: Passenger Cars (g/mi)	Credit Value: Light-Duty Trucks and Medium-Duty Passenger Vehicles (g/mi)
Glass or glazing	≤2.9	≤3.9
Active seat ventilation	1.0	1.3
Solar reflective paint	0.4	0.5
Passive cabin ventilation	1.7	2.3
Active cabin ventilation	2.1	2.8

b. The maximum credit allowed for thermal control technologies is limited to 3.0 g/mi for passenger cars and to 4.3 g/mi for light-duty trucks and medium-duty passenger vehicles. The maximum credit allowed for glass or glazing is limited to 2.9 g/mi for passenger cars and to 3.9 g/mi for light-duty trucks and medium-duty passenger vehicles.

c. Glass or glazing credits are calculated using the following equation:

$$\text{Credit} = \left[Z \times \sum_{i=1}^{n} \frac{T_i \times G_i}{G} \right]$$

Where:

Credit = the total glass or glazing credits, in grams per mile, for a vehicle, which may not exceed 3.0 g/mi for passenger cars or 4.3 g/mi for light-duty trucks and medium-duty passenger vehicles;

Z = 0.3 for passenger cars and 0.4 for light-duty trucks and medium-duty passenger vehicles;

G_i = the measured glass area of window i, in square meters and rounded to the nearest tenth;

G = the total glass area of the vehicle, in square meters and rounded to the nearest tenth;

Ti = the estimated temperature reduction for the glass area of window *i*, determined using the following formula:

$$T_i = 0.3987 \times (Tts_{base} - Tts_{new})$$

Where:

Tts_{new} = the total solar transmittance of the glass, measured according to ISO 13837:2008, "Safety glazing materials – Method for determination of solar transmittance" (incorporated by reference, herein).

Tts_{base} = 62 for the windshield, side-front, side-rear, rear-quarter, and backlite locations, and 40 for rooflite locations.

2. The maximum allowable decrease in the manufacturer's combined passenger car and light-duty truck plus medium-duty passenger vehicle fleet average CO_2 emissions attributable to use of the default credit values in subsection (a)(8)(A)1 is 10 grams per mile. If the total of the CO_2 g/mi credit values from the table in subsection (a)(8)(A)1 does not exceed 10 g/mi for any passenger automobile or light truck in a manufacturer's fleet, then the total off-cycle credits may be calculated according to subsection (a)(8)(D). If the total of the CO_2 g/mi credit values from the table in subsection (a)(8)(A)1 exceeds 10 g/mi for any passenger car, light-duty truck, or medium-duty passenger vehicle in a manufacturer's fleet, then the gram per mile decrease for the combined passenger car and light-duty truck plus medium-duty passenger vehicle fleet must be determined according to subsection (a)(8)(A)2.a to determine whether the 10 g/mi limitation has been exceeded.

a. Determine the gram per mile decrease for the combined passenger car and light-duty truck plus medium-duty passenger vehicle fleet using the following formula:

$$\text{Decrease} = \frac{Credits \times 1{,}000{,}000}{[(\text{Prod}_C \times 195{,}264) + (\text{Prod}_T \times 225{,}865)]}$$

Where:

Credits = The total of passenger car and light-duty truck plus medium-duty passenger vehicles credits, in Megagrams, determined according to subsection (a)(8)(D) and limited to those credits accrued by using the default gram per mile values in subsection (a)(8)(A)1.

Prod_C = The number of passenger cars produced by the manufacturer and delivered for sale in the U.S.

Prod_T = The number of light-duty trucks and medium-duty passenger vehicles produced by the manufacturer and delivered for sale in the U.S.

b. If the value determined in subsection (a)(8)(A)2.a is greater than 10 grams per mile, the total credits, in Megagrams, that may be accrued by a manufacturer using the default gram per mile values in subsection (a)(8)(A)1 shall be determined using the following formula:

$$\text{Credit (Megagrams)} = \frac{[10 \times ((\text{Prod}_C \times 195{,}264) + (\text{Prod}_T \times 225{,}865))]}{1{,}000{,}000}$$

Where:

Prod_C = The number of passenger cars produced by the manufacturer and delivered for sale in the U.S.

Prod_T = The number of light-duty trucks and medium-duty passenger vehicles produced by the manufacturer and delivered for sale in the U.S.

c. If the value determined in subsection (a)(8)(A)2.a is not greater than 10 grams per mile, then the credits that may be accrued by a manufacturer using the default gram per mile values in subsection (a)(8)(A)1 do not exceed the allowable limit, and total credits may be determined for each category of vehicles according to subsection (a)(8)(D).

d. If the value determined in subsection (a)(8)(A)2.a is greater than 10 grams per mile, then the combined passenger car and light-duty truck plus medium-duty passenger vehicle credits, in Megagrams, that may be accrued using the calculations in subsection

(a)(8)(D) must not exceed the value determined in subsection (a)(8)(A)2.b. This limitation should generally be done by reducing the amount of credits attributable to the vehicle category that caused the limit to be exceeded such that the total value does not exceed the value determined in subsection (a)(8)(A)2.b.

3. In lieu of using the default gram per mile values specified in subsection (a)(8)(A)1 for specific technologies, a manufacturer may determine an alternative value for any of the specified technologies. An alternative value must be determined using one of the methods specified in subsection (a)(8)(B) or subsection (a)(8)(C).

(B) *Technology demonstration using EPA 5-cycle methodology.* To demonstrate an off-cycle technology and to determine a CO_2 credit using the EPA 5-cycle methodology, the manufacturer shall determine the off-cycle city/highway combined carbon-related exhaust emissions benefit by using the EPA 5-cycle methodology described in 40 CFR Part 600. Testing shall be performed on a representative vehicle, selected using good engineering judgment, for each model type for which the credit is being demonstrated. The emission benefit of a technology is determined by testing both with and without the off-cycle technology operating. Multiple off-cycle technologies may be demonstrated on a test vehicle. The manufacturer shall conduct the following steps and submit all test data to the Executive Officer.

1. Testing without the off-cycle technology installed and/or operating. Determine carbon-related exhaust emissions over the FTP, the HWFET, the US06, the SC03, and the cold temperature FTP test procedures according to the test procedure provisions specified in 40 CFR part 600 subpart B and using the calculation procedures specified in §600.113–08 of this chapter. Run each of these tests a minimum of three times without the off-cycle technology installed and operating and average the per phase (bag) results for each test procedure. Calculate the 5-cycle weighted city/highway combined carbon-related exhaust emissions from the averaged per phase results, where the 5-cycle city value is weighted 55% and the 5-cycle highway value is weighted 45%. The resulting combined city/highway value is the baseline 5-cycle carbon-related exhaust emission value for the vehicle.

2. Testing with the off-cycle technology installed and/or operating. Determine carbon-related exhaust emissions over the US06, the SC03, and the cold temperature FTP test procedures according to the test procedure provisions specified in 40 CFR part 600 subpart B and using the calculation procedures specified in 40 CFR §600.113–08. Run each of these tests a minimum of three times with the off-cycle technology installed and operating and average the per phase (bag) results for each test procedure. Calculate the 5-cycle weighted city/highway combined

carbon-related exhaust emissions from the averaged per phase results, where the 5-cycle city value is weighted 55% and the 5-cycle highway value is weighted 45%. Use the averaged per phase results for the FTP and HWFET determined in subsection (a)(8)(B)1 for operation without the off-cycle technology in this calculation. The resulting combined city/highway value is the 5-cycle carbon-related exhaust emission value showing the off-cycle benefit of the technology but excluding any benefit of the technology on the FTP and HWFET.

3. Subtract the combined city/highway value determined in subsection (a)(8)(B)1 from the value determined in subsection (a)(8)(B)2. The result is the off-cycle benefit of the technology or technologies being evaluated. If this benefit is greater than or equal to three percent of the value determined in subsection (a)(8)(B)1 then the manufacturer may use this value, rounded to the nearest tenth of a gram per mile, to determine credits under subsection (a)(8)(C).

4. If the value calculated in subsection (a)(8)(B)3 is less than two percent of the value determined in subsection (a)(8)(B)1, then the manufacturer must repeat the testing required under subsections (a)(8)(B)1 and (a)(8)(B)2, except instead of running each test three times they shall run each test two additional times. The off-cycle benefit of the technology or technologies being evaluated shall be calculated as in subsection (a)(8)(B)3 using all the tests conducted under subsections (a)(8)(B)1, (a)(8)(B)2, and (a)(8)(B)4. If the value calculated in subsection (a)(8)(B)3 is less than two percent of the value determined in subsection (a)(8)(B)1, then the manufacturer must verify the emission reduction potential of the off-cycle technology or technologies using the EPA Vehicle Simulation Tool, and if the results support a credit value that is less than two percent of the value determined in subsection (a)(8)(B)1 then the manufacturer may use the off-cycle benefit of the technology or technologies calculated as in subsection (a)(8)(B)3 using all the tests conducted under subsections (a)(8)(B)1, (a)(8)(B)2, and (a)(8)(B)4, rounded to the nearest tenth of a gram per mile, to determine credits under subsection (a)(8)(C).

(C) *Review and approval process for off-cycle credits.*

1. *Initial steps required.*

a. A manufacturer requesting off-cycle credits under the provisions of subsection (a)(8)(B) must conduct the testing and/or simulation described in that paragraph.

b. A manufacturer requesting off-cycle credits under subsection (a)(8)(B) must conduct testing and/or prepare engineering

analyses that demonstrate the in-use durability of the technology for the full useful life of the vehicle.

2. *Data and information requirements.* The manufacturer seeking off-cycle credits must submit an application for off-cycle credits determined under subsection (a)(8)(B). The application must contain the following:

a. A detailed description of the off-cycle technology and how it functions to reduce CO_2 emissions under conditions not represented on the FTP and HWFET.

b. A list of the vehicle model(s) which will be equipped with the technology.

c. A detailed description of the test vehicles selected and an engineering analysis that supports the selection of those vehicles for testing.

d. All testing and/or simulation data required under subsection (a)(8)(B), as applicable, plus any other data the manufacturer has considered in the analysis.

e. An estimate of the off-cycle benefit by vehicle model and the fleetwide benefit based on projected sales of vehicle models equipped with the technology.

f. An engineering analysis and/or component durability testing data or whole vehicle testing data demonstrating the in-use durability of the off-cycle technology components.

3. R*eview of the off-cycle credit application.* Upon receipt of an application from a manufacturer, the Executive Officer will do the following:

a. Review the application for completeness and notify the manufacturer within 30 days if additional information is required.

b. Review the data and information provided in the application to determine if the application supports the level of credits estimated by the manufacturer.

4. *Decision on off-cycle application.* The Executive Officer will notify the manufacturer in writing of its decision to approve or deny the application within 60 days of receiving a complete application, and if denied, the Executive Officer will provide the reasons for the denial.

(D) *Calculation of total off-cycle credits.* Total off-cycle credits in grams per mile of CO_2 (rounded to the nearest tenth of a gram per mile) shall be calculated separately for passenger cars and light-duty trucks plus medium-duty passenger vehicles according to the following formula:

$$\text{Total Credits (g/mi)} = \text{Credit} \times \text{Production}$$

Where:

Credit = the credit value in grams per mile determined in subsection (a)(8)(A) or subsection (a)(8)(B).

Production = The total number of passenger cars or light-duty trucks plus medium-duty passenger vehicles, whichever is applicable, produced and delivered for sale in California, produced with the off-cycle technology to which to the credit value determined in subsection (a)(8)(A) or subsection (a)(8)(B) applies.

(9) *Credits for certain full-size pickup trucks.* Full-size pickup trucks may be eligible for additional credits based on the implementation of hybrid technologies or on exhaust emission performance, as described in this subsection (a)(9). Credits may be generated under either subsection (a)(9)(A) or subsection (a)(9)(B) for a qualifying pickup truck, but not both.

(A) *Credits for implementation of gasoline-electric hybrid technology.* Full-size pickup trucks that implement hybrid gasoline-electric technologies may be eligible for an additional credit under this subsection (a)(9)(A). Pickup trucks using the credits under this subsection (a)(9)(A) may not use the credits described in subsection (a)(9)(B).

1. Full-size pickup trucks that are mild hybrid gasoline-electric vehicles and that are produced in the 2017 through 2021 model years are eligible for a credit of 10 grams/mile. To receive this credit, the manufacturer must produce a quantity of mild hybrid full-size pickup trucks such that the proportion of production of such vehicles, when compared to the manufacturer's total production of full-size pickup trucks, is not less than the amount specified in the table below for each model year.

Model year	Required minimum percent of full-size pickup trucks
2017	30%
2018	40%
2019	55%
2020	70%
2021	80%

2. Full-size pickup trucks that are strong hybrid gasoline-electric vehicles and that are produced in the 2017 through 2025 model years are eligible for a credit of 20 grams/mile. To receive this credit, the manufacturer must produce a quantity of strong hybrid full-size pickup trucks such that the proportion of production of such vehicles, when compared to the manufacturer's total production of full-size pickup trucks, is not less than 10 percent for each model year.

(B) *Credits for emission reduction performance.* 2017 through 2021 model year full-size pickup trucks that achieve carbon-related exhaust emission values below the applicable target value determined in subsection (a)(1)(B) may be eligible for an additional credit. Pickup trucks using the credits under this subsection (a)(9)(B) may not use the credits described in subsection (a)(9)(A).

1. Full-size pickup trucks that achieve carbon-related exhaust emissions less than or equal to the applicable target value determined in subsection (a)(1)(B) multiplied by 0.85 (rounded to the nearest gram per mile) and greater than the applicable target value determined in subsection (a)(1)(B) multiplied by 0.80 (rounded to the nearest gram per mile) in a model year are eligible for a credit of 10 grams/mile. A pickup truck that qualifies for this credit in a model year may claim this credit for subsequent model years through the 2021 model year if the carbon-related exhaust emissions of that pickup truck do not increase relative to the emissions in the model year in which the pickup truck qualified for the credit. To qualify for this credit in each model year, the manufacturer must produce a quantity of full-size pickup trucks that meet the emission requirements of this subsection (a)(9)(B)1 such that the proportion of production of such vehicles, when compared to the manufacturer's total

production of full-size pickup trucks, is not less than the amount specified in the table below for each model year.

Model year	Required minimum percent of full-size pickup trucks
2017	15%
2018	20%
2019	28%
2020	35%
2021	40%

2. Full-size pickup trucks that achieve carbon-related exhaust emissions less than or equal to the applicable target value determined in subsection (a)(1)(B) multiplied by 0.80 (rounded to the nearest gram per mile) in a model year are eligible for a credit of 20 grams/mile. A pickup truck that qualifies for this credit in a model year may claim this credit for a maximum of five subsequent model years if the carbon-related exhaust emissions of that pickup truck do not increase relative to the emissions in the model year in which the pickup truck first qualified for the credit. This credit may not be claimed in any model year after 2025. To qualify for this credit, the manufacturer must produce a quantity of full-size pickup trucks that meet the emission requirements of subsection (a)(9)(B)1 such that the proportion of production of such vehicles, when compared to the manufacturer's total production of full-size pickup trucks, is not less than 10 percent in each model year.

(C) *Calculation of total full-size pickup truck credits.* Total credits in grams per mile of CO_2 (rounded to the nearest whole gram per mile) shall be calculated for qualifying full-size pickup trucks according to the following formula:

$$\text{Total Credits (g/mi)} = (10 \times \text{Production}_{10}) + (20 \times \text{Production}_{20})$$

Where:

Production_{10} = The total number of full-size pickup trucks produced and delivered for sale in California with a credit value of 10 grams per mile from subsection (a)(9)(A) and subsection (a)(9)(B).

Production_{20} = The total number of full-size pickup trucks produced and delivered for sale in California with a credit value of 20 grams per mile from subsection (a)(9)(A) and subsection (a)(9)(B).

(b) *Calculation of Greenhouse Gas Credits/Debits.* Credits that are earned as part of the 2012 through 2016 MY National greenhouse gas program shall not be applicable to California's greenhouse gas program. Debits that are earned as part of the 2012 through 2016 MY National greenhouse gas program shall not be applicable to California's greenhouse gas program.

(1) *Calculation of Greenhouse Gas Credits for Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles.*

(A) A manufacturer that achieves fleet average CO_2 values lower than the fleet average CO_2 requirement for the corresponding model year shall receive credits for each model year in units of g/mi. A manufacturer that achieves fleet average CO_2 values higher than the fleet average CO_2 requirement for the corresponding model year shall receive debits for each model year in units of g/mi. Manufacturers must calculate greenhouse gas credits and greenhouse gas debits separately for passenger cars and for combined light-duty trucks and medium-duty passenger vehicles as follows:

CO_2 Credits or Debits = (CO_2 Standard - Manufacturer's Fleet Average CO_2 Value) × (Total No. of Vehicles Produced and Delivered for Sale in California, Including ZEVs and HEVs).

Where:

CO_2 Standard = the applicable standard for the model year as determined in subsection (a)(1)(C);

Manufacturer's Fleet Average CO_2 Value = average calculated according to subsection (a)(5);

(B) A manufacturer's total Greenhouse Gas credits or debits generated in a model year shall be the sum of its CO_2 credits or debits and any of the following credits or debits, if applicable. The manufacturer shall calculate, maintain, and report Greenhouse Gas credits or debits separately for its passenger car fleet and for its light-duty truck plus medium-duty passenger vehicle fleet.

1. Air conditioning leakage credits earned according to the provisions of subsection (a)(6);

2. Air conditioning efficiency credits earned according to the provisions of subsection (a)(7);

3. Off-cycle technology credits earned according to the provisions of subsection (a)(8).

4. CO_2-equivalent debits earned according to the provisions of subsection (a)(2)(D).

(2) A manufacturer with 2017 and subsequent model year fleet average Greenhouse Gas values greater than the fleet average CO_2 standard applicable for the corresponding model year shall receive debits in units of g/mi Greenhouse Gas equal to the amount of negative credits determined by the aforementioned equation. For the 2017 and subsequent model years, the total g/mi Greenhouse Gas credits or debits earned for passenger cars and for light-duty trucks and medium-duty passenger vehicles shall be summed together. The resulting amount shall constitute the g/mi Greenhouse Gas credits or debits accrued by the manufacturer for the model year.

(3) *Procedure for Offsetting Greenhouse Gas Debits.*

(A) A manufacturer shall equalize Greenhouse Gas emission debits by earning g/mi Greenhouse Gas emission credits in an amount equal to the g/mi Greenhouse Gas debits, or by submitting a commensurate amount of g/mi Greenhouse Gas credits to the Executive Officer that were earned previously or acquired from another manufacturer. A manufacturer shall equalize combined Greenhouse Gas debits for passenger cars, light-duty trucks, and medium-duty passenger vehicles within five model years after they are earned. If emission debits are not equalized within the specified time period, the manufacturer shall be subject to the Health and Safety Code section 43211 civil penalty applicable to a manufacturer which sells a new motor vehicle that does not meet the applicable emission standards adopted by the state board. The cause of action shall be deemed to accrue when the emission debits are not equalized by the end of the specified time period. For a manufacturer demonstrating compliance under Option 2 in subsection (a)(5)(D), the emission debits that are subject to a civil penalty under Health and Safety Code section 43211 shall be calculated separately for California, the District of Columbia, and each individual state that is included in the fleet average greenhouse gas requirements in subsection (a)(1). These emission debits shall be calculated for each individual state using the formula in subsections (b)(1) and (b)(2), except that the "Total No. of Vehicles Produced and Delivered for Sale in California, including ZEVs and HEVs" shall be calculated separately for the District of Columbia and each individual state.

For the purposes of Health and Safety Code section 43211, the number of passenger cars not meeting the state board's emission standards shall be determined by dividing the total amount of g/mi Greenhouse Gas emission debits for the model year calculated for California by the g/mi Greenhouse Gas fleet average requirement for passenger car applicable for the model year in which the debits were first incurred. For the purposes of Health and Safety Code section 43211, the number of light-duty trucks and medium-duty passenger vehicles not meeting the state board's emission standards shall be determined by dividing the

total amount of g/mi Greenhouse Gas emission debits for the model year calculated for California by the g/mi Greenhouse Gas fleet average requirement for light-duty trucks and medium-duty passenger vehicles, applicable for the model year in which the debits were first incurred.

(B) Greenhouse Gas emission credits earned in the 2017 and subsequent model years shall retain full value through the fifth model year after they are earned, and will have no value if not used by the beginning of the sixth model year after being earned.

(4) *Use of Greenhouse Gas Emission Credits to Offset a Manufacturer's ZEV Obligations.*

(A) For a given model year, a manufacturer that has Greenhouse Gas credits remaining after equalizing all of its Greenhouse Gas debits may use those Greenhouse Gas credits to comply with its ZEV obligations for that model year, in accordance with the provisions set forth in the "California Exhaust Emission Standards and Test Procedures for 2009 through 2017 Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," incorporated by reference in section 1962.1, or the "California Exhaust Emission Standards and Test Procedures for 2018 and Subsequent Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," incorporated by reference in section 1962.2.

(B) Any Greenhouse Gas credits used by a manufacturer to comply with its ZEV obligations shall retain no value for the purposes of complying with this section 1961.3.

(5) Credits and debits that are earned as part of the 2012 through 2016 MY National Greenhouse Gas Program, shall have no value for the purpose of complying with this section 1961.3.

(c) *Test Procedures.* The certification requirements and test procedures for determining compliance with the emission standards in this section are set forth in the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," incorporated by reference in section 1961.2. In the case of hybrid electric vehicles, the certification requirements and test procedures for determining compliance with the emission standards in this section are set forth in the "California Exhaust Emission Standards and Test Procedures for 2009 through 2017 Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," incorporated by reference in section 1962.1, or the "California Exhaust Emission Standards and Test Procedures for

2018 and Subsequent Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes," incorporated by reference in section 1962.2, as applicable.

(d) *Abbreviations.* The following abbreviations are used in this section 1961.3:

"CFR" means Code of Federal Regulations.
"CH_4" means methane.
"CO_2" means carbon dioxide.
"FTP" means Federal Test Procedure.
"GHG" means greenhouse gas.
"g/mi" means grams per mile.
"GVW" means gross vehicle weight.
"GVWR" means gross vehicle weight rating.
"GWP" means the global warming potential.
"HEV" means hybrid-electric vehicle.
"HWFET" means Highway Fuel Economy Test (HWFET; 40 CFR 600 Subpart B).
"LDT" means light-duty truck.
"LVW" means loaded vehicle weight.
"MDPV" means medium-duty passenger vehicle.
"mg/mi" means milligrams per mile.
"MY" means model year.
"NHTSA" means National Highway Traffic Safety Administration.
"N_2O" means nitrous oxide.
"ZEV" means zero-emission vehicle.

(e) *Definitions Specific to this Section.* The following definitions apply to this section 1961.3:

(1) "A/C Direct Emissions" means any refrigerant released from a motor vehicle's air conditioning system.

(2) "Active Aerodynamic Improvements" means technologies that are activated only at certain speeds to improve aerodynamic efficiency by a minimum of three percent, while preserving other vehicle attributes or functions.

(3) "Active Cabin Ventilation" means devices that mechanically move heated air from the cabin interior to the exterior of the vehicle.

(4) "Active Transmission Warmup" means a system that uses waste heat from the exhaust system to warm the transmission fluid to an operating temperature range quickly using a heat exchanger in the exhaust system, increasing the overall transmission efficiency by reducing parasitic losses associated with the transmission fluid, such as losses related to friction and fluid viscosity.

(5) "Active Engine Warmup" means a system using waste heat from the exhaust system to warm up targeted parts of the engine so that it reduces engine friction losses and enables the closed-loop fuel control to activate more quickly. It allows a faster transition from cold operation to warm operation, decreasing CO_2 emissions.

(6) "Active Seat Ventilation" means a device that draws air from the seating surface which is in contact with the occupant and exhausts it to a location away from the seat.

(7) "Blower motor controls which limit waste energy" means a method of controlling fan and blower speeds that does not use resistive elements to decrease the voltage supplied to the motor.

(8) "Default to recirculated air mode" means that the default position of the mechanism which controls the source of air supplied to the air conditioning system shall change from outside air to recirculated air when the operator or the automatic climate control system has engaged the air conditioning system (i.e., evaporator is removing heat), except under those conditions where dehumidification is required for visibility (i.e., defogger mode). In vehicles equipped with interior air quality sensors (e.g., humidity sensor, or carbon dioxide sensor), the controls may determine proper blend of air supply sources to maintain freshness of the cabin air and prevent fogging of windows while continuing to maximize the use of recirculated air. At any time, the vehicle operator may manually select the non-recirculated air setting during vehicle operation but the system must default to recirculated air mode on subsequent vehicle operations (i.e., next vehicle start). The climate control system may delay switching to recirculation mode until the interior air temperature is less than the outside air temperature, at which time the system must switch to recirculated air mode.

(9) "Electric Heater Circulation Pump" means a pump system installed in a stop-start equipped vehicle or in a hybrid electric vehicle or plug-in hybrid electric vehicle that continues to circulate hot coolant through the heater core when the engine is stopped during a stop-start event. This system must be calibrated to keep the engine off for 1 minute or more when the external ambient temperature is 30 deg F.

(10) "Emergency Vehicle" means a motor vehicle manufactured primarily for use as an ambulance or combination ambulance-hearse or for use by the United States Government or a State or local government for law enforcement.

(11) "Engine Heat Recovery" means a system that captures heat that would otherwise be lost through the exhaust system or through the radiator and

converting that heat to electrical energy that is used to meet the electrical requirements of the vehicle. Such a system must have a capacity of at least 100W to achieve 0.7 g/mi of credit. Every additional 100W of capacity will result in an additional 0.7 g/mi of credit.

(12) "Engine Start-Stop" means a technology which enables a vehicle to automatically turn off the engine when the vehicle comes to a rest and restart the engine when the driver applies pressure to the accelerator or releases the brake.

(13) "EPA Vehicle Simulation Tool" means the "EPA Vehicle Simulation Tool" as incorporated by reference in 40 CFR §86.1 in the Notice of Proposed Rulemaking for EPA's 2017 and subsequent MY National Greenhouse Gas Program, as proposed November 16, 2011 [Insert Federal Register for the 2017 and subsequent MY National Greenhouse Gas Final Rule as proposed at 76 Fed. Reg. 74854, 75357 (December 1, 2011)], herein.

(14) "Executive Officer" means the Executive Officer of the California Air Resources Board.

(15) "Footprint" means the product of average track width (rounded to the nearest tenth of an inch) and wheelbase (measured in inches and rounded to the nearest tenth of an inch), divided by 144 and then rounded to the nearest tenth of a square foot, where the average track width is the average of the front and rear track widths, where each is measured in inches and rounded to the nearest tenth of an inch.

(16) "Federal Test Procedure" or "FTP" means 40 CFR, Part 86, Subpart B, as amended by the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles."

(17) "Full-size pickup truck" means a light-duty truck that has a passenger compartment and an open cargo box and which meets the following specifications:

1. A minimum cargo bed width between the wheelhouses of 48 inches, measured as the minimum lateral distance between the limiting interferences (pass-through) of the wheelhouses. The measurement shall exclude the transitional arc, local protrusions, and depressions or pockets, if present. An open cargo box means a vehicle where the cargo box does not have a permanent roof. Vehicles sold with detachable covers are considered "open" for the purposes of these criteria.
2. A minimum open cargo box length of 60 inches, where the length is defined by the lesser of the pickup bed length at the top of the body and the pickup bed length at the floor, where the length at the top of the body is defined as the longitudinal distance from the inside front of the

pickup bed to the inside of the closed endgate as measured at the cargo floor surface along vehicle centerline, and the length at the floor is defined as the longitudinal distance from the inside front of the pickup bed to the inside of the closed endgate as measured at the cargo floor surface along vehicle centerline.

3. A minimum towing capability of 5,000 pounds, where minimum towing capability is determined by subtracting the gross vehicle weight rating from the gross combined weight rating, or a minimum payload capability of 1,700 pounds, where minimum payload capability is determined by subtracting the curb weight from the gross vehicle weight rating.

(18) "Greenhouse Gas" means the following gases: carbon dioxide, methane, nitrous oxide, and hydrofluorocarbons.

(19) "GWP" means the global warming potential of the refrigerant over a 100-year horizon, as specified in Intergovernmental Panel on Climate Change (IPCC) 2007: Climate Change 2007 – The Physical Science Basis. S. Solomon et al. (editors), Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change, Cambridge University Press, Cambridge, UK and New York, NY, USA, ISBN 0-521-70596-7, or determined by ARB if such information is not available in the IPCC Fourth Assessment Report.

(20) "High Efficiency Exterior Lighting" means a lighting technology that, when installed on the vehicle, is expected to reduce the total electrical demand of the exterior lighting system by a minimum of 60 watts when compared to conventional lighting systems. To be eligible for this credit the high efficiency lighting must be installed in the following components: parking/position, front and rear turn signals, front and rear side markers, stop/brake lights (including the center-mounted location), taillights, backup/reverse lights, and license plate lighting.

(21) "Improved condensers and/or evaporators" means that the coefficient of performance (COP) of air conditioning system using improved evaporator and condenser designs is 10 percent higher, as determined using the bench test procedures described in SAE J2765 "Procedure for Measuring System COP of a Mobile Air Conditioning System on a Test Bench," when compared to a system using standard, or prior model year, component designs. SAE J2765 is incorporated by reference herein. The manufacturer must submit an engineering analysis demonstrating the increased improvement of the system relative to the baseline design, where the baseline component(s) for comparison is the version which a manufacturer most recently had in production on the same vehicle design or in a similar or related vehicle model. The dimensional characteristics (e.g., tube configuration/thickness/spacing, and fin density) of the baseline component(s) shall be compared to the new component(s) to demonstrate the improvement in coefficient of performance.

(22) "Mild hybrid gasoline-electric vehicle" means a vehicle that has start/stop capability and regenerative braking capability, where the recaptured braking energy over the FTP is at least 15 percent but less than 75 percent of the total braking energy, where the percent of recaptured braking energy is measured and calculated according to 40 CFR §600.108(g).

(23) "Model Type" means a unique combination of car line, basic engine, and transmission class.

(24) "2012 through 2016 MY National Greenhouse Gas Program" means the national program that applies to new 2012 through 2016 model year passenger cars, light-duty-trucks, and medium-duty passenger vehicles as adopted by the U.S. Environmental Protection Agency on April 1, 2010 (75 Fed. Reg. 25324, 25677 (May 7, 2010)).

(25) "Oil separator" means a mechanism that removes at least 50 percent of the oil entrained in the oil/refrigerant mixture exiting the compressor and returns it to the compressor housing or compressor inlet, or a compressor design that does not rely on the circulation of an oil/refrigerant mixture for lubrication.

(26) "Passive Cabin Ventilation" means ducts or devices which utilize convective airflow to move heated air from the cabin interior to the exterior of the vehicle.

(27) "Plug-in Hybrid Electric Vehicle" means "off-vehicle charge capable hybrid electric vehicle" as defined in the "California Exhaust Emission Standards and Test Procedures for 2018 and Subsequent Model Zero-Emission Vehicles and Hybrid Electric Vehicles, in the Passenger Car, Light-Duty Truck and Medium-Duty Vehicle Classes."

(28) "Reduced reheat, with externally controlled, fixed-displacement or pneumatic variable displacement compressor" means a system in which the output of either compressor is controlled by cycling the compressor clutch off-and-on via an electronic signal, based on input from sensors (e.g., position or setpoint of interior temperature control, interior temperature, evaporator outlet air temperature, or refrigerant temperature) and air temperature at the outlet of the evaporator can be controlled to a level at 41°F, or higher.

(29) "Reduced reheat, with externally-controlled, variable displacement compressor" means a system in which compressor displacement is controlled via an electronic signal, based on input from sensors (e.g., position or setpoint of interior temperature control, interior temperature, evaporator outlet air temperature, or refrigerant temperature) and air temperature at the outlet of the evaporator can be controlled to a level at 41°F, or higher.

(30) "SC03" means the SC03 test cycle as set forth in the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures Passenger Cars, Light Duty Trucks, and Medium Duty Vehicles."

(31) "Solar Reflective Paint" means a vehicle paint or surface coating which reflects at least 65 percent of the impinging infrared solar energy, as determined using ASTM standards E903-96 (Standard Test Method for Solar Absorptance, Reflectance, and Transmittance of Materials Using Integrating Spheres, DOI: 10.1520/E0903-96 (Withdrawn 2005)), E1918-06 (Standard Test Method for Measuring Solar Reflectance of Horizontal and Low-Sloped Surfaces in the Field, DOI: 10.1520/E1918-06), or C1549-09 (Standard Test Method for Determination of Solar Reflectance Near Ambient Temperature Using a Portable Solar Reflectometer, DOI: 10.1520/C1549-09). These ASTM standards are incorporated by reference, herein.

(32) "Solar Roof Panels" means the installation of solar panels on an electric vehicle or a plug-in hybrid electric vehicle such that the solar energy is used to provide energy to the electric drive system of the vehicle by charging the battery or directly providing power to the electric motor with the equivalent of at least 50 Watts of rated electricity output.

(33) "Strong hybrid gasoline-electric vehicle" means a vehicle that has start/stop capability and regenerative braking capability, where the recaptured braking energy over the Federal Test Procedure is at least 75 percent of the total braking energy, where the percent of recaptured braking energy is measured and calculated according to 40 CFR §600.108(g).

(34) "Subconfiguration" means a unique combination within a vehicle configuration of equivalent test weight, road load horsepower, and any other operational characteristics or parameters which is accepted by USEPA.

(35) "US06" means the US06 test cycle as set forth in the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures Passenger Cars, Light Duty Trucks, and Medium Duty Vehicles."

(36) "Worst-Case" means the vehicle configuration within each test group that is expected to have the highest CO_2-equivalent value, as calculated in section (a)(5).

(f) Severability. Each provision of this section is severable, and in the event that any provision of this section is held to be invalid, the remainder of both this section and this article remains in full force and effect.

Note: Authority cited: Sections 39500, 39600, 39601, 43013, 43018, 43018.5, 43101, 43104 and 43105, Health and Safety Code. Reference: Sections 39002, 39003, 39667, 43000, 43009.5, 43013, 43018, 43018.5, 43100, 43101, 43101.5, 43102, 43104, 43105, 43106, 43204, 43205, and 43211, Health and Safety Code.

8. Amend title 13, CCR, section 1965 to read as follows:

§1965. Emission Control, Smog Index, and Environmental Performance Labels - 1979 and Subsequent Model-Year Motor Vehicles.

In addition to all other requirements, emission control labels are required by the California certification procedures contained in the "California Motor Vehicle Emission Control and Smog Index Label Specifications for 1978 through 2003 Model Year Motorcycles, Light-, Medium- And Heavy-Duty Engines And Vehicles," adopted March 1, 1978, as last amended September 5, 2003, which is incorporated herein by reference, the "California 2001 through 2014 Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and ~~for~~ 2009 through 2016 ~~and Subsequent~~ Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," incorporated by reference in §1961(d), the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," incorporated by reference in title 13, CCR section 1961.2(d), the "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Diesel-Engines and Vehicles," incorporated by reference in §1956.8(b), the "California Interim Certification Procedures for 2004 and Subsequent Model Hybrid-Electric Vehicle Classes," incorporated by reference in §1956.8(b) and (d), and the "California Exhaust Emission Standards and Test Procedures for 2004 and Subsequent Model Heavy-Duty Otto-Cycle Engines," incorporated by reference in §1956.8(d). Smog index labels for passenger cars and light-duty trucks shall conform to the "California Smog Index Label Specifications for 2004 through 2009 Model Year Passenger Cars and Light-Duty Trucks," adopted September 5, 2003, as last amended May 2, 2008, which is incorporated herein by reference. Environmental Performance labels for passenger cars, light-duty trucks, and medium-duty passenger vehicles shall conform to the "California Environmental Performance Label Specifications for 2009 and Subsequent Model Year Passenger Cars, Light-Duty Trucks, and Medium-Duty Passenger Vehicles," adopted May 2, 2008, as last amended [INSERT DATE OF AMENDMENT], which is incorporated herein by reference. Motorcycles shall meet the requirements of Title 40 Code of Federal Regulations section 86.413-78, as last amended October 28, 1977, which is incorporated herein by reference.

NOTE: Authority cited: Sections 39600, 39601, 43200, and 43200.1, Health and Safety Code. Reference: Sections 39002, 39003, 43000, 43013, 43018.5, 43100, 43101, 43102, 43104, 43107, 43200, and 43200.1, Health and Safety Code.

9. Amend title 13, CCR, section 1968.2 to read as follows:

§1968.2. Malfunction and Diagnostic System Requirements – 2004 and Subsequent Model-Year Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles and Engines.

* * * *

(c) ***Definitions.***

* * * *

"Calculated load value" refers to an indication of the percent engine capacity that is being used and is defined in Society of Automotive Engineers (SAE) J1979 "E/E Diagnostic Test Modes ~~– Equivalent to ISO/DIS 15031-5:April 30, 2002~~", ~~April 2002~~ (SAE J1979), incorporated by reference (section (g)(1.4)[1]). For diesel applications, in lieu of the definition in SAE J1979, the calculated load value ~~is~~ may alternatively be determined by the ratio of current output torque to maximum output torque at current engine speed as defined by suspect parameter number (SPN) 92 of SAE J1939 "Recommended Practice for a Serial Control and Communications Vehicle Network" (SAE J1939), incorporated by reference.

* * * *

"Fueled engine operation" is the state where any fuel is introduced into the engine for the purpose of combustion.

* * * *

"Hybrid vehicle" refers to a vehicle (including a plug-in hybrid electric vehicle) that can draw propulsion energy from either or both of the following on-vehicle sources of stored energy: 1) a consumable fuel and 2) an energy storage device such as a battery, capacitor, or flywheel.

* * * *

"Plug-in hybrid electric vehicle" refers to a hybrid vehicle that has the capability to charge a battery from an off-vehicle electric energy source that cannot be connected or coupled to the vehicle in any manner while the vehicle is being driven.

* * * *

"Propulsion system active" is the state where the powertrain (e.g., engine, electric machine) is enabled by the driver (e.g., after ignition on for

conventional vehicles, after power button pushed for some hybrid vehicles, or after remote start activation) such that the vehicle is ready to be used (e.g., vehicle is ready to be driven, ready to be shifted from "park" to "drive", heating, ventilation, and air conditioning (HVAC) turned on to condition cabin prior to driving). For purposes of this definition, "the state where the powertrain is enabled" does not include activations that are not driver-initiated (e.g., conditions where portions of the vehicle system wake up to perform OBD II monitoring or off-board charging).

* * * *

"Warm-up cycle" means a driving cycle with sufficient vehicle operation such that the coolant temperature has risen by at least 40 degrees Fahrenheit from engine starting and reaches a minimum temperature of at least 160 degrees Fahrenheit (140 degrees Fahrenheit for applications with diesel engines). Alternatively, manufacturers may define warm-up cycle as a driving cycle with vehicle operation in which the criteria specified in sections (d)(2.5.2)(B)(iii)a., b., and c. are met.

* * * *

(d) General Requirements.

Section (d) sets forth the general requirements of the OBD II system. Specific performance requirements for components and systems that shall be monitored are set forth in sections (e) and (f) below.

* * * *

(2) *MIL and Fault Code Requirements.*

* * * *

(2.5) Erasing a permanent fault code. The OBD system shall erase a permanent fault code under the following conditions:

(2.5.1) If the OBD II system is commanding the MIL on, the OBD II system shall erase a permanent fault code only if the OBD II system itself determines that the malfunction that caused the permanent fault code to be stored is no longer present and is not commanding the MIL on, pursuant to the requirements of section (d)(2.3) (which for purposes of this section shall apply to all monitors). Erasure of the permanent fault code shall occur in conjunction with extinguishing the MIL or no later than the start of the first driving cycle that begins with the MIL commanded off.

(2.5.2) If all fault information in the on-board computer other than the permanent fault code has been cleared (i.e., through the use of a scan tool or battery disconnect) and the OBD II system is not commanding the MIL on:

(A) Except as provided for in sections (d)(2.5.2)(C) through (E), if the monitor of the malfunction that caused the permanent fault code to be stored is subject to the minimum ratio requirements of section

(d)(3.2) (e.g., catalyst monitor, comprehensive component input component rationality monitors), the OBD II system shall erase the permanent fault code at the end of a driving cycle if the monitor has run and made one or more determinations during a driving cycle that the malfunction of the component or the system is not present and has not made any determinations within the same driving cycle that the malfunction is present.

(B) Except as provided for in sections (d)(2.5.2)(D) and (E), if the monitor of the malfunction that caused the permanent fault code to be stored is not subject to the minimum ratio requirements of section (d)(3.2) (e.g., gasoline misfire monitor, fuel system monitor, comprehensive component circuit continuity monitors), the OBD II system shall erase the permanent fault code at the end of a driving cycle if:

(i) The monitor has run and made one or more determinations during a driving cycle that the malfunction of the component or the system is not present and has not made any determinations within the same driving cycle that the malfunction is present;

(ii) The monitor has not made any determinations that the malfunction is present subsequent to the most recent driving cycle in which the criteria of section (d)(2.5.2)(B)(i) are met; and

(iii) The following criteria are satisfied on any single driving cycle (which may be a different driving cycle than that in which the criteria of section (d)(2.5.2)(B)(i) are satisfied):

a. Except as provided in section (d)(2.5.2)(B)(iii)f. below, ~~C~~cumulative time since engine start is greater than or equal to 600 seconds;

b. Except as provided in section (d)(2.5.2)(B)(iii)e. below, cumulative vehicle operation at or above 25 miles per hour occurs for greater than or equal to 300 seconds (medium-duty vehicles with diesel engines certified on an engine dynamometer may use cumulative operation at or above 1150 rpm in lieu of at or above 25 miles per hour for purposes of this criteria);

c. Continuous vehicle operation at idle (i.e., accelerator pedal released by driver and either vehicle speed less than or equal to one mile per hour or engine speed less than or equal to 200 rpm above normal warmed-up idle (as determined in the drive position for vehicles equipped with an automatic transmission)) for greater than or equal to 30 seconds; and

d. For 2013 and subsequent model year engines, the monitor has not made any determination that the malfunction is present.

e. For 2004 through 2012 model year medium-duty vehicles with diesel engines certified on an engine dynamometer,

manufacturers may use diesel engine operation at or above 15 percent calculated load in lieu of 1150 rpm for the criterion in section (d)(2.5.2)(B)(iii)b. above.

f. For hybrid vehicles, manufacturers shall use "cumulative propulsion system active time" in lieu of "cumulative time since engine start" for the criterion in section (d)(2.5.2)(B)(iii)a.

(iv) Monitors required to use "similar conditions" as defined in section (c) to store and erase pending and confirmed fault codes may not require that the similar conditions be met prior to erasure of the permanent fault code.

(C) For monitors subject to section (d)(2.5.2)(A), the manufacturer may choose to erase the permanent fault code using the criteria under section (d)(2.5.2)(B) in lieu of the criteria under section (d)(2.5.2)(A).

(D) For 2009 and 2010 model year vehicles meeting the permanent fault code requirements of section (d)(2.2.5), manufacturers may request Executive Officer approval to use alternate criteria to erase the permanent fault code. The Executive Officer shall approve alternate criteria that:

(i) Will not likely require driving conditions that are longer and more difficult to meet than those required under section (d)(2.5.2)(B), and

(ii) Do not require access to enhanced scan tools (i.e., tools that are not generic SAE J1978 scan tools) to determine conditions necessary to erase the permanent fault code.

(E) If alternate criteria to erase the permanent fault code are approved by the Executive Officer under section (d)(2.5.2)(D), a manufacturer may continue to use the approved alternate criteria for 2011 model year vehicles previously certified in the 2009 or 2010 model year to the alternate criteria and carried over to the 2011 model year.

* * * *

(3) *Monitoring Conditions.*

Section (d)(3) sets forth the general monitoring requirements while sections (e) and (f) set forth the specific monitoring requirements as well as identify which of the following general monitoring requirements in section (d)(3) are applicable for each monitored component or system identified in sections (e) and (f).

* * * *

(3.2) As specifically provided for in sections (e) and (f), manufacturers shall define monitoring conditions in accordance with the criteria in sections (d)(3.2.1) through (3.2.3). The requirements of section (d)(3.2) shall be phased in as follows: 30 percent of all 2005 model year vehicles, 60 percent of all 2006 model year vehicles, and 100 percent of all 2007 and subsequent model year vehicles. Manufacturers may use an alternate phase-in schedule in lieu of the required phase-in schedule if

the alternate phase-in schedule provides for equivalent compliance volume as defined in section (c) with the exception that 100 percent of 2007 and subsequent model year vehicles shall comply with the requirements. Small volume manufacturers shall meet the requirements on 100 percent of 2007 and subsequent model year vehicles but shall not be required to meet the specific phase-in requirements for the 2005 and 2006 model years.

(3.2.1) Manufacturers shall define monitoring conditions that, in addition to meeting the criteria in section (d)(3.1), ensure that the monitor yields an in-use performance ratio (as defined in section (d)(4)) that meets or exceeds the minimum acceptable in-use monitor performance ratio on in-use vehicles. For purposes of this regulation, except as provided below in section (d)(3.2.1)(D), the minimum acceptable in-use monitor performance ratio is:

(A) 0.260 for secondary air system monitors and other cold start related monitors utilizing a denominator incremented in accordance with section (d)(4.3.2)(E);

(B) For evaporative system monitors:

(i) 0.260 for monitors designed to detect malfunctions identified in section (e)(4.2.2)(C) (i.e., 0.020 inch leak detection); and

(ii) 0.520 for monitors designed to detect malfunctions identified in section (e)(4.2.2)(A) and (B) (i.e., purge flow and 0.040 inch leak detection);

(C) 0.336 for catalyst, oxygen sensor, EGR, VVT system, and all other monitors specifically required in sections (e) and (f) to meet the monitoring condition requirements of section (d)(3.2);

(D) For introductory years:

(i) through the 2007 model year, for the first three years a vehicle is certified to the in-use performance ratio monitoring requirements of section (d)(3.2), 0.100 for all monitors specified in section (d)(3.2.1)(A) through (C) above. For example, the 0.100 ratio shall apply to the 2004, 2005, and 2006 model years for vehicles first certified in the 2004 model year and to the 2007, 2008, and 2009 model years for vehicles first certified in the 2007 model year.

(ii) through the 2014 model year, for fuel system air-fuel ratio cylinder imbalance monitors, 0.100;

(iii) through the 2011 model year, for secondary exhaust gas sensor monitors specified in (e)(7.2.2)(C), 0.100;

(iv) through the 2012 model year, for vehicles subject to the monitoring requirements of section (f), 0.100 for all monitors specified in section (d)(3.2.1)(C) above~~.~~;

(v) through the 2016 model year for plug-in hybrid electric vehicles, 0.100 for all monitors specifically required in sections (e) and (f) to meet the monitoring condition requirements of section (d)(3.2) and that are for systems or components that require engine

operation.

* * * *

(4) *In-Use Monitor Performance Ratio Definition.*

* * * *

(4.3) Denominator Specifications

* * * *

(4.3.2) Specifications for incrementing:

* * * *

(B) Except as provided for in sections (d)(4.3.2)(H), (J), and (K), t~~T~~he denominator for each monitor shall be incremented within ten seconds if and only if the following criteria are satisfied on a single driving cycle:

(i) Cumulative time since engine start is greater than or equal to 600 seconds while at an elevation of less than 8,000 feet above sea level and at an ambient temperature of greater than or equal to 20 degrees Fahrenheit;

(ii) Except as provided in section (d)(4.3.2)(B)(iv) below, cumulative vehicle operation at or above 25 miles per hour occurs for greater than or equal to 300 seconds while at an elevation of less than 8,000 feet above sea level and at an ambient temperature of greater than or equal to 20 degrees Fahrenheit (medium-duty vehicles with diesel engines certified on an engine dynamometer may use cumulative operation at or above 1150 rpm in lieu of at or above 25 miles per hour for purposes of this criteria);

(iii) Continuous vehicle operation at idle (i.e., accelerator pedal released by driver and either vehicle speed less than or equal to one mile per hour or engine speed less than or equal to 200 rpm above normal warmed-up idle (as determined in the drive position for vehicles equipped with an automatic transmission)) for greater than or equal to 30 seconds while at an elevation of less than 8,000 feet above sea level and at an ambient temperature of greater than or equal to 20 degrees Fahrenheit.

(iv) For 2004 through 2012 model year medium-duty vehicles with diesel engines certified on an engine dynamometer, manufacturers may use diesel engine operation at or above 15 percent calculated load in lieu of 1150 rpm for the criterion in section (d)(4.3.2)(B)(ii) above.

* * * *

(D) Except as provided for in sections (d)(4.3.2)(D)(iv) and (d)(4.3.2)(L), ~~In addition to the requirements of section (d)(4.3.2)(B) above,~~ the evaporative system monitor denominator(s) shall be incremented if and only if:

(i) The requirements of section (d)(4.3.2)(B) have been met ~~Cumulative time since engine start is greater than or equal to 600 seconds while at an ambient temperature of greater than or~~

~~equal to 40 degrees Fahrenheit but less than or equal to 95 degrees Fahrenheit; and~~;

(ii) Cumulative time since engine start is greater than or equal to 600 seconds while at an ambient temperature of greater than or equal to 40 degrees Fahrenheit but less than or equal to 95 degrees Fahrenheit; and ~~Engine cold start occurs with engine coolant temperature at engine start greater than or equal to 40 degrees Fahrenheit but less than or equal to 95 degrees Fahrenheit and less than or equal to 12 degrees Fahrenheit higher than ambient temperature at engine start.~~

(iii) Engine cold start occurs with engine coolant temperature at engine start greater than or equal to 40 degrees Fahrenheit but less than or equal to 95 degrees Fahrenheit and less than or equal to 12 degrees Fahrenheit higher than ambient temperature at engine start.

(iv) For plug-in hybrid electric vehicles, manufacturers may choose to increment the evaporative system denominator(s) using the criteria under section (d)(4.3.2)(L) in lieu of the criteria under sections (d)(4.3.2)(D)(i) through (iii) above.

* * * *

(F) In addition to the requirements of section (d)(4.3.2)(B) above, the denominator(s) for the following monitors of output components (except those operated only at engine start-up and subject to the requirements of the previous section (d)(4.3.2)(E)) shall be incremented if and only if the component is commanded to function (e.g., commanded "on", "open", "closed", "locked", etc.) on two or more occasions for greater than two seconds during the driving cycle or for a cumulative time greater than or equal to ten seconds, whichever occurs first:

(i) Air conditioning system (section (e)(12))

(ii) Variable valve timing and/or control system (sections (e)(13) and (f)(13))

(iii) "Other emission control or source device" (sections (e)(16) and (f)(16))

(iv) Comprehensive component output component (sections (e)(15) and (f)(15)) (e.g., turbocharger waste-gates, variable length manifold runners, torque converter clutch lock-up solenoids, etc.)

(v) PM sensor heater (section (f)(5.2.4)(A))

* * * *

(H) For monitors of the following components, the manufacturer may request Executive Officer approval to use alternate or additional criteria to that set forth in section (d)(4.3.2)(B) above for incrementing the denominator. Executive Officer approval of the proposed criteria shall be based on the equivalence of the proposed criteria in measuring the frequency of monitor operation

relative to the amount of vehicle operation in accordance with the criteria in section (d)(4.3.2)(B) above:

(i) Engine cooling system input components (sections (e)(10) and (f)(11))

(ii) Air conditioning system input components (section (e)(12))

(iii) Direct ozone reduction systems (section (e)(14))

(iv) "Other emission control or source devices" (sections (e)(16) and (f)(16))

(v) Comprehensive component input components that require extended monitoring evaluation (sections (e)(15) and (f)(15)) (e.g., stuck fuel level sensor rationality)

(vi) Comprehensive component input component temperature sensor rationality monitors (sections (e)(15) and (f)(15)) (e.g, intake air temperature sensor, ambient temperature sensor, fuel temperature sensor)

(vii) PM filter frequent regeneration (section (f)(9.2.2))

(viii) PM sensor monitoring capablity monitor (section (f)(5.2.2)(D))

* * * *

(J) For ~~hybrid vehicles,~~ vehicles that employ alternate engine start hardware or strategies (e.g., integrated starter and generators)~~,~~ or alternate fuel vehicles (e.g., dedicated, bi-fuel, or dual-fuel applications), the manufacturer may request Executive Officer approval to use alternate criteria to that set forth in section (d)(4.3.2)(B) above for incrementing the denominator. In general, the Executive Officer shall not approve alternate criteria for vehicles that only employ engine shut off at or near idle/vehicle stop conditions. Executive Officer approval of the alternate criteria shall be based on the equivalence of the alternate criteria to determine the amount of vehicle operation relative to the measure of conventional vehicle operation in accordance with the criteria in section (d)(4.3.2)(B) above.

(K) For 2014 and subsequent model year hybrid vehicles, in lieu of the criteria in section (d)(4.3.2)(B) above, the denominator for each monitor shall be incremented within ten seconds if and only if the following criteria are satisfied on a single driving cycle:

(i) Cumulative propulsion system active time is greater than or equal to 600 seconds while at an elevation of less than 8,000 feet above sea level and at an ambient temperature of greater than or equal to 20 degrees Fahrenheit;

(ii) Cumulative vehicle operation at or above 25 miles per hour occurs for greater than or equal to 300 seconds while at an elevation of less than 8,000 feet above sea level and at an ambient temperature of greater than or equal to 20 degrees Fahrenheit (medium-duty vehicles with diesel engines certified on an engine dynamometer may use cumulative operation at or above 1150 rpm in lieu of at or above 25 miles per hour for

purposes of this criteria);

(iii) Continuous vehicle operation at idle (i.e., accelerator pedal released by driver and either vehicle speed less than or equal to one mile per hour or engine speed less than or equal to 200 rpm above normal warmed-up idle (as determined in the drive position for vehicles equipped with an automatic transmission)) for greater than or equal to 30 seconds while at an elevation of less than 8,000 feet above sea level and at an ambient temperature of greater than or equal to 20 degrees Fahrenheit; and

(iv) Cumulative fueled engine operation for greater than or equal to 10 seconds while at an elevation of less than 8,000 feet above sea level and at an ambient temperature of greater than or equal to 20 degrees Fahrenheit.

(L) For 2015 and subsequent model year plug-in hybrid electric vehicles, in addition to the requirements of sections (d)(4.3.2)(K)(i) through (iii) above, the evaporative system monitor denominator(s) shall be incremented if and only if:

(i) Cumulative propulsion system active time is greater than or equal to 600 seconds while at an ambient temperature of greater than or equal to 40 degrees Fahrenheit but less than or equal to 95 degrees Fahrenheit;

(ii) Engine coolant temperature at the start of propulsion system active is greater than or equal to 40 degrees Fahrenheit but less than or equal to 95 degrees Fahrenheit; and

(iii) Continuous time while the vehicle is not in the state of 'propulsion system active' during the period immediately preceding the start of the driving cycle is greater than or equal to 6 hours.

* * * *

(5) *Standardized tracking and reporting of monitor performance.*

* * * *

(5.5) Ignition cycle counter

(5.5.1) Definition:

(A) The ignition cycle counter is defined as a counter that indicates the number of ignition cycles a vehicle has experienced as defined in section(s) (d)(5.5.2)(B) and (C).

(B) Except as required in section (d)(5.5.1)(C) below, the OBD II system shall report one ignition cycle counter (as defined in section (d)(5.5.2)(B)) ~~The ignition cycle counter shall be reported in accordance with the specifications in section (g)(5.2.1)~~.

(C) For 2014 and subsequent model year plug-in hybrid electric vehicles, the OBD II system shall report two ignition cycle counters (as defined in sections (d)(5.5.2)(B) and (C)).

(D) The ignition cycle counter(s) shall be reported in accordance with the specifications in section (g)(5.2.1).

(5.5.2) Specifications for incrementing:

(A) The ignition cycle counter(s), when incremented, shall be incremented by an integer of one. The ignition cycle counter(s) may not be incremented more than once per driving cycle.

(B) The ignition cycle counter shall be incremented within ten seconds if and only if the following criteria are met:

(i) Except as required in section (d)(5.5.2)(B)(ii) below, the vehicle meets the engine start definition (see section (c)) for at least two seconds plus or minus one second.

(ii) For hybrid vehicles, the vehicle meets the propulsion system active definition (see section (c)) for at least two seconds plus or minus one second.

(C) In addition to the counter described in section (d)(5.5.2)(B) above, 2014 and subsequent model year plug-in hybrid electric vehicles shall track and report a second ignition cycle counter that shall be incremented within ten seconds if and only if the vehicle has met the fueled engine operation definition (see section (c)) for at least two seconds plus or minus one second ~~The OBD II system shall disable further incrementing of the ignition cycle counter within ten seconds if a malfunction of any component used to determine if the criteria in section (d)(5.5.2)(B) are satisfied (i.e., engine speed or time of operation) has been detected and the corresponding pending fault code has been stored. The ignition cycle counter may not be disabled from incrementing for any other condition. Incrementing of the ignition cycle counter shall resume within ten seconds when the malfunction is no longer present (e.g., pending code erased through self-clearing or by a scan tool command)~~.

(D) The OBD II system shall disable further incrementing of the ignition cycle counter(s) within ten seconds if a malfunction of any component used to determine if the criteria in section (d)(5.5.2)(B) and (C) are satisfied (e.g., engine speed or time of operation) has been detected and the corresponding pending fault code has been stored. The ignition cycle counter(s) may not be disabled from incrementing for any other condition. Incrementing of the ignition cycle counter(s) shall resume within ten seconds when the malfunction is no longer present (e.g., pending code erased through self-clearing or by a scan tool command).

* * * *

(e) *Monitoring Requirements for Gasoline/Spark-Ignited Engines.*

* * * *

(3) *Misfire Monitoring*

* * * *

(3.3) Monitoring Conditions:

(3.3.1) Manufacturers shall continuously monitor for misfire under the following conditions:

(A) Except as provided in section (e)(3.3.6) below, f~~F~~rom no later than the end of the second crankshaft revolution after engine start,

* * * *

(3.3.6) For engines that employ engine shutoff strategies that do not require the vehicle operator to restart the engine to continue driving (e.g., hybrid vehicle with engine shutoff at idle), a manufacturer shall request Executive Officer approval of the monitoring conditions under which misfire monitoring occurs after engine fueling begins for the initial start and after each time fueling resumes. Executive Officer approval of the monitoring conditions shall be based on the equivalence of the conditions to those specified in section (e)(3.3.1)(A) above.

* * * *

(f) *Monitoring Requirements for Diesel/Compression-Ignition Engines.*

(1) *Non-Methane Hydrocarbon (NMHC) Converting Catalyst Monitoring*

* * * *

(1.2) Malfunction Criteria:

* * * *

(1.2.3) Other Aftertreatment Assistance Functions. Additionally, for 2010 and subsequent model year vehicles, the catalyst(s) shall be monitored for other aftertreatment assistance functions:

* * * *

(B) For 201~~0~~5 and subsequent model year passenger cars, light-duty trucks, and MDPVs certified to a chassis dynamometer tailpipe emission standard and 201~~3~~5 and subsequent model year medium-duty vehicles (including MDPVs) certified to an engine dynamometer tailpipe emission standard, for catalysts used to generate a feedgas constituency to assist SCR systems (e.g., to increase NO_2 concentration upstream of an SCR system), the OBD II system shall detect a malfunction when the catalyst is unable to generate the necessary feedgas constituents for proper SCR system operation.

* * * *

(9) *Particulate Matter (PM) Filter Monitoring*

* * * *

(9.2) Malfunction Criteria:

* * * *

(9.2.4) NMHC conversion: For 201~~0~~5 and subsequent model year passenger cars, light-duty trucks, and MDPVs certified to a chassis dynamometer tailpipe emission standard and 201~~3~~5 and subsequent model year medium-duty vehicles (including MDPVs) certified to an engine dynamometer tailpipe emission standard with catalyzed PM filters that convert NMHC emissions, the OBD II system shall monitor the catalyst function of the PM filter and

detect a malfunction when the NMHC conversion capability decreases to the point that NMHC emissions exceed the applicable emission levels specified in section (f)(9.2.2)(A). If no failure or deterioration of the NMHC conversion capability could result in a vehicle's NMHC emissions exceeding these emission levels, the OBD II system shall detect a malfunction when the system has no detectable amount of NMHC conversion capability.

* * * *

(15) *Comprehensive Component Monitoring*

* * * *

(15.2) Malfunction Criteria:

* * * *

(15.2.2) Output Components/Systems:

* * * *

(F) For ~~2013~~2015 and subsequent model year vehicles that utilize fuel control system components (e.g., injectors, fuel pump) that have tolerance compensation features implemented in hardware or software during production or repair procedures (e.g., individually coded injectors for flow characteristics that are programmed into an electronic control unit to compensate for injector to injector tolerances, fuel pumps that use in-line resistors to correct for differences in fuel pump volume output), the components shall be monitored to ensure the proper compensation is being used. The system shall detect a fault if the compensation being used by the control system does not match the compensation designated for the installed component (e.g., the flow characteristic coding designated on a specific injector does not match the compensation being used by the fuel control system for that injector). If a manufacturer demonstrates that a single component (e.g., injector) using the wrong compensation cannot cause a measurable increase in emissions during any reasonable driving condition, the manufacturer shall detect a malfunction for the minimum number of components using the wrong compensation needed to cause an emission increase. Further, the stored fault code shall identify the specific component that does not match the compensation.

* * * *

(17) *Exceptions to Monitoring Requirements*

(17.1) Except as provided in sections (f)(17.1.1) through (17.1.4) below, upon request of a manufacturer or upon the best engineering judgment of the ARB, the Executive Officer may revise the emission threshold for a malfunction on any diagnostic required in section (f) for medium-duty vehicles if the most reliable monitoring method developed requires a higher threshold to prevent significant errors of commission in detecting a malfunction. Additionally, for 2007 through ~~2009~~2013 model year light-duty vehicles and 2007 through ~~2012~~ 2013 model year medium-duty vehicles, the Executive Officer may revise the PM

filter malfunction criteria of section (f)(9.2.1) to exclude detection of specific failure modes (e.g., combined failure of partially melted and partially cracked substrates) if the most reliable monitoring method developed requires the exclusion of specific failure modes to prevent significant errors of commission in detecting a malfunction.

* * * *

(g) *Standardization Requirements*

(1) *Reference Documents:*
The following Society of Automotive Engineers (SAE) and International Organization for Standardization (ISO) documents are incorporated by reference into this regulation:

* * * *

(1.4) SAE J1979 "E/E Diagnostic Test Modes", May 2007 (SAE J1979).
(1.4.1) SAE J1979-DA, "Digital Annex of E/E Diagnostic Test Modes", October 2011.

* * * *

(4) *Required Emission Related Functions:*
The following standardized functions shall be implemented in accordance with the specifications in SAE J1979 to allow for access to the required information by a scan tool meeting SAE J1978 specifications:

* * * *

(4.2) Data Stream: The following signals shall be made available on demand through the standardized data link connector in accordance with SAE J1979 specifications. The actual signal value shall always be used instead of a default or limp home value.

* * * *

(4.2.6) Additionally, for all 2013 and subsequent model year vehicles so equipped:
(A) EGR temperature, variable geometry turbo control status (e.g., open loop, closed loop), reductant level (e.g., urea tank fill level), alcohol fuel percentage, ~~type of fuel currently being used,~~ NOx adsorber regeneration status, NOx adsorber deSOx status, hybrid battery pack remaining charge; and
(B) ~~PM sensor output and~~ distance traveled while low/empty SCR reductant driver warning/inducement active.
(4.2.7) Additionally, for all 2015 and subsequent model year vehicles: type of fuel currently being used.

(4.3) Freeze Frame.

* * * *

(4.3.2) "Freeze frame" conditions must include the fault code which caused the data to be stored and all of the signals required in section (g)(4.2.1) except number of stored confirmed fault codes, OBD requirements to which the engine is certified, MIL status, and absolute throttle position in accordance with (g)(4.3.3). Freeze frame conditions shall also include all of the signals required on the

vehicle in sections (g)(4.2.2) through (g)(4.2.5)(D), (g)(4.2.5)(F), ~~and~~ (g)(4.2.6)(A), and (g)(4.2.7) that are used for diagnostic or control purposes in the specific diagnostic or emission-critical powertrain control unit that stored the fault code except: oxygen sensor output, air/fuel ratio sensor output, catalyst temperature, evaporative system vapor pressure, glow plug lamp status, PM sensor output, NOx sensor output, monitor status since last engine shut off, distance traveled while MIL activated, distance traveled since fault memory last cleared, and number of warm-up cycles since fault memory last cleared.

* * * *

(k) ***Deficiencies***

* * * *

(2) Manufacturers of non-complying systems are subject to fines pursuant to section 43016 of the California Health and Safety Code. Except as allowed in section (k)(7) for light-duty and medium-duty diesel vehicles, the specified fines apply to the third and subsequently identified deficiencies, with the exception that fines shall apply to all monitoring system deficiencies wherein a required monitoring strategy is completely absent from the OBD system.

* * * *

(4) Manufacturers must re-apply for Executive Officer approval of a deficiency each model year. In considering the request to carry-over a deficiency, the Executive Officer shall consider the factors identified in section (k)(1) including the manufacturer's progress towards correcting the deficiency. For all deficiencies except for deficiencies associated with PM filter monitoring section (f)(9.2.1)(A), t~~T~~he Executive Officer may not allow manufacturers to carry over monitoring system deficiencies for more than two model years unless it can be demonstrated that substantial vehicle hardware modifications and additional lead time beyond two years would be necessary to correct the deficiency, in which case the Executive Officer shall allow the deficiency to be carried over for three model years. For deficiencies associated with PM filter monitoring section (f)(9.2.1)(A), if the manufacturer can demonstrate that substantial vehicle hardware modifications and additional lead time would be necessary to correct the deficiency, the Executive shall allow the deficiency to be carried over up to and including the 2013 model year.

* * * *

(7) Exceptions to Fines Requirements.

(7.1) For 2007 through 2009 model year light-duty and 2007 through 2012 model year medium-duty diesel vehicles, in cases where one or more of the deficiencies is for the aftertreatment monitoring requirements of sections (f)(1), (2), (8), or (9) and the deficient monitor is properly able to detect all malfunctions prior to emissions exceeding twice the required monitor threshold (e.g., before emissions exceed 10 times the

standard for NMHC if the threshold is 5.0 times the standard for NMHC), the specified fines shall apply to the fourth and subsequently identified deficiencies in lieu of the third and subsequently identified deficiencies. If none of the deficiencies are for the requirements of sections (f)(1), (2), (8), or (9) or if the deficient aftertreatment monitor exceeds twice the required monitor threshold, the specified fines shall apply to the third and subsequently identified deficiencies. In all cases, the exception that fines shall apply to all monitoring system deficiencies wherein a required monitoring strategy is completely absent from the OBD system still applies.

(7.2) For 2013 through 2014 model year light-duty and medium-duty diesel vehicles that utilize PM sensors for PM filter filtering performance monitoring (section (f)(9.2.1)(A)), in cases where the deficiency is for a monitor required to detect malfunctions of the PM filter filtering performance (section (f)(9.2.1)(A)), the PM sensor (section (f)(5.2.2)), or the PM sensor heater (section (f)(5.2.4)), the deficiency shall be exempt from the specified fines of section (k)(3) and the deficiency shall not be included in the count of deficiencies used in (k)(2) to determine the number of deficiencies subject to fines.

* * * *

NOTE: Authority cited: Sections 39600, 39601, 43000.5, 43013, 43018, 43100, 43101, 43104, 43105, 43105.5 and 43106, Health and Safety Code. Reference: Sections 39002, 39003, 39010, 39018, 39021.5, 39024, 39024.5, 39027, 39027.3, 39028, 39029, 39031, 39032, 39032.5, 39033, 39035, 39037.05, 39037.5, 39038, 39039, 39040, 39042, 39042.5, 39046, 39047, 39053, 39054, 39058, 39059, 39060, 39515, 39600-39601, 43000, 43000.5, 43004, 43006, 43013, 43016, 43018, 43100, 43101, 43102, 43104, 43105, 43105.5, 43106, 43150, 43151, 43152, 43153, 43154, 43155, 43156, 43204, 43211, and 43212, Health and Safety Code.

10. Amend title 13, CCR, section 1968.5 to read as follows:

§1968.5. Enforcement of Malfunction and Diagnostic System Requirements for 2004 and Subsequent Model-Year Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles and Engines.

* * * *

(b) ***Testing Procedures***

* * * *

(6) *Finding of Nonconformance after Enforcement Testing.*
After conducting enforcement testing pursuant to section (b)(4) above, the Executive Officer shall make a finding of nonconformance of the OBD II system in the identified motor vehicle class if:

* * * *

(B) *OBD II Ratio Testing.*

(i) For monitors specified in sections (b)(6)(B)(i)a. through e. below, the data collected from the vehicles in the test sample indicate either that the average in-use monitor performance ratio for one or more of the monitors in the test sample group is less than 0.100 or that 66.0 percent or more of the vehicles in the test sample group have an in-use monitor performance ratio of less than 0.100 for the same monitor:

a. monitors on 2004 through ~~2014~~2016 model year vehicles certified to a ratio of 0.100 in accordance with title 13, CCR section 1968.2(d)(3.2.1)-(D),

b. monitors specified in title 13, CCR section 1968.2(e) on 2007 through 2012 model year vehicles for the first three model years the monitor is certified to the in-use performance ratio monitoring requirements of title 13, CCR sections 1968.2(d)(3.2.1)(A) through (C),

c. the fuel system air-fuel ratio cylinder imbalance monitor specified in title 13, CCR section 1968.2(e)(6.2.1)(C) on 2015 through 2017 model year vehicles,

d. the secondary exhaust gas sensor monitor specified in title 13, CCR section 1968.2(e)(7.2.2)(C) on 2012 through 2014 model year vehicles, and

e. monitors specified in title 13, CCR section 1968.2(f) on 2013 through 2015 model year vehicles.

(ii) For monitors that are certified to the ratios in title 13, CCR sections 1968.2(d)(3.2.1)(A) through (C) and are not described in sections (b)(6)(B)(i)b. through e. above, the data collected

from the vehicles in the test sample indicate either that 66.0 percent or more of the vehicles in the test sample group have an in-use monitor performance ratio of less than the required minimum ratio defined in title 13, CCR section 1968.2(d)(3.2.1) for the same monitor or that the average in-use monitor performance ratio for one or more of the monitors in the motor vehicle class is less than the required minimum ratio defined in title 13, CCR section 1968.2(d)(3.2.1) as defined by determining the average in-use monitor performance ratio for one or more of the monitors in the test sample group is less than:

a. 0.230 for secondary air system monitors and other cold start related monitors utilizing a denominator incremented in accordance with title 13, CCR section 1968.2(d)(4.3.2)(E) (e.g., cold start strategy monitors, etc.);
b. For evaporative system monitors:
   1. 0.230 for monitors designed to detect malfunctions identified in title 13, CCR section 1968.2(e)(4.2.2)(C) (i.e., 0.020 inch leak detection);
   2. 0.460 for monitors designed to detect malfunctions identified in title 13, CCR section 1968.2(e)(4.2.2)(A) and (B) (i.e., purge flow and 0.040 inch leak detection);
c. 0.297 for catalyst, oxygen sensor, EGR, VVT system, and all other monitors specifically required in section title 13, CCR sections 1968.2(e) and (f) to meet the monitoring condition requirements of title 13, CCR section 1968.2(d)(3.2).

* * * *

(c) *Remedial Action*

* * * *

(3) *Ordered Remedial Action-Mandatory Recall.*

(A) Except as provided in sections (c)(3)(B) below, the Executive Officer shall order the recall and repair of all vehicles in a motor vehicle class that have been determined to be equipped with a nonconforming OBD II system if enforcement testing conducted pursuant to section (b) above or information received from the manufacturer indicates that:

(i) For monitors on 2007 and subsequent model year vehicles certified to the ratios in title 13, CCR sections 1968.2(d)(3.2.1)(A) through (C), the average in-use monitor performance ratio for one or more of the major monitors in the test sample group is less than or equal to 33.0 percent of the applicable required minimum ratio established in title 13, CCR section 1968.2(d)(3.2.1) (e.g., if the required ratio is 0.336, less

than or equal to a ratio of 0.111) or 66.0 percent or more of the vehicles in the test sample group have an in-use monitor performance ratio of less than or equal to 33.0 percent of the applicable required minimum ratio established in title 13, CCR section 1968.2(d)(3.2.1) for the same major monitor. For monitors on 2004 through ~~2014~~2016 model year vehicles certified to the 0.100 ratio in title 13, CCR section 1968.2(d)(3.2.1)(D), the Executive Officer shall determine the remedial action for nonconformances regarding the in-use monitor performance ratio in accordance with section (c)(4) below.

* * * *

NOTE: Authority cited: Sections 39600, 39601, 43000.5, 43013, 43018, 43100, 43101, 43104, 43105, 43105.5 43106, 43154, 43211, and 43212, Health and Safety Code. Reference: Sections 39002, 39003, 39010, 39018, 39021.5, 39024, 39024.5, 39027, 39027.3, 39028, 39029, 39031, 39032, 39032.5, 39033, 39035, 39037.05, 39037.5, 39038, 39039, 39040, 39042, 39042.5, 39046, 39047, 39053, 39054, 39058, 39059, 39060, 39515, 39600-39601, 43000, 43000.5, 43004, 43006, 43013, 43016, 43018, 43100, 43101, 43102, 43104, 43105, 43105.5, 43106, 43150, 43151, 43152, 43153, 43154, 43155, 43156, 43204, 43211, and 43212, Health and Safety Code.

11. Amend title 13, CCR, section 1976 to read as follows:

§ 1976. Standards and Test Procedures for Motor Vehicle Fuel Evaporative Emissions.

(a) *[Fuel evaporative emission standards for 1970 through 1977 model passenger cars and light-duty trucks. No change.]*

(b)(1) Evaporative emissions for 1978 and subsequent model gasoline-fueled, 1983 and subsequent model liquefied petroleum gas-fueled, and 1993 and subsequent model alcohol-fueled motor vehicles and hybrid electric vehicles subject to exhaust emission standards under this article, except petroleum-fueled diesel vehicles, compressed natural gas-fueled vehicles, hybrid electric vehicles that have sealed fuel systems which can be demonstrated to have no evaporative emissions, and motorcycles, shall not exceed the following standards:

(A) *[Evaporative emission standards for 1978 through 1994 model motor vehicles. No change.]*

(B) *[Evaporative emission standards on the three-day diurnal test for 1995 through 2005 model motor vehicles. No change.]*

(C) *[Evaporative emission standards on the supplemental two-day diurnal test for 1995 through 2005 model motor vehicles. No change.]*

(D) *[Zero-emission vehicle evaporative requirements. No change.]*

(E) For 2001 through 2014 model year vehicles, ~~T~~the optional zero-fuel evaporative emission standards for the three-day and two-day diurnal-plus-hot-soak tests are 0.35 grams per test for passenger cars, 0.50 grams per test for light-duty trucks 6,000 lbs. GVWR and under, and 0.75 grams per test for light-duty trucks from 6,001 to 8,500 lbs. GVWR, to account for vehicle non-fuel evaporative emissions (resulting from paints, upholstery, tires, and other vehicle sources). Vehicles demonstrating compliance with these evaporative emission standards shall also have zero (0.0) grams of fuel evaporative emissions per test for the three-day and two-day diurnal-plus-hot-soak tests. The "useful life" shall be 15 years or 150,000 miles, whichever occurs first. In lieu of demonstrating compliance with the zero (0.0) grams of fuel evaporative emissions per test over the three-day and two-day diurnal-plus-hot-soak tests, the manufacturer may submit for advance Executive Officer approval a test plan to demonstrate that the vehicle has zero (0.0) grams of fuel evaporative emissions throughout its useful life.

Additionally, in the case of a SULEV vehicle for which a manufacturer is seeking a partial ZEV credit, the manufacturer may prior to certification elect to have

measured fuel evaporative emissions reduced by a specified value in all certification and in-use testing of the vehicle as long as measured mass exhaust emissions of NMOG for the vehicle are increased in all certification and in-use testing. The measured fuel evaporative emissions shall be reduced in increments of 0.1 gram per test, and the measured mass exhaust emissions of NMOG from the vehicle shall be increased by a gram per mile factor, to be determined by the Executive Officer, for every 0.1 gram per test by which the measured fuel evaporative emissions are reduced. For the purpose of this calculation, the evaporative emissions shall be measured, in grams per test, to a minimum of three significant figures.

(F) For the 2004 ~~and subsequent~~ through 2014 model motor vehicles identified below, tested in accordance with the test procedures described in Title 40, Code of Federal Regulations, sections 86.130-78 through 86.143-90 as they existed July 1, 1989 and as modified by the "California Evaporative Emission Standards and Test Procedures for 2001 and Subsequent Model Motor Vehicles" incorporated by reference in section 1976(c), the evaporative emission standards are:

Vehicle Type	*Hydrocarbon[1] Standards[2][3][4]*		
	Running Loss (grams per mile)	*Three Day Diurnal + Hot Soak (grams per test)*	*Two-Day Diurnal + Hot Soak (grams per test)*
Passenger cars	0.05	0.50	0.65
Light-duty trucks (under 8,501 lbs. GVWR)			
6,000 lbs. GVWR and under	0.05	0.65	0.85
6,001 - 8,500 lbs. GVWR	0.05	0.90	1.15
Medium-duty vehicles (8,501 - 14,000 lbs. GVWR)	0.05	1.00	1.25
Heavy-duty vehicles (over 14,000 lbs. GVWR)	0.05	1.00	1.25

1 Organic Material Hydrocarbon Equivalent for alcohol-fueled vehicles.

2 For all vehicles certified to these standards, the "useful life" shall be 15 years or 150,000 miles, whichever first occurs. Approval of vehicles which are not exhaust emission tested using a chassis dynamometer pursuant to section 1960.1 or 1961, title 13, California Code of Regulations shall be based on an engineering evaluation of the system and data submitted by the applicant.

3 (a) These evaporative emission standards shall be phased-in beginning with the 2004 model year. Each manufacturer, except small volume manufacturers, shall certify at a minimum the specified percentage of its vehicle fleet to the evaporative emission standards in this table or

the optional zero-evaporative emission standards in section 1976(b)(1)(E) according to the schedule set forth below. For purposes of this paragraph (a), each manufacturer's vehicle fleet consists of the total projected California sales of the manufacturer's gasoline-fueled, liquefied petroleum-fueled and alcohol-fueled passenger cars, light-duty trucks, medium-duty vehicles, and heavy-duty vehicles.

Model Year	*Minimum Percentage of Vehicles Certified to the Standards in §§1976(b)(1)(F) and (b)(1)(E)*
2004	40
2005	80
2006 and subsequent	100

A small volume manufacturer shall certify 100 percent of its 2006 and subsequent model vehicle fleet to the evaporative emission standards in the table or the optional zero-evaporative emission standards in section 1976(b)(1)(E).

All 2004 through 2005 model-year motor vehicles which are not subject to these standards or the standards in section 1976(b)(1)(E) pursuant to the phase-in schedule shall comply with the requirements of sections 1976(b)(1)(B) and (C).

(b) A manufacturer may use an "Alternative or Equivalent Phase-in Schedule" to comply with the phase-in requirements. An "Alternative Phase-in" is one that achieves at least equivalent emission reductions by the end of the last model year of the scheduled phase-in. Model-year emission reductions shall be calculated by multiplying the percent of vehicles (based on the manufacturer's projected California sales volume of the applicable vehicle fleet) meeting the new requirements per model year by the number of model years implemented prior to and including the last model year of the scheduled phase-in. The "cumulative total" is the summation of the model-year emission reductions (e.g., the three model-year 40/80/100 percent phase-in schedule would be calculated as: (40%*3 years) + (80%*2 years) + (100%*1 year) =380). The required cumulative total for the phase-in of these standards is 380 emission reductions. Any alternative phase-in that results in an equal or larger cumulative total than the required cumulative total by the end of the last model year of the scheduled phase-in shall be considered acceptable by the Executive Officer only if all vehicles subject to the phase-in comply with the respective requirements in the last model year of the required phase-in schedule. A manufacturer shall be allowed to include vehicles introduced before the first model year of the scheduled phase-in (e.g., in the previous example, 10 percent introduced one year before the scheduled phase-in begins would be calculated as: (10%*4 years)=40) and added to the cumulative total.

(c) These evaporative emission standards do not apply to zero-emission vehicles.

[4] In-use compliance whole vehicle testing shall not begin until the motor vehicle is at least one year from the production date and has accumulated a minimum of 10,000 miles. For vehicles introduced prior to the 2007 model year, in-use compliance standards of 1.75 times the "Three-Day Diurnal + Hot-Soak" and "Two-Day Diurnal + Hot-Soak" gram per test standards shall apply for only the first three model years of an evaporative family certified to a new standard.

(G) For 2015 and subsequent model motor vehicles, the following evaporative emission requirements apply:

1. A manufacturer must certify all vehicles subject to this section to the emission standards specified in either Option 1 or Option 2 below.

a. *Option 1.* The evaporative emissions from 2015 and subsequent model motor vehicles, tested in accordance with the test procedure sequence described in the "California Evaporative Emission Standards and Test Procedures for 2001 and Subsequent Model Motor Vehicles," incorporated by reference in section 1976(c), shall not exceed:

Vehicle Type	*Hydrocarbon[1] Emission Standards[2]*		
	Running Loss (grams per mile)	*Three-Day Diurnal + Hot Soak and Two-Day Diurnal + Hot Soak*	
		Whole Vehicle (grams per test)	*Fuel Only[3] (grams per test)*
Passenger cars	0.05	0.350	0.0
Light-duty trucks 6,000 lbs. GVWR and under	0.05	0.500	0.0
Light-duty trucks 6,001 - 8,500 lbs. GVWR	0.05	0.750	0.0
Medium-duty passenger vehicles	0.05	0.750	0.0
Medium-duty vehicles (8,501 - 14,000 lbs. GVWR);	0.05	0.750	0.0
Heavy-duty vehicles (over 14,000 lbs. GVWR)	0.05	0.750	0.0

1 Organic Material Hydrocarbon Equivalent for alcohol-fueled vehicles.

2 For all vehicles certified to these standards, the "useful life" shall be 15 years or 150,000 miles, whichever occurs first. Approval of vehicles that are not exhaust emission tested using a chassis dynamometer pursuant to section 1961, title 13, California Code of Regulations shall be based on an engineering evaluation of the system and data submitted by the applicant.

3 In lieu of demonstrating compliance with the fuel-only emission standard (0.0 grams per test) over the three-day and two-day diurnal plus hot soak tests, a manufacturer may, with advance Executive Officer approval, demonstrate compliance through an alternate test plan.

b. *Option 2.* The evaporative emissions from 2015 and subsequent model motor vehicles, tested in accordance with the test

procedure sequence described in the "California Evaporative Emission Standards and Test Procedures for 2001 and Subsequent Model Motor Vehicles," incorporated by reference in section 1976(c), shall not exceed:

Vehicle Type	*Hydrocarbon[1] Emission Standards[2]*		
	Running Loss (grams per mile)	*Highest Whole Vehicle Diurnal + Hot Soak[3][4][5] (grams per test)*	*Canister Bleed[6] (grams per test)*
Passenger cars; and Light-duty trucks 6,000 lbs. GVWR and under, and 0 - 3,750 lbs. LVW	0.05	0.300	0.020
Light-duty trucks 6,000 lbs. GVWR and under, and 3,751 – 5,750 lbs. LVW	0.05	0.400	0.020
Light-duty trucks 6,001 - 8,500 lbs. GVWR; and Medium-duty passenger vehicles	0.05	0.500	0.020
Medium-duty vehicles (8,501 - 14,000 lbs. GVWR); and Heavy-duty vehicles (over 14,000 lbs. GVWR)	0.05	0.600	0.030

1 Organic Material Hydrocarbon Equivalent for alcohol-fueled vehicles.

2 For vehicles certified to the running loss and the highest whole vehicle diurnal plus hot soak emission standards, the "useful life" shall be 15 years or 150,000 miles, whichever occurs first. Approval of vehicles that are not exhaust emission tested using a chassis dynamometer pursuant to section 1961, title 13, California Code of Regulations shall be based on an engineering evaluation of the system and data submitted by the applicant. The canister bleed emission standard does not have a useful life requirement.

3 The manufacturer shall determine compliance by selecting the highest whole vehicle diurnal plus hot soak emission value of the Three-Day Diurnal Plus Hot Soak Test and of the Two-Day Diurnal Plus Hot Soak Test.

4 *Fleet-Average Option for the Highest Whole Vehicle Diurnal Plus Hot Soak Emission Standard Within Each Emission Standard Category.* A manufacturer may optionally comply with the highest whole vehicle diurnal plus hot soak emission standards by using fleet-average hydrocarbon emission values. To participate, a manufacturer must utilize the fleet-average option for all of its emission standard categories and calculate a separate fleet-average hydrocarbon emission value for each emission standard category. The

emission standard categories are as follows: (1) passenger cars and light-duty trucks 6,000 pounds GVWR and under, and 0 - 3,750 pounds LVW; (2) light-duty trucks 6,000 pounds GVWR and under, and 3,751 – 5,750 pounds LVW; (3) light-duty trucks 6,001 - 8,500 pounds GVWR and medium-duty passenger vehicles; and (4) medium-duty and heavy-duty vehicles. The fleet-average hydrocarbon emission value for each emission standard category shall be calculated as follows:

$$\frac{\sum_{i=1}^{n}\left[(\text{number of vehicles in the evaporative family})_i \times (\text{family emission limit})_i\right]}{\sum_{i=1}^{n}(\text{number of vehicles in the evaporative family})_i}$$

where "n" = a manufacturer's total number of Option 2 certification evaporative families within an emission standard category for a given model year;

"number of vehicles in the evaporative family" = the number of vehicles produced and delivered for sale in California in the evaporative family;

"family emission limit" = the numerical value selected by the manufacturer for the evaporative family that serves as the emission standard for the evaporative family with respect to all testing, instead of the emission standard specified in this section 1976 (b)(1)(G)1.b. The family emission limit shall not exceed 0.500 grams per test for passenger cars; 0.650 grams per test for light duty trucks 6,000 pounds GVWR and under; 0.900 grams per test for light-duty trucks 6,001 - 8,500 pounds GVWR; and 1.000 grams for medium-duty passenger vehicles, medium-duty vehicles, and heavy-duty vehicles. In addition, the family emission limit shall be set in increments of 0.025 grams per test.

5 *Calculation of Hydrocarbon Credits or Debits for the Fleet-Average Option.*

(1) *Calculation of Hydrocarbon Credits or Debits.* For each emission standard category in the model year, a manufacturer shall calculate the hydrocarbon credits or debits, as follows:

[(Applicable Hydrocarbon Emission Standard for the Emission Standard Category) – (Manufacturer's Fleet-Average Hydrocarbon Emission Value for the Emission Standard Category)] X (Total Number of Affected Vehicles)

where "Total Number of Affected Vehicles" = the total number of vehicles in the evaporative families participating in the fleet-average option, which are produced and delivered for sale in California, for the emission standard category of the given model year.

A negative number constitutes hydrocarbon debits, and a positive number constitutes hydrocarbon credits accrued by the manufacturer for the given model year. Hydrocarbon credits earned in a given model year shall retain full value through the fifth model year after they are earned. At the beginning of the sixth model year, the hydrocarbon credits will have no value.

(2) *Procedure for Offsetting Hydrocarbon Debits.* A manufacturer shall offset hydrocarbon debits with hydrocarbon credits for each emission standard category within three model years after the debits have been incurred. If total hydrocarbon debits are not equalized within three

model years after they have been incurred, the manufacturer shall be subject to the Health and Safety Code section 43211 civil penalties applicable to a manufacturer which sells a new motor vehicle that does not meet the applicable emission standards adopted by the state board. The cause of action shall be deemed to accrue when the hydrocarbon debits are not equalized by the end of the specified time period. For the purposes of Health and Safety Code section 43211, the number of vehicles not meeting the state board's emission standards shall be determined by dividing the total amount of hydrocarbon debits for the model year in the emission standard category by the applicable hydrocarbon emission standard for the model year in which the debits were first incurred.

Additionally, a manufacturer may use the excess hydrocarbon credits from the emission standard categories of (1) passenger cars and light-duty trucks 6,000 pounds GVWR and under, and 0 - 3,750 pounds LVW and (2) light-duty trucks 6,000 pounds GVWR and under, and 3,751 – 5,750 pounds LVW to equalize the hydrocarbon debits that remain at the end of the three model year offset period of any emission standard category.

6 *Vehicle Canister Bleed Emission.* Compliance with the canister bleed emission standard shall be determined based on the Bleed Emission Test Procedure described in the "California Evaporative Emission Standards and Test Procedures for 2001 and Subsequent Model Motor Vehicles," incorporated by reference in section 1976(c), and demonstrated on a stabilized canister system. Vehicles with a non-integrated refueling canister-only system are exempt from the canister bleed emission standard.

2. *Phase-In Schedule.* For each model year, a manufacturer shall certify, at a minimum, the specified percentage of its vehicle fleet to the evaporative emission standards set forth in section 1976(b)(1)(G)1.a. or section 1976(b)(1)(G)1.b., according to the schedule set forth below. For the purpose of this section 1976(b)(1)(G)2., the manufacturer's vehicle fleet consists of the vehicles produced and delivered for sale by the manufacturer in California that are subject to the emission standards in section 1976(b)(1)(G)1. All 2015 through 2022 model motor vehicles that are not subject to these standards pursuant to the phase-in schedule shall comply with the requirements for 2004 through 2014 model motor vehicles, as described in section 1976(b)(1)(F).

Model Years	*Minimum Percentage of Vehicle Fleet* [1][2]
2015, 2016, and 2017	Average of vehicles certified to section 1976(b)(1)(E) in model years 2012, 2013, and 2014[3]
2018 and 2019	60
2020 and 2021	80
2022 and subsequent	100

1 For the 2018 through 2022 model years only, a manufacturer may use an alternate phase-in schedule to comply with the phase-in requirements. An alternate phase-in schedule must achieve equivalent compliance volume by the end of the last model year of the scheduled phase-in (2022). The compliance volume is the number calculated by multiplying the percent of vehicles (based on the manufacturer's projected sales volume of all vehicles) meeting the new requirements in each model year by the number of years implemented prior to and

including the last model year of the scheduled phase-in, then summing these yearly results to determine a cumulative total. The cumulative total of the five year (60/60/80/80/100) scheduled phase-in set forth above is calculated as follows: (60*5 years) + (60*4 years) + (80*3 years) + (80*2 years) + (100*1 year) = 1040. Accordingly, the required cumulative total for any alternate phase-in schedule of these emission standards is 1040. The Executive Officer shall consider acceptable any alternate phase-in schedule that results in an equal or larger cumulative total by the end of the last model year of the scheduled phase-in (2022).

[2] Small volume manufacturers are not required to comply with the phase-in schedule set forth in this table. Instead, they shall certify 100 percent of their 2022 and subsequent model year vehicle fleet to the evaporative emission standards set forth in section 1976(b)(1)(G)1.a. or section 1976(b)(1)(G)1.b.

[3] The minimum percentage required in the 2015, 2016, and 2017 model years is determined by averaging the percentage of vehicles certified to the emission standards in section 1976(b)(1)(E) in each of the manufacturer's 2012, 2013, and 2014 model year vehicle fleets. For the purpose of calculating this average, a manufacturer shall use the percentage of vehicles produced and delivered for sale in California for the 2012 and 2013 model years, and the percentage of projected sales in California for the 2014 model year.

3. *Carry-Over of 2014 Model-Year Evaporative Families Certified to the Zero-Fuel Evaporative Emission Standards.* A manufacturer may carry over 2014 model motor vehicles certified to the zero-fuel (0.0 grams per test) evaporative emission standards set forth in section 1976(b)(1)(E) through the 2018 model year and be considered compliant with the requirements of section 1976(b)(1)(G)1. If the manufacturer chooses to participate in the fleet-average option for the highest whole vehicle diurnal plus hot soak emission standard, the following family emission limits are assigned to these evaporative families for the calculation of the manufacturer's fleet-average hydrocarbon emission value.

Vehicle Type	*Highest Whole Vehicle Diurnal + Hot Soak (grams per test)*
Passenger cars	0.300
Light-duty trucks 6,000 lbs. GVWR and under, and 0 - 3,750 lbs. LVW	0.300
Light-duty trucks 6,000 lbs. GVWR and under, and 3,751 – 5,750 lbs. LVW	0.400
Light-duty trucks 6,001 - 8,500 lbs. GVWR	0.500

4. *Pooling Provision.* The following pooling provision applies to the fleet-average option for the Highest Whole Vehicle Diurnal Plus Hot Soak

Emission Standard in section 1976(b)(1)(G)1.b. and to the phase-in requirements in section 1976(b)(1)(G)2.

a. For the fleet-average option set forth in section 1976(b)(1)(G)1.b., a manufacturer must demonstrate compliance, for each model year, based on one of two options applicable throughout the model year, either:

Pooling Option 1: the total number of passenger cars, light-duty trucks, medium-duty passenger vehicles, medium-duty vehicles, and heavy-duty vehicles that are certified to the California evaporative emission standards in section 1976(b)(1)(G)1.b., and are produced and delivered for sale in California; or

Pooling Option 2: the total number of passenger cars, light-duty trucks, medium-duty passenger vehicles, medium-duty vehicles, and heavy-duty vehicles that are certified to the California evaporative emission standards in section 1976(b)(1)(G)1.b., and are produced and delivered for sale in California, the District of Columbia, and all states that have adopted California's evaporative emission standards set forth in section 1976(b)(1)(G)1. for that model year pursuant to section 177 of the federal Clean Air Act (42 U.S.C. § 7507).

b. For the phase-in requirements in section 1976(b)(1)(G)2., a manufacturer must demonstrate compliance, for each model year, based on one of two options applicable throughout the model year, either:

Pooling Option 1: the total number of passenger cars, light-duty trucks, medium-duty passenger vehicles, medium-duty vehicles, and heavy-duty vehicles that are certified to the California evaporative emission standards in section 1976(b)(1)(G)1., and are produced and delivered for sale in California; or

Pooling Option 2: the total number of passenger cars, light-duty trucks, medium-duty passenger vehicles, medium-duty vehicles, and heavy-duty vehicles that are certified to the California evaporative emission standards in section 1976(b)(1)(G)1., and are produced and delivered for sale in California, the District of Columbia, and all states that have adopted California's evaporative emission standards set forth in section 1976(b)(1)(G)1. for that model year pursuant to section 177 of the federal Clean Air Act (42 U.S.C. § 7507).

c. A manufacturer that selects Pooling Option 2 must notify the Executive Officer of that selection in writing prior to the start of the applicable model year or must comply with Pooling Option 1.

d. When a manufacturer is demonstrating compliance using Pooling Option 2 for a given model year, the term "in California" as used

in section 1976(b)(1)(G) means California, the District of Columbia, and all states that have adopted California's evaporative emission standards for that model year pursuant to Section 177 of the federal Clean Air Act (42 U.S.C. § 7507).

e. A manufacturer that selects Pooling Option 2 must provide to the Executive Officer separate values for the number of vehicles produced and delivered for sale in the District of Columbia and for each individual state within the average.

(b)(2) *[Evaporative emission standards for gasoline-fueled motorcycles. No change.]*

(c) The test procedures for determining compliance with the standards in subsection (b) above applicable to 1978 through 2000 model year vehicles are set forth in "California Evaporative Emission Standards and Test Procedures for 1978-2000 Model Motor Vehicles," adopted by the state board on April 16, 1975, as last amended August 5, 1999, which is incorporated herein by reference. The test procedures for determining compliance with standards applicable to 2001 and subsequent model year vehicles are set forth in the "California Evaporative Emission Standards and Test Procedures for 2001 and Subsequent Model Motor Vehicles," adopted by the state board on August 5, 1999, and as last amended ~~September 27, 2010~~ [INSERT DATE OF AMENDMENT], which is incorporated herein by reference.

(d) *[Motorcycle requirements. No change.]*

(e) *[Motorcycle requirements. No change.]*

(f) *Definitions Specific to this Section.*

(1) and (2) *[No change].*

(3) "Non-integrated refueling emission control system" is defined in 40 Code of Federal Regulations §86.1803-01.

(4) "Non-integrated refueling canister-only system" means a subclass of a non-integrated refueling emission control system, where other non-refueling related evaporative emissions from the vehicle are stored in the fuel tank, instead of in a vapor storage unit(s).

Note: Authority cited: Sections 39500, 39600, 39601, 39667, 43013, 43018, 43101, 43104, 43105, 43106 and 43107, Health and Safety Code. Reference: Sections 39002, 39003, 39500, 39667, 43000, 43009.5, 43013, 43018, 43100, 43101, 43101.5, 43102, 43104, 43105, 43106, 43107, 43204 and 43205 Health and Safety Code.

12. Amend title 13, CCR, section 1978 to read as follows:

§1978. Standards and Test Procedures for Vehicle Refueling Emissions.

(a)(1) Vehicle refueling emissions for 1998 and subsequent model gasoline-fueled, alcohol-fueled, diesel-fueled, liquefied petroleum gas-fueled, fuel-flexible, and hybrid electric passenger cars, light-duty trucks, and medium-duty vehicles with a gross vehicle weight rating less than 8501 pounds, ~~shall not exceed the following standards.~~ and 2015 and subsequent model gasoline-fueled, alcohol-fueled, diesel-fueled, liquefied petroleum gas-fueled, fuel-flexible, and hybrid electric medium-duty vehicles with a gross vehicle weight rating between 8,501 and 14,000 pounds, shall not exceed the following standards. Natural gas-fueled vehicles are exempt from meeting these refueling standards, but the refueling receptacles on natural gas-fueled vehicles must comply with the receptacle provisions of the American National Standards Institute/American Gas Association Standard for Compressed Natural Gas Vehicle Fueling Connection Devices, ANSI/AGA NGV1 standard-1994, which is incorporated herein by reference. The standards apply equally to certification and in-use vehicles.

Hydrocarbons (for gasoline-fueled, diesel-fueled, and hybrid electric vehicles): 0.20 grams per gallon of fuel dispensed.

Organic Material Hydrocarbon Equivalent (for alcohol-fueled, fuel-flexible, and hybrid electric vehicles): 0.20 grams per gallon of fuel dispensed.

Hydrocarbons (for liquefied petroleum gas-fueled vehicles): 0.15 gram per gallon of fuel dispensed.

(2) Vehicles powered by diesel fuel are not required to conduct testing to demonstrate compliance with the refueling emission standards set forth above, provided that all of the following provisions are met:

(A) The manufacturer can attest to the following evaluation: "Due to the low vapor pressure of diesel fuel and the vehicle tank temperatures, hydrocarbon vapor concentrations are low and the vehicle meets the 0.20 grams/gallon refueling emission standard without a control system."

(B) The certification requirement described in paragraph (A) is provided in writing and applies for the full useful life of the vehicle, as defined in section 2112.

In addition to the above provisions, the ARB reserves the authority to require testing to enforce compliance and to prevent noncompliance with the refueling emission standard.

Vehicles certified to the refueling emission standard under this provision shall not be counted in the phase-in sales percentage compliance determinations.

(3) Through model year 2014, the~~The~~ manufacturer shall adhere to the following phase-in schedule, as determined by projected vehicle sales throughout the United States, with the exception of small volume manufacturers.

	ORVR Model Year Phase-In Schedule		
Class of Vehicle	*40% Fleet*	*80% Fleet*	*100% Fleet*
Passenger Cars	1998	1999	2000
Light-Duty Trucks 0-6,000 lbs. GVWR	2001	2002	2003
Light-Duty Trucks/ Medium-Duty Vehicles (6,001-8,500 lbs. GVWR)	2004	2005	2006

(A) Prior to the 2001 model year, small volume manufacturers are defined for purposes of this section as any vehicle manufacturer with California actual sales less than or equal to 3000 new vehicles per model year based on the average number of vehicles sold by the manufacturer in the previous three consecutive years.

(B) Small volume manufacturers of passenger cars, as defined in subsection (a)(3)(A), are exempt from the implementation schedule in subsection (a)(3) for model year 1998 and 1999. For small volume manufacturers of passenger cars, the standards of subsection (a)(1), and the associated test procedures, shall not apply until model year 2000, when 100 percent compliance with the standards of this section is required. Small volume manufacturers of light-duty trucks and medium-duty vehicles are not exempt from the implementation schedule in subsection (a)(3).

(4) Beginning with model year 2015, all vehicles subject to the refueling emission standards in section 1978(a)(1) shall demonstrate compliance except incomplete vehicles of 14,000 pounds gross vehicle weight rating or less that are optionally certified to complete heavy-duty vehicle standards under the provisions of 40 CFR §86.1801–01(c)(2).

(5) *Carry-Over of 2014 Model Year Families:* 2014 model year motor vehicles certified to the refueling emission standards of section 1978(a)(1) may carry over to the 2015 through 2018 model years and be considered compliant.

(b) The test procedures for determining compliance with standards applicable to 1998 through 2000 gasoline, alcohol, diesel, and hybrid electric passenger cars, light-duty trucks, and medium-duty vehicles are set forth in the "California

Refueling Emission Standards and Test Procedures for 1998-2000 Model Year Motor Vehicles," as amended August 5, 1999, which is incorporated herein by reference. The test procedures for determining compliance with standards applicable to 2001 and subsequent gasoline, alcohol, diesel, and hybrid electric passenger cars, light-duty trucks, and medium-duty vehicles are set forth in the "California Refueling Emission Standards and Test Procedures for 2001 and Subsequent Model Motor Vehicles," adopted August 5, 1999, and last amended ~~September 27, 2010~~][insert date of amendment for this rulemaking], which is incorporated herein by reference.

NOTE: Authority cited: Sections 39500, 39600, 39601, 39667, 43013, 43018, 43101, 43104, 43105, and 43106, Health and Safety Code. Reference: Sections 39002, 39003, 39500, 39667, 43000, 43009.5, 43013, 43018, 43100, 43101, 43101.5, 43102, 43104, 43105, 43106, 43204 and 43205, Health and Safety Code.

13. Amend title 13, CCR, section 2037 to read as follows:

§2037. Defects Warranty Requirements for 1990 and Subsequent Model Passenger Cars, Light-Duty Trucks, Medium-Duty Vehicles, and Motor Vehicle Engines Used in Such Vehicles.

* * * *

(g) Prior to the 2001 model year, each manufacturer shall submit the documents required by sections (c)(5), (e), and (f) with the manufacturer's preliminary application for new vehicle or engine certification for approval by the Executive Officer. For 2001 and subsequent model years, each manufacturer shall submit the documents required by section (c)(5), (e), and (f) with the Part 2 Application for Certification pursuant to the "California 2001 through 2014 Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and ~~for~~ 2009 through 2016 ~~and Subsequent~~ Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," incorporated by reference in title 13, CCR section 1961(d), or the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," incorporated by reference in title 13, CCR section 1961.2(d), as applicable. The Executive Officer may reject or require modification of any of the documents required by sections (c), (e), and (f) for, among other reasons, incompleteness and lack of clarity. Approval by the Executive Officer of the documents required by sections (c), (e), and (f) shall be a condition of certification. The Executive Officer shall approve or disapprove the documents required by sections (c), (e), and (f) within 90 days of the date such documents are received from the manufacturer. Any disapproval shall be accompanied by a statement of the reasons thereof. In the event of disapproval, the manufacturer may petition the Board to review the decision of the Executive Officer.

* * * *

NOTE: Authority cited: Sections 39600 and 39601, Health and Safety Code. Reference: Sections 43106, 43204, 43205, 44004, 44010, 44011, 44012, 44015, and 44017, Health and Safety Code.

14. Amend title 13, CCR, section 2038, to read as follows:

§2038. Performance Warranty Requirements for 1990 and Subsequent Model Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles, and Motor Vehicle Engines Used in Such Vehicles

* * * *

(c) *Written Instructions.*

* * * *

(3) For 2001 and subsequent model years, each vehicle or engine manufacturer shall submit the documents required by section (c)(1) with the Part 2 Application for Certification pursuant to the "California 2001 through 2014 Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and ~~for~~ 2009 through 2016 ~~and Subsequent~~ Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," incorporated by reference in title 13, CCR section 1961(d), or the "California 2015 and Subsequent Model Criteria Pollutant Exhaust Emission Standards and Test Procedures and 2017 and Subsequent Model Greenhouse Gas Exhaust Emission Standards and Test Procedures for Passenger Cars, Light-Duty Trucks, and Medium-Duty Vehicles," incorporated by reference in title 13, CCR section 1961.2(d), as applicable.

* * * *

NOTE: Authority cited: Sections 39600 and 39601, Health and Safety Code. Reference: Sections 43106, 43204, 43205, 44004, 44010, 44011, 44012, 44014, and 44015, Health and Safety Code.

15. Amend title 13, CCR, section 2062 to read as follows:

§2062. Assembly-Line Test Procedures - 1998 and Subsequent Model Years.

New 1998 through 2000 model-year passenger cars, light-duty trucks, and medium-duty vehicles, subject to certification and manufactured for sale in California, except for zero-emission vehicles and medium-duty vehicles certified according to the optional standards and test procedures of Section 1956.8, Title 13, California Code of Regulations, shall be tested in accordance with the "California Assembly-Line Test Procedures for 1998 through 2000 Model-Year Passenger Cars, Light-Duty Trucks and Medium-Duty Vehicles," adopted June 24, 1996, as last amended August 5, 1999, which is incorporated herein by reference. New 2001 and subsequent model-year passenger cars, light-duty trucks, and medium-duty vehicles, subject to certification and manufactured for sale in California, except for zero-emission vehicles and medium-duty vehicles certified according to the optional standards and test procedures of Section 1956.8, Title 13, California Code of Regulations, shall be tested in accordance with the "California Assembly-Line Test Procedures for 2001 and Subsequent Model-Year Passenger Cars, Light-Duty Trucks and Medium-Duty Vehicles." adopted August 5, 1999, which is incorporated herein by reference. These test procedures shall also apply to federally certified light-duty motor vehicles, except as provided in "Guidelines for Certification of 1983 ~~and Subsequent~~ Through 2002 Model-Year Federally Certified Light-Duty Motor Vehicles for Sale in California," adopted July 20, 1982, as last amended ~~July 12, 1991~~ July 30, 2002, and the "Guidelines for Certification of 2003 and Subsequent Model-Year Federally Certified Light-Duty Motor Vehicles for Sale in California," adopted July 30, 2002, which ~~is~~ are incorporated herein by reference.

NOTE: Authority cited: Sections 39515, 39600, 39601, 43013, 43018, 43101, 43104 and 43210, Health and Safety Code. Reference: Sections 39002, 39003, 39500, 43000, 43013, 43018, 43100, 43101, 43101.5, 43102, 43104, 43105, 43106, 43204, 43210, 43211, and 43212, Health and Safety Code.

16. Amend Title 13, CCR, section 2112 to read as follows:

§2112. Definitions.

* * * *

(b) "Correlation factor" means a pollutant-specific multiplicative factor calculated by a manufacturer for an engine family or test group which establishes a relationship between chassis exhaust emission data, as determined from the test procedures specified in section 1960.1, ~~or~~ 1961, or 1961.2, Title 13, California Code of Regulations, and engine exhaust emission data, as determined from the test procedures specified in section 1956.8, Title 13, California Code of Regulations.

* * * *

(l)(9) For 2001 ~~and subsequent~~ through 2019 model year medium-duty low-emission, ultra-low-emission and super-ultra-low-emission vehicles certified to the primary standards in section 1961(a)(1), and motor vehicle engines used in such vehicles, a period of use of ten years or 120,000 miles, whichever occurs first. For 2001 ~~and subsequent~~ through 2019 medium-duty low-emission, ultra-low-emission and super-ultra-low-emission vehicles certified to the optional 150,000 mile standards in section 1961(a)(1), and motor vehicle engines used in such vehicles, a period of use of fifteen years or 150,000 miles, whichever occurs first. For all other 1995 and subsequent model-year medium-duty vehicles, and motor vehicle engines used in such vehicles, and 1992 through 1994 model-year medium-duty low-emission, and ultra-low-emission vehicles certified to the standards in Section 1960.1(h)(2), and motor vehicle engines used in such vehicles, a period of use of eleven years or 120,000 miles, whichever occurs first.

* * * *

(l)(18) For those passenger cars, light-duty trucks, and medium-duty vehicles certified to the standards in section 1961.2, the useful life shall be fifteen years or 150,000 miles, whichever occurs first.

[renumber subsections (l)(18) through (l)(23) as (l)(19) through (l)(24)]

* * * *

NOTE: Authority cited: Sections 39600, 39601, 43013, 43018, 43101, 43104, 43105, and 43806, Health and Safety Code; and Section 28114, Vehicle Code. Reference: Sections 39002, 39003, 39500, 43000, 43009.5, 43013, 43018, 43100, 43101, 43101.5, 43102, 43104, 43105, 43106, 43107, 43202, 43204-43205.5, 43206, 43210, 43211, 43212, 43213, and 43806, Health and Safety Code; and Section 28114, Vehicle Code.

17. Amend title 13, CCR, section 2139 to read as follows:

§2139. Testing.

After the vehicles have been accepted and restorative maintenance, if any, has been performed, the ARB or its designated laboratory shall perform the applicable emission tests pursuant to the following:

(a) For passenger cars and light-duty trucks, in-use compliance emission tests shall be performed pursuant to section 1960.1, ~~or~~ 1961, or 1961.2, Title 13, California Code of Regulations, as applicable.

(b) For medium-duty vehicles certified according to the chassis standards and test procedures specified in section 1960.1, ~~or~~ 1961, or 1961.2, Title 13, California Code of Regulations and the documents incorporated by reference therein, in-use compliance emission tests shall be performed pursuant to section 1960.1, ~~or~~ 1961, or 1961.2, Title 13, California Code of Regulations, as applicable.

(c) For medium-duty engines and vehicles certified according to the optional engine test procedures specified in section 1956.8, Title 13, California Code of Regulations and the documents incorporated by reference therein, in-use compliance emission tests shall be performed pursuant to one of the following procedures:

* * * *

(2) Medium-duty vehicles may be tested according to the chassis test procedures specified in section 1960.1(k), ~~or~~ 1961, or 1961.2, as applicable, if a manufacturer develops correlation factors which establish the relationship between engine and chassis testing for each engine family or test group and submits these correlation factors within one year after the beginning of production. The correlation factors shall be applied to the measured in-use engine exhaust emission data to determine the in-use engine exhaust emission levels. All correlation factors and supporting data included in a manufacturer's application must be submitted to and approved by the Executive Officer in advance of their use by a manufacturer. Correlation factors intended to apply to a specific engine family or test group shall be applicable for each vehicle model incorporating that specific engine. Manufacturers shall submit test data demonstrating the applicability of the correlation factors for vehicle models comprising a minimum of 80 percent of their engine sales for that specific engine family or test group. The correlation factors for the remaining fleet may be determined through an engineering evaluation based upon a comparison with similar vehicle models. The Executive Officer shall approve a submitted correlation factor if it accurately corresponds to other established empirical and

theoretical correlation factors and to emission test data available to the Executive Officer.

A manufacturer may choose to use the results from the chassis in-use testing as a screening test. If an engine family or test group does not demonstrate compliance with any of the applicable in-use engine standards, as determined from the chassis test data and the applied correlation factors, the manufacturer shall be subject to the requirements and cost of in-use compliance engine testing, as specified in section 2139(c)(1). The manufacturer shall be subject to engine testing for any non-complying engine family or test group for each subsequent year until compliance with the engine emission standards is demonstrated.

Subsequent to approval of the correlation factors, the Executive Officer may make a determination that the original correlation factors are not valid. Such a determination may be based upon in-use emission data, including chassis and engine testing. Upon determination that the correlation factors for a specific engine family or test group are not valid, the manufacturer of the engine family or test group shall be subject to the enforcement testing requirements and costs of in-use compliance engine testing, as specified in section 2139(c)(1).

* * * *

NOTE: Authority cited: Sections 39600, 39601, 43013, 43018, 43101, 43104 and 43105, Health and Safety Code. Reference: Sections 39002, 39003, 43000, 43009.5, 43013, 43018, 43100, 43101, 43101.5, 43102, 43103, 43104, 43105, 43106, 43107, 43204-43205.5, and 43211-43213 Health and Safety Code.

18. Amend title 13, CCR, section 2140 to read as follows:

§2140. Notification and Use of Test Results.

* * * *

(b) If the results of the in-use vehicle emission tests conducted pursuant to Section 2139 indicate that the average emissions of the test vehicles for any pollutant exceed the applicable emission standards specified in Title 13, California Code of Regulations, Section 1960.1, 1961, 1961.2, 1956.8, 1958, 2412, 2423, or 2442, the entire vehicle population so represented shall be deemed to exceed such standards. The Executive Officer shall notify the manufacturer of the test results and upon receipt of the notification, the manufacturer shall have 45 days to submit an influenced recall plan in accordance with Sections 2113 through 2121, Title 13, California Code of Regulations. If no such recall plan is submitted, the Executive Officer may order corrective action including recall of the affected vehicles in accordance with Sections 2122 through 2135, Title 13, California Code of Regulations.

NOTE: Authority cited: Sections 39600, 39601, 43013, 43018 and 43105, Health and Safety Code. Reference: Sections 43000, 43009.5, 43013, 43018, 43101, 43104, 43105, 43106, 43107, 43204-43205.5 and 43211-43213, Health and Safety Code.

19. Amend title 13, CCR, section 2145 to read as follows:

§2145. Field Information Report.

* * * *

(b) All field information reports shall be submitted to the Chief, Mobile Source Operations Division, 9528 Telstar Avenue, El Monte, CA 91731, and shall contain the following information in substantially the format outlined below:

* * * *

(3) A description of each class or category of California-certified vehicles or engines affected including make, model, model-year, engine family or test group and such other information as may be required to identify the vehicles or engines affected. The description shall include those engine families or test groups related to the affected engine family or test group through common certification test data allowed under ~~Title 40, Code of Federal Regulations, Section 86.085-24(f), as amended December 10, 1984 or~~ Title 40 Code of Federal Regulations, Section 86.1839-01, as ~~adopted May 4, 1999~~ amended January 17, 2006 ("carry-over" and "carry-across" engine families or test groups).

* * * *

NOTE: Authority cited: Sections 39600, 39601 and 43105, Health and Safety Code. Reference: Sections 43000, 43009.5, 43018, 43101, 43104, 43105, 43106, 43107 and 43204-43205.5, Health and Safety Code.

20. Amend title 13, CCR, section 2147 to read as follows:

§2147. Demonstration of Compliance with Emission Standards.

* * * *

(b) A manufacturer may test properly maintained in-use vehicles with the failed emission-related component pursuant to the applicable certification emission tests specified in Title 13, California Code of Regulations, Section 1960.1, ~~or~~ 1961, or 1961.2, as applicable, for passenger cars, light-duty trucks, and medium-duty vehicles, Section 1956.8 for heavy-duty engines and vehicles, Section 1958 for motorcycles, and Section 2442 for sterndrive/inboard marine engines. The emissions shall be projected to the end of the vehicle's or engine's useful life using in-use deterioration factors. The in-use deterioration factors shall be chosen by the manufacturer from among the following:

* * * *

(3) subject to approval by the Executive Officer, a manufacturer-generated deterioration factor. The Executive Officer shall approve such deterioration factor if it is based on in-use data generated from certification emission tests performed on properly maintained and used vehicles in accordance with the procedures set forth in Section 1960.1, ~~or~~ 1961, or 1961.2, of Title 13 of the California Code of Regulations, as applicable, for passenger cars, light-duty trucks, and medium-duty vehicles; Section 1956.8 of Title 13 of the California Code of Regulations for heavy duty vehicles and engines; and Section 1958 of Title 13 of the California Code of Regulations for motorcycles, and if the vehicles from which it was derived are representative of the in-use fleet with regard to emissions performance and are equipped with similar emission control technology as vehicles with the failed component.

* * * *

NOTE: Authority cited: Sections 39600, 39601 and 43105, Health and Safety Code. Reference: Sections 43000, 43009.5, 43018, 43101, 43104, 43105, 43106, 43107 and 43204-43205.5, Health and Safety Code.

21. Amend title 13, CCR, section 2235 to read as follows:

§ 2235. Requirements.

New 1977 ~~and subsequent~~ through 2014 model-year gasoline-fueled motor vehicles and 1993 ~~and subsequent~~ through 2014 model-year methanol-fueled passenger cars, light-duty trucks, medium-duty vehicles and heavy-duty vehicles shall not be sold, offered for sale or registered in California unless such vehicles comply with the Air Resources Board's "Specifications for Fill Pipes and Openings of 1977 through 2014 Model Motor Vehicle Fuel Tanks," dated March 19, 1976 as last amended ~~January 22, 1990~~ [INSERT DATE OF AMENDMENT] or, in the case of motorcycles, are exempted pursuant to Chapter 1, Article 2, Section 1976(b). New 2015 and subsequent model-year gasoline and alcohol fueled passenger cars, light trucks, medium-duty vehicles, and heavy-duty vehicles shall not be sold, offered for sale, or registered in California unless such vehicles comply with the "Specifications for Fill Pipes and Openings of 2015 and Subsequent Model Motor Vehicle Fuel Tanks," dated [INSERT DATE OF ADOPTION]. Motorcycles are exempted pursuant to Chapter 1, Article 2, Section 1976(b).

NOTE: Authority cited: Sections 39600, 39601, 43013, 43018, 43101, 43104, 43107, and 43835, Health and Safety Code. Reference: Sections 39003, 43000, 43013, 43018, 43101, 43104, 43106, 43204, and 43835, Health and Safety Code; and Sections 28111 and 28112, Vehicle Code.

22. Amend title 13, CCR, section 2317 to read as follows:

§ 2317. Satisfaction of Designated Clean Fuels Requirements with a Substitute Fuel.

(a) Any person may petition the state board to designate by regulation a substitute fuel which may be used instead of a primary designated clean fuel to satisfy any requirements in this chapter pertaining to a designated clean fuel. The state board shall designate such a substitute fuel if it is satisfied that the petitioner has demonstrated all of the following:

(1) That use of the fuel in low-emission vehicles certified on the primary designated clean fuel will result in emissions of NMOG (on a reactivity-adjusted basis), NOx, and CO no greater than the corresponding emissions from such vehicles fueled with the primary designated clean fuel, as determined pursuant to the procedures set forth in the "California Test Procedure for Evaluating Substitute Fuels and New Clean Fuels through 2014," as ~~adopted November 2, 1993~~ amended [INSERT DATE OF AMENDMENT] or the "California Test Procedure for Evaluating Substitute Fuels and New Clean Fuels in 2015 and Subsequent Years," as adopted [INSET DATE OF AMENDMENT], as applicable, which ~~is~~ are incorporated herein by reference.

(2) That use of the fuel in low-emission vehicles certified on the primary designated clean fuel will result in potential health risks from exposure to benzene, 1,3-butadiene, formaldehyde, and acetadehyde in the aggregate no greater than the corresponding potential health risks for such vehicles fueled with the primary designated clean fuel, as determined pursuant to the procedures set forth in the "California Test Procedure for Evaluating Substitute Fuels and New Clean Fuels through 2014" or the "California Test Procedure for Evaluating Substitute Fuels and New Clean Fuels in 2015 and Subsequent Years," as applicable. ~~," as adopted November 2, 1993,~~ which ~~is~~ are incorporated herein by reference.

(3) That if the proposed substitute fuel may be used to fuel any motor vehicle other than low-emission vehicles certified on the primary designated clean fuel:

(A) Use of the substitute fuel in such other motor vehicles would not increase emissions of NMOG (on a reactivity-adjusted basis), NOx, and CO as determined pursuant to the procedures set forth in the "California Test Procedure for Evaluating ~~the Emission Impacts of~~ Substitute Fuels ~~or~~ and New Clean Fuels through 2014" or the "California Test Procedure for Evaluating Substitute Fuels and New Clean Fuels in 2015 and Subsequent Years," as applicable,~~" as adopted November 2, 1993,~~ which ~~is~~ are incorporated herein by reference; and

Date of Release: December 7, 2011; 45-day Notice Version
Date of Hearing: January 26, 2012

(B) Use of the substitute fuel in such other motor vehicles would result in potential health risks from exposure to benzene, 1,3-butadiene, formaldehyde, and acetadehyde in the aggregate no greater than the corresponding potential health risk from the emissions from such vehicles when operating on their customary fuel, as determined pursuant to the procedures set forth in the "California Test Procedure for Evaluating ~~the Emission Impacts of~~ Substitute Fuels ~~or~~ and New Clean Fuels through 2014" or the "California Test Procedure for Evaluating Substitute Fuels and New Clean Fuels in 2015 and Subsequent Years," as applicable,~~" as adopted November 2, 1993,~~ which ~~is~~ are incorporated herein by reference; and

(C) Use of the substitute fuel in such other motor vehicles would not result in increased deterioration of the emission control system on the vehicle and would not void the warranties of any such vehicles.

* * * *

NOTE: Authority cited: Sections 39600, 39601, 39667, 43013, 43018 and 43101, Health and Safety Code; and Western Oil and Gas Ass'n. v. Orange County Air Pollution Control District , 14 Cal. 3d 411, 121 Cal. Rptr. 249 (1975). Reference: Sections 39000, 39001, 39002, 39003, 39500, 39515, 39516, 39667, 43000, 43013, 43018 and 43101, Health and Safety Code; and Western Oil and Gas Ass'n. v. Orange County Air Pollution Control District , 14 Cal. 3d 411, 121 Cal. Rptr. 249 (1975).